

“The Missing Manual series is simply the most intelligent and usable series of guidebooks...”
—KEVIN KELLY, CO-FOUNDER OF WIRED

CSS3

the missing manual[®]

The book that should have been in the box[®]

Fully Revised
3rd Edition
Covers HTML5



O'REILLY[®]

David Sawyer McFarland



Answers found here!

CSS3 lets you create professional-looking websites, but learning its finer points can be tricky—even for seasoned web developers. This Missing Manual shows you how to take your HTML and CSS skills to the next level, with valuable tips, tricks, and step-by-step instructions. You'll quickly learn how to build web pages that look great and run fast on devices and screens of all sizes.

the missing manual®

The book that should have been in the box®

The important stuff you need to know

- **Start with the basics.** Write CSS3-friendly HTML, including the HTML5 tags recognized by today's browsers.
- **Apply real-world design.** Format text, create navigation tools, and enhance pages with graphics.
- **Make your pages lively.** Create eye-catching animations and give your visitors attractive tables and forms.
- **Take control of page layouts.** Use professional design techniques such as floats and positioning.
- **Look great on any device.** Craft websites that adapt to desktop, tablet, and mobile browsers.
- **Get advanced techniques.** Use CSS3 more effectively and efficiently, and ensure that your web pages look good when printed.



David Sawyer McFarland,

president of

Sawyer McFarland

Media, Inc., has spent the last 15 years building and managing websites for Macworld.com and UC Berkeley, among other clients. Also a trainer, David has written bestselling Missing Manuals on Dreamweaver, CSS, and JavaScript.

US \$34.99

CAN \$36.99

ISBN: 978-1-449-32594-7



O'REILLY®

missingmanuals.com
twitter: @missingmanuals
facebook.com/MissingManuals

CSS3

Third Edition

the missing manual[®]

The book that should have been in the box[®]

David Sawyer McFarland

O'REILLY[®]

Beijing | Cambridge | Farnham | Köln | Sebastopol | Tokyo

CSS3: The Missing Manual, Third Edition

by David Sawyer McFarland

Copyright © 2013 Sawyer McFarland Media, Inc. All rights reserved.
Printed in the United States of America.

Published by O'Reilly Media, Inc.,
1005 Gravenstein Highway North, Sebastopol, CA 95472.

O'Reilly books may be purchased for educational, business, or sales promotional use. Online editions are also available for most titles (<http://my.safaribooksonline.com>). For more information, contact our corporate/institutional sales department: (800) 998-9938 or corporate@oreilly.com.

August 2006: First Edition.
August 2009: Second Edition.
December 2012: Third Edition.

Revision History for the Third Edition:

2012-12-07	First release
2013-01-11	Second release
2013-05-31	Third release
2013-11-01	Fourth release
2014-04-11	Fifth release

See <http://oreilly.com/catalog/errata.csp?isbn=0636920024996> for release details.

The Missing Manual is a registered trademark of O'Reilly Media, Inc. The Missing Manual logo, and “The book that should have been in the box” are trademarks of O'Reilly Media, Inc. Many of the designations used by manufacturers and sellers to distinguish their products are claimed as trademarks. Where those designations appear in this book, and O'Reilly Media is aware of a trademark claim, the designations are capitalized.

While every precaution has been taken in the preparation of this book, the publisher assumes no responsibility for errors or omissions, or for damages resulting from the use of the information contained in it.

ISBN-13: 978-1-449-32594-7

[LSI]

Contents

The Missing Credits **vii**

Introduction **1**

Part One: **CSS Basics**

CHAPTER 1: **HTML for CSS** **17**

HTML: Past and Present 17

Writing HTML for CSS 20

The Importance of the Doctype 30

Making Sure Internet Explorer Is Up-to-Date 32

CHAPTER 2: **Creating Styles and Style Sheets** **35**

Anatomy of a Style 35

Understanding Style Sheets 38

Internal Style Sheets 40

External Style Sheets 41

Tutorial: Creating Your First Styles 43

CHAPTER 3: **Selectors: Identifying What to Style** **55**

Tag Selectors: Page-Wide Styling 56

Class Selectors: Pinpoint Control 57

ID Selectors: Specific Page Elements 60

Styling Groups of Tags 62

Styling Tags Within Tags 63

Pseudo-Classes and Pseudo-Elements 68

Attribute Selectors 72

Child Selectors 74

Siblings 79

The `:not()` Selector 80

Tutorial: Selector Sampler 81

CHAPTER 4: **Saving Time with Style Inheritance** **93**

What Is Inheritance? 93

How Inheritance Streamlines Style Sheets 95

The Limits of Inheritance 95

Tutorial: Inheritance 97

CHAPTER 5:	Managing Multiple Styles: The Cascade	103
	How Styles Cascade	104
	Specificity: Which Style Wins	108
	Controlling the Cascade	111
	Tutorial: The Cascade in Action	117

Part Two: **Applied CSS**

CHAPTER 6:	Formatting Text	127
	Using Fonts	127
	Using Web Fonts	132
	Discovering Google Web Fonts	146
	Adding Color to Text	154
	Changing Font Size	157
	Formatting Words and Letters	162
	Adding Text Shadow	166
	Formatting Entire Paragraphs	167
	Styling Lists	173
	Tutorial: Text Formatting in Action	178

CHAPTER 7:	Margins, Padding, and Borders	193
	Understanding the Box Model	193
	Controlling Space with Margins and Padding	195
	Adding Borders	202
	Coloring the Background	206
	Creating Rounded Corners	207
	Adding Drop Shadows	210
	Determining Height and Width	212
	Wrapping Content with Floating Elements	220
	Tutorial: Margins, Backgrounds, and Borders	225

CHAPTER 8:	Adding Graphics to Web Pages	239
	Discovering CSS and the Tag	239
	Adding Background Images	240
	Controlling Repetition	244
	Positioning a Background Image	245
	Using Background Property Shorthand	255
	Using Multiple Background Images	257
	Utilizing Gradient Backgrounds	259
	Applying Easy Gradients with Colorzilla	269
	Tutorial: Enhancing Images	272
	Tutorial: Creating a Photo Gallery	278
	Tutorial: Using Background Images	283

CHAPTER 9:	Sprucing Up Your Site’s Navigation	293
	Selecting Which Links to Style.....	293
	Styling Links	297
	Building Navigation Bars.....	303
	CSS-Style Preloading Rollovers.....	313
	Styling Particular Types of Links	315
	Tutorial: Styling Links.....	318
	Tutorial: Creating a Navigation Bar	324
CHAPTER 10:	CSS Transforms, Transitions, and Animations	335
	Transforms.....	335
	Transitions	345
	Animations.....	354
	Tutorial	366
CHAPTER 11:	Formatting Tables and Forms	375
	Using Tables the Right Way	375
	Styling Tables	378
	Styling Forms	384
	Tutorial: Styling a Table.....	390
	Tutorial: Styling a Form.....	395

Part Three: **CSS Page Layout**

CHAPTER 12:	Introducing CSS Layout	405
	Types of Web Page Layouts.....	405
	How CSS Layout Works.....	408
	Layout Strategies	412
CHAPTER 13:	Building Float-Based Layouts	417
	Applying Floats to Your Layouts.....	421
	Overcoming Float Problems.....	425
	Tutorial: Multiple Column Layouts.....	440
CHAPTER 14:	Responsive Web Design	453
	Responsive Web Design Basics.....	454
	Setting Up a Web Page for RWD.....	455
	Media Queries.....	457
	Flexible Grids.....	465
	Fluid Images	470
	Responsive Web Design Tutorial.....	474

CHAPTER 15:	Positioning Elements on a Web Page	487
	How Positioning Properties Work	488
	Powerful Positioning Strategies	502
	Tutorial: Positioning Page Elements	507

Part Four: **Advanced CSS**

CHAPTER 16:	CSS for the Printed Page	519
	How Media Style Sheets Work	519
	How to Add Media Style Sheets	522
	Creating Print Style Sheets	523
	Tutorial: Building a Print Style Sheet	530
CHAPTER 17:	Improving Your CSS Habits	539
	Adding Comments	539
	Organizing Styles and Style Sheets	541
	Eliminating Browser Style Interference	548
	Using Descendent Selectors	553
	Trying Different CSS for Internet Explorer	558

Part Five: **Appendixes**

APPENDIX A:	CSS Property Reference	563
	CSS Values	563
	Text Properties	567
	List Properties	572
	Padding, Borders, and Margins	573
	Backgrounds	579
	Page Layout Properties	582
	Animation, Transform, and Transition Properties	588
	Table Properties	593
	Miscellaneous Properties	595
APPENDIX B:	CSS Resources	599
	References	599
	CSS Help	600
	CSS Tips, Tricks, and Advice	600
	CSS Navigation	601
	CSS Layout	602
	Showcase Sites	603
	CSS Books	604
	CSS Software	604
	Index	607

The Missing Credits

ABOUT THE AUTHOR



David Sawyer McFarland is president of Sawyer McFarland Media, Inc., a web development and training company in Portland, Oregon. He's been building websites since 1995, when he designed his first website: an online magazine for communication professionals. He's served as the webmaster at the University of California at Berkeley and the Berkeley Multimedia Research Center, and he has helped build, design, and program numerous websites for clients including

Macworld.com.

In addition to building websites, David is also a writer, trainer, and instructor. He's taught web design at the UC Berkeley Graduate School of Journalism, the Center for Electronic Art, the Academy of Art College, Ex'Pressions Center for New Media, and the Art Institute of Portland. He currently teaches in the Multimedia Program at Portland State University. He's written articles about web design for *Practical Web Design*, *Macworld* magazine, and *CreativePro.com*.

David is also the author of *Dreamweaver: The Missing Manual* and *JavaScript: The Missing Manual*.

He welcomes feedback about this book by email: missing@sawmac.com. (If you're seeking technical help, however, please refer to the sources listed in Appendix B.)

ABOUT THE CREATIVE TEAM

Nan Barber (editor) has worked with the Missing Manual series since the previous century. She lives in Massachusetts with her husband and iMac. Email: nanbarber@oreilly.com.

Holly Bauer (production editor) lives in Ye Olde Cambridge, Mass., where she is an avid home cook, prolific DIYer, and mid-century modern design enthusiast. Email: holly@oreilly.com.

Nancy Reinhardt (proofreader) lives in the Midwest, where she enjoys summer weekends at the lake, boating, swimming, and reading voraciously. Nan is not only a freelance copyeditor and proofreader, but she's also a published romance novelist. Check out her work at www.nanreinhardt.com. Email: nanleigh1@gmail.com.

Nancy A. Guenther (indexer) indexed this book on behalf of Potomac Indexing, LLC, an international indexing partnership at www.potomacindexing.com. She has been a full-time freelance indexer since 1983, specializing in computer software, American studies, and business. Her website is www.guenther.bizland.com.

Daniel J. Quinn (technical reviewer) is a freelance web developer at DQuinn.net. For the past five years, he has worked as a senior UI engineer at award-winning digital agency Genuine Interactive, specializing in WordPress and content strategy for brands like Sam Adams, MassMutual, and Children’s Hospital Boston. Today, Daniel serves as web developer for Harvard University’s Digital Communications department. He regularly works with a team of local designers and can be reached at daniel@dquinn.net.

Jason Arnold (technical reviewer) lives in Santa Rosa, California, with his wife and three daughters. He works at Healdsburg District Hospital as a Telemetry Technician and teaches Kenpo Karate to children. He is currently working toward his nursing degree at Santa Rosa Junior College. In his free time, he does Kenpo Karate with his daughters and is always on the lookout for an extra tech project to stay busy.

ACKNOWLEDGEMENTS

Many thanks to all those who helped with this book, including my students, who always help me see complex concepts through beginners’ eyes. Thanks to my technical editors, Daniel Quinn and Jason Arnold, who saved me from any embarrassing mistakes, and Zoe Gillenwater whose valuable advice for the first edition of this book lives on. Also, we all owe a big debt of gratitude to the many web designers who have broken new ground by using CSS in creative ways and shared their discoveries with the web design community.

Finally, thanks to David Pogue, whose unflagging enthusiasm and endurance is inspiring; Nan Barber for refining my writing, fixing my mistakes, and keeping me on track; my wife, Scholle, for her love and support; my son, Graham, who suggested that I’d get this book done a lot faster if I just typed “Blah, blah, blah, blah, BOO!” for each chapter; my wonderful daughter, Kate, whose smile is always a great pick-me-up; and to my family: Mom, Doug, Mary, David, Marisa, Tessa, Phyllis, Les, Del, Patricia, and Mike.

—David Sawyer McFarland

THE MISSING MANUAL SERIES

Missing Manuals are witty, superbly written guides to computer products that don’t come with printed manuals (which is just about all of them). Each book features a handcrafted index and cross-references to specific pages (not just chapters). Recent and upcoming titles include:

Access 2010: The Missing Manual by Matthew MacDonald

Access 2013: The Missing Manual by Matthew MacDonald

Adobe Edge Animate: The Missing Manual by Chris Grover

Buying a Home: The Missing Manual by Nancy Conner

Creating a Website: The Missing Manual, Third Edition, by Matthew MacDonald

David Pogue's Digital Photography: The Missing Manual by David Pogue

Dreamweaver CS6: The Missing Manual by David Sawyer McFarland

Droid 2: The Missing Manual by Preston Gralla

Droid X2: The Missing Manual by Preston Gralla

Excel 2010: The Missing Manual by Matthew MacDonald

FileMaker Pro 12: The Missing Manual by Susan Prosser and Stuart Gripman

Flash CS6: The Missing Manual by Chris Grover

Galaxy S II: The Missing Manual by Preston Gralla

Galaxy Tab: The Missing Manual by Preston Gralla

Google+: The Missing Manual by Kevin Purdy

Google SketchUp: The Missing Manual by Chris Grover

HTML5: The Missing Manual by Matthew MacDonald

iMovie '11 & iDVD: The Missing Manual by David Pogue and Aaron Miller

iPad: The Missing Manual, Fourth Edition by J.D. Biersdorfer

iPhone: The Missing Manual, Fifth Edition by David Pogue

iPhone App Development: The Missing Manual by Craig Hockenberry

iPhoto '11: The Missing Manual by David Pogue and Lesa Snider

iPod: The Missing Manual, Tenth Edition by J.D. Biersdorfer and David Pogue

JavaScript & jQuery: The Missing Manual, Second Edition by David Sawyer McFarland

Kindle Fire: The Missing Manual by Peter Meyers

Living Green: The Missing Manual by Nancy Conner

Mac OS X Mountain Lion: The Missing Manual by David Pogue

Microsoft Project 2010: The Missing Manual by Bonnie Biafore

Motorola Xoom: The Missing Manual by Preston Gralla

Netbooks: The Missing Manual by J.D. Biersdorfer

NOOK HD: The Missing Manual by Preston Gralla

Office 2010: The Missing Manual by Nancy Conner, Chris Grover, and Matthew MacDonald

Office 2011 for Macintosh: The Missing Manual by Chris Grover

Office 2013: The Missing Manual by Nancy Conner and Matthew MacDonald

Personal Investing: The Missing Manual by Bonnie Biafore

Photoshop CS6: The Missing Manual by Lesa Snider

Photoshop Elements 10: The Missing Manual by Barbara Brundage

PHP & MySQL: The Missing Manual, Second Edition by Brett McLaughlin

QuickBooks 2012: The Missing Manual by Bonnie Biafore

Switching to the Mac: The Missing Manual, Lion Edition by David Pogue

Windows 7: The Missing Manual by David Pogue

Windows 8: The Missing Manual by David Pogue

Your Body: The Missing Manual by Matthew MacDonald

Your Brain: The Missing Manual by Matthew MacDonald

Your Money: The Missing Manual by J.D. Roth

For a full list of all Missing Manuals in print, go to www.missingmanuals.com/library.html.

Introduction

Cascading Style Sheets—CSS for short—give you creative control over the layout and design of your web pages. Using CSS, you can dress up your site's text with eye-catching headlines, drop caps, and borders, just like the ones in glossy magazines. You can also arrange images with precision, create columns and banners, and highlight your links with dynamic rollover effects. You can even make elements fade in or out of view, move objects around the page, or make a button slowly change colors when a visitor mouses over it.

Anything that can do all that must be pretty complicated, right? Au contraire! The whole idea behind CSS is to streamline the process of styling web pages. In the next few pages, you'll learn about the basics of CSS. In Chapter 1, you'll get right to work creating a CSS-powered web page.

■ How CSS Works

CSS works with HTML, but it's not HTML. It's a different language altogether. While HTML provides structure to a document by organizing information into headers, paragraphs, bulleted lists, and so on, CSS works hand-in-hand with the web browser to make HTML *look* good.

For example, you might use HTML to turn a phrase into a top-level heading, indicating that it introduces the content on the rest of the page. However, you'd use CSS to format that heading with, say, big and bold red type and position it 50 pixels from the left edge of the window. In CSS, that text formatting comprises a *style*—a rule describing the appearance of a particular portion of a web page. A *style sheet* is a set of these styles.

You can also create styles specifically for working with images. For instance, a style can align an image along the right edge of a web page, surround the image with a colorful border, and place a 50-pixel margin between the image and the surrounding text.

Once you've created a style, you can apply it to text, images, headings, or other elements on a page. For example, you can select a paragraph of text and apply a style to instantly change the text's size, color, and font. You can also create styles for specific HTML tags, so, for example, all first-level headings (<h1> tags) in your site are displayed in the same style, no matter where they appear.

■ The Benefits of CSS

Before CSS, web designers were limited to the layout and styling options of HTML. And if you surfed the Web in 1995, then you understand the emphasis on *limited*. HTML still forms the foundation of all pages on the World Wide Web, but it's simply not a design tool. Sure, HTML provides basic formatting options for text, images, tables, and other web page elements, and patient, meticulous webmasters can make pages look pretty good using only HTML. But the result is often sluggish web pages laden with clunky code.

CSS, in contrast, offers the following advantages:

- Style sheets offer far more formatting choices than HTML. With CSS, you can format paragraphs as they appear in a magazine or newspaper (the first line indented and no space between each paragraph, for example) and control the *leading* (the space between lines of type in a paragraph).
- When you use CSS to add a background image to a page, you get to decide whether and how it *tiles* (repeats). HTML can't even begin to do that.
- Even better, CSS styles take up much less space than HTML's formatting options, such as the much-hated tag. You can usually trim a lot of kilobytes from text-heavy web pages by using CSS. As a result, your pages look great *and* load faster.
- Style sheets also make updating your site easier. You can collect all your styles into a single external style sheet that's linked to every page in your site. Then, when you edit a style, that change immediately ripples through your site *wherever* that style appears. You can completely change the appearance of a site just by editing a single style sheet.

■ What You Need to Know

This book assumes you've already got some knowledge of HTML (and maybe some CSS experience as well). Perhaps you've built a site or two (or at least a page or two) and have some familiarity with the sea of tags—<html>, <p>, <h1>, <table>,

and so on—that make up the Hypertext Markup Language. CSS can't do anything without HTML, so to move forward you need to know how to create a web page by using basic HTML.

If you've used HTML in the past to create web pages, but feel like your knowledge is a bit rusty, the next section provides a basic refresher.

TIP

If you're just getting your feet wet learning HTML, then check out these free online tutorials: HTML Dog (www.htmldog.com/guides/htmlbeginner) and W3Schools (www.w3schools.com/html). If you're a printed page fan, then you may want to pick up a copy of *Creating a Website: The Missing Manual*, Third Edition or *Head First HTML and CSS*, Second Edition (both O'Reilly).

HTML: The Barebones Structure

HTML (Hypertext Markup Language) uses simple commands called *tags* to define the various parts of a web page. For example, this HTML code creates a simple web page:

```
<!doctype html>
<html>
  <head>
    <meta charset="UTF-8">
    <title>Hey, I am the title of this web page</title>
  </head>
  <body>
    <p>Hey, I am a paragraph on this web page.</p>
  </body>
</html>
```

It may not be exciting, but this example has all the basic elements a web page needs. You'll notice something called a *doctype* declaration at the very beginning of the code, followed by `<html>` (with the brackets), a head, a body, and some stuff—the actual page contents—inside the body, ending in a final `</html>`.

Document Types

All web pages begin with a doctype—a line of code that identifies what flavor of HTML you used to write the page. Two doctypes have been used for years—HTML 4.01 and XHTML 1.0—and each of those doctypes has two styles: *strict* and *transitional*. For example, the HTML 4.01 transitional doctype looks like the following (the other doctypes for HTML 4.01 and XHTML 1.0 look similar):

```
<!DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN" "http://www.
w3.org/TR/html4/loose.dtd">
```

NOTE

For examples of all various doctypes, visit www.webstandards.org/learn/reference/templates.

If you look at the code for the sample HTML page in this section, you'll see that it uses a much more succinct doctype:

```
<!doctype html>
```

That's HTML5's new—and simpler—doctype. HTML5 is intended to be easier to use and more streamlined than its predecessors. This book uses the HTML5 doctype, which is supported by every popular browser (even the old Internet Explorer 6). And because HTML5 is the future of the Web, there's no reason to use the older doctypes any longer.

NOTE

Just because the HTML doctype works in older browsers doesn't mean that those browsers understand all HTML5 tags or features. Internet Explorer 8 and earlier, for example, don't recognize the new HTML5 tags. To style tags with CSS for those versions of IE, you have to employ a little JavaScript. You'll learn how to get older browsers up to speed on page 30.

But no matter which doctype you prefer, the important thing is to always use one. Without it, your pages will look different depending on your visitor's browser, since browsers display CSS differently if they don't have a doctype for guidance.

Each doctype requires you to write your HTML in a certain way. For example, the tag for a line break looks like this in HTML 4.01:

```
<br>
```

But in XHTML, it looks like this:

```
<br />
```

And there's another advantage of HTML5: it accepts either one.

How HTML Tags Work

In the simple HTML example on page 3, as in the HTML code of any web page, most commands appear in pairs that surround a block of text or other commands. Sandwiched between brackets, these *tags* are instructions that tell a web browser how to display the web page. Tags are the “markup” part of the Hypertext Markup Language.

The starting (*opening*) tag of each pair tells the browser where the instruction begins, and the ending tag tells it where the instruction ends. Ending or *closing* tags always include a forward slash (/) after the first bracket symbol (<).

On any web page, you'll usually find at least these four elements.

- The first line of a web page is the **DOCTYPE declaration**, discussed in the previous section.
- The `<html>` tag appears once at the beginning of a web page and again (with an added forward slash) at the end: `</html>`. This tag tells a web browser that

the information contained in this document is written in HTML, as opposed to some other language. All the contents of a page, including other tags, appear between the opening and closing `<html>` tags.

If you were to think of a web page as a tree, the `<html>` tag would be its root. Springing from the trunk are two branches that represent the two main parts of any web page: the *head* and the *body*.

- The *head* of a web page contains the title of the page (“Izzie’s Mail-Order Pencils”). It may also include other, invisible information, like a page description, that browsers and search engines use. You surround the head section with opening and closing `<head>` tags.

In addition, the head section can include information that browsers use to format the page’s HTML and to add interactivity. As you’ll see, the `<head>` section can contain CSS code (like the kind you’ll learn to write in this book) or a link to another file containing CSS information.

- The *body*, as set apart by its surrounding `<body>` tags, contains all the content that appears inside a browser window—headlines, text, pictures, and so on.

Within the `<body>` tag, you commonly find tags like these:

- You tell a web browser where a paragraph of text begins with a `<p>` (opening paragraph tag), and where it ends with a `</p>` (closing paragraph tag).
- The `` tag emphasizes text. When you surround some text with it and its partner tag, ``, you get boldface type. The HTML snippet `Warning!` tells a web browser to strongly emphasize the word “Warning!”
- The `<a>` tag, or anchor tag, creates a *hyperlink* in a web page. When clicked, a hyperlink—or *link*—can lead anywhere on the Web. You tell the browser where the link points by putting a web address inside the `<a>` tags. For instance, you can type `Click here!`.

The browser knows that when your visitor clicks the words “Click here!” it should go to the Missing Manual website. The `href` part of the tag is called an *attribute*, and the URL (the Uniform Resource Locator or web address) is the *value*. In this example, `http://www.missingmanuals.com` is the *value* of the `href` attribute.

■ XHTML, Too

Like any technology, HTML has evolved over time. Although standard HTML has served its purpose well, it’s always been a somewhat sloppy language. Among other things, it lets you use uppercase, lowercase, and mixed-case letters in tags (`<body>` and `<BODY>` are both correct, for example) and permits unclosed tags (so you can use a `<p>` tag without a closing `</p>` tag to create a paragraph). While this flexibility may make page-writing easier, it also makes life more difficult for web browsers, smart phones, and other technologies that interact with data on the Web.

Additionally, HTML doesn't work with one of the hottest Internet languages: XML, or Extensible Markup Language.

To keep pace with the times, an improved version of HTML, called XHTML, was introduced back in 2000, and you'll find it used frequently on many sites (in fact, XHTML is just an "XML-ified" version of HTML). XHTML was seen as the future (back in 2000), but has since been supplanted by HTML5. While web browsers still understand XHTML (and probably will for a long time), this book doesn't include it.

■ HTML5: The Wheel Turns Again

When the W3C—the group responsible for many Internet technologies—introduced XHTML as an intermediate step in the transition to XML as the prime language of the Web, the web development community heralded it as the next big thing. History has shown that prediction to be a bit grandiose. As it turns out, the complexity of moving to XML kept browser manufacturers from following the XML path the World Wide Web Consortium laid down. Instead, the W3C closed down the XHTML working group in favor of HTML5—a new version of HTML that moves away from XML and back to HTML, albeit an enhanced version. With the support of all browser manufacturers, HTML5 is the new next big thing. Some browsers, including Google Chrome and Firefox, already recognize parts of HTML5, and even mainstream news outlets like Time, Newsweek, and CNN drop "HTML5" into their technology reporting.

HTML5 isn't some radically new technology. In fact, unlike XHTML, which was intended to foster a new way to build web pages, HTML5 is about making sure the Web continues to work the way it always has. Most of the basics of HTML are still in place. Also, HTML5 adds a few new elements, meant to support the way web designers currently build websites. For example, in HTML5, the `<header>` tag can contain the content you'd usually find at the top of a page, such as a logo and site-wide navigation links; the new `<nav>` tag encloses the set of links used to navigate a site; and the `<footer>` tag houses the stuff you usually put at the bottom of a page, like legal notices, email contacts, and so on.

In addition, HTML5 adds new tags that let you insert video and audio into a page, and new form tags that add sophisticated elements, like sliders and pop-up date pickers, as well as built-in browser support for form validation (which ensures visitors correctly fill out your forms). Unfortunately, browser support for these new features isn't consistent, and it's difficult to use the new tags without some pretty elaborate workarounds.

Although HTML5 may not be entirely ready for primetime, there's no reason not to start using the HTML5 doctype and even some basic HTML5 now. (You'll need to give Internet Explorer 8 and earlier a bit of help, though; see the box on page 24.) You'll find HTML5 throughout this book, especially in the next chapter.

■ Software for CSS

To create web pages made up of HTML and CSS, you need nothing more than a basic text editor like Notepad (Windows) or TextEdit (Mac). But after typing a few hundred lines of HTML and CSS, you may want to try a program better suited to working with web pages. This section lists some common programs, some free and some you have to buy.

NOTE

There are literally hundreds of tools that can help you create web pages, so the following isn't a complete list. Think of it as a greatest-hits tour of the most popular programs that CSS fans are using today.

Free Programs

There are plenty of free programs out there for editing web pages and style sheets. If you're still using Notepad or TextEdit, give one of these a try. Here's a short list to get you started:

- **JEdit** (Windows, Mac, Linux; <http://jedit.org>). This free, Java-based text editor works on almost any computer and includes many features that you'd find in commercial text editors, like syntax highlighting for CSS.
- **Notepad++** (Windows; <http://notepad-plus.sourceforge.net>). A lot of people swear by this fast text editor. It even has built-in features that make it ideal for writing HTML and CSS, like syntax highlighting—color coding tags and special keywords to make it easier to identify the page's HTML and CSS elements.
- **TextWrangler** (Mac; www.barebones.com/products/textwrangler). This free software is actually a pared-down version of BBEdit, the sophisticated, well-known Mac text editor. TextWrangler doesn't have all of BBEdit's built-in HTML tools, but it does include syntax highlighting, FTP (so you can upload files to a web server), and more.

Commercial Software

Commercial website development programs range from inexpensive text editors to complete website construction tools with all the bells and whistles:

- **EditPlus** (Windows; www.editplus.com) is an inexpensive (\$35) text editor that includes syntax highlighting, FTP, auto-complete, and other wrist-saving features.
- **skEdit** (Mac; www.skedit.com) is an inexpensive (\$30) web page editor, complete with FTP/SFTP, code hints, and other useful features.
- **Coda2** (Mac; www.panic.com/coda) is a full-featured web development toolkit (\$99). It includes a text editor, page preview, FTP/SFTP, and graphic CSS-creating tools for creating CSS.
- **Sublime Text** (Mac, Windows, Linux; www.sublimetext.com) is a relatively new text editor. It's beloved by many web coders.

- **Dreamweaver** (Mac and Windows; www.adobe.com/products/dreamweaver) is a visual web page editor (\$399). It lets you see how your page looks in a web browser. The program also includes a powerful text-editor and excellent CSS creation and management tools. Check out *Dreamweaver CS6: The Missing Manual* for the full skinny on how to use this powerful program.
- **Expression Web 2** (Windows; www.microsoft.com/expression) is Microsoft's entry in the web design field (\$149). It includes many professional web design tools, including excellent CSS tools.

NOTE

The various types of software discussed in this section are general-purpose programs that let you edit both HTML/XHTML and CSS. With them, you need to learn only one program for your web development needs. But if you already have a beloved HTML/XHTML editor that doesn't do CSS, then you may want to check out one of the CSS-specific editing programs covered in Appendix B.

About This Book

The World Wide Web is really easy to use. After all, grandmothers in Boise and first graders in Tallahassee log onto the Web every day. Unfortunately, the rules that govern how the Web *works* aren't so easy to understand. The computer scientists and other techie types who write the official documentation aren't interested in explaining their concepts to the average Joe (or Joanne). Just check out www.w3.org/TR/css3-transforms to get a taste of the technical mumbo-jumbo these geeks speak.

People just learning CSS often don't know where to begin. And CSS's finer points can trip up even seasoned web pros. The purpose of this book, then, is to serve as the manual that should have come with CSS. In this book's pages, you'll find step-by-step instructions for using CSS to create beautiful web pages.

CSS3: The Missing Manual is designed to help readers at every technical level. To get the most out of this book, you should know a sampling of HTML and maybe even CSS. So if you've never built a web page before, then check out the tutorial that starts on page 43. The primary discussions in these chapters are written for advanced-beginners or intermediates. But if you're new to building web pages, special boxes called "Up to Speed" provide the introductory information you need to understand the topic at hand. If you're an advanced web page jockey, on the other hand, then keep your eye out for similar boxes called "Power Users' Clinic." They offer more technical tips, tricks, and shortcuts for the experienced computer fan.

UP TO SPEED

The Different Flavors of CSS

Like operating systems and iPods, CSS spins off new versions continuously (well, not as frequently as iPod models). CSS 1, introduced in 1996, laid the groundwork for Cascading Style Sheets. The basic structure of a style, the selector concept (Chapter 3), and most of the CSS properties in this book were all in that very first version.

CSS 2 added new features, including the ability to target your CSS to different printers, monitors, and other devices. CSS 2 also added new selectors and the ability to precisely position elements on a web page.

This book completely covers CSS 2.1, which is the current accepted standard. It incorporates all of CSS 1, adds several new properties, and corrects a few problems with the CSS 2 guidelines.

CSS 2.1 included a few additions and revisions. It wasn't a radical change from version 2, and most web browsers have adapted to the new rules just fine, thank you.

More recently, CSS3 has been getting a lot of press (along with its cousin HTML5). Unlike previous versions of CSS, CSS3 isn't

actually one single standard. As CSS has grown in complexity, the W3C has split CSS up into separate modules—the Selectors module, the Values and Units module, the Box Alignment module, and so on. Since each module can develop independently of the others, there isn't any single standard called "CSS3." In fact, level 3 of the Selectors module is complete, and work on level 4 is underway.

In other words, what's known as CSS3 is really just a loose collection of different modules at various states of completion. Browser manufacturers have already incorporated parts of the newer modules, but other modules aren't supported in any browsers. In the future, there won't be any CSS4; there will just be new versions of the different modules, each at a different level of work.

For these reasons, this book covers the core CSS 2.1 (which has simply been rolled over into the various modules of CSS3), as well as the most exciting, popular, and widely supported new CSS properties.

NOTE

This book periodically recommends other CSS books, covering topics that are too specialized or tangential for a manual. Sometimes the recommended titles are from Missing Manual series publisher O'Reilly—but not always. If there's a great book out there that's not part of the O'Reilly family, we'll let you know about it.

About the Outline

CSS3: The Missing Manual is divided into five parts; the first four each contain several chapters while the last part contains appendices:

- **Part One: CSS Basics**, shows you how to create style sheets and provides an overview of key CSS concepts like inheritance, selectors, and the cascade. Along the way, you'll learn the best HTML writing practices when working with CSS. Tutorials reinforce the part's main concepts and give you a good taste of the power of CSS.

- **Part Two: Applied CSS**, takes you into the real world of web design. You'll learn the most important CSS properties and how to use them to format text, create useful navigation tools, and enhance your page with graphics. You'll learn how to create simple animations with CSS. This section also provides advice on how to make attractive tables and forms.
- **Part Three: CSS Page Layout**, helps you with one of the most confusing, but most rewarding, aspects of CSS—controlling the placement of elements on a page. You'll learn how to create common designs (like 2- and 3-column layouts), how to add sidebars, as well as about floats and positioning—two common CSS techniques for controlling page layout. You'll also learn how to craft websites that adapt to look good on desktop, tablet, and mobile browsers.
- **Part Four: Advanced CSS**, teaches you how to make web pages look good when printed and covers advanced techniques for using CSS more effectively and efficiently.
- **Part Five: Appendixes**, provides two sets of resources. The CSS Property Reference summarizes each CSS property in small, easy-to-digest chunks so you can quickly learn about useful CSS properties you may not have seen before or brush up on what you already know. The last appendix covers tools and resources for creating and using CSS.

■ The Very Basics

To use this book, and indeed to use a computer, you need to know a few basics. You should be familiar with these terms and concepts:

- **Clicking.** This book gives you three kinds of instructions that require you to use your computer's mouse or trackpad. To *click* means to point the arrow cursor at something on the screen and then—without moving the cursor at all—to press and release the clicker button on the mouse (or laptop trackpad). A right-click is the same thing using the right mouse button. (On a Mac, press Control as you click if you don't have a right mouse button.)

To *double-click* means to click twice in rapid succession, again without moving the cursor at all. And to *drag* means to move the cursor *while* pressing the button.

When you're told to **⌘-click** something on the Mac, or *Ctrl-click* something on a PC, you click while pressing the **⌘** or Ctrl key (both of which are near the space bar).

- **Menus.** The *menus* are the words at the top of your screen or window: File, Edit, and so on. Click one to make a list of commands appear, as though they're written on a window shade you've just pulled down. This book assumes that you know how to open a program, surf the Web, and download files. You should know how to use the Start menu (Windows) or the Dock or **Ⓜ** menu (Mac), as well as the Control Panel (Windows) or System Preferences (Mac OS X).

- **Keyboard shortcuts.** Every time you take your hand off the keyboard to move the mouse, you lose time and potentially disrupt your creative flow. That's why many experienced computer fans use keystroke combinations instead of menu commands wherever possible. When you see a shortcut like Ctrl+S (⌘-S) (which saves changes to the current document), it's telling you to hold down the Ctrl or ⌘ key, and, while it's down, type the letter S, and then release both keys.

About→These→Arrows

Throughout this book, and throughout the Missing Manual series, you'll find sentences like this one: "Open the System→Library→ Fonts folder." That's shorthand for a much longer instruction that directs you to open three nested folders in sequence, like this: "On your hard drive, you'll find a folder called System. Open that. Inside the System folder window is a folder called Library; double-click it to open it. Inside *that* folder is yet another one called Fonts. Double-click to open it, too."

Similarly, this kind of arrow shorthand helps to simplify the business of choosing commands in menus, as shown in Figure I-1.




FIGURE I-1

In this book, arrow notations help simplify menu instructions. For example, View→Text Size→Increase is a more compact way of saying, "From the View menu, choose Text Size; from the submenu that then appears, choose Increase." (By the way, when you see a keystroke combination after a menu command, like Ctrl++ here, that means you can press those keys as a shortcut.)

■ About the Online Resources

As the owner of a Missing Manual, you've got more than just a book to read. Online, you'll find example files so you can get some hands-on experience, as well as tips, articles, and maybe even a video or two. You can also communicate with the Missing Manual team and tell us what you love (or hate) about the book. Head over to www.missingmanuals.com, or go directly to one of the following sections.

Living Examples

This book is designed to get your work onto the Web faster and more professionally. It's only natural, then, that half the value of this book lies on the Web.

As you read the book's chapters, you'll encounter a number of *living examples*—step-by-step tutorials that you can build yourself, using raw materials (like graphics and half-completed web pages) that you can download from www.sawmac.com/css3/. You may not gain very much by simply reading these step-by-step lessons while relaxing in your porch hammock. But if you work through them at the computer, you'll discover that these tutorials give you insight into the way professional designers build web pages.

You'll also find, in this book's lessons, the URLs of the finished pages, so that you can compare your work with the final result. In other words, you won't just see pictures of how the web pages *should* look; you'll find the actual, working web pages on the Internet.

About MissingManuals.com

At www.missingmanuals.com, you'll find articles, tips, and updates to *CSS3: The Missing Manual*. In fact, we invite and encourage you to submit such corrections and updates yourself. In an effort to keep the book as up-to-date and accurate as possible, each time we print more copies of this book, we'll make any confirmed corrections you've suggested. We'll also note such changes on the website, so that you can mark important corrections into your own copy of the book, if you like. (Go to www.missingmanuals.com/feedback, choose the book's name from the pop-up menu, and then click Go to see the changes.)

Also on our Feedback page, you can get expert answers to questions that come to you while reading this book, write a book review, and find groups for folks who share your interest in CSS.

We'd love to hear your suggestions for new books in the Missing Manual line. There's a place for that on missingmanuals.com, too. And while you're online, you can also register this book at www.oreilly.com (you can jump directly to the registration page by going here: www.oreilly.com/register). Registering means we can send you updates about this book, and you'll be eligible for special offers like discounts on future editions of *CSS3: The Missing Manual*.

Errata

In an effort to keep this book as up-to-date and accurate as possible, each time we print more copies, we'll make any confirmed corrections you've suggested. We also note such changes on the book's website, so you can mark important corrections into your own copy of the book, if you like. Go to oreil.ly/css3_mm to report an error and view existing corrections.

■ Safari® Books Online

Safari® Books Online is an on-demand digital library that lets you easily search over 7,500 technology and creative reference books and videos to find the answers you need quickly.

With a subscription, you can read any page and watch any video from our library online. Read books on your cellphone and mobile devices. Access new titles before they're available for print, and get exclusive access to manuscripts in development and post feedback for the authors. Copy and paste code samples, organize your favorites, download chapters, bookmark key sections, create notes, print out pages, and benefit from tons of other time-saving features.

CSS Basics

CHAPTER 1:
HTML for CSS

CHAPTER 2:
Creating Styles and Style Sheets

CHAPTER 3:
Selectors: Identifying What to Style

CHAPTER 4:
Saving Time with Style Inheritance

CHAPTER 5:
Managing Multiple Styles: The Cascade



HTML for CSS

To get the most out of CSS, your HTML code needs to provide a solid, well-built foundation. This chapter shows you how to write better, more CSS-friendly HTML. The good news is that when you use CSS throughout your site, HTML actually becomes *easier* to write. You no longer need to worry about trying to turn HTML into the design maven it was never intended to be. Instead, CSS offers most of the graphic design touches you'll likely ever want, and HTML pages written to work with CSS are easier to create since they require less code and less typing. They'll also download faster—a welcome bonus your site's visitors will appreciate (see Figure 1-1).

■ HTML: Past and Present

As discussed in the Introduction, HTML provides the foundation for every page you encounter on the World Wide Web. When you add CSS into the mix, the way you use HTML changes. Say goodbye to repurposing awkward HTML tags merely to achieve certain visual effects. Some HTML tags and attributes—like the old `` tag—you can forget completely.




FIGURE 1-1

CSS-driven web design makes writing HTML easier. The two designs pictured here look similar, but the top page is styled completely with CSS, while the bottom page uses only HTML. The size of the HTML file for the top page is only 4k, while the HTML-only page is nearly 4 times that size at 14k. The HTML-only approach requires a lot more code to achieve nearly the same visual effects: 213 lines of HTML code compared with 71 lines for the CSS version.

HTML Past: Whatever Looked Good

When a bunch of scientists created the Web to help share and keep track of technical documentation, nobody called in the graphic designers. All the scientists needed HTML to do was structure information for easy comprehension. For example, the `<h1>` tag indicates an important headline, while the `<h2>` tag represents a lesser heading,

usually a subheading of the `<h1>` tag. Another favorite, the `` (ordered list) tag, creates a numbered list for things like “Top 10 reasons not to play with jellyfish.”

But as soon as people besides scientists started using HTML, they wanted their web pages to look good. So web designers started to use tags to control appearance rather than structure information. For example, you can use the `<blockquote>` tag (intended for material that’s quoted from another source) on any text that you want to indent a little bit. You can use heading tags to make any text bigger and bolder—regardless of whether it functions as a heading.

In an even more elaborate workaround, designers learned how to use the `<table>` tag to create columns of text and accurately place pictures and text on a page. Unfortunately, since that tag was intended to display spreadsheet-like data—research results, train schedules, and so on—designers had to get creative by using the `<table>` tag in unusual ways, sometimes nesting a table within a table within a table to make their pages look good.

Meanwhile, browser makers introduced new tags and attributes for the specific purpose of making a page look better. The `` tag, for example, lets you specify a font color, typeface, and one of seven different sizes. (If you’re keeping score at home, that’s about 100 fewer sizes than you can get with, say, Microsoft Word.)

Finally, when designers couldn’t get exactly what they wanted, they often resorted to using graphics. For example, they’d create a large graphic to capture the exact font and layout for web page elements and then slice the Photoshop files into smaller files and piece them back together inside tables to recreate the original design.

While all of the preceding techniques—using tags in creative ways, taking advantage of design-specific tag attributes, and making extensive use of graphics—provide design control over your pages, they also add a lot of additional HTML code (and more wrinkles to your forehead).

HTML Present: Scaffolding for CSS

No matter what content your web page holds—the fishing season calendar, driving directions to the nearest IKEA, or pictures from your kid’s birthday party—it’s the page’s design that makes it look like either a professional enterprise or a part-timer’s hobby. Good design enhances the message of your site, helps visitors find what they’re looking for, and determines how the rest of the world sees your website. That’s why web designers went through the contortions described in the previous section to force HTML to look good. By taking on those design duties, CSS lets HTML go back to doing what it does best—structure content.

Using HTML to control the look of text and other web page elements is obsolete. Don’t worry if HTML’s `<h1>` tag is too big for your taste or bulleted lists aren’t spaced just right. You can take care of that later using CSS. Instead, think of HTML as a method of adding structure to the content you want up on the Web. Use HTML to organize your content and CSS to make that content look great.

■ Writing HTML for CSS

If you're new to web design, you may need some helpful hints to guide your forays into HTML (and to steer clear of well-intentioned, but out-of-date HTML techniques). Or if you've been building web pages for a while, you may have picked up a few bad HTML-writing habits that you're better off forgetting. The rest of this chapter introduces you to some HTML writing habits that will make your mother proud—and help you get the most out of CSS.

Think Structure

HTML adds meaning to text by logically dividing it and identifying the role that text plays on the page: For example, the `<h1>` tag is the most important introduction to a page's content. Other headers let you divide the content into other, less important, but related sections. Just like the book you're holding, for example, a web page should have a logical structure. Each chapter in this book has a title (think `<h1>`) and several sections (think `<h2>`), which in turn contain smaller subsections. Imagine how much harder it would be to read these pages if every word just ran together as one long paragraph.

NOTE

For a tutorial on HTML, visit www.w3schools.com/html/html_intro.asp. For a quick list of all available HTML tags, visit Sitepoint.com's HTML reference at <http://reference.sitepoint.com/html>.

HTML provides many other tags besides headers for *marking up* content to identify its role on the page. (After all, the M in HTML stands for *markup*.) Among the most popular are the `<p>` tag for paragraphs of text and the `` tag for creating bulleted (non-numbered) lists. Lesser-known tags can indicate very specific types of content, like `<abbr>` for abbreviations and `<code>` for computer code.

When writing HTML for CSS, use a tag that comes close to matching the role the content plays in the page, not the way it looks (see Figure 1-2). For example, a bunch of links in a navigation bar isn't really a headline, and it isn't a regular paragraph of text. It's most like a bulleted list of options, so the `` tag is a good choice. If you're saying, "But items in a bulleted list are stacked vertically one on top of the other, and I want a horizontal navigation bar where each link sits next to the previous link," don't worry. With CSS magic you can convert a vertical list of links into a stylish horizontal navigation bar as described in Chapter 9.


```
<p>
<strong>
<font color="#0066FF" size="5" face="Verdana,
Arial, Helvetica, sans-serif">Urban Agrarian
Lifestyle</font></strong>
<br />
<font color="#FF3300" size="4" face="Georgia,
Times New Roman, Times, serif">
<em>
<strong>A Revolution in Indoor Agriculture
<br /></strong></em></font>
Lorem ipsum dolor sit amet...</p>
```

The Urban Agrarian Lifestyle

A Revolution in Indoor Agriculture

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad minim veniam, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure.

```
<h1>The Urban Agrarian Lifestyle</h1>
<h2>A Revolution in Indoor Agriculture</h2>
<p>Lorem ipsum dolor sit amet...</p>
```

FIGURE 1-2

Old school, new school. Before CSS, designers had to resort to the tag and other extra HTML to achieve certain visual effects (top). You can achieve the same look (and often a better one) with a lot less HTML code (bottom). In addition, using CSS for formatting frees you up to write HTML that follows the logical structure of the page's content.

Two HTML Tags to Keep in Mind

HTML's motley assortment of tags doesn't cover the wide range of content you'll probably add to a page. Sure, <code> is great for marking up computer program code, but most folks would find a <recipe> tag handier. Too bad there isn't one. Fortunately, HTML provides two generic tags that let you better identify content, and, in the process, provide "handles" that let you attach CSS styles to different elements on a page.

UP TO SPEED

Simple HTML Is Search Engine Friendly

Once you take the mental leap of picturing HTML as the way to structure a document's content, and CSS as the tool for making that content look good, you'll discover additional benefits to writing lean, mean HTML. For one thing, you may boost your search-engine ranking as determined by sites like Google, Yahoo, and Bing. That's because when search engines crawl the Web, indexing the content on websites, they must go through *all* the HTML on a page to discover the actual content. The old HTML way of using special tags (like ``) and lots of tables to design a page gets in the way of a search engine's job. In fact, some search engines stop reading a page's HTML after a certain number of characters. When you use a lot of HTML just

for design, the search engine may miss important content on the page or even fail to rank it at all.

By contrast, simple, structured HTML is easy for a search engine to read and index. Using an `<h1>` tag to indicate the most important topic of the page (as opposed to just making the text big and bold) is smart strategy: Search engines give greater weight to the contents inside that tag while indexing the page.

To see Google's suggestions for building search-friendly websites, visit <http://support.google.com/webmasters/bin/answer.py?hl=en&answer=35769>.

■ UNDERSTANDING THE `<DIV>` AND `` TAGS

The `<div>` tag and the `` tag are like empty vessels that you fill with content. A `div` is a block, meaning it has a line break before it and after it, while a `span` appears inline, as part of a paragraph. Otherwise, `div`s and `span`s have no inherent visual properties, so you can use CSS to make them look any way you want. The `<div>` (for *division*) tag indicates any discrete block of content, much like a paragraph or a headline. But more often it's used to group any number of *other* elements, so you can insert a headline, a bunch of paragraphs, and a bulleted list inside a single `<div>` block. The `<div>` tag is a great way to subdivide a page into logical areas, like a banner, footer, sidebar, and so on. Using CSS, you can later position each area to create sophisticated page layouts (a topic that's covered in Part III of this book).

The `` tag is used for *inline* elements; that is, words or phrases that appear inside of a larger paragraph or heading. Treat it just like other inline HTML tags such as the `<a>` tag (for adding a link to some text in a paragraph) or the `` tag (for emphasizing a word in a paragraph). For example, you could use a `` tag to indicate the name of a company, and then use CSS to highlight the name by using a different font, color, and so on. Here's an example of those tags in action, complete with a sneak peek of a couple of attributes—`id` and `class`—frequently used to attach styles to parts of a page.

```
<div id="footer">
  <p>Copyright 2006, <span class="bizName">CosmoFarmer.com</span></p>
  <p>Call customer service at 555-555-5501 for more information</p>
</div>
```

This brief introduction isn't the last you'll see of these tags. They're used frequently in CSS-heavy web pages, and in this book you'll learn how to use them in combination with CSS to gain creative control over your web pages.

■ ADDITIONAL TAGS IN HTML5

The `<div>` tag is rather generic—it's simply a block-level element used to divide a page into sections. One of the goals of HTML5 is to provide other, more *semantic* tags for web designers to choose from. Making your HTML more semantic simply means using tags that accurately describe the content they contain. As mentioned earlier in this section, you should use the `<h1>` (heading 1) tag when placing text that describes the primary content of a page. Likewise, the `<code>` tag tells you clearly what kind of information is placed inside—programming code.

HTML5 includes many different tags whose names reflect the type of content they contain, and can be used in place of the `<div>` tag. The `<article>` tag, for example, is used to mark off a section of a page that contains a complete, independent composition...in other words, an “article” as in a blog post, an online magazine article, or simply the main text of the page. Likewise, the `<header>` tag indicates a header or banner, the top part of a page usually containing a logo, site-wide navigation, page title and tagline, and so on.

NOTE

To learn more about the new HTML tags, visit HTML5 Doctor (<http://html5doctor.com>) and www.w3schools.com/html/html5_intro.asp.

Many of the new HTML5 tags are intended to expand upon the generic `<div>` tag. Here are a few other HTML5 tags frequently used to structure the content on a page:

- The **`<section>`** tag contains a grouping of related content, such as the chapter of a book. For example, you could divide the content of a home page into three sections: one for an introduction to the site, one for contact information, and another for latest news.
- The **`<aside>`** tag holds content that is related to content around it. A sidebar in a print magazine, for example.
- The **`<footer>`** tag contains information you'd usually place in the footer of a page, such as a copyright notice, legal information, some site navigation links, and so on. You're not limited, however, to just a single `<footer>` per page; you can put a footer inside an `<article>`, for example, to hold information related to that article, like footnotes, references, or citations.
- The **`<nav>`** element is used to contain primary navigation links.
- The **`<figure>`** tag is used for an illustrative figure. You can place an `` tag inside it, as well as another new HTML5 tag—the `<figcaption>` tag, which is used to display a caption explaining the photo or illustration within the `<figure>`.

TIP Understanding which HTML5 tag to use—should your text be an `<article>` or a `<section>`?—can be tricky. For a handy flowchart that makes sense of HTML5’s new sectioning elements, download the PDF from the HTML5doctor.com at <http://html5doctor.com/downloads/h5d-sectioning-flowchart.pdf>.

There are other HTML5 elements, and many of them simply provide a more descriptive alternative to the `<div>` tag. This book uses both the `<div>` tag and the new HTML5 tags to help organize web-page content. The downside of HTML5 is that Internet Explorer 8 and earlier don’t recognize the new tags without a little bit of help (see the box below).

In addition, aside from feeling like you’re keeping up with the latest web design trends, there’s really no tangible benefit to using some of these HTML5 tags. For example, simply using the `<article>` tag to hold the main story on a web page, doesn’t make Google like you any better. You can comfortably continue using the `<div>` tag, and avoid the HTML5 sectioning elements if you like.

WORKAROUND WORKSHOP

Getting IE 8 to Understand HTML5

HTML5 provides many new HTML tags to play with. From tags that clearly describe the kind of content they hold, like the `<nav>` tag, to ones that provide added functionality, like the `<video>` tag for embedding videos and the `<audio>` tag for embedding sound and music. As you learn more about HTML5, you’ll probably start applying these new tags to your web pages.

Unfortunately, Internet Explorer 8 and earlier don’t recognize these new tags, and won’t respond to any CSS you apply to them. That’s right—if you’re using HTML5 and viewing web pages in IE 8, this book is useless to you. Well...not exactly. There is a way to kick those old versions of IE into gear, so they’ll understand all the CSS that applies to HTML5 tags.

Simply place the following code before the closing `</head>` tag at the top of your HTML file:

```
<!--[if lt IE 9]>
```

```
<script src="//html5shiv.googlecode.com/
svn/trunk/html5.js"></script>
<![endif]-->
```

This tricky bit of code uses what’s called an “Internet Explorer conditional comment” (IECC for short) to embed a bit of JavaScript code that’s only visible to versions of Internet Explorer earlier than IE 9. In other words, only IE 6, 7, and 8 respond to this code, and all other browsers (including newer versions of IE) simply ignore it. This code makes earlier versions of IE load a small JavaScript program that forces the browser to recognize HTML5 tags and apply the CSS that applies to those tags.

This code only affects how the browser displays and prints HTML5 tags; it doesn’t make the browser “understand” an HTML5 tag that actually does something. For example, IE 8 and earlier don’t understand the `<video>` tag and can’t play HTML5 video (even with the added JavaScript code).

Keep Your Layout in Mind

While you’ll use the `<h1>` tag to identify the main topic of the page and the `<p>` tag to add a paragraph of text, you’ll eventually want to organize a page’s content into a pleasing layout. As you learn how to use CSS to lay out a page in Part Three of this book, it doesn’t hurt to keep your design in mind while you write the page’s HTML.

You can think of web page layout as the artful arrangement of boxes (see Figure 1-3 for an example). After all, a two-column design consisting of two vertical columns of text is really just two rectangular boxes sitting side-by-side. A header consisting of a logo, tagline, search box, and site navigation is really just a wide rectangular box sitting across the top of the browser window. In other words, if you imagine the groupings and layout of content on a page, you'd see boxes sitting on top of one another, next to each other, and below each other.



FIGURE 1-3

This basic two-column layout includes a banner (top), a column of main content (middle, left), a sidebar (middle, right), and a footer (bottom). These are the main structural boxes making up this page's layout.

In your HTML, you create these boxes, or structural units, using the `<div>` tag. Simply wrap the HTML tags that make up the banner area, for example, in one div, a column's worth of HTML in another, and so on. If you're HTML5 savvy, you might create the design pictured in Figure 1-3, with a `<header>` tag for the top banner, an `<article>` tag for the main text, an `<aside>` or `<section>` tag for the sidebar, and a `<footer>` tag for the page's footer. In other words, if you plan to place a group of HTML tags together, somewhere on a page, then you'll need to wrap those tags in a sectioning element like a `<div>`, `<article>`, `<section>`, or `<aside>`.

HTML to Forget

CSS lets you write simpler HTML for one big reason: You can stop using a bunch of tags and attributes that only make a page better looking. The `` tag is the most glaring example. Its sole purpose is to add a color, size and font to text. It doesn't do anything to make the structure of the page more understandable.

Here's a list of tags and attributes you can easily replace with CSS:

- **Ditch `` for controlling the display of text.** CSS does a much better job with text. (See Chapter 6 for text-formatting techniques.)
- **Don't use the `` and `<i>` tags to emphasize text.** If you want text to really be emphasized, use the `` tag, which browsers normally display as bold. For a slightly less emphatic point, use the `` tag, which browsers display as italic.

While HTML4 tried to phase the `` and `<i>` tags out, HTML5 has brought them back. In HTML5 the `` tag is meant to merely make text bold without adding any meaning to that text (that is, you just want the text to be bold looking but you don't want people to treat that text like you're shouting it). Likewise, the `<i>` tag is used for italicizing text, but not emphasizing its meaning.

NOTE

To italicize a publication's title, the `<cite>` tag kills two birds with one stone. It puts the title in *italics* and tags it as a cited work for search engines' benefit. This one's a keeper.

- **Skip the `<table>` tag for page layout.** Use it only to display tabular information like spreadsheets, schedules, and charts. As you'll see in Part Three of this book, you can do all your layout with CSS for much less time and code than the table-tag tango.
- **Avoid the awkward `<body>` tag attributes** that enhance only the presentation of the content: `background`, `bgcolor`, `text`, `link`, `alink`, and `vlink` set colors and images for the page, text, and links. CSS gets the job done better (see Chapter 7 and Chapter 8 for CSS equivalents of these attributes).
- **Don't abuse the `
` tag.** If you grew up using the `
` tag (`
` in XHTML) to insert a line break without creating a new paragraph, then you're in for a treat. (Browsers automatically—and sometimes infuriatingly—insert a bit of space between paragraphs, including between headers and `<p>` tags. In the past, designers used elaborate workarounds to avoid paragraph spacing they didn't want, like replacing a single `<p>` tag with a bunch of line breaks and using a `` tag to make the first line of the paragraph *look like* a headline.) Using CSS's margin controls, you can easily set the amount of space you want to see between paragraphs, headers, and other block-level elements.

NOTE In the next chapter, you'll learn about a technique called a "CSS Reset," which eliminates the gaps browsers normally insert between paragraphs and other tags (see page 115).

As a general rule, adding attributes to tags that set colors, borders, background images, or alignment—including attributes that let you format a table's colors, backgrounds, and borders—is pure old-school HTML. So is using alignment properties to position images and center text in paragraphs and table cells. Instead, look to CSS to control text placement (page 169), borders (page 202), backgrounds (page 206), and image alignment (page 239).

UP TO SPEED

Validate Your Web Pages

HTML follows certain rules: For example, the `<html>` tag wraps around the other tags on a page, and the `<title>` tag needs to appear within the `<head>` tag. XHTML provides an even more strict set of rules to follow, while HTML5 is a bit more lax. It's easy to forget these rules or simply make a typo. Incorrect (or *invalid*, as the geeks would say) HTML causes problems like making your page look different in different web browsers. More importantly, even valid CSS may not work as expected with invalid HTML. Fortunately, there are tools for checking whether the HTML in your web pages is correctly written.

The easiest way to check—that is, *validate*—your pages is on the W3C's website at <http://validator.w3.org> (see Figure 1-4). Get the Web Developer extension for Firefox (<http://chrispederick.com/work/web-developer>); it provides a quick way to test a page in the W3C validator.

The W3C, or World Wide Web Consortium, is the organization responsible for determining the standards for many of the technologies and languages of the Web, including HTML and CSS. If the W3C validator finds any errors in your page, it tells you what those errors are. If you use Firefox, you can download an extension that lets you validate a web page directly in that browser, without having to visit the W3C site. It can even attempt to fix any problems it encounters. You can get the extension here: <http://users.skynet.be/mgueury/mozilla/>. Chrome users can download the HTML Tidy extension for Chrome from <http://bit.ly/SCONRY>. A similar tool is available for the Safari browser as well: www.zappatic.net/safaritidy.




FIGURE 1-4
The W3C HTML validator located at <http://validator.w3.org> lets you quickly make sure the HTML in a page is sound. You can point the validator to an already existing page on the Web, upload an HTML file from your computer, or just paste the HTML of a web page into a form box and then click the Check button.

Tips to Guide Your Way

It's always good to have a map for getting the lay of the land. If you're still not sure how to use HTML to create well-structured web pages, then here are a few tips to get you started:

- Use headings to indicate the relative importance of text. Again, think outline. When two headings have equal importance in the topic of your page, use the same level header on both. If one is less important or a subtopic of the other, then use the next level header. For example, follow an `<h2>` with an `<h3>` tag (see Figure 1-5). In general, it's good to use headings in order and try not to skip heading numbers. For example, don't follow an `<h2>` tag with an `<h5>` tag.




FIGURE 1-5

Use the headline tags (<h1>, <h2>, and so on) as you would if you were outlining a school report: Put them in order of importance, beginning with an <h1> tag, which should shout “Listen up! This is what this whole page is about.”

- Use the **<p>** tag for paragraphs of text.
- Use unordered lists (****) when you’ve got a list of several related items, such as navigation links, headlines, or a set of tips like these.
- Use numbered lists (****) to indicate steps in a process or define the order of a set of items. The tutorials in this book are a good example, as is a list of rankings like “Top 10 websites popular with monks.”
- To create a glossary of terms and their definitions or descriptions, use the **<dl>** (definition list) tag in conjunction with the **<dt>** (definition term) and **<dd>** (definition description) tags. (For an example of how to use this combo, visit www.w3schools.com/tags/tryit.asp?filename=tryhtml_list_definition.)
- If you want to include a quotation like a snippet of text from another website, a movie review, or just some wise saying of your grandfather’s, try the **<blockquote>** tag for long passages or the **<q>** tag to place a short quote within a longer paragraph, like this:


```
<p>Mark Twain is said to have written <q>The coldest winter I ever spent was a summer in San Francisco</q>. Unfortunately, he never actually wrote that famous quote.</p>
```
- Take advantage of obscure tags like the **<cite>** tag for referencing a book title, newspaper article, or website, and the **<address>** tag to identify and supply contact information for the author of a page (great for a copyright notice).

- As explained in full on page 26, steer clear of any tag or attribute aimed just at changing the appearance of a text or image. CSS, as you'll see, can do it all.
- When there just isn't an HTML tag that fits the bill, but you want to identify an element on a page or a bunch of elements on a page so you can apply a distinctive look, use the `<div>` and `` tags (see page 21). You'll get more advice on how to use these in later chapters.
- Don't overuse `<div>` tags. Some web designers think all they need are `<div>` tags, ignoring tags that might be more appropriate. For example, to create a navigation bar, you could add a `<div>` tag to a page and fill it with a bunch of links. A better approach would be to use a bulleted list (`` tag). After all, a navigation bar is really just a list of links. As discussed on page 23, HTML5 provides several new tags that can take the place of the `<div>` tag, like the `<article>`, `<section>`, and `<footer>` tags. For a navigation bar, you could use the HTML5 `<nav>` tag.
- Remember to close tags. The opening `<p>` tag needs its partner in crime (the closing `</p>` tag), as do all other tags, except the few self-closers like `
` and `` (`
` and `` in XHTML).
- Validate your pages with the W3C validator (see Figure 1-4 and the box on page 27). Poorly written or typo-ridden HTML causes many weird browser errors.

■ The Importance of the Doctype

HTML follows certain rules—these rules are contained in a *Document Type Definition* file, otherwise known as a DTD. A DTD is a text file that explains what tags, attributes, and values are valid for a particular type of HTML. And for each version of HTML, there's a corresponding DTD. By now you may be asking, “But what's all this got to do with CSS?”

Everything—if you want your web pages to appear correctly and consistently in web browsers. You tell a web browser which version of HTML or XHTML you're using by including what's called a *doctype declaration* at the beginning of a web page. This doctype declaration is the first line in the HTML file, and defines what version of HTML you're using (such as HTML5 or HTML 4.01 Transitional). When you mistype the doctype declaration or leave it out, you can throw most browsers into an altered state called *quirks mode*.

Quirks mode is browser manufacturers' attempt to make their software behave like browsers did circa 1999 (in the Netscape 4 and Internet Explorer 5 days). If a modern browser encounters a page that's missing the correct doctype, then it thinks, “Gee, this page must have been written a long time ago, in an HTML editor far, far away. I'll pretend I'm a really old browser and display the page just as one of those

buggy old browsers would display it.” That’s why, without a correct doctype, your lovingly CSS-styled web pages may not look as they should, according to current standards. If you unwittingly view your web page in quirks mode when checking it in a browser, you may end up trying to fix display problems that are related to an incorrect doctype and not the incorrect use of HTML or CSS.

NOTE For more (read: technical) information on quirks mode, visit www.quirksmode.org/css/quirksmode.html and https://developer.mozilla.org/en/Mozilla%2527s_Quirks_Mode.

Fortunately, it’s easy to get the doctype correct. All you need to know is what version of HTML you’re using. If you’re using HTML5, things are easy. The doctype is simply:

```
<!doctype html>
```

Put this at the top of your HTML file and you’re good to go. If you’re still using older versions of HTML or XHTML such as HTML 4.01 Transitional and XHTML 1.0 Transitional, then the doctype is a lot more convoluted.

If you’re using HTML 4.01 Transitional, for example, type the following doctype declaration at the very beginning of every page you create:

```
<!DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN" "http://www.w3.org/TR/html4/loose.dtd">
```

The doctype declaration for XHTML 1.0 Transitional is similar. It’s also necessary to add a little code to the opening `<html>` tag that’s used to identify the file’s XML type—in this case, it’s XHTML—like this:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN" "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml">
```

If this entire discussion is making your head ache and your eyes slowly shut, keep your life simple by using the HTML5 doctype. It’s short, easy to remember, and works in all browsers. You can use this doctype even if you don’t touch any of the new HTML5 tags.

NOTE Most visual web page tools like Dreamweaver and Expression Web automatically add a doctype declaration whenever you create a new web page, and many HTML-savvy text editors have shortcuts for adding doctypes.

FREQUENTLY ASKED QUESTION

Should I Care About IE 6, 7, or 8?

I keep hearing that Internet Explorer 6 is dead and we don't need to worry about it anymore. Is this true? What about other versions of IE?

If you're a web designer, you've probably got the latest version of Internet Explorer, Firefox, Safari, Chrome, or Opera on your computer. Previous versions of this book talked quite a bit about Internet Explorer 6 and even provided a section on how to deal with IE 6 bugs. That's all been removed, since IE 6 is rapidly disappearing.

If you're building sites with a US audience in mind, as of August 2012, less than .6 percent of US web surfers use that outdated browser; in the UK, it's 1.1%. The exact figure varies depending on whom you ask (for example, <http://gs.statcounter.com> has worldwide IE 6 usage at .57 percent and www.ie6countdown.com says it's at 6 percent as of August 2012). In China, IE 6 is still widely used.

However, even statistics that include the geographic region of your site's audience don't truly reflect what visitors to your site use. If you build a site aimed at tech-savvy web designers, odds are that IE 6 hasn't been to your site in a long time. However, if your site's aimed at people in China, you may need to deal with IE 6. The best way to find out how much of your traffic comes via IE 6 is to look at your web server's log files or sign

up for Google Analytics (www.google.com/analytics) so you can track your visitors' browsers (among many other things).

For the great majority of web design projects, IE 6 is effectively gone. In addition, IE 7 is also rapidly disappearing, with just 1.16 percent worldwide market share as of August 2012 (http://gs.statcounter.com/#browser_version-ww-monthly-201108-201208).

IE 8, however, you still need to contend with. Windows XP is still a popular operating system, and Microsoft chose not to bring Internet Explorer 9 or later to that operating system. So as long as XP is around, Internet Explorer 8 will be around, too. (To keep up with advances in web development, XP users can switch to Chrome or Firefox.) According to StatCounter, in August 2012, IE 8 accounted for 13.65 percent of all web browsers (http://gs.statcounter.com/#browser_version-ww-monthly-201108-201208). According to NetMarketShare, IE 8 accounts for a whopping 26 percent of web browsers (<http://marketshare.hitslink.com/browser-market-share.aspx?qprid=2&qpcustomid=0>). Since IE 8 doesn't understand HTML5 tags, you can't directly format them with CSS either—you have to turn to a JavaScript workaround as described in the box on page 24.

■ Making Sure Internet Explorer Is Up-to-Date

Thanks to Microsoft's auto-update feature, Windows PCs now update Internet Explorer to the latest version. Windows 7 and 8 users have the latest version of Internet Explorer installed—IE 10 at the time of this writing. IE 10 supports many of the exciting and powerful new HTML5 and CSS3 properties. As you'll learn in this book, CSS3 provides many exciting design possibilities like drop shadows (page 210), gradient backgrounds (page 259), and rounded corners (page 207), to name a few.

Unfortunately, not all Windows users will be able to take advantage of these advancements in web design. As explained in the box on page 32, the widely used Windows XP operating system can run only Internet Explorer 8 or earlier. In fact, IE 8 is still the most common version of Internet Explorer used on the Web. This book will point out CSS properties that won't work in IE 8, as well as possible workarounds.

Because IE 8 is still very popular, you need to keep a couple of things in mind. IE 8 is sort of like a chameleon: It can take on the appearance of a different version. If you're not careful, it may not display your web pages the way you want it to. For example, and most importantly, you must include a proper doctype. As mentioned in the previous section, without a doctype, browsers switch into quirks mode. Well, when IE 8 goes into quirks mode, it tries to replicate the look of IE 5 (!?).

But wait—there's more! IE 8 can also pretend to be IE 7. When someone viewing your site in IE 8 clicks a "compatibility view" button, IE 8 goes into IE 7 mode, displaying pages without IE 8's full CSS 2.1 goodness. The same thing happens if Microsoft puts your website onto its Compatibility View List—a list of sites that Microsoft has determined look better in IE 7 than in IE 8. If you're designing a site using the guidelines in this book, you won't want IE 8 to act like IE 7...ever.

Fortunately, there's a way to tell IE 8 to stop all this nonsense and just be IE 8. Adding a single META tag to a web page instructs IE 8 to ignore Compatibility View and the Compatibility View List and always display the page by using its most standards-compliant mode:

```
<meta http-equiv="X-UA-Compatible" content="IE=edge" />
```

Put this instruction in the page's <head> section (below the <title> tag is a good place). This tag works for current versions of IE, too: The "IE=edge" part of the tag will instruct versions of Internet Explorer later than IE 8 to also display web pages in their standard mode. Unfortunately, you must do this on every page of your site.

Now that your HTML ship is steering in the right direction, it's time to jump into the fun stuff (and the reason you bought this book): Cascading Style Sheets.

UP TO SPEED

Cross-Browser Testing

There are a lot of web browsers out there. If you use Windows, you automatically get Internet Explorer and can install additional browsers like Firefox, Safari, Opera, or Google's Chrome. On a Mac, you can stick with the already-installed Safari browser, or run Firefox or Chrome. While the very latest browsers are mostly comparable when displaying CSS-driven web pages, you can't say the same for IE 8, which is still in widespread use.

To really make sure your sites work for the largest audience, you need a way to test your designs in as wide a range of browsers as possible. Here are a few techniques:

Windows. Normally, Windows computers can only run one version of IE—you can't test in IE 6, IE 7, and IE 8 on the same computer. Well, normally you can't, but *you* can if you run *virtual machines* on your Windows computer to create completely separate versions of Internet Explorer that you can then test in. It's a fair amount of work, but it gives you the most accurate way of testing a page in multiple versions of IE. Visit www.howtogeek.com/102261/how-to-run-internet-explorer-7-8-and-9-at-the-same-time-using-virtual-machines to learn more about how to do this.

You should also install the other major browsers on your computer: Firefox, Opera, and Chrome. Apple has discontinued Safari for Windows, so you can simply rely on Chrome (which has a similar underlying rendering engine) or use one of the services listed later in this box (like Adobe Browserlab) to test your designs in Safari.

Mac. Testing is a bit trickier for Mac people. You *have* to test in Internet Explorer—it's still one of the most used browsers in the world, and the lack of most CSS3 properties in IE 8 means that your painstakingly crafted design might look great for you, but fall apart in IE 8. You have a few options: First, you can buy (or borrow) a Windows machine; second, if you have an Intel Mac, you can install Windows using Apple's Boot Camp software (www.apple.com/macosx/features/bootcamp.html); a third option is to install virtualization software like VMware Fusion or Parallels Desktop on your Mac. This software lets you run a virtual Windows machine side-by-side with the Mac OS. You can jump between Mac and Windows to test in various browsers in

both operating systems. It's the most efficient testing technique for Mac users. Both Boot Camp and virtualization software require a copy of the Windows OS.

Everyone. Another option that works for both Windows and Macs and doesn't require installing extra software is one of the many cross-browser testing services that let you see what your pages look like in many different operating systems and browsers.

- **CrossBrowserTesting.com** (<http://CrossBrowserTesting.com>) is \$30 a month (ouch) for 150 minutes of use and offers an added benefit—interactive testing. You get to see your page running remotely on a PC under your control—you can test features that a screenshot can't capture, like Flash movie playback, animation, and JavaScript interactions.
- **BrowserStack** (www.browserstack.com) is another service that lets you test your pages interactively via your web browser. For \$19 a month, it's like renting multiple Windows and Mac machines with multiple versions of IE, Chrome, Firefox, and Safari installed.
- **Browsershots** (www.browsershots.org) is a free alternative that provides screenshots for a wide range of browsers on Windows and Linux.
- You can also see what a page looks like in IE 9, 8 7, 6, and even 5.5 for free with **NetRenderer** (<http://ipinfo.info/netrenderer>), though. You need to have the pages you want to test up on a publicly accessible website. Visit <http://ipinfo.info/netrenderer>, type the URL of the page, and in a few moments you'll see a screen shot. Unfortunately, it doesn't take a picture of a complete web page—just the top part that you'd normally see on a screen. On the other hand, it's free.
- Finally, you can use Adobe's **BrowserLab** tool (<https://browserlab.adobe.com>) to get snapshots of a web page in all major browsers. If you use Dreamweaver to build sites, for example, you can launch BrowserLab from within the program and preview the page you're currently working on.

Creating Styles and Style Sheets

Even the most complex and beautiful websites, like the one in Figure 2-1, start with a single CSS style. As you add multiple styles and style sheets, you can develop fully formed websites that inspire designers and amaze visitors. Whether you're a CSS novice or a Style Sheet Samurai, you need to obey a few basic rules about how to create styles and style sheets. In this chapter, you'll start at square one, learning the basics of creating and using styles and style sheets.

TIP

Some people learn better by doing rather than reading. If you'd like to try your hand at creating styles and style sheets first and then come back here to read up on what you just did, turn to page 43 for a hands-on tutorial.

■ Anatomy of a Style

A single style defining the look of one element on a page is a pretty basic beast. It's essentially just a rule that tells a web browser how to format something on a web page—turn a headline blue, draw a red border around a photo, or create a 150-pixel-wide sidebar box to hold a list of links. If a style could talk, it would say something like, “Hey Browser, make *this* look like *that*.” A style is, in fact, made up of two elements: the web page element that the browser formats (the *selector*) and the actual formatting instructions (the *declaration block*). For example, a selector can be a headline, a paragraph of text, a photo, and so on. Declaration blocks can turn that text blue, add a red border around a paragraph, position the photo in the center of the page—the possibilities are endless.




FIGURE 2-1

Every CSS-driven web page starts with a single CSS style. Here, a basic style (bottom) sets the groundwork for the body of the entire page (top).

```
body{
width: 896px;
height: 100%;
min-height: 100%;
margin: 0 auto;
padding: 50px 48px 0;
line-height: 1;
color: #333;
background: #FFF;
font-family: ff-tisa-web-pro, Georgia, sans-serif;
-webkit-text-size-adjust: 100%;
}
```

NOTE

Technical types often follow the lead of the W3C and call CSS styles *rules*. This book uses the terms “style” and “rule” interchangeably.

Of course, CSS styles can't communicate in nice clear English like the previous paragraph. They have their own language. For example, to set a standard font color and font size for all paragraphs on a web page, you'd write the following:

```
p { color: red; font-size: 1.5em; }
```

This style simply says, "Make the text in all paragraphs—marked with `<p>` tags—red and 1.5 ems tall." (An *em* is a unit of measurement that's based on a browser's normal text size. More on that in Chapter 6.) As Figure 2-2 illustrates, even a simple style like this example contains several elements:

- **Selector.** As described earlier, the selector tells a web browser which element or elements on a page to style—like a headline, paragraph, image, or link. In Figure 2-2, the `p` selector refers to the `<p>` tag. This selector makes web browsers format all `<p>` tags by using the formatting directions in this style. With the wide range of selectors that CSS offers and a little creativity, you'll master your pages' formatting. (The next chapter covers selectors in depth.)
- **Declaration Block.** The code following the selector includes all the formatting options you want to apply to the selector. The block begins with an opening brace (`{`) and ends with a closing brace (`}`).
- **Declaration.** Between the opening and closing braces of a declaration block, you add one or more *declarations*, or formatting instructions. Every declaration has two parts, a *property* and a *value*. A colon separates the property name and its value, and the whole declaration ends with a semicolon.
- **Property.** CSS offers a wide range of formatting options, called *properties*. A property is a word—or a few hyphenated words—indicating a certain style effect. Most properties have straightforward names like `font-size`, `margin-top`, and `text-align`. For example, the `background-color` property sets—you guessed it—a background color. You'll learn about oodles of CSS properties throughout this book. You must add a colon after the property name to separate it from the value.

TIP

Appendix A has a handy glossary of CSS properties.

- **Value.** Finally, you get to express your creative genius by assigning a *value* to a CSS property—by making a background blue, red, purple, or chartreuse, for example. As upcoming chapters explain, different CSS properties require specific types of values—a color (like `red`, or `#FF0000`), a length (like `18px`, `200%`, or `5em`), a URL (like `images/background.gif`), or a specific keyword (like `top`, `center`, or `bottom`).




FIGURE 2-2
A style (or rule) is made of two main parts: a selector, which tells web browsers what to format, and a declaration block, which lists the formatting instructions that the browsers use to style the selector.

You don't need to write a style on a single line, as pictured in Figure 2-2. Many styles have multiple formatting properties, so you can make them easier to read by breaking them up into multiple lines. For example, you may want to put the selector and opening brace on the first line, each declaration on its own line, and the closing brace by itself on the last line, like so:

```
p {
    color: red;
    font-size: 1.5em;
}
```

Web browsers ignore spaces and tabs, so feel free to add them to make your CSS more readable. For example, it's helpful to indent properties, with either a tab or a couple of spaces, to visibly separate the selector from the declarations, making it easy to tell which is which. In addition, putting one space between the colon and the property value is optional but adds to the readability of the style. In fact, you can put as much white space between the two as you want. For example, `color:red`, `color: red`, and `color : red` all work.

NOTE Don't forget to end each property/value pair with a semicolon:

```
color: red;
```

Leaving off that semicolon can trip up browsers, breaking your style sheet and ruining the look of your web page. Don't worry, this mistake is very common—just make sure you use a CSS validator, as described in the box on page 41.

■ Understanding Style Sheets

Of course, a single style won't transform a web page into a work of art. It may make your paragraphs red, but to infuse your websites with great design, you need many different styles. A collection of CSS styles comprises a *style sheet*. A style sheet can be one of two types—*internal* or *external*, depending on whether the style information is located in the web page itself or in a separate file linked to the web page.

Internal or External—How to Choose

Most of the time, external style sheets are the way to go, since they make building web pages easier and updating websites faster. An external style sheet collects all your style information in a single file that you then link to a web page with just a single line of code. You can attach the same external style sheet to every page in your website, providing a unified design. It also makes a complete site makeover as easy as editing a single text file.

On the receiving end, external style sheets help web pages load faster. When you use an external style sheet, your web pages can contain only basic HTML—no byte-hogging HTML tables or `` tags and no internal CSS style code. Furthermore, when a web browser downloads an external style sheet, it stores the file on your visitor's computer (in a behind-the-scenes folder called a *cache*) for quick access. When your visitor hops to other pages on the site that use the same external style sheet, there's no need for the browser to download the style sheet again. The browser simply downloads the requested HTML file and pulls the external style sheet from its cache—a significant savings in download time.

NOTE

When you're working on your website and previewing it in a browser, the cache can work against you. See the box below for a workaround.

WORKAROUND WORKSHOP

Don't Get Caught in the Cache

A browser's cache is a great speed-boost for Web surfers. Whenever the cache downloads and stores a frequently used file—like an external CSS file or an image—it saves precious moments traveling the highways of the Internet. Instead of re-downloading the next time it needs the same file, the browser can go straight to the new stuff—like a yet-to-be-viewed page or graphic.

But what's good for your visitors isn't always good for you. Because the web browser caches and recalls downloaded external CSS files, you can often get tripped up as you work on a site design. Say you're working on a page that uses an external style sheet, and you preview the page in a browser. Something doesn't look quite right, so you return to your web

editor and change the external CSS file. When you return to the web browser and reload the page, the change you just made doesn't appear! You've just been caught by the cache. When you reload a web page, browsers don't always reload the external style sheet, so you may not be seeing the latest and greatest version of your styles.

To get around this snafu, you can *force reload* a page (which also reloads all linked files) by pressing the Ctrl (⌘) key and clicking the browser's Reload button; Ctrl+F5 also works for Chrome and Internet Explorer; Ctrl+Shift+R (⌘-Shift-R) is Firefox's keyboard shortcut; and Ctrl+R (⌘-R) works for both Safari and Chrome.

Internal Style Sheets

An internal style sheet is a collection of styles that's part of the web page's code. It always appears between opening and closing HTML `<style>` tags in the page's `<head>` portion. Here's an example:

```
<style>
h1 {
  color: #FF7643;
  font-family: Arial;
}
p {
  color: red;
  font-size: 1.5em;
}
</style>
</head>
<body>

<!-- The rest of your page follows... -->
```

NOTE You can place the `<style>` tag and its styles after the `<title>` tag in the head of the page, but web designers usually place them right before the closing `</head>` tag as shown here. If you also use JavaScript in your pages, add the JavaScript code *after* the style sheet. Many JavaScript programs rely on CSS, so by adding your CSS first, you can make sure the JavaScript program has all the information it needs to get its job done.

The `<style>` tag is HTML, not CSS. But its job is to tell the web browser that the information contained within the tags is CSS code and not HTML. Creating an internal style sheet is as simple as typing one or more styles between the `<style>` tags.

NOTE HTML5 simply requires `<style>` for the opening tag of an internal style sheet. Earlier versions of HTML and XHTML require an additional attribute on the opening `<style>` tag:

```
<style type="text/css">
```

If you leave that attribute off a non-HTML5 page, you'll get an error if you try to validate the web page. Yet another reason to use HTML5.

Internal style sheets are easy to add to a web page and provide an immediate visual boost to your HTML. But they aren't the most efficient method for designing an entire website composed of many web pages. For one thing, you need to copy and paste the internal style sheet into each page of your site—a time-consuming chore that adds bandwidth-hogging code to each page.

But internal style sheets are even more of a hassle when you want to update the look of a site. For example, say you want to change the `<h1>` tag, which you originally decided should appear as large, green, bold type. But now you want small,

blue type in the Courier typeface. Using internal style sheets, you'd need to edit every page. Who has that kind of time? Fortunately, there's a simple solution to this dilemma—external style sheets.

NOTE

It's also possible (though rarely advisable) to add styling information to an individual HTML tag without using a style sheet. The tutorial on page 44 shows you how to perform that maneuver by using an *inline* style.

External Style Sheets

An external style sheet is nothing more than a text file containing all your CSS rules. It never contains any HTML code—so don't include the `<style>` tag. In addition, always end the file name with the extension `.css`. You can name the file whatever you like, but it pays to be descriptive. Use *global.css*, *site.css*, or, simply, *styles.css*, for example, to indicate a style sheet used by every page on the site, or use *form.css* to name a file containing styles used to make a web form look good.

UP TO SPEED

Validate Your CSS

Just as you should make sure you've correctly written the HTML in your web pages using the W3C HTML validator (see the box on page 27), you should also check your CSS code to make sure it's kosher. The W3C provides an online tool for CSS checking as well: <http://jigsaw.w3.org/css-validator>. It operates just like the HTML validator: You can type the URL of a web page (or even just the address to an external CSS file), upload a CSS file, or copy and paste CSS code into a web form and submit it for validation.

It's easy to make a typo when writing CSS, and one small mistake can throw all of your carefully planned designs out of whack. When your CSS-infused web page doesn't look as you expect, a simple CSS error may be the cause. The W3C CSS validator is a good first stop when troubleshooting your designs.

TIP

If you have a page with an internal style sheet but want to use an external style sheet, then just cut all of the code between the `<style>` tags (without the tags themselves). Then create a new text file and paste the CSS into the file. Save the file with a `.css` extension—*styles.css*, for example—and link it to your page, using one of the techniques described next.

Once you create an external style sheet, you must connect it to the web page you wish to format. You can attach a style sheet to a web page using HTML's `<link>` tag or CSS's own `@import` directive—a command that basically does the same thing as the link tag. All current web browsers treat these two techniques the same, and both let you attach style sheets to a web page, so choosing one is mostly a matter of preference.

NOTE The `@import` directive can do one thing the `<link>` tag can't: attach external style sheets to an external style sheet. This advanced technique is discussed at the bottom of this page.

Linking a Style Sheet by Using HTML

The most common method of adding an external style sheet to a web page is to use the HTML `<link>` tag. You write the tag slightly differently depending on whether you're using HTML5, HTML 4.01, or XHTML. For example, here's HTML5:

```
<link rel="stylesheet" href="css/styles.css">
```

HTML 4.01 is similar, but requires an additional `type` attribute:

```
<link rel="stylesheet" type="text/css" href="css/styles.css">
```

Finally, XHTML is just like HTML 4.01, but it requires a closing slash at the end of the tag:

```
<link rel="stylesheet" type="text/css" href="css/styles.css" />
```

Because HTML5 requires less code, we'd recommend that you use HTML5. All doc-types require two attributes:

- **rel="stylesheet"** indicates the type of link—in this case, a link to a style sheet.
- **href** points to the location of the external CSS file on the site. The value of this property is a URL and will vary depending on where you keep your CSS file. It works the same as the **src** attribute you use when adding an image to a page or the **href** attribute of a link pointing to another page.

TIP You can attach multiple style sheets to a web page by adding multiple `<link>` tags, each pointing to a different style sheet file. This technique is a great way to organize your CSS styles, as you can see in Chapter 15.

Linking a Style Sheet by Using CSS

CSS includes a built-in way to add external style sheets—the `@import` directive. You add the directive inside of an HTML `<style>` tag, like so:

```
<style>  
    @import url(css/styles.css);  
</style>
```

NOTE If you're using an HTML 4.01 or XHTML doctype, then you need to add `type="text/css"` to the opening `<style>` tag. See the note on page 40.

Unlike HTML's `<link>` tag, `@import` is part of the CSS language and has some definite un-HTML-like qualities:

- To make the connection to the external CSS file, you use `url` instead of `href` and enclose the path in parentheses. So in this example, `css/styles.css` is the path to the external CSS file. Quotes around the URL are optional, so `url(css/styles.css)` and `url("css/styles.css")` both work.
- As with the `<link>` tag, you can include multiple external style sheets by using more than one `@import`:

```
<style type="text/css">  
  @import url(css/styles.css);  
  @import url(css/form.css);  
</style>
```

- You can add regular CSS styles after the `@import` directives if you want to create a rule that applies just to that one page, but still use the site's global design rules to format the rest of the page.

NOTE

You'll learn how rules interact and how you can create a rule that overrides other rules on page 113. You can even create an external CSS file that contains only `@import` directives linking to *other* external style sheets, a technique often used to help organize your styles (see page 547).

Here's an example:

```
<style>  
  @import url(css/styles.css);  
  @import url(css/form.css);  
  p { color:red; }  
</style>
```

You must place all the `@import` lines *before* any CSS rules, as shown here. Web browsers ignore any style sheets you import after a CSS rule, so if you reversed the order of the code above and had the `p` style appear first, then the browser ignores any styles in `style.css` or `form.css` style sheets.

Which to use? Although both methods work, the `<link>` tag is more common. In a few cases, using the `@import` technique can slow your style sheets' download speed (visit www.stevesouders.com/blog/2009/04/09/dont-use-import to find out when this can happen and why). So, if you don't have a strong preference for either, just use the `<link>` method.

Tutorial: Creating Your First Styles

The rest of this chapter takes you through the basic steps for adding inline styles, writing CSS rules, and creating internal and external style sheets. As you work through this book, you'll work through various CSS designs, from simple design elements to complete CSS-enabled web page layouts. To get started, download the tutorial

files located on the book's companion website at www.sawmac.com/css3. Click the tutorial link and download the zip archive containing the files. Each chapter's files are in a separate folder, named *02* (for Chapter 2), *03* (for Chapter 3), and so on.

Next, launch your favorite web page-editing software, whether it's a simple text editor, like Notepad or TextEdit, or a visually oriented program, like Dreamweaver or Microsoft Expression Web (for information on selecting an editor, see page 7).

Creating an Inline Style

When you type a CSS rule directly into a page's HTML, you're creating an *inline* style. Inline styles offer none of the time- and bandwidth-saving benefits of style sheets, so the pros hardly ever use them. Still, in a pinch, if you absolutely must change the styling on a single element on a single page, then you may want to resort to an inline style. (For example, when creating HTML-formatted email messages, it's best to use inline styles. That's the only way to get CSS to work in Gmail, for instance.) And if you do, you at least want the style to work properly. The important thing is to carefully place the style within the tag you want to format. Here's an example that shows you exactly how to do it:

1. In your web page-editing program, open the file *02*→*basic.html*.

This simple-but-elegant HTML5 file contains a couple of different headings, a few paragraphs, and a copyright notice inside an `<address>` tag. You'll start by creating an inline style for the `<h1>` tag.

2. Click inside the opening `<h1>` tag and type `style="color: #666666;"`.

The tag should look like this:

```
<h1 style="color: #666666;">
```

The style attribute is HTML, not CSS, so you use the equal sign after it and enclose all of the CSS code inside quotes. Only the stuff inside the quotes is CSS. In this case, you've added a property named `color`—which affects the color of text—and you've set that property to `#666666` (a hexadecimal code for defining a color that's gray). You'll learn more about coloring text on page 154. The colon separates the property name from the property value that you want. Next you'll check the results in a web browser.

3. Open the *basic.html* page in a web browser.

For example, start up your favorite web browser and choose File→Open File (or press Ctrl+O [⌘-O] and select the *basic.html* file in the *02 tutorial* folder from your computer; or just drag the file from the desktop—or wherever you've saved the tutorial files—into an open browser window). Many HTML editors also

include a “Preview in Browser” function, which, with a simple keyboard shortcut or menu option, opens the page in a web browser. It’s worth checking your program’s manual to see if it includes this timesaving feature.

When you view the page in a browser, the headline is now gray. Inline styles can include more than one CSS property. You’ll add another property next.

4. Return to your HTML editor, click after the semicolon following #666666, and type font-size: 3em;

The semicolon separates two different property settings. The <h1> tag should look like this:

```
<h1 style="color: #666666; font-size: 3em;">
```

5. Preview the page in a web browser. For example, click your browser window’s Reload button (but make sure you’ve saved the HTML file first).

The headline is now massive in size. And you’ve had a taste of how labor-intensive inline styles are. Making all the <h1> headings on a page look like this one could take days of typing and add acres of HTML code.

6. Return to your page editor and delete the entire style property, which returns the heading tag back to its normal <h1>.

Next, you’ll create a style sheet within a web page. (You’ll find a finished version of this part of the tutorial in the *02_finished* folder in a file named *inline.html*.)

Creating an Internal Style Sheet

A better approach than inline styles is using a style sheet that contains multiple CSS rules to control multiple elements of a page. In this section, you’ll create a style that affects all top-level headings in one fell swoop. This single rule automatically formats every <h1> tag on the page.

1. With the file *basic.html* open in your text editor, click directly after the closing </title> tag. Then hit Enter (Return) and type <style>.

The HTML should now look like the following (the stuff you’ve added is in bold):

```
<title>CSS:The Missing Manual -- Chapter 2</title>  
<style>  
</head>
```

The opening <style> tag marks the beginning of the style sheet. It’s always a good idea to close a tag right after you type the opening tag, since it’s so easy to forget this step once you jump into writing your CSS. In this case, you’ll close the <style> tag before adding any CSS.

2. Press Enter twice and type </style>.

Now, you’ll add a CSS selector that marks the beginning of your first style.

3. Click between the opening and closing `<style>` tags and type `h1 {`.

The `h1` indicates the tag to which the web browser should apply the upcoming style.

The weird bracket thingy after the `h1` is called an opening brace, and it marks the beginning of the CSS properties for this style. In other words, it says, “The fun stuff comes right after me.” As with closing tags, it’s a good idea to type the closing brace of a style before actually adding any style properties.

4. Press Enter twice and type a single closing brace: `}`.

As the partner of the opening brace you typed in the last step, this brace’s job is to tell the web browser, “This particular CSS rule ends here.” Now time for the fun stuff.

5. Click in the empty line between the two braces. Hit the Tab key, and type `color: #666666;`.

You’ve typed the same style property as the inline version—`color`—and set it to `#666666`. The final semicolon marks the end of the property declaration.

NOTE

Technically, you don’t have to put the style property on its own line, but it’s a good idea. With one property per line, it’s a lot easier to quickly scan a style sheet and see all the properties for each style. Also, the tab is another helpful visual organizing technique (you can also insert a few spaces instead). The indentation makes it easy to discern all of your rules at a glance, since the selectors (like `h1` here) line up along the left edge, with the properties spaced a bit out of the way.

6. Press Enter again and add two additional properties, like so:

```
font-size: 3em;  
margin: 0;
```

Make sure you don’t leave off the semicolon at the end of each line, otherwise the CSS won’t display correctly in a browser.

Each of these properties adds a different visual effect to the headline. The first assigns a size and font to the text, while the second removes space from around the headline. Part 2 of this book covers all these properties in detail.

Congratulations—you’ve just created an internal style sheet. The code you’ve added should look like the bolded text:

```
<title>CSS: The Missing Manual -- Chapter 2</title>  
<style>  
h1 {  
  color: #666666;  
  font-size: 3em;  
  margin: 0;
```

```
}  
</style>  
</head>
```

7. Save the page and preview it in a web browser.

You can preview the page by opening it in a web browser as described in Step 3 on page 44, or, if the page is still open in a browser window, then just click the Reload button.

Next you'll add another style.

NOTE

Always remember to add the closing `</style>` tag at the end of an internal style sheet. When you don't, a web browser displays the CSS style code followed by a completely unformatted web page—or no web page at all.

8. Back in your text-editing program, click after the closing brace of the `h1` style you just created, press Enter, and then add the following rule:

```
p {  
  color: #616161;  
  line-height: 150%;  
  margin-top: 10px;  
  margin-left: 60px;  
}
```

This rule formats every paragraph on the page. Don't worry too much right now about what each of these CSS properties is doing. Later chapters cover these properties in depth. For now, just practice typing the code correctly and get a feel for how to add CSS to a page.

9. Preview the page in a browser.

The page is starting to shape up and should look like Figure 2-3. You can see what stylistic direction the page is headed in. You can see a completed version of this tutorial by opening the `internal.html` file in the `02_finished` folder.

The process you've just worked through is CSS in a nutshell: Start with an HTML page, add a style sheet, and create CSS rules to make the page look great. In the next part of this tutorial, you'll see how to work more efficiently using external style sheets.




FIGURE 2-3

CSS easily formats text in creative ways, letting you change fonts, text colors, font sizes, and a lot more, as you'll see in Chapter 6.

CSS: The Missing Manual

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt.

Lorem Ipsum Dolor Sat

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem. Ut enim ad minima veniam, quis nostrum exercitationem ullam corporis suscipit laboriosam, nisi ut aliquid ex ea commodi consequatur? Quis autem vel eum iure reprehenderit qui in ea voluptate velit esse quam nihil molestiae consequatur, vel illum qui dolorem eum fugiat quo voluptas nulla pariatur?

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem. Ut enim ad minima veniam, quis nostrum exercitationem ullam corporis suscipit laboriosam, nisi ut aliquid ex ea commodi consequatur? Quis autem vel eum iure reprehenderit qui in ea voluptate velit esse quam nihil molestiae consequatur, vel illum qui dolorem eum fugiat quo voluptas nulla pariatur?

Nisi Ut Aliquid

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem. Ut enim ad minima veniam, quis nostrum exercitationem ullam corporis suscipit laboriosam, nisi ut aliquid ex ea commodi consequatur? Quis autem vel eum iure reprehenderit qui in ea voluptate velit esse quam nihil molestiae consequatur, vel illum qui dolorem eum fugiat quo voluptas nulla pariatur?

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem. Ut enim ad minima veniam, quis nostrum exercitationem ullam corporis suscipit laboriosam, nisi ut aliquid ex ea commodi consequatur? Quis autem vel eum iure reprehenderit qui in ea voluptate velit esse quam nihil molestiae consequatur, vel illum qui dolorem eum fugiat quo voluptas nulla pariatur?

Copyright 2010, Voluptas Nulla

Creating an External Style Sheet

Since it groups all of your styles at the top of the page, an internal style sheet is a lot easier to create and maintain than the inline style you created a few pages ago. Also, an internal style sheet lets you format any number of instances of a tag on a page, like every `<p>` tag, by typing one simple rule. But an external style sheet gets even better—it can store all of the styles for an *entire website*. Editing one style in the external style sheet updates the whole site. In this section, you'll take the styles you created in the previous section and put them in an external style sheet.

1. **In your text-editing program, create a new file and save it as `styles.css` in the same folder as the web page you've been working on.**

External style sheet files end with the extension `.css`. The file name `styles.css` indicates that the styles contained in the file apply throughout the site. (But you can use any file name you like, as long as it ends with the `.css` extension.)

Start by adding a new style to the style sheet.

2. Type the following rule into the *styles.css* file:

```
html {  
  padding-top: 25px;  
  background-image: url(images/bg_page.png);  
}
```

This rule applies to the HTML tag—the tag that surrounds all other HTML tags on a page. The `padding-top` property adds space between the top of the tag and the content that goes inside it. In other words, what you just typed will add 25 pixels of space between the top of the browser window and the content inside the page. The `background-image` adds a background image to the page. The CSS `background-image` property can display the graphic in many different ways—in this case, the graphic will tile seamlessly from left to right and top to bottom, covering the entire browser window. You can read more about background image properties on page 240.

3. Add a second rule following after the rule you just typed to the *styles.css* file:

```
body {  
  width: 80%;  
  padding: 20px;  
  margin: 0 auto;  
  box-shadow: 10px 10px 10px rgba(0,0,0,.5);  
  background-color: #E1EDEB;  
}
```

This rule applies to the `body` tag—the tag that holds all the content visible in a web browser window. There are a lot of different things going on in this style, and each of these properties is covered in-depth later in the book. But in a nutshell, this style creates a box for the page's content that's 80 percent the width of the browser window, has a little bit of space inside that moves text from the edge of the box (that's the `padding` property), and centers the box on the page (that's the `margin` property, and the particular trick of centering a page's content is discussed in the tutorial starting on page 89). Finally, the box gets a light blue background color and a transparent black drop shadow.

Instead of recreating the work you did earlier, just copy the styles you created in the previous section and paste them into this style sheet.

4. Open the *basic.html* page that you've been working on and copy all of the text *inside* the `<style>` tags. (Don't copy the `<style>` tags themselves.)

Copy the style information the same way you'd copy any text. For example, choose `Edit`→`Copy` or press `Ctrl+C` (⌘-C).

5. In the *styles.css* file, paste the style information by selecting `Edit`→`Paste` or pressing `Ctrl+V` (⌘-V).

An external style sheet never contains any HTML—that's why you didn't copy the `<style>` tags.

6. Save *styles.css*.

Now you just need to clean up your old file and link the new style sheet to it.

7. Return to the *basic.html* file in your text editor and delete the `<style>` tags and all the CSS rules you typed in earlier.

You no longer need these styles, since they're in the external style sheet you're about to attach. In this tutorial, you'll take a dip into the exciting world of web fonts. You'll learn all about web fonts starting on page 132, but the basic idea is that you can use nearly any font you want in a web page—even a font that your site's visitors don't have installed on their own computers—simply by providing a link to that font file. There are many different ways to use web fonts, but in this example, you'll use Google's web font service.

8. In the space where the styles used to be (between the closing `</title>` tag and the closing `</head>` tag), type the following:

```
<link href="http://fonts.googleapis.com/css?family=Gravitas+One"
rel="stylesheet">
```

Again, don't worry about the details yet. All you need to know for now is that when a web browser encounters this link, it downloads a font named Gravitas One from a Google server, which your CSS styles can freely use to make distinctive-looking text.

Next, you'll link to the external style sheet you created earlier.

9. After the `<link>` tag you added in the previous step, type:

```
<link href="styles.css" rel="stylesheet">
```

The `<link>` tag is one way to attach a style sheet to a page; another option is the CSS `@import` directive, as discussed on page 42. The link tag specifies the location of the external style sheet. The `rel` attribute simply lets the browser know that it's linking to a style sheet.

NOTE

In this example, the style sheet file is in the same folder as the web page, so using the file's name for the `href` value provides a simple "document-relative" path. If it were in a different folder from the page, then the path would be a bit more complicated. In either case, you'd use a *document-* or *root-relative* path to indicate where the file is. The routine is the same as when you create a link to a web page or set a path to an image file when using the HTML `` tag. (For a brief primer on document- and root-relative links, visit www.communitymx.com/content/article.cfm?cid=230AD.)

10. Save the file and preview it in a web browser.

You'll see the same text styles for the `<h1>` and `<p>` tags that you created in the internal style sheet on page 45. In addition, there's now a speckled, tan background (the background image you applied on the `<html>` tag), as well as a blue box. That box is the `<body>` tag, and its width is 80 percent that of the browser window. Try resizing the browser window and notice that the box changes width

as well. There's also a drop shadow on the box; you can see through the drop shadow to the speckled background. That's thanks to a CSS3 color type—`rgba` color—that includes a transparency setting (you'll read about it on page 155).

NOTE If the web page doesn't have any formatting (for example, the top headline isn't big, bold, and dusty brown), then you've probably mistyped the code from step 6 or saved the `styles.css` file in a folder other than the one where the `basic.html` file is. In this case, just move the `styles.css` into the same folder.

Now, you'll use the web font you linked to in Step 8.

- 11. In your text editor, return to the `styles.css` file.** For the `h1` style, add the following two lines:

```
font-family: 'Gravitas One', 'Arial Black', serif;  
font-weight: normal;
```

The finished style should look like this (additions in bold):

```
h1 {  
  font-family: 'Gravitas One', 'Arial Black', serif;  
  font-weight: normal;  
  color: #666666;  
  font-size: 3em;  
  margin: 0;  
}
```

If you preview the page now, you'll see the new font “Gravitas One” for the headline.

NOTE If you don't see the new font—it's kind of chunky looking with thin lines (serifs) at the ends of the letters—then one of a couple of things could be wrong. If you're not connected to the Internet, you won't be able to download the font from Google; second, you may have mistyped either the `<link>` tag (see step 8 on the previous page), or the font-family declaration (line 2 above).

To demonstrate how useful it can be to keep your styles in their own external file, you'll attach the style sheet to another web page.

- 12. Open the file `02→another_page.html`.**

This page contains some of the same HTML tags—`h1`, `h2`, `p`, and so on—as the other web page you've been working on.

- 13. Click after the closing `</title>` tag and press Enter (Return).**

You'll now link to both the web font and the external style sheet.

14. Type the same `<link>` tags you did in Steps 8 and 9.

The web page code should look like this (the code you just typed appears in bold):

```
<title>Another Page</title>
<link href="http://fonts.googleapis.com/css?family=Gravitas+One"
rel="stylesheet">
<link href="styles.css" rel="stylesheet">
</head>
```

15. Save the page and preview it in a web browser.

Ta-da! Just two lines of code added to the web page is enough to instantly transform its appearance. To demonstrate how easy it is to update an external style sheet, you'll do so by editing one style and adding another.

16. Open the `styles.css` file and add the CSS declaration `font-family: "Palatino Linotype", Baskerville, serif;` at the beginning of the `p` style.

The code should look like this (the bold text is what you've just added):

```
p {
  font-family: "Palatino Linotype", Baskerville, serif;
  color: #616161;
  line-height: 150%;
  margin-top: 10px;
  margin-left: 80px;
}
```

In this case, you're not using a web font, but relying on the site visitor to already have one of the fonts listed on his machine (you'll learn all about using fonts on page 127). Next, create a new rule for the `h2` tag.

17. Click at the end of the `p` style's closing `}`, press `Enter`, and add the following rule:

```
h2 {
  color: #B1967C;
  font-family: 'Gravitas One', 'Arial Black', serif;
  font-weight: normal;
  font-size: 2.2em;
  border-bottom: 2px white solid;
  background: url(images/head-icon.png) no-repeat 10px 10px;
  padding: 0 0 2px 60px;
  margin: 0;
}
```

Some of these CSS properties you've encountered already. Some are new—like the `border-bottom` property for adding a line underneath the headline. And some—like the `background` property—provide a shortcut for combining several

different properties—in this case, the `background-image`, and `background-repeat`—into a single property. Don't worry about the specifics of these properties, you'll learn them all in great detail in upcoming chapters (Chapter 6 covers font properties; Chapter 8 covers backgrounds; Chapter 7 covers padding and margins).

The styles you've created so far affect mainly tags—the `h1`, `h2`, and `p`—and they affect every instance of those tags. In other words, the `p` style you created formats every single paragraph on the page. If you want to target just one paragraph, you need to use a different kind of style.

18. Click at the end of the `h2` style's closing `}`, press Enter, and add the following rule:

```
.intro {  
  color: #6A94CC;  
  font-family: Arial, Helvetica, sans-serif;  
  font-size: 1.2em;  
  margin-left: 0;  
  margin-bottom: 25px;  
}
```

If you preview the `basic.html` page in a web browser, you'll see that this new style has no effect...yet. This type of style, called a *class selector*, formats only the specific tags you apply the class to. In order for this new style to work, you need to edit some HTML.

19. Save the file `styles.css` and switch to the `basic.html` file in your text editor.

Locate the opening `<p>` tag following the `<h1>` tag and add `class="intro"` so the opening tag looks like this:

```
<p class="intro">
```

You don't have to add a period before the word `intro` as you did when you created the style in Step 18 (you'll learn why in the next chapter). This little extra HTML applies the style to the first paragraph (and only that one paragraph).

Repeat this step for the `another_page.html` file—in other words, add `class="intro"` to the first `<p>` tag on that page.

20. Save all the files and preview both the `basic.html` and `another_page.html` files in a web browser. Figure 2-4 shows the completed `basic.html` file.

Notice that the appearance of both pages changes, based on the simple edits you made to the CSS file. Close your eyes and imagine your website has a thousand pages. Aaaahhhhhh, the power. (You'll find a completed version of this tutorial in the `02_finished` folder.)

For added practice, add a style to format the `<address>` tag (that tag is used at the bottom of the HTML file to hold the copyright notice). For example, you might change its color, and indent it 80 pixels to match the indent of the `<p>` tags.




FIGURE 2-4

Using an external style sheet, you can update an entire site's worth of web pages by editing a single CSS file. In addition, by moving all of the CSS code out of an HTML document and into a separate file, you cut down on the file size of your web pages so they load faster.

Selectors: Identifying What to Style

Every CSS style has two basic parts: a selector and a declaration block. (And if that's news to you, go back and read the previous chapter.) The declaration block carries the formatting properties—text color, font size, and so on—but that's just the pretty stuff. The magic of CSS lies in those first few characters at the beginning of every rule—the selector. By telling CSS *what* you want it to format (see Figure 3-1), the selector gives you full control of your page's appearance. If you're into sweeping generalizations, then you can use a selector that applies to many elements on a page at once. But if you're a little more detail oriented (OK, a *lot* more), other selectors let you single out one specific item or a collection of similar items. CSS selectors give you a lot of power: This chapter shows you how to use them.

```
h1 {  
    font-family: Arial, sans-serif;  
    color: #CCCCFF;  
}
```

FIGURE 3-1

The first part of a style, the selector, indicates the element or elements of a page to format. In this case, h1 stands for “every heading 1, or <h1>, tag on this page.”

NOTE

If you'd rather get some hands-on experience before studying the ins and outs of CSS selectors, then jump to the tutorial in the next section on page 81.

Tag Selectors: Page-Wide Styling

Tag selectors—sometimes called *type* or *element* selectors—are extremely efficient styling tools, since they apply to every occurrence of an HTML tag on a web page. With them, you can make sweeping design changes to a page with very little effort. For example, when you want to format every paragraph of text on a page, using the same font, color, and size, you merely create a style using `p` (as in the `<p>` tag) as the selector. In essence, a tag selector redefines how a browser displays a particular tag.

Prior to CSS, in order to format text, you had to wrap that text in a `` tag. To add the same look to every paragraph on a page, you often had to use the `` tag multiple times. This process was a lot of work and required a lot of HTML, making pages slower to download and more time-consuming to update. With tag selectors, you don't actually have to do anything to the HTML—just create the CSS rule, and let the browser do the rest.

Tag selectors are easy to spot in a CSS rule, since they bear the exact same name as the tag they style—`p`, `h1`, `table`, `img`, and so on. For example, in Figure 3-2, the `h2` selector (top) applies some font styling to all `<h2>` tags on a web page (bottom).

```
h2 {  
  font-family:"Century Gothic", "Gill Sans", sans-serif;  
  color:#000000;  
  margin-bottom:0;  
}
```




FIGURE 3-2

A tag selector affects every instance of the tag on the page. This page has three `<h2>` tags (indicated by the black labels at the left edge of the browser window). A single CSS style with a selector of `h2` controls the presentation of every `<h2>` tag on the page.

NOTE

As Figure 3-2 makes clear, tag selectors don't get the less than (<) and greater than (>) symbols that surround HTML tags. So when you're writing a rule for the <p> tag, for example, just type the tag's name—p.

Tag selectors have their downsides, however. What if you want *some* paragraphs to look different from other paragraphs? A simple tag selector won't do, since it doesn't provide enough information for a web browser to identify the difference between the <p> tags you want to highlight in purple, bold, and large type from the <p> tags you want to leave with normal, black text. Fortunately, CSS provides several ways to solve this problem—the most straightforward method is called a *class selector*.

■ Class Selectors: Pinpoint Control

When you want to give one or more elements a look that's different from related tags on a page—for example, give one or two images on a page a red border while leaving the majority of other images unstyled—you can use a *class selector*. If you're familiar with styles in word-processing programs like Microsoft Word, then class selectors will feel familiar. You create a class selector by giving it a name and then applying it to just the HTML tags you wish to format. For example, you can create a class style named `.copyright` and then apply it only to a paragraph containing copyright information, without affecting any other paragraphs.

Class selectors also let you pinpoint an exact element on a page, regardless of its tag. Say you want to format a word or two inside a paragraph, for example. In this case, you don't want the entire <p> tag affected, just a single phrase inside it. You can use a class selector to indicate just those words. You can even use a class selector to apply the same formatting to multiple elements that have different HTML tags. For example, you can give one paragraph and one second-level heading the same styling—perhaps a color and a font you've selected to highlight special information, as shown in Figure 3-3. Unlike tag selectors, which limit you to the existing HTML tags on the page, you can create as many class selectors as you like and put them anywhere you want.

NOTE

When you want to apply a class selector to just a few words contained inside another tag (like the middle paragraph in Figure 3-3), you need a little help from the tag. See the box on page 60 for more detail.

You've probably noticed the period that starts every class selector's name—such as `.copyright` and `.special`. It's one of a few rules to keep in mind when naming a class:

- All class selector names must begin with a period. That's how web browsers spot a class selector in the style sheet.
- CSS permits only letters, numbers, hyphens, and underscores in class names.

```
.special {
  color:#FF0000;
  font-family:"Monotype Corsiva";
}
```



class="special"

FIGURE 3-3

Class selectors let you make highly targeted design changes. For example, you can stylize one instance of an `<h2>` heading (“Wet Sod is Heavy Sod”). The class selector `.special` tells the browser to apply the style to just that single `<h2>` tag. Once you’ve created a class selector, you can use it on other tags, like the top paragraph on this page.

- After the period, the name must always start with a *letter*. For example, `.9lives` isn’t a valid class name, but `.crazy8` is. You can have classes named `.copy-right` and `.banner_image`, but not `.-bad` or `._as_bad`.
- Class names are case sensitive. For example, CSS considers `.SIDEBAR` and `.sidebar` two different classes.

Apart from the name, you create class styles exactly like tag styles. After the class name, simply slap on a declaration block containing all the styling you desire:

```
.special {  
  color:#FF0000;  
  font-family:"Monotype Corsiva";  
}
```

Because tag styles apply across the board to all tags on a web page, you merely have to define them in the head of the page: The HTML tags that make them work are already in place. The extra freedom you get with class styles, though, comes with a little more work. Using class selectors is a two-step process. After you create a class rule, you must then indicate *where* you want to apply that formatting. To do so, you add a class attribute to the HTML tag you wish to style.

Say you create a class `.special` that you'll use to highlight particular page elements. To add this style to a paragraph, add a class attribute to the `<p>` tag, like so:

```
<p class="special">
```

NOTE

In the HTML, as part of the class attribute, you *don't* put a period before the class name. The period is only required for the class selector name in a *style sheet*.

When a web browser encounters this tag, it knows to apply the formatting rules contained in the `.special` style to the paragraph. You can also apply class formatting to only part of a paragraph or heading by adding a `` tag. For example, to highlight just one word in a paragraph using the `.special` style, you could write this:

```
<p>Welcome to <span class="special">Café Soy lent Green</span>, the restaurant  
with something a little different.</p>
```

Once you create a class style, you can apply it to just about any tag on the page. In fact, you can apply the same class to different tags, so you can create a `.special` style with a specific font and color and apply it to `<h2>`, `<p>`, and `` tags.

UP TO SPEED

Divs and Spans

Chapter 1 introduced you to `<div>` and ``, two generic HTML tags that you can bend to your CSS wishes. When there's no HTML tag that exactly delineates where you want to put a class or ID style you've created, use a `<div>` or `` to fill in the gaps.

The `div` tag identifies a logical *division* of the page, like a banner, navigation bar, sidebar, or footer. You can also use it to surround any element that takes up a chunk of the page, including headings, bulleted lists, or paragraphs. (Programmer types call these *block-level* elements because they form a complete “block” of content, with line breaks before and after them.) The `<div>` tag works just like a paragraph tag: Type the opening `<div>`, add some text, a photo, or some other content inside it, and then end it with the closing `</div>`.

The `div` tag has the unique ability to contain *several* block-level elements, making it a great way to group tags that are logically related such as the logo and navigation bar in a page's banner or a series of news stories that compose a sidebar. Once grouped in this way, you can apply specific formatting to just the tags inside the particular `div` or move the entire `div`-tagged chunk of content into a particular area, such as the right side of the browser window (CSS can help you control the visual layout of your pages in this manner, as described in Part 3 of this book).

For example, say you added a photo to a web page; the photo also has a caption that accompanies it. You could wrap a `<div>`

tag (with a class applied to it) around the photo and the caption to group both elements together:

```
<div class="photo">
  
  <p>Mom, dad and me on our yearly trip
    to Antarctica.</p>
</div>
```

Depending on what you put in the declaration block, the `.photo` class can add a decorative border, background color, and so on to both photo and caption. Part 3 of this book shows you even more powerful ways to use `<div>` tags—including nested `divs`.

A `` tag, on the other hand, lets you apply a class or ID style to just *part* of a tag. You can place `` tags around individual words and phrases (often called *inline* elements) within paragraphs to format them independently. Here, a class called `.companyName` styles the inline elements “CosmoFarmer.com,” “Disney,” and “ESPN”:

```
<p>Welcome to <span class="companyName">
CosmoFarmer.com</span>, the parent
company of such well-known corporations
as <span class="companyName"> Disney
</span> and <span class="companyName">
ESPN </span>...well, not really.</p>
```

■ ID Selectors: Specific Page Elements

CSS reserves the ID selector for *identifying* a unique part of a page, like a banner, navigation bar, or the main content area. Just like a class selector, you create an ID by giving it a name in CSS, and then you apply it by adding the ID to your page's HTML code. So what's the difference? As explained in the box on page 62, ID selectors have some specific uses in JavaScript-based or very lengthy web pages. Otherwise, compelling reasons to use IDs over classes are few.

NOTE There's a growing trend in the web design community to abandon ID selectors in CSS. The reasoning requires greater knowledge of CSS than is presented so far in this book. You won't find IDs much in this book, and you'll learn all the gory details why ID selectors are often not a good idea on page 114.

Although many web designers don't use ID selectors as much as they once did, it's good to know what they are, and how they work. Should you decide to use an ID selector, creating one is easy. Just as a period indicates the name of a class selector, a pound or hash symbol identifies an ID style. Otherwise, follow the exact same naming rules used for classes (page 57). This example provides a background color and a width and height for the element:

```
#banner {  
  background: #CC0000;  
  height: 300px;  
  width: 720px;  
}
```

Applying IDs in HTML is similar to applying classes but uses a different attribute named, logically enough, *id*. For example, to apply the style above to a `<div>` tag, you'd write this HTML:

```
<div id="banner">
```

Likewise, to indicate that the last paragraph of a page is that page's one and only copyright notice, you can create an ID style named `#copyright` and add it to that paragraph's tag:

```
<p id="copyright">
```

NOTE As with class styles, you use the `#` symbol only when naming the style in the style sheet. You leave the `#` off when using the ID's name as part of an HTML tag: `<div id="banner">`.

POWER USERS' CLINIC

Proper IDs

ID attributes in HTML have a few powers that class attributes lack. These benefits actually have nothing to do with CSS, so you may never need an ID. But if you're curious:

- One easy way for JavaScript programmers to locate and manipulate parts of a page is by applying an ID to a page element, and then using JavaScript to reference that ID. For example, programmers often apply an ID to a form element like a text box for collecting a visitor's name. The ID lets JavaScript access that form element and work its magic—like making sure the field isn't empty when the visitor clicks Submit.
- IDs also let you link to a specific part of a page, making long web pages quicker to navigate. If you have an alphabetic glossary of terms, then you can use an ID

selector to create links to the letters of the alphabet. When your visitors click “R,” they jump immediately to all the “R” words on the page. You don't actually need to create any CSS for this—it works purely with HTML. First, add an ID attribute to the spot on the page you wish to link to. For example, in a glossary you can add an h2 tag with a letter from the alphabet followed by the glossary listings—perhaps in a definition list or a series of paragraphs. Just add an appropriate ID to each of those h2 tags: `<h2 id="R">R</h2>`. To create the link in HTML, add the pound symbol and the ID name to the end of the URL, followed by the ID name—`index.html#R`. This link points directly to an element with the ID of #R on the page `index.html`. (When used this way, the ID behaves just like a named anchor—`R`—in HTML.)

■ Styling Groups of Tags

Sometimes you need a quick way to apply the same formatting to several different elements. For example, maybe you'd like all the headers on a page to share the same color and font. Creating a separate style for each header—h1, h2, h3, h4, and so on—is way too much work, and if you later want to change the color of all of the headers, then you have six different styles to update. A better approach is to use a *group* selector. Group selectors let you apply a style to multiple selectors at the same time.

Constructing Group Selectors

To work with selectors as a group, simply create a list of selectors separated by commas. So to style all the heading tags with the same color, you can create the following rule:

```
h1, h2, h3, h4, h5, h6 { color: #F1CD33; }
```

This example consists of only tag selectors, but you can use any valid selector (or combination of selector types) in a group selector. For example, here's a selector that applies the same font color to the `<h1>` tag, the `<p>` tag, any tag styled with the `.copyright` class, and the tag with the `#banner` ID:

```
h1, p, .copyright, #banner { color: #F1CD33; }
```

TIP If you want a bunch of page elements to share *some* but not all of the same formatting properties, then you can create a group selector with the shared formatting options and also create individual rules with unique formatting for each individual element. In other words, two (or more) different styles can format the same tag. The ability to use multiple styles to format a single element is a powerful CSS feature. See Chapter 5 for details.

The Universal Selector (Asterisk)

Think of a group selector as shorthand for applying the same style properties to several different page elements. CSS also gives you a sort of über group selector—the *universal* selector. An asterisk (*) is universal selector shorthand for selecting *every single* tag.

For example, say you want all the tags on your page to appear in bold type. Your group selector might look something like the following:

```
a, p, img, h1, h2, h3, h4, h5 ...yadda yadda... { font-weight: bold; }
```

The asterisk, however, is a much shorter way to tell CSS to select *all* HTML tags on the page:

```
* { font-weight: bold; }
```

You can even use the universal selector as part of a descendent selector, so you can apply a style to all the tags that descend from a particular page element. For example, `.banner *` selects every tag inside the page element to which you've applied the `banner` class. (You'll read about descendent selectors next.)

Since the universal selector doesn't specify any particular type of tag, it's hard to predict its effect on an entire website's worth of pages all composed of a variety of different HTML tags. To format many different page elements, web page gurus rely on *inheritance*—a CSS trait discussed in depth in the next chapter.

■ Styling Tags Within Tags

Choosing whether to style your page with tag selectors or class selectors is a tradeoff. Tag selectors are fast and easy, but they make every occurrence of a tag look the same, which is fine—if you want every `<h2>` on your page to look exactly like all the rest. Class and ID selectors give you the flexibility to style individual page elements independently, but creating class or ID styles also requires you to add the appropriate class or ID to the HTML tags you wish to style. Not only does this add work for you, but also code to your HTML file. What you need is a way to combine the ease of tag selectors with the precision of classes and IDs. CSS has just the thing—*descendent selectors*.

You use descendent selectors to format a whole bunch of tags in a similar manner (just like tag selectors), but only when they're in a particular part of a web page. It's like saying, "Hey you `<a>` tags in the navigation bar, listen up. I've got some formatting for you. All you other `<a>` tags, just move along; there's nothing to see here."

Descendent selectors let you format a tag based on its relationship to other tags. To understand how it works, you need to delve a little bit more deeply into HTML. On the bright side, the concepts underlying descendent selectors help you understand several other selector types, too, as discussed later in this chapter.

NOTE Descendent selectors can be confusing at first, but they're among the most important techniques for efficiently and accurately applying CSS. Take the time to master them.

The HTML Family Tree

The HTML that forms any web page is akin to a family tree, where the HTML tags represent various family members. The first HTML tag you use on a page—the `<html>` tag—is like the grandpappy of all other tags. The `<html>` tag surrounds the `<head>` tag and the `<body>` tag, which makes `<html>` the *ancestor* of both. Similarly, a tag inside of another tag is a *descendent*. The `<title>` tag in the following example is the `<head>` tag's descendent:

```
<html>
  <head>
    <title>A Simple Document</title>
  </head>
  <body>
    <h1>Header</h1>
    <p>A paragraph of <strong>important</strong>text.</p>
  </body>
</html>
```

You can turn the above HTML code into a diagram, like Figure 3-4, showing the relationships between the page's tags. First there's the `<html>` tag; it's divided into two sections represented by the `<head>` and `<body>` tags. Those two tags contain other tags that in turn may contain other tags. By seeing which tags appear inside which other tags, you can diagram any web page.




FIGURE 3-4

HTML consists of nested tags—tags within tags within even more tags. The relationship between these tags—how they're nested within each other—forms a kind of family tree.

Tree diagrams help you figure out how CSS sees the relationship of one element on a page to another. Many of the selectors in this chapter, including descendent selectors, rely on these relationships. The most important relationships are:

- **Ancestor.** As explained at the beginning of this chapter, an HTML tag that wraps around another tag is its ancestor. In Figure 3-4, the `<html>` tag is an ancestor of all other tags, while the `<body>` tag is an ancestor for all of the tags *inside* of it—the `<h1>`, `<p>`, and `` tags.
- **Descendent.** A tag inside one or more tags is a descendent. In Figure 3-4, the `<body>` tag is a descendent of the `<html>` tag, while the `<p>` tag is a descendent of *both* the `<body>` and `<html>` tags.
- **Parent.** A parent tag is the *closest* ancestor of another tag. In Figure 3-4, a parent is the first tag directly connected to and above another tag. Thus, the `<html>` tag is the parent of the `<head>` and `<body>` tags, but of no other tags. And, in this diagram, the `<p>` tag is the parent of the `` tag.
- **Child.** A tag that's directly enclosed by another tag is a child. In Figure 3-4, both the `<h1>` and `<p>` tags are children of the `<body>` tag, but the `` tag isn't. Since the `` tag is directly wrapped inside the `<p>` tag, it's a child of the `<p>` tag.
- **Sibling.** Tags that are children of the same tag are called *siblings*, just like brothers and sisters. In an HTML diagram, sibling tags are next to each other and connected to the same parent. In Figure 3-4, the `<head>` and `<body>` tags are siblings, as are the `<h1>` and `<p>` tags.

Thankfully, that's where CSS draws the line with this family metaphor, so you don't have to worry about aunts, uncles, or cousins. (Though rumor has it CSS10 *will* include in-laws.)

Building Descendent Selectors

Descendent selectors let you take advantage of the HTML family tree by formatting tags differently when they appear inside certain other tags or styles. For example, say you have an `<h1>` tag on your web page, and you want to emphasize a word within that heading with the `` tag. The trouble is, most browsers display both heading tags and the `` tag in bold, so anyone viewing the page can't see any difference between the emphasized word and the other words in the headline. Creating a tag selector to change the `` tag's color and make it stand out from the headline isn't much of a solution: You end up changing the color of *every* `` tag on the page, like it or not. A descendent selector lets you do what you really want—change the color of the `` tag *only when* it appears inside of an `<h1>` tag.

The solution to the `<h1>` and `` dilemma looks like this:

```
h1 strong { color: red; }
```

Here *any* `` tag inside an `h1` is red, but other instances of the `` tag on the page aren't affected. You could achieve the same result by creating a class style—`.strongHeader`, for example—but you'd then have to edit the HTML by adding `class="strongHeader"` to the `` tag inside the header. The descendent selector approach adds no HTML and no more work beyond creating the style!

Descendent selectors style elements that are nested inside other elements, following the exact same pattern of ancestors and descendants as the tags in the HTML family tree. You create a descendent selector by tacking together selectors according to the part of the family tree you want to format, with the most senior ancestor on the left and the actual tag you're targeting on the far right. For example, in Figure 3-5, notice the three links (the `<a>` tag) inside of bulleted list items and another link inside of a paragraph. To format the bulleted links differently than the other links on the page, you can create the following descendent selector:

```
li a { font-family: Arial; }
```




FIGURE 3-5
This simple tree diagram (right) represents the structure of the web page pictured to the left. Every tag on a web page is a descendent of the `<html>` tag, since `<html>` wraps around them all. A tag can descend from multiple tags. For example, the first `<a>` tag listed in this diagram is a descendent of the ``, `<p>`, `<body>`, and `<html>` tags.

This rule says, “Format all links (`a`) that appear inside a list item (`li`) by using the Arial font.” A descendent selector can contain more than just two elements. The following are all valid selectors for the `<a>` tags inside of the bulleted lists in Figure 3-5:

```
ul li a
body li a
html li a
html body ul li a
```

NOTE Although, in general, it's best to write as short a descendent selector as possible, one reason you would tack on additional descendent selectors is if you've written several different rules that simultaneously format a tag. Formatting instructions from a long-winded descendent selector can override simple class or tag styles. More on that in the next chapter.

These four selectors—all of which do the same thing—demonstrate that you don't have to describe the entire lineage of the tag you want to format. For instance, in the second example, `body li a~ul` isn't needed. This selector works as long as there's an `<a>` tag that's a descendent (somewhere up the line) of an `` tag (which is also a descendent of the `<body>` tag). This selector can just as easily apply to an `<a>` that's inside an `` tag, that's inside a `` tag, that's inside an `` tag, and so on.

You're not limited to just tag selectors, either. You can build complex descendent selectors combining different types of selectors. For example, suppose you want your links to appear in yellow only when they're inside an introductory element (which you've designated with a class style named `intro`). The following selector does the trick:

```
.intro a { color: yellow; }
```

Quick translation: Apply this style to every link (`a`) that's a descendent of another tag that has the `intro` class applied to it.

Creating Modules

Descendent selectors are often used to format a *module* of code—that is, a collection of HTML that serves a particular function on a page. For example, say you had a `<div>` on the page, used for listing the latest company news. You might have HTML like this:

```
<div>
  <h2>Our company is great!</h2>
  <p>More information about why our company is so great</p>
  <h2>Another news item</h2>
  <p>Information about the other news item...</p>
  <h2>...and so on...</h2>
  <p>... and so on... </p>
</div>
```

If you simply slap a class on that opening `<div>` tag—`<div class="news">`—then you can create descendent selectors that format the HTML tags within the news section differently. For example,

```
.news h2 { color: red; }
.news p { color: blue; }
```

Now the `<h2>` tags within the news section will be red, and the paragraphs, blue. It's even possible (and common) to create descendent selectors with multiple class names. For example, say you're building a page that provides a directory of addresses for members of an organization. You might wrap each contact in its own `div`, and further refine the elements inside that `div` with a class like this:

```
<div class="contact">
  <p class="name">John Smith</p>
  <p class="phone">555-555-1234</p>
  <p class="address">1234 Elem St</p>
</div>
```

Then you could create several descendent selectors to style just those contact elements like this:

```
.contact .name { font-weight: bold; }  
.contact .phone { color: blue ;}  
.contact .address { color: red; }
```

NOTE In a style sheet, you may sometimes see something like this:

```
p.intro
```

This may look like a descendent selector—since there is both an HTML tag and a class—but it’s not. There’s no space between the `p` and the `.intro`, which means that the `intro` class must be applied specifically to a `<p>` tag (`<p class="intro">`) for this style to work. If you add a space, you get a different effect:

```
p .intro { color: yellow; }
```

This seemingly slight variation selects any tag styled with the `.intro` class, which is itself a descendent of a `<p>` tag. In other words, it doesn’t select a paragraph, it selects another tag inside a paragraph. In general, to keep your class styles as flexible as possible, it is better to leave off the HTML tag (in other words use just `.intro` instead of `p.intro`).

Pseudo-Classes and Pseudo-Elements

Sometimes you need to select parts of a web page that don’t have tags per se, but are nonetheless easy to identify, like the first line of a paragraph or a link as you move your mouse over it. CSS gives you a handful of selectors for these doohickeys—pseudo-classes and pseudo-elements.

Styles for Links

Four pseudo-classes let you format links in four different states based on how a visitor has interacted with that link. They identify when a link is in one of the following four states:

- **a:link** selects any link that your guest hasn’t visited yet, while the mouse isn’t hovering over or clicking it. This style is your regular, unused web link.
- **a:visited** is a link that your visitor has clicked before, according to the web browser’s history. You can style this type of link differently than a regular link to tell your visitor, “Hey, you’ve been there already!” (See the box on page 294 for the limitations surrounding this selector.)
- **a:hover** lets you change the look of a link as your visitor passes the mouse over it. The rollover effects you can create aren’t just for fun—they can provide useful visual feedback for buttons on a navigation bar.

You can also use the `:hover` pseudo-class on elements other than links. For example, you can use it to highlight text in a `<p>` or `<div>` when your guests mouse over it. In that case, instead of using `a:hover` (which is for links) to add a hover effect, you can create a style named `p:hover` to create a specific effect when someone mouses over any paragraph. If you just want to style tags with a specific class of `highlight` applied to them, then create a style named `.highlight:hover`.

- **a:active** lets you determine how a link looks as your visitor clicks. In other words, it covers the brief nanosecond when someone's pressing the mouse button, before releasing it.

Chapter 9 shows you how to design links by using these selectors to help your visitors click their way around your site.

NOTE

You can live a long, productive life without reading about the selectors in the next few sections. Many web designers never use them. The selectors you've learned so far—tag, class, ID, descendent, group, and so on—let you build absolutely beautiful, functional, and easily maintained websites. If you're ready for the fun stuff—designing web pages—then skip to the tutorial on page 81. You can always finish reading this discussion some cold, rainy night by the fire.

Styling Paragraph Parts

The typographic features that make books and magazines look cool, elegant, and polished didn't exist in the early web era. (After all, when did scientists ever worry about looking cool?) CSS provides two pseudo-elements—`:first-letter` and `:first-line`—that give your web pages the design finesse that print has enjoyed for centuries.

The `:first-letter` pseudo-element lets you create a drop cap—an initial letter that jumps out from the rest of the paragraph with bigger or bolder font formatting, as at the beginning of a book chapter.

Styling the `:first-line` of a paragraph in a different color keeps your reader's eye moving and makes text appear appealing and fresh. (If you're intrigued, Chapter 6 is all about formatting text, and page 171 covers these two pseudo-elements in depth.)

NOTE

CSS3 changes the syntax for pseudo-elements. In CSS 2.1, pseudo-elements begin with a single colon, like this:

```
:first-letter
```

CSS3 adds an additional colon to differentiate pseudo-classes like `:hover` from pseudo-elements. So `:first-letter` and `:first-line`, are now `::first-letter` and `::first-line`. Fortunately, to maintain support with older sites, browsers will continue to support the single colon version of pseudo-elements. That's a good thing since Internet Explorer 8 doesn't understand the double-colon syntax, so for the time being, stick with the single colon for now, since all other browsers still use that as well.

More Pseudo-Classes and Pseudo-Elements

The CSS guidelines define several powerful pseudo-class and pseudo-element selectors besides the ones covered so far. Support for these selectors in all but the oldest browsers is very good.

■ :FOCUS

The `:focus` pseudo-class works much like the `:hover` pseudo-class. While `:hover` applies when a visitor mouses over a link, `:focus` applies when the visitor does something to indicate her attention to a web page element—usually by clicking or tabbing into it. In programming lingo, when a visitor clicks in a text box on a web form, she puts the *focus* on that text box. That click is a web designer’s only clue as to where the visitor is focusing her attention.

The `:focus` selector is mostly useful for giving your visitor feedback, like changing the background color of a text box to indicate where she’s about to type. (Single-line text fields, password fields, and multi-line `<textarea>` boxes are common targets for the `:focus` selector.) This style, for example, adds a light yellow color to any text box a visitor clicks or tabs into:

```
input:focus { background-color: #FFFFCC; }
```

The `:focus` selector applies only while the element is in focus. When a visitor tabs into another text field or clicks anywhere else on the page, she takes the focus—and the CSS properties—away from the text box.

TIP

One good resource for seeing which browsers support which CSS selector is www.quirksmode.org/css/contents.html.

■ :BEFORE

The `:before` pseudo-element does something no other selector can: It lets you add content preceding a given element. For example, say you wanted to put “HOT TIP!” before certain paragraphs to make them stand out, like the boxes in this book that say “UP TO SPEED” and “POWER USERS’ CLINIC.” Instead of typing that text in your page’s HTML, you can let the `:before` selector do it for you. This approach not only saves on code, but also if you decide to change the message from “HOT TIP!” to, say, “Things to know,” then you can change every page on your site with one quick change to your style sheet. (The downside is that this special message is invisible to browsers that don’t understand CSS or don’t understand the `:before` selector.)

First, create a class (`.tip`, say) and apply it to the paragraphs that you want to precede with the message, like so: `<p class="tip">`. Then, add your message text to the style sheet:

```
p.tip:before {content: "HOT TIP!" }
```

Whenever a browser encounters the `.tip` class in a `<p>` tag, it dutifully inserts the text “HOT TIP!” just before the paragraph.

The technical term for text you add with this selector is *generated content*, since web browsers create (generate) it on the fly. In the page's HTML source code, this material doesn't exist. Whether you realize it or not, browsers generate their own content all the time, like the bullets in bulleted lists and numbers in ordered lists. If you want, you can even use the `:before` selector to define how a browser displays its bullets and numbers for lists.

Internet Explorer 8 and up as well as all other major browsers support the `:before` selector (and the `:after` selector coming up next). You'll find more information on using these selectors in the box on page 259.

■ :AFTER

Exactly like the `:before` selector, the `:after` pseudo-element adds generated content—but after the element, not before. You can use this selector, for example, to add closing quotation marks (") after quoted material.

NOTE

Both `:before` and `:after` are pseudo-elements like `:first-line` and `:first-letter`. As mentioned in the note on page 69, CSS3 adds double-colons to pseudo-elements, so `:before`, and `:after` are written as `::before` and `::after` in CSS3. Fortunately, browsers support the older notation, so you can continue to use `:before` and `:after`, which have the added benefit of working in Internet Explorer 8.

■ ::SELECTION

This CSS3 selector refers to items that a visitor has selected on a page. For example, when a visitor clicks and drags over text, the browser highlights that text, and the visitor can then copy the text. Normally, browsers add a blue background behind the text. Internet Explorer changes the text color to white. However, you can control the background color and text color by defining this selector. For example, if you wanted to make selected text white with a violet background you could add this style to a page's style sheet:

```
::selection {
    color: #FFFFFF;
    background-color: #993366;
}
```

The only properties you can set with this selector are `color` and `background-color`, so you can't go wild and change the font size, fonts, margins, or other visual changes that would surely drive your site visitors crazy. (Thanks for protecting us from ourselves, CSS!)

NOTE

There's no single-colon version of the selection pseudo-element, so you must use the double colon. In other words, `::selection` works, but `:selection` won't.

This selector works in Internet Explorer 9, Opera, Chrome, and Safari, but not IE 8 or Firefox. You can, however, add support for Firefox by adding what's called a *vendor-prefix* to the selector, like this:

```
::-moz-selection {  
    color: #FFFFFF;  
    background-color: #993366;  
}
```

To get this to work in Firefox and the other browsers, you need to have both styles in your style sheet—just place one after the other. (You’ll learn more details about vendor prefixes and why you need them in the box on page 209.)

If you really want to go crazy, you can specify a different background color just for text selected inside a particular element. For example, to make only text inside paragraphs red with a pink background, just add the `p` element selector before `::selection`, like this:

```
p::selection {  
    color: red;  
    background-color: pink;  
}
```

TIP

Learning how to write selectors can sometimes feel like learning hieroglyphics. To translate a selector into straightforward language, visit the Selectoracle at <http://gallery.theopalgroup.com/selectoracle>. This great resource lets you type in a selector and then it spits out a clear description of which page elements on a page the style affects.

Attribute Selectors

CSS provides a way to format a tag based on any HTML attributes it has. For example, say you want to place borders around the images on your page—but only around the important photos. You don’t want to include your logo, buttons, and other little doodads that also have an `` tag. Fortunately, you realize that you’ve given all the photos descriptions using the `title` attribute, which means you can use an *attribute selector* to identify just the important images.

TIP

The HTML `title` attribute is a great way to add tooltips (pop-up messages) to links and images on a page. It’s also one way to inform search engines about the useful information on a web page. Learn more about it at <http://webdesign.about.com/od/htmltags/a/aa101005.htm>.

With attribute selectors, you can single out tags that have a particular property. For example, here’s how to select all `` tags with a `title` attribute:

```
img[title]
```

The first part of the selector is the name of the tag (`img`) while the attribute’s name goes in brackets: `[title]`.

CSS doesn't limit attribute selectors to tag names: You can combine them with classes, too. For example, `.photo[title]` selects every element with the `.photo` class style and an HTML title attribute.

To get more specific, you can select elements that not only share a particular attribute but also have an exact value set for that attribute. For example, when you want to highlight links that point to a particular URL, create an eye-catching attribute selector, like so:

```
a[href="http://www.cafesoylentgreen.com"]{
  color:red;
  font-weight:bold;
}
```

Adding a value to an attribute selector is very useful when working with forms. Many form elements have the same tag, even if they look and act differently. The checkbox, text box, submit button, and other form fields all share the `<input>` tag. The type attribute's value is what gives the field its form and function. For example, `<input type="text">` creates a text box, and `<input type="checkbox">` creates a checkbox.

To select just text boxes in a form, for example, use this selector:

```
input[type="text"]
```

The attribute selector is very versatile. It lets you not only find tags that have a specific value for an attribute (for example, find all form fields with a type of checkbox) but even select elements with an attribute value that *begins with*, *ends with*, or *contains* a specific value. While this might sound like overkill, it's actually quite handy.

For example, suppose you want to create a specific style to highlight external links (links that point outside of your own website) to indicate, "Hey, you'll leave this site if you click this." Assuming you don't use absolute links to link to any pages in your own site, you can assume that any external link begins with `http://`—the first part of any absolute link.

If that's the case, the selector would look like this:

```
a[href^="http://"]
```

The `^=` translates to "begins with," so you can use this selector to format any link that begins with `http://`. You can use it to style a link that points to `http://www.google.com` as well as a link to `http://www.sawmac.com`. In other words, it selects any external link.

NOTE

This selector won't work for any secure connections over SSL—in other words, any links that begin with `https://`. To create a style that affects those as well, you could create a group selector (page 84) like this:

```
a[href^="http://"], a[href^=" https://"]
```

Similarly, there are times when you want to select an element with an attribute that *ends* in a specific value. Again, links are handy for this task. Say you want to add

a little document icon next to any links that point to a PDF file. Since PDF documents end in .pdf, you know a link pointing to one of those files will end in .pdf—for example, ``. So to select just those types of links, you'd create a selector like this:

```
a[href$=".pdf"]
```

The full style might look something like this:

```
a[href$=".pdf"] {  
  background: url(doc_icon.png) no-repeat;  
  padding-left: 15px;  
};
```

Don't worry too much about the particular properties in this style—you'll learn about padding on page 195 and background images on page 240. Just pay attention to that cool selector: `$=` translates to “ends with.” You can use this selector to format links that point to Word docs (`a[href$=".doc"]`), movies (`a[href$=".mp4"]`), and so on.

Finally, you can even select elements with attributes that contain another value. For example, say you like to highlight photos of your employees throughout the site. You might want all of those photos to have a common style, like a thick green border and a gray background. One way to do this is to create a class style—`.headshot`, for example—and manually add a class attribute to the appropriate `` tags. However, if you name the photos consistently, then there's a faster method.

For example, say you name each of those images with the word *headshot* in them—for example, `mcfarland_headshot.png`, `mccord_headshot.jpg`, `headshot_albert.jpg`, and so on. Each of these files has the word *headshot* somewhere in the file, so the `src` attribute of the `` tag used to insert each image also contains the word *headshot*. You can create a selector for just those images like this:

```
img[src*="headshot"]
```

This translates to “select all images whose `src` attribute has the word *headshot* somewhere in it.” It's a simple, elegant way to format just those images.

■ Child Selectors

Similar to the descendent selectors described earlier in this chapter, CSS lets you format the children of another tag with a *child* selector. The child selector uses an additional symbol—an angle bracket (`>`) to indicate the relationship between the two elements. For example, the selector `body > h1` selects any `<h1>` tag that's a child of the `<body>` tag.

Unlike a descendent selector, which applies to *all* descendants of a tag (children, grandchildren, and so on), the child selector lets you specify which child of which parent you mean. For example, in Figure 3-6, there are two `<h2>` tags. Using a plain old descendent selector—`body h2`—selects both `<h2>` tags. Even though both `<h2>`

tags are inside of the `<body>` tag, only the second one is a child of the `<body>` tag. The first `<h2>` is directly inside of a `<div>` tag, so its parent is the `<div>`. Since the two `<h2>` tags have different parents, you can use a child selector to get at them individually. To select only the first `<h2>` tag, your child selector looks like this: `body > h2`. If you want the second `<h2>` tag, then you must use this child selector instead: `div > h2`.




FIGURE 3-6

The diagram (right) shows the relationship between HTML tags (left).

CSS3 also includes some very specific pseudo-classes for selecting child elements. They let you fine-tune your selectors for many different arrangements of HTML.

■ :FIRST-CHILD

Going back to the HTML family tree analogy for a moment, recall what a child tag is: any tag directly enclosed by another tag. (For example, in Figure 3-6, `<h1>`, `<div>`, `<h2>`, and `` are all children of the `<body>` tag.) The `:first-child` pseudo-element lets you select and format just the *first* of however many children an element may have.

In Figure 3-6, if you want to select the first `<h1>` tag on the page, create a selector like this:

```
h1:first-child
```

This selector applies to any `<h1>` tag that is a first child. In Figure 3-6, the results are obvious: there's only one `<h1>` tag and it's the first tag on the page. Therefore it's a child of the `<body>` element. However, `:first-child` can be confusing. For example, if you change the `<h2>` tag inside the `<div>` pictured in Figure 3-6 to an `<h1>` tag,

then `h1:first-child` would select both the `<h1>` directly inside the `<body>` tag and the `<h1>` inside the `div` (since that `<h1>` is the first-child of the `div`).

■ :LAST-CHILD

This is like `:first-child` discussed earlier, but just with the last child of an element. For example, to style the last item in a list, you use the `ul li:last-child` selector (see Figure 3-7).




FIGURE 3-7

CSS's wide range of child selectors gives you a variety of ways to select child elements. These selectors are great when you want to highlight the first, last, or an alternating number of items in a list.

■ NTH-CHILD

This complex selector is very useful. With it, you can easily style every other row in a table, every third list item, or style any combination of alternating child elements (see Figure 3-7). This selector requires a value to determine which children to select. The easiest option is a keyword—either `odd` or `even`—which lets you select alternating odd or even child elements. For example, if you want to provide one background color for each even row in a table and another color in the background of each odd-numbered row, you can write two styles like this:

```
tr:nth-child(odd) { background-color: #D9F0FF; }
tr:nth-child(even) { background-color: #FFFFFF; }
```

Now that's a really simple way to color alternating table rows (see Figure 3-8). But `:nth-child()` has even more power up its sleeve. You can also select, say, every third child element in a series, starting with the second child element. For example, suppose you want to highlight every third table cell (`<td>` tag) inside a row, starting with the second table cell (see Figure 3-8). Here's a style to achieve that:

```
tr td:nth-child(3n+2) { background-color:#900; }
```

Basically, the number before the `n` (3 in this case) represents which child element you're after. So, `3n` means every third element, while `4n` means every fourth element. The plus sign followed by a number (`+2` in this example) indicates which element to

start at, so +2 means start at the second child element, while +5 means start at the fifth child element. So `:nth-child(5n + 4)` selects every fifth child element starting at the fourth child element.

Alternating Table Rows

FIGURE 3-8

Table-striping the easy way: with child selectors. You can even stripe alternating columns by targeting every other <td> tag within a row, or, as in this case, every third column beginning with the second one. Now that's precision!

Child Type Selectors

CSS3 includes a selector that works much like the child selectors in the previous section but applies to children with a specific type of HTML tag. For example, say you want to format the first paragraph inside a sidebar in a particular way, but on some pages, that sidebar starts with an `<h2>` tag, and on other pages, it starts with a `<p>` tag. You can't use `:first-child` to select that paragraph, since in some cases it's the *second* child (following the `<h2>`). However, it's always the first paragraph (`<p>` tag) in that sidebar, even if other tags come before it, so you can select it with a type selector called **:first-of-type**.

NOTE `:last-child`, `:first-of-type`, and `:nth-child()` are supported in all modern browsers including Internet Explorer 9 and above. Alas, these don't work in IE 8.

■ :FIRST-OF-TYPE

Works just like `:first-child` but applies to a child that has a particular tag. For example, say you have a sidebar element with the class `sidebar`. To style the first paragraph in that sidebar, use this selector:

```
.sidebar p:first-of-type
```

Notice the `p` in `p:first-of-type`. It indicates the tag you're going to format.

■ :LAST-OF-TYPE

Works like `:last-child` but applies to the last instance of a particular type of tag. For example, if you want to format the last paragraph in the sidebar div in a particular way, but you're not sure whether there are other tags coming after the paragraph (like a bulleted list, headline, or image). Here's the style:

```
.sidebar p:last-of-type
```

NOTE Remember, these type selectors also have to be children of a particular tag. So `p:first-of-type` means “the first child that is a paragraph tag.”

■ :NTH-OF-TYPE

Works like `:nth-child()` but it applies to alternating children that have a specific tag. You may find this selector handy if you have something like a big paragraph of text that’s peppered with photos. The `` tag is an inline tag, so you can have a `<p>` tag with a bunch of `` tags inside it. And say you want to alternately float the images left and right, as shown in Figure 3-9. You can do so with these two styles:

```
img:nth-of-type(odd) { float: left; }
img:nth-of-type(even) { float: right; }
```


As you can see, you use the same keywords (`odd` or `even`) and formula (here, `2n + 1`) for `:nth-of-type()` as you do for `:nth-child()`.

In fact, you can use `:nth-of-type()` to select alternating table rows as well:

```
tr:nth-of-type(odd) { background-color: #D9F0FF; }
tr:nth-of-type(even) { background-color: #FFFFFF; }
```


In the case of CSS selectors, there’s always more than one way to skin an HTML tag—there are usually five or more! (Just keep in mind that none of these child type selectors are supported in Internet Explorer 8 or earlier.)

Type Selectors



Ullamco laboris nisi sed do eiusmod tempor incididunt excepteur sint occaecat. In reprehenderit in voluptate velit esse cillum dolore ut labore et dolore magna Ullamco laboris nisi mollit anim id est laborum. Cupidatat non proident, excepteur sint occaecat qui officia deserunt. Velit esse cillum dolore ut aliquip ex ea commodo consequat. Eu fugiat nulla pariatur. In reprehenderit in voluptate. In reprehenderit in voluptate lorem ipsum dolor sit amet, caliqua. Sunt in

culpa quis nostrud exercitation mollit anim id est laborum. Sed do eiusmod tempor incididunt lorem ipsum dolor sit amet, excepteur sint occaecat. Ut aliquip ex ea commodo consequat. Ut enim ad minim veniam, consectetur adipiscing elit, sed do eiusmod tempor



incididunt. Cupidatat non proident. Velit esse cillum dolore sed do eiusmod tempor incididunt ut enim ad minim veniam. Consectetur adipiscing elit, ullamco laboris nisi in reprehenderit in voluptate. Duis aute irure dolor quis nostrud exercitation eu fugiat nulla pariatur. Sed do eiusmod tempor incididunt consectetur adipiscing elit, ut labore et dolore magna aliqua. In reprehenderit in voluptate

ut aliquip ex ea commodo consequat. Sunt in culpa sed do eiusmod tempor incididunt duis aute irure dolor. Ut enim ad minim veniam, lorem ipsum dolor sit amet, ullamco laboris nisi. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Quis nostrud exercitation consectetur adipiscing elit, in reprehenderit in voluptate. upidatat non proident. Ut enim ad minim veniam, consectetur adipiscing elit, sunt in culpa.




FIGURE 3-9

With the `:nth-of-type()` selector, you can easily select every other image inside a tag, alternating between left and right alignment.

FREQUENTLY ASKED QUESTION

Making Lists Look Great

When would I ever use a child selector? Just from reading this chapter, I already know enough selectors to get at just about any page element, so why learn another?

There's one design challenge where child selectors can't be beat—and it comes up in more websites than you think. Any time you have an unordered list with one or more unordered lists nested inside (as in Figure 3-6), you can use child selectors to visually organize these categories and subcategories of information. You can format the first level of list items one way, and the second level of list items another way. Content presented in this manner looks neat, professional, and readable (and your visitors will love you for it).

First, create a class style for the outermost nested level in your list and call it, say, `.mainList`. For this top level, you might use a sans-serif font, a little larger than your other text, perhaps in bold or a different color. Subsequent categories can be smaller, in a serif font like Times for easiest reading. When you have a lot of text, styling each subcategory level a bit differently helps visually orient your visitors in the material.

Apply the `.mainList` class style to the first `` tag: `<ul class="mainList">`. Then use a child selector (`ul.mainList > li`) to select just the first set of list items, and add your desired text styling for the first subcategory. This styling applies to the `` tags that are children of the `` tag with the `.mainList` style applied to it. Then, to style the child `` tags of any subsequent nested `` tags use this selector `ul.mainList > li > ul > li`. (A descendent selector like `ul li`, by contrast, selects the list items of all unordered lists on the page—nested ones and all.)

You'll need to keep a concept you'll learn in the next chapter—inheritance—in mind. Basically, certain CSS properties applied to one tag are inherited by tags inside them. So even if you use a child selector to target the children of one tag, properties may pass on to other tags inside that child. The `:not()` selector, discussed on page 80, is one way to avoid this.

Siblings

Parent-child relationships aren't the only ones in the HTML family tree. Sometimes you need to select a tag based not on its parent tag but on its surrounding siblings—the tags that share a common parent. A tag that appears immediately after another tag in HTML is called an *adjacent sibling*. In Figure 3-6, the `<div>` tag is the adjacent sibling of the `<h1>` tag, the `<p>` tag is the adjacent sibling of the `<h2>` tag, and so on.

Using an adjacent sibling selector, you can, for example, give the first paragraph after each heading different formatting from the paragraphs that follow. Suppose you want to remove the margin that appears above that `<p>` tag so that it sits right below the heading without any gap. Or perhaps you want to give the paragraph a distinct color and font size, like a little introductory statement.

The adjacent sibling selector uses a plus sign (+) to join one element to the next. So to select every paragraph following each `<h2>` tag, use this selector: `h2 + p` (spaces are optional, so `h2+p` works as well). The last element in the selector (`p`, in this case) is what gets the formatting, but only when it's directly after its brother `<h2>`.

There's another sibling selector called the *general sibling combinatory selector* (say that three times fast). It's simply a ~ (tilde) and it means "select all siblings of this type." For example, while `h2 + p` selects a single `<p>` tag that immediately follows an `<h2>` tag, `h2 ~ p` selects *all* `<p>` tags that are siblings (that is, on the same level) of the `h2`. To be honest, you may never find a good use for this selector, but CSS is nothing if not thorough.

■ The :not() Selector

The `:not()` selector, also called the negation pseudo-class, lets you select something that's not something else. For example, you can use it to apply a class to a paragraph—`<p class="classy">`—and create a CSS class selector to format it, like this:

```
.classy { color: red; }
```

But what if you want to select all paragraphs, except the `classy` paragraphs? That's where the `:not()` selector comes in. You put a CSS selector inside the parentheses to indicate what you *don't* want to select. For example:

```
p:not(.classy) { color: blue; }
```

This style makes the text color blue for all paragraphs that do not have the `classy` class applied to them.

The `:not()` selector can come in handy when you're using attribute selectors discussed on page 72. For example, you saw on page 73 that you can use an attribute selector to pick all links that point outside your website, like this:

```
a[href^="http://"]
```

As you've probably noticed, that selector doesn't specifically select all links that point outside your site, it simply selects all links that use absolute URLs—that is, URLs beginning with `http://`. For many sites, that's the same thing; many sites use document- or root-relative links to point to other pages within the site, and absolute URLs to link to other sites. However, in some cases, you may use absolute URLs to point to pages within your site.

For example, some content management systems (WordPress, for example) use absolute URLs to point to blog posts within the site. In this case, if you want to style links that point outside your site, you need to refine the basic attribute selector by also employing the `:not()` selector. For example, say your site's domain name is `mysite.com`. To select links that point outside your site, you'll want to select all absolute links that *don't* point to the domain `mysite.com`. Here's how you would do that:

```
a[href^="http://"]:not([href^="http://mysite.com"])
```

Translated into English, this selector says “Select all links, whose href attribute begins with `http://`, but *not* ones that begin with `http://mysite.com`.” As you’ll recall from page 72, in an attribute selector, `^=` means “begins with.” A shorter way to write the same thing would be this:

```
a[href^="http://"]:not([href*="mysite.com"])
```

In an attribute selector `*=` means “contains,” so this would exclude any absolute URL that contains `mysite.com`. This would include `http://www.mysite.com` as well as `http://mysite.com`.

There are some limitations to the `:not()` selector:

- You can only use *simple selectors* with the `:not()` selector. In other words you can use element selectors (like `html`, or `p`), the universal selector (`*` [see page 63]), classes (`.footer`, for example), IDs (`#banner`, for example), or pseudo-classes (`:hover`, `:checked`, `:first-child`, and so on). So the following are all valid:

```
.footnote:not(div)
img:not(.portrait)
div:not(#banner)
li:not(:first-child)
```

- You can’t use descendent selectors (like `div p a`), pseudo-elements (like `::first-line`), group selectors, or combinators (like the adjacent sibling selector `h2 + p`).
- You can’t string multiple `:not()` selectors together. For example, the following is invalid:

```
a[href^="http://"]:not([href*="google.com"]):not([href="yahoo.com"])
```

In other words, you can only use `:not()` once with a selector.

■ Tutorial: Selector Sampler

In the rest of this chapter, you’ll create a variety of selector types and see how each affects a web page. This tutorial starts with the basic selector types and then moves on to more advanced styles.

To get started, you need to download the tutorial files located on this book’s companion website at www.sawmac.com/css3. Click the tutorial link and download the files. All of the files are enclosed in a zip archive, so you’ll need to unzip them first. (Detailed instructions for unzipping the files are on the website.) The files for this tutorial are contained inside the folder named `03`.

INDIGNANTLY ASKED QUESTION

Keeping It Internal

Hey, what's up with the internal style sheet in this tutorial? Chapter 2 recommends using external style sheets for a bunch of reasons.

Think you're pretty smart, eh? Yes, external style sheets usually make for faster, more efficient websites, for all the reasons mentioned in Chapter 2. However, internal style sheets make your life easier when you're designing a single page at a time, as in this tutorial. You get to work in just one web page file instead of flipping back and forth between the external style sheet file and the web page.

Furthermore, you can preview your results without constantly refreshing your browser's cache; flip back to the box on page 39 for more on that quirkiness.

Many web designers like to begin their designs with an internal style sheet, since it's faster and avoids any problems with all that cache nonsense. Here's their secret: Once they've perfected their design, they simply cut the code from the internal style sheet, paste it into an external style sheet, and then link the style sheet to their site's pages as described on page 42.

1. Open *selector_basics.html* in your favorite text editor.

This page is made of very basic HTML tags. The most exciting thing about it is the graphic banner (see Figure 3-10). But you'll liven things up in this tutorial. You'll start by adding an internal style sheet to this file.

2. Click directly after the closing `</title>` tag, hit Enter (Return), and type `<style>`. Press Enter twice and then type `</style>`.

These are the opening and closing style tags—it's a good idea to type both tags at the same time, so you don't accidentally forget to add the closing `</style>` tag. Together, these two tags tell a web browser that the information between them is Cascading Style Sheet instructions. The HTML should now look like this (the stuff you added is in bold):

```
<title>Selector Basics</title>  
<style>  
  
</style>  
</head>
```

Type selectors—such as the tag selector you're about to create—are the most basic type of selector. (If you completed the tutorial in the last chapter, you've already created a few.)

**FIGURE 3-10**

Plain HTML looks cold and monotonous in a web browser. But with a little CSS, you can turn drab (shown here) into fab (Figure 3-11) in 31 easy steps.

NOTE

If you're using HTML 4.01 or XHTML doctypes (instead of HTML5), you'll need to add the `type="text/css"` attribute to the opening style tag like this:

```
<style type="text/css">
```

3. Click between the opening and closing style tags you just added and type `p {`, hit return twice, and type the closing `}`.

It's a good idea to always add the closing brace immediately after typing the opening brace, just so you don't forget. To create a tag selector, simply use the name of the HTML tag you wish to format. This style applies to all paragraphs of text within `<p>` tags.

4. **Click between the style’s opening and closing braces ({ }) and add the following four CSS properties to supply the style’s formatting—color, size, font, and left indent:**

```
p {  
  color: #505050;  
  font-size: 1em;  
  font-family: "Helvetica Neue", Arial, Helvetica, sans-serif;  
  margin-left: 100px;  
}
```

Press Enter to place each CSS property on its own line. It’s also a good idea to visually organize your CSS code by indenting each property with the Tab key (some designers use two spaces instead of a tab—it’s up to you).

NOTE These property names and their values may look unfamiliar. For now, just type them as is. You’ll learn what 1em and 100px mean, along with all the ins and outs of text-formatting properties, in Chapter 6.

Your style sheet is complete. Time for a look-see.

5. **Open the page in a web browser to preview your work.**

Unless you tinker with the preference settings, most browsers display black text in a standard serif font like Times. If your CSS style works properly, then you should see seven indented paragraphs in a sans-serif font in a darkish gray color.

Creating a Group Selector

Sometimes you’ll want several different elements on a page to share the same look. For instance, you may want all your headings to have the same font and color for a consistent style. Instead of creating separate styles and duplicating the same property settings for each tag—<h1>, <h2>, and so on—you can group the tags together into a single selector.

1. **Return to your text editor and the *selector_basics.html* file.**

You’ll add a new style below the <p> tag style you just created.

2. **Click at the end of the closing brace of the tag selector, press Enter to start a new line, and the following code:**

```
h1, h2, h3 {  
  
}
```

As explained earlier in this chapter, a group selector is simply a list of selectors separated by commas. This rule applies the same formatting, which you’ll add next, to all <h1>, <h2>, and <h3> tags on the page.

3. Click in the empty line between the opening { and closing } and add five CSS properties:

```
color: #BD8100;  
font-family: Baskerville, "Palatino Linotype", Times, serif;  
border-top: 2px solid #86A100;  
padding-top: 7px;  
padding-left: 100px;
```

There's a lot going on here, but basically you're setting the color and font type for the headlines, adding a border line above the headlines for visual interest, and controlling the top and left spacing by using the padding property. In a nutshell, this property adds space from the edges of an element without affecting a background or border—you're scooting the headline text in from the left and down from the top without moving the border line that spans the entire page.

4. Save the file, and preview it in a web browser.

The <h1> heading near the top of the page and the <h2> and <h3> headings lower on the page all have the same font and font color as well as a green border along their tops (see Figure 3-11).

Creating and Applying a Class Selector

Tag selectors are quick and efficient, but they're a bit indiscriminate in how they style a page. What if you want to style a single <p> tag differently than all the other <p> tags on a page? A class selector is the answer.

1. Return to your text editor and the *selector_basics.html* file.

Add a new style below the group selector style you just created.

2. Click at the end of the closing brace of the h1, h2, h3 selector, press Enter (Return), and then type

```
.note {  
  
}
```

This style's name, *note*, indicates its purpose: to highlight paragraphs that contain extra bits of information for your site's visitors. Once you create a class style, you can apply it wherever these notes appear—like the second paragraph, in this case.




FIGURE 3-11

A simple tag selector can completely transform the appearance of every instance of a tag, making quick work of styling all the paragraphs of text on a page. And in this case a group selector does even more by formatting every instance of three different headline tags!

3. Click in the empty line between the opening { and closing } and add the following list of properties to the style:

```
color: #333;
border: 2px dashed #BD8110;
background-color: #FBF8A9;
margin-top: 25px;
margin-bottom: 35px;
padding: 20px;
```

Most of these properties should look familiar by now, but the background-color property may be new to you. Logically enough, it adds a color to the background of the element. The completed style should look like this:

```
.note {  
  color: #333;  
  border: 2px dashed #BD8110;  
  background-color: #FBF8A9;  
  margin-top: 25px;  
  margin-bottom: 35px;  
  padding: 20px;  
}
```

If you preview the page now, you see no changes. Unlike tag selectors, class selectors don't have any effect on a web page until you apply the style in the HTML code.

4. In the page's HTML, there are two <p> tags that begin with the word "Note" inside tags.

To apply a class style to a tag, simply add a class attribute, followed by the class selector's name—in this case, the note style you just created.

5. Click just after the p in the first <p> tag, and then type a space followed by class="note". The HTML should now look like this (what you just typed is in bold):

```
<p class="note" ><strong>NOTE:</strong> Ut enim ad
```

Be sure *not* to type class=".note". In CSS, the period is necessary to indicate a class style name; in HTML, it's verboten. Repeat this step for the second paragraph (it's just above the <h3> tag with the text "Not Me!").

NOTE

There's no reason you can't add this class to other tags as well, not just the <p> tag. If you happen to want to apply this formatting to an <h2> tag, for example, then your HTML would look like this: <h2 class="note">.

6. Save and preview the web page in a browser.

The note paragraph is nicely highlighted on the page (see Figure 3-12).



FIGURE 3-12

You can make detailed formatting changes with class selectors. A class style gives selected paragraphs different formatting from all other paragraphs on the page. The distinctive note box pictured here uses a class style to stand out from the crowd.

NOTE

If your page doesn't look like Figure 3-12, then you may have mistyped the name of a property or its value. Double-check your code with the steps above. Also, make sure to end each declaration—property: value combination—with a semicolon and conclude the style with a closing brace at the very end. When your style is not working correctly, missing semicolons and closing braces are frequent culprits.

Creating a Descendent Selector

On the [selectors_basics.html](#) page, you applied the note class to two paragraphs. Each of those paragraphs begins with the word “Note:” in bold—actually the word is wrapped inside the HTML `` tag, which all browsers display as bolded text. But what if you want to format those bolded words in bright orange? You could create a tag style for the `` tag, but that would affect all `` tags on the page, and you only want to change the strong tag inside those note boxes. One solution would be to create a class style—.noteText, for example—and apply it to each of the `` tags inside the note boxes. But that's a lot of work, and you might forget to apply the class if you have a lot of pages with those notes.

A better method is to create a descendent selector (page 88), which targets only the `` tag when it's inside one of these note boxes. Fortunately, that's easy to do.

1. **Return to your text editor and the `selector_basics.html` file.** Create a new empty line for the descendent selector style.

If you just completed the previous steps, click after the closing brace of the `.note` style, and then hit Enter (Return).

2. **Type `.note strong {`.**

The last tag in the selector—`strong`—is the element you ultimately want to format. In this case, the style formats the `` tag only when it's *inside* another tag with the class `note` applied to it. It has no effect on `` tags inside other paragraphs, lists, or heading tags, for example.

3. **Hit Enter, type `color: #FC6512;`, and then hit Enter (Return) again to create another blank line.** Finish the style by typing the closing brace character.

The finished style should look like this:

```
.note strong {  
  color: #FC6512;  
}
```

4. **Save the page and preview it in a web browser.**

The word “Note:” should appear in orange in each of the note boxes on the page.

Descendent selectors are among the most powerful CSS tools. Professional web designers use them extensively to target particular tags without littering the HTML with CSS classes. You'll learn a lot more about descendent selectors as they're used throughout this book.

Creating and Applying an ID Selector

You can apply class selectors to multiple elements on a page. For example, earlier you created a `.note` class style and applied it to two paragraphs, but you could apply it to even more paragraphs (or even other tags) if you wanted to. ID selectors look and act just like classes, but you can apply an ID only *once* per page. As mentioned on page 61, many web designers now shy away from ID selectors (you'll learn exactly why on page 114). However, that doesn't mean you shouldn't learn how to use them.

In this exercise, you'll create a style that sets a specific width for a web page's content, centers it in the middle of the browser window, and adds a decorative background image to the page. You'll apply the ID to the page's `<body>` tag to indicate a unique page design.

1. **Return to your text editor and the `selector_basics.html` file.**

You'll add a new style below the `.note strong` class style you created before.

2. **Click after the previous style's closing bracket (}), hit Enter (Return) to create a new line, and then type #article {.**

ID selectors always begin with the pound symbol (#). The style's name indicates which type of page this is—it's common on websites to have different designs for different types of web pages. For example, the home page will look different from a page advertising a product, which may look different from a page with the text of a blog post. In this case, you're going to identify this page as an "article" (as in a newspaper) by creating and applying an ID to the <body> tag.

3. **Hit Enter again, and then type:**

```
background-color: #FDF8AB;
background-image: url(images/bg_page.png);
background-repeat: repeat-y;
background-position: center top;
padding: 0;
margin: 0 auto;
width: 760px;
```

There are a lot of properties here, but basically you're adding a color to the page, inserting an image in the background (and controlling how it's positioned), removing space around the browser window's edges, setting a fixed width for the page's content, and centering everything in the middle of the page.

4. **Finish the style by typing the closing brace.** The whole thing should look like this:

```
#article {
  background-color: #FDF8AB;
  background-image: url(images/bg_page.png);
  background-repeat: repeat-y;
  background-position: center top;
  padding: 0;
  margin: 0 auto;
  width: 760px;
}
```

Just as with a class, this style doesn't *do* anything until you apply it to the page. So you'll add an ID attribute to the page's HTML, indicating where you want the ID style to apply.

5. **Find the page's opening <body> tag and add id="article" so that the tag looks like this (your changes are in bold):**

```
<body id="article" >
```

Now the <body> tag reflects the formatting defined in the #article style. As with all things CSS, there are many ways to arrive at the same destination: You can instead use a class style and apply it to the <body> tag (as long as you don't apply it more than once on the page; otherwise any other elements with the

article class will get that same formatting). You can even create a plain body element style with the same formatting properties as long as all the other pages on your site share these same formatting choices. But in this case, you're using an ID selector since the point of this style—identifying the type of page—is in keeping with the general notion of ID selectors.

6. Save the page, and preview it in a browser.

Everything on the page (the logo and all the text) now has a set width and floats in the center of the browser window. Even if you resize the browser window—try it!—the content remains centered. In addition, a drop shadow appears on either side of the content, thanks to the handy `background-image` property (you'll learn about that cool property in depth on page 240).

Finishing Touches

For fun, you'll add one more advanced style—an adjacent sibling selector discussed on page 79—to format the paragraph immediately following the first headline on the page. (You can achieve the same effect by creating a class style and applying it to that paragraph, but the adjacent sibling selector requires no changes to your HTML.)

1. **Return to your text editor and the `selector_basics.html` file.** Create a new empty line for a new style.

If you just completed the previous steps, click after the closing brace of the `#article` style, and then hit Enter (Return).

2. **Type `h1+p {`.**

This style will apply to any paragraph that *immediately* follows an `<h1>` tag—in other words, the first paragraph after the top headline on the page. It won't apply to the second or any subsequent paragraphs. This selector provides an easy way to create a unique look for an introductory paragraph to set it off visually and highlight the beginning of an article.

3. **Hit Enter, and then add the following list of properties to the style:**

```
color: #FF6600;  
font-size: 1.2em;  
line-height: 140%;  
margin-top: 20px;
```

Here you're changing the font color and size as well as adding a bit of space above the paragraph. The `line-height` property (which you'll read about on page 167) controls the space between lines in a paragraph (also known as *leading*).

4. **Finally, complete the style by pressing Enter and typing the closing brace.** The completed class style should look like this:

```
h1+p {  
  color: #FF6600;  
  font-size: 1.2em;
```

```
line-height: 140%;
margin-top: 20px;
}
```

If you preview the page now, you'll see that the top paragraph is orange and the text is larger and there's more space between each line of text (see Figure 3-13). If you actually deleted this paragraph in the HTML, you'd see that the remaining paragraph would suddenly be orange with larger text, since it would be the new adjacent sibling of the <h1> tag.

NOTE Internet Explorer 6 doesn't understand adjacent sibling selectors, so in that browser, the first paragraph will look just like all the others on the page.

And there you have it: a quick tour through various selector types. You'll get familiar with all of these selectors (and more) as you go through the tutorials later in the book, but by now, you should be getting the hang of the different types and why you'd use one over the other.

NOTE You can see a completed version of the page you've just created in the *03_finished* folder.




FIGURE 3-13
The page has really come together. The set width, the drop shadow effect, and the typographic details have really improved the look of the boring HTML page you started with.

Saving Time with Style Inheritance

Children inherit traits from their parents—eye color, height, male-pattern baldness, and so on. Sometimes, we inherit traits from more distant ancestors, like grandparents or great-grandparents. As you saw in the previous chapter, the metaphor of family relations is part of the structure of HTML as well. And just like humans, HTML tags can inherit CSS properties from their ancestors.

■ What Is Inheritance?

In a nutshell, inheritance is the process by which some CSS properties applied to one tag are passed on to nested tags. For example, a `<p>` tag is always nested inside of the `<body>` tag, so properties applied to the `<body>` tag get inherited by the `<p>` tag. Say you created a CSS tag style (page 62) for the `<body>` tag that sets the `color` property to a dark red. Tags that are descendants of the `<body>` tag—that is, the ones inside the `<body>` tag—will inherit that color property. That means that any text in those tags—`<h1>`, `<h2>`, `<p>`, whatever—will appear in that same dark red color.


Inheritance works through multiple generations as well. If a tag like the `` or `` tag appears inside of a `<p>` tag, then the `` and the `` tags also inherit properties from any style applied to the `<body>` tag.

NOTE As discussed in Chapter 3, any tag inside of another tag is a *descendant* of that tag. So a `<p>` tag inside the `<body>` tag is a descendant of the `<body>`, while the `<body>` tag is an *ancestor* of the `<p>` tag. *Descendants* (think kids and grandchildren) inherit properties from ancestors (think parents and grandparents).

Although this sounds a bit confusing, inheritance is a *really* big timesaver. Imagine if no properties were passed onto nested tags and you had a paragraph that contained other tags like the `` tag to emphasize text or the `<a>` tag to add a link. If you created a style that made the paragraph purple, 24px tall, using the Arial font, it would be weird if all the text inside the `` tag reverted to its regular, “browser boring” style (see Figure 4-1). You’d then have to create another style to format the `` tag to match the appearance of the `<p>` tag. What a drag.

FIGURE 4-1

Inheritance lets tags copy properties from the tags that surround them. Top: The paragraph tag is set with a specific font-family, size, and color. The tags inside each paragraph inherit those properties so they look like the rest of the paragraph. Bottom: If inheritance didn't exist, the same page would look like this figure. Notice how the `strong`, `em`, and `a` tags inside the paragraph retain the font-family, size, and color defined by the browser. To make them look like the rest of the paragraph, you'd have to create additional styles—a big waste of time.



CosmoFarmer.com Projects

High Rise Project: Raised Bed Gardening

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent luptatum zzril delenit a

Step 1: Get Your Materials

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent luptatum zzril delenit a

Step 2: Waterproof Your Floor

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent luptatum zzril delenit a



CosmoFarmer.com Projects

High Rise Project: Raised Bed Gardening

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent luptatum zzril delenit a

Step 1: Get Your Materials

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent luptatum zzril delenit a

Step 2: Waterproof Your Floor

Lorem ipsum dolor sit amet, consectetur adipiscing elit, sed diam nonummy nibh euismod tincidunt ut laoreet dolore magna aliquam erat volutpat. Ut wisi enim ad *minim veniam*, quis nostrud exerci tation ullamcorper suscipit lobortis nisl ut aliquip ex ea commodo consequat. Duis autem vel eum iriure dolor in hendrerit in vulputate velit esse molestie consequat, vel illum dolore eu feugiat nulla facilisis at vero eros et accumsan et iusto odio dignissim qui blandit praesent

Inheritance doesn't just apply to tag styles. It works with any type of style; so when you apply a class style (see page 57) to a tag, any tags inside that tag inherit properties from the styled tag. Same holds true for ID styles, descendant selectors, and the other types of styles discussed in Chapter 3.

■ How Inheritance Streamlines Style Sheets

You can use inheritance to your advantage to streamline your style sheets. Say you want all the text on a page to use the same font. Instead of creating styles for each tag, simply create a tag style for the `<body>` tag. (Or create a class style and apply it to the `<body>` tag.) In the style, specify the font you wish to use, and all of the tags on the page inherit the font: `body { font-family: Arial, Helvetica, sans-serif; }`. Fast and easy.

You can also use inheritance to apply style properties to a *section* of a page. For example, like many web designers, you may use the `<div>` tag (page 21) to define an area of a page like a banner, sidebar, or footer; or, if you're using HTML5 elements, you might use one of the new sectioning elements like `<header>`, `<aside>`, `<footer>`, or `<article>`. By applying a style to that outer tag, you can specify particular CSS properties for all of the tags inside just that section of the page. If you want all the text in a sidebar to be the same color, you'd create a style setting the `color` property, and then apply it to the `<div>`, `<header>`, `<article>`, or other sectioning element. Any `<p>`, `<h1>`, or other tags inside inherit the same font color.

■ The Limits of Inheritance

Inheritance isn't all-powerful. Many CSS properties don't pass down to descendant tags at all. For example, the `border` property (which lets you draw a box around an element) isn't inherited, and with good reason. If it were, then every tag inside an element with the `border` property would also have a border around it. For example, if you added a border to the `<body>` tag, then every bulleted list would also have a box around it, and each bulleted item in the list would also have a border (Figure 4-2).

NOTE

There's a list of CSS properties in Appendix A, including details on which ones get inherited.

Here are examples of times when inheritance doesn't strictly apply:

- As a general rule, properties that affect the placement of elements on the page or the margins, background colors, and borders of elements aren't inherited.




FIGURE 4-2

Fortunately, not all properties are inherited. The border applied to the paragraphs at top isn't inherited by the tags inside those paragraphs. If they were, you'd end up with an unattractive mess of boxes within boxes within boxes (bottom).

- Web browsers use their own inherent styles to format various tags: Headings are big and bold, links are blue, and so on. When you define a font-size for the text on a page and apply it to the <body> tag, headings still appear larger than paragraphs, and <h1> tags are still larger than <h2> tags. It's the same when you apply a font color to the <body>; the links on the page still appear in good old-fashioned, web-browser blue.

NOTE

It's usually a good idea to eliminate these built-in browser styles—it'll make designing sites that work consistently among different browsers easier. In Chapter 5, on page 115, you'll learn how to do that.

- When styles conflict, the more specific style wins out. In other words, when you've specifically applied CSS properties to an element—like specifying the font size for an unordered list—and those properties conflict with any inherited properties—like a font-size set for the `<body>` tag—the browser uses the font size applied to the `` tag.

NOTE

These types of conflicts between styles are very common, and the rules for how a browser deals with them are called the *cascade*. You'll learn about that in Chapter 5.

Tutorial: Inheritance

In this three-part tutorial, you'll see how inheritance works. First, you'll create a simple tag selector and watch it pass its characteristics on to nested tags. Then, you'll create a class style that uses inheritance to alter the formatting of an entire page. Finally, you'll see where CSS makes some welcome exceptions to the inheritance rule.

To get started, you need to download the tutorial files located on this book's companion website at www.sawmac.com/css3. Click the tutorial link and download the files. All of the files are enclosed in a zip archive, so you'll need to unzip them first. (Detailed instructions for unzipping the files are on the website.) The files for this tutorial are contained in the folder named *04*.

A Basic Example: One Level of Inheritance

To see how inheritance works, start by adding a single tag style and see how it affects the tags nested inside. The next two parts of this tutorial will build upon your work here, so save the file when you're done.

1. Open the file *inheritance.html* in your favorite text editor.

Now add an internal style sheet to this file.

NOTE

In general, it's better to use external style sheets for a website, for reasons discussed in Chapter 2 (page 48). But sometimes it's easier to start your CSS-based design in an internal style sheet, as in this example, and turn it into an external style sheet later.

- #### 2. Click directly after the closing `</title>` tag.
- Hit Enter (Return), and then type `<style>`. Press Enter twice, and type the closing tag `</style>`—to indicate the end of the style sheet.

These tags mark the area where CSS instructions go.

Now, you'll create a style that applies to all `<p>` tags.

NOTE

If you're using HTML 4.01 or XHTML doctypes (instead of HTML5 as in this tutorial) you'll need to add the `type="text/css"` attribute to the opening style tag like this:

```
<style type="text/css">
```

- 3. Click in the empty line between the opening and closing `<style>` tags and type `p {`.** Hit Enter twice and type the closing brace: `}`.

You've created a tag selector that applies to all `<p>` tags on the page.

- 4. Click between the two braces and type `color: #FF6600;`.** The completed style should look like this:

```
p {  
  color: #FF6600;  
}
```

As you've seen in the previous tutorials, the `color` property sets the color of text. Your style sheet is complete.

- 5. Open the page in a web browser to preview your work.**

The color of the page's four paragraphs has changed from black to orange (see Figure 4-3).

But notice how this `<p>` tag style affects *other* tags: Tags *inside* of the `<p>` tag also change color. For example, the text inside the `` and `` tags inside each paragraph also changes to orange while maintaining its italic and bold formatting. This kind of behavior makes a lot of sense. After all, when you set the color of text in a paragraph, you expect *all* the text in the paragraph—regardless of any other tags inside that paragraph—to be the same color.

Without inheritance, creating style sheets would be very labor intensive. If the `` and `` tags didn't inherit the color property from the `<p>` tag selector, then you'd have to create additional styles—perhaps descendant selectors like `p em` and `p strong`—to correctly format the text.

However, you'll notice that the link at the end of the first paragraph doesn't change color—it retains its link-blue color. As mentioned on page 96, browsers have their own styles for certain elements, so inheritance doesn't apply. You'll learn more about this behavior in Chapter 5.

Using Inheritance to Restyle an Entire Page

Inheritance works with class styles as well—any tag with any kind of style applied to it passes CSS properties to its descendants. With that in mind, you can use inheritance to make quick, sweeping changes to an entire page.

- 1. Return to your text editor and the *inheritance.html* file.**


You'll add a new style below the `<p>` tag style you created.

2. **Click at the end of the closing brace of the p selector.** Press Enter (Return) to create a new line, and then type `.pageStyle {`. Hit Enter twice, and type the closing brace: `}`.

You're about to create a new class style that you'll apply to the body tag.

3. **Click between the two braces, and then add the following list of properties to the style:**

```
font-family: "Helvetica Neue", Arial, Helvetica, sans-serif;
font-size: 18px;
color: #BD8100;
width: 900px;
margin: 0 auto;
```



The whole thing should look like this:

```
.pageStyle {
  font-family: "Helvetica Neue", Arial, Helvetica, sans-serif;
  font-size: 18px;
  color: #BD8100;
  width: 900px;
  margin: 0 auto;
}
```

This completed class style sets a font, font size, and color. It also sets a width and centers the style on the page (you saw this trick in the previous tutorial on page 90 for creating a fixed, centered area for a page's content).

4. Find the opening `<body>` tag (just a couple lines below the style you just created), and then type `class="pageStyle"`.

The tag should now look like this: `<body class="pageStyle">`. It applies the class to the body tag. Thanks to inheritance, all tags inside of the body tag (which are also all the tags visible inside a browser window) inherit this style's properties and therefore use the same font.

5. Save and preview the web page in a browser.


As you can see in Figure 4-4, your class style has created a seamless, consistent appearance throughout all text in the body of the page. Both headings and paragraphs inside the `<body>` tag have taken on the new font styling.

The page as a whole looks great, but now look more closely: The color change affected only the headings and the bulleted list on the page, and even though the style specified an exact font-size, the headline text is a different size than the paragraphs. How did CSS know that you didn't want your headings to be the same 18-pixel size as the body text? And why didn't the nested `<p>` tags inherit your new color styling from the `<body>` tag?

NOTE

Why use a class—`pageStyle`—instead of a tag style—`body`—to redefine the look of the page? Well, in this case, a tag style would work fine. But, applying a class to the `<body>` tag is a great way to customize the look of different pages on your site. For example, if all pages on your site share the same external style sheet, a body tag style would apply to the `<body>` tag of every page on your site. But by creating different classes (or IDs) you can create a different style for the `<body>` tag for different sections of the site or different types of pages.

You're seeing the "cascading" aspect of Cascading Style Sheets in action. In this example, your `<p>` tags have two color styles in conflict—the `<p>` tag style you created on page 98 and the class style you created here. When styles collide, the browser has to pick one. As discussed on page 104, the browser uses the more specific styling—the color you assigned explicitly for `<p>` tag. You'll learn much more about the rules of the cascade in Chapter 5.

**FIGURE 4-4**

A style applied to the `body` tag passes its properties onto all the tags you see in the web browser, making it easy to apply global formatting effects to a page.

Inheritance Inaction

Inheritance doesn't always apply, and that isn't necessarily a bad thing. For some properties, inheritance would have a negative effect on a page's appearance. You'll see another example of inheritance *in action* in the final section of this tutorial. Margins, padding, and borders (among other properties) don't get inherited by descendant tags—and you wouldn't want them to, as you'll see in this example.

1. Return to your text editor and the *inheritance.html* file.

You'll expand on the `p` tag style you just created.

2. Locate the `p` style, click at the end of the color property (`color : #FF6600;`), and then press **Enter (Return)** to create a new line.

You'll indent the paragraphs on the page by adding a left margin.

3. Add three properties to the style so that it looks like this:

```
p {
  color: #FF6600;
  margin-left: 50px;
  padding-left: 20px;
  border-left: solid 25px #BD8100;
}
```

The `margin-left` property indents the paragraph 50 pixels from the left; the `padding` property indents the paragraph text 20 pixels from the border.

4. Save the file and preview it in a web browser.

Notice that all of the `<p>` tags are indented 50px from the left edge of the browser window and that they each have a thick brown border on the left. However, the tags *inside* the `<p>` tag (for example, the `` tag) don't have any additional indentation or border (see Figure 4-5). This behavior makes sense: It would look weird if there were an additional 50px of space to the left of each `` and each `` tag inside of a paragraph!

To see what would happen if those properties were inherited, edit the `p` selector so that it looks like this: `p, p *`, which makes it into a group selector (page 84). The first part is just the `p` selector you already created. The second part—`p *`—means “select all tags inside of a `p` tag and apply this style to them.” (The `*`, or universal selector, is described on page 63.)




FIGURE 4-5

While most properties are inherited (like color), there are plenty—like margins, padding, and borders—that don't pass on to nested tags. The CSS Property Reference in Appendix A indicates which properties are and are not inherited.

NOTE You can find a completed version of the page you created in this tutorial in the `04_finished` folder.

Managing Multiple Styles: The Cascade

As you create increasingly complex style sheets, you'll sometimes wonder why a particular element on a page looks the way it does. CSS's inheritance feature, as discussed in Chapter 4, creates the possibility that any tag on a page is potentially affected by any of the tags that wrap around it. For example, the `<body>` tag can pass properties on to a paragraph, and a paragraph may pass its own formatting instructions on to a link within the paragraph. In other words, that link can inherit CSS properties from *both* the `<body>` and the `<p>` tag—essentially creating a kind of Frankenstyle that combines parts of two different CSS styles.

Then there are times when styles collide—the same CSS property is defined in multiple styles, all applying to a particular element on the page (for example, a `<p>` tag style in an external style sheet and another `<p>` tag style in an internal style sheet). When that happens, you can see some pretty weird stuff, like text that appears bright blue, even though you specifically applied a class style with the text color set to red. Fortunately, there's actually a system at work: a basic CSS mechanism known as the *cascade*, which governs how styles interact and which styles get precedence when there's a conflict.

NOTE

This chapter deals with issues that arise when you build complex style sheets that rely on inheritance and more sophisticated types of selectors like descendent selectors (page 88). The rules are all pretty logical, but they're about as fun to master as the tax code. If that's got your spirits sagging, consider skipping the details and doing the tutorial on page 117 to get a taste of what the cascade is and why it matters. Or jump right to the next chapter, which explores fun and visually exciting ways to format text. You can always return to this chapter later, after you've mastered the basics of CSS.

■ How Styles Cascade


The *cascade* is a set of rules for determining which style properties get applied to an element. It specifies how a web browser should handle multiple styles that apply to the same tag and what to do when CSS properties conflict. Style conflicts happen in two cases: through inheritance when the same property is inherited from multiple ancestors, and when one or more styles apply to the same element (maybe you've applied a class style to a paragraph and also created a `<p>` tag style, so both styles apply to that paragraph).

Inherited Styles Accumulate

As you read in the last chapter, CSS inheritance ensures that related elements—like all the words inside a paragraph, even those inside a link or another tag—share similar formatting. It spares you from creating specific styles for each tag on a page. But since one tag can inherit properties from *any* ancestor tag—a link, for example, inheriting the same font as its parent `<p>` tag—determining why a particular tag is formatted one way can be a bit tricky. Imagine a font family applied to the `<body>` tag, a font size applied to a `<p>` tag, and a font color applied to an `<a>` tag. Any `<a>` tag inside of a paragraph would inherit the font from the body and the size from the paragraph. In other words, the inherited styles combine to form a hybrid style.

The page shown in Figure 5-1 has three styles: one for the `<body>`, one for the `<p>` tag, and one for the `` tag. The CSS looks like this:

```
body { font-family: Verdana, Arial, Helvetica, sans-serif; }
p { color: #F30; }
strong { font-size: 24px; }
```



The `` tag is nested inside a paragraph, which is inside the `<body>` tag. That `` tag inherits from both of its ancestors, so it inherits the font-family property from the body and the color property from its parent paragraph. In addition, the `` tag has a bit of CSS applied directly to it—a 24px font size. The final appearance of the tag is a combination of all three styles. In other words, the `` tag appears exactly as if you'd created a style like this:

```
strong {  
  font-family: Verdana, Arial, Helvetica, sans-serif;  
  color: #F30;  
  font-size: 24px;  
}
```

Nearest Ancestor Wins

In the previous example, various inherited and applied tags smoothly combined to create an overall formatting package. But what happens when inherited CSS properties conflict? Think about a page where you've set the font color for the body tag to red and the paragraph tag to green. Now imagine that within one paragraph, there's a `` tag. The `` tag inherits from both the body and p tag styles, so is the text inside the `` tag red or green? Ladies and gentleman, we have a winner: the green from the paragraph style. That's because the web browser obeys the style that's closest to the tag in question.

In this example, any properties inherited from the `<body>` tag are rather generic. They apply to all tags. A style applied to a `<p>` tag, on the other hand, is more narrowly defined. Its properties apply only to `<p>` tags and the tags inside them.

In a nutshell, if a tag doesn't have a specific style applied to it, then, in the case of any conflicts from inherited properties, the nearest ancestor wins (see Figure 5-2, number 1).

Here's one more example, just to make sure the concept sinks in. If a CSS style defining the color of text were applied to a `<table>` tag, and another style defining a *different* text color were applied to a `<td>` tag inside that table, then tags inside that table cell (`<td>`) such as a paragraph, headline, or unordered list would use the color from the `<td>` style, since it's the closest ancestor.

The Directly Applied Style Wins

Taking the “nearest ancestor” rule to its logical conclusion, there's one style that always becomes king of the CSS family tree—any style applied directly to a given tag. Suppose a font color is set for the body, paragraph, *and* strong tags. The paragraph style is more specific than the body style, but the style applied to the `` tag is more specific than either one. It formats the `` tags and only the `` tags, overriding any conflicting properties inherited from the other tags (see Figure 5-2, number 2). In other words, properties from a style specifically applied to a tag beat out any inherited properties.

This rule explains why some inherited properties don't appear to inherit. A link inside a paragraph whose text is red still appears browser-link blue. That's because browsers have their own predefined style for the `<a>` tag, so an inherited text color won't apply.




FIGURE 5-2
Here's how web browsers figure out which properties to display when inherited properties conflict: The `` tag in the first paragraph (1) inherits the font family and color from both the `<body>` tag and the paragraph. But since the body and paragraph have different fonts and colors applied to them, the `` tag uses the font and color specified for its closest ancestor—the `<p>` tag. When a style applies directly to a tag—the font-family and color are specified for the `` tag (2)—browsers ignore conflicting inherited properties.

NOTE You can learn how to overcome preset styles for the `<a>` tag and change link colors to your heart's content. See page 115.

One Tag, Many Styles

Inheritance is one way that a tag can be affected by multiple styles. But it's also possible to have multiple styles apply *directly* to a given tag. For example, say you have an external style sheet with a `<p>` tag style and attach it to a page that has an internal style sheet that *also* includes a `<p>` tag style. And just to make things really interesting, one of the `<p>` tags on the page has a class style applied to it. So for that one tag, three different styles directly format it. Which style—or *styles*—should the browser obey?

The answer: It depends. Based on the types of styles and the order in which they're created, a browser may apply one or more of them at once. Here are a few situations in which multiple styles can apply to the same tag:

- **The tag has both a tag selector and a class style applied to it.** For example, a tag style for the `<h2>` tag, a class style named `.leadHeadLine` and this HTML: `<h2 class="leadHeadLine">Your Future Revealed!</h2>`. Both styles apply to this `<h2>` tag.

NOTE

Hold onto your hat if you're worried about what happens when these multiple styles conflict; details to follow.

- **The same style name appears more than once in the style sheet.** There could be a group selector (page 84), like `.leadHeadline`, `.secondaryHeadline`, `.newsHeadline`, and the class style `.leadHeadline` in the same style sheet. Both of these rules define how any element with a class of `leadHeadline` looks.
- **A tag has both a class and an ID style applied to it.** Maybe it's an ID named `#banner`, a class named `.news`, and this HTML: `<div id="banner" class="news">`. Properties from both the `banner` and `news` styles apply to this `<div>` tag.
- **There's more than one style sheet containing the *same* style name attached to a page.** The same-named styles can arrive in an external style sheet and an internal style sheet. Or, the same style can appear in multiple external style sheets that are all linked to the same page.
- **There are complex selectors targeting the same tag.** This situation is common when you use descendent selectors (page 88). For example, say you have a `div` tag in a page (like this: `<div id="mainContent">`), and inside the `div` is a paragraph with a class applied to it: `<p class="byline">`. The following selectors apply to this paragraph:

```
#mainContent p
#mainContent .byline
p.byline
.byline
```

If more than one style applies to a particular element, then a web browser combines the properties of all those styles, *as long as they don't conflict*. An example will make this concept clearer. Imagine you have a paragraph that lists the name of the web page's author, including a link to his email address. The HTML might look like this:

```
<p class="byline">Written by <a href="mailto:jean@cosmofarmer.com">Jean Graine
de Pomme</a></p>
```

Meanwhile, the page's style sheet has three styles that format the link:

```
a { color: #6378df; }
p a { font-weight: bold; }
.byline a { text-decoration: none; }
```

The first style turns all `<a>` tags powder blue; the second style makes all `<a>` tags that appear inside a `<p>` tag bold; and the third style removes the underline from any links that appear inside an element with the `byline` class applied to it.

All three styles apply to that very popular `<a>` tag, but since none of the properties are the same, there are no conflicts between the rules. The situation is similar to the inheritance example (page 104): the styles combine to make one überstyle containing all three properties, so this particular link appears powder blue, bold, and underline-free.

NOTE Your head will really start to ache when you realize that this particular link's formatting can also be affected by inherited properties. For example, it would inherit any font family that's applied to the paragraph. A few tools can help sort out what's going on in the cascade. (See the box on page 110.)

■ Specificity: Which Style Wins

The previous example is pretty straightforward. But what if the three link styles above each had a *different* font specified for the `font-family` property? Which of the three fonts would a web browser pay attention to?

As you know if you've been reading carefully so far, the cascade provides a set of rules that helps a web browser sort out any property conflicts; namely, *properties from the most specific style win*. But as with the styles listed above, sometimes it's not clear which style is most specific. Thankfully, CSS provides a formula for determining a style's *specificity* that's based on a value assigned to the style's selector—a tag selector, class selector, ID selector, and so on. Here's how the system works:

- A tag selector is worth **1 point**.
- A class selector is worth **10 points**.
- An ID selector is worth **100 points**.
- An inline style (page 44) is worth **1,000 points**.

NOTE The math involved in calculating specificity is actually a bit more complicated than described here. But this formula works in all but the weirdest cases. To read how web browsers actually calculate specificity, visit www.w3.org/TR/css3-selectors/#specificity.

The bigger the number, the greater the specificity. So say you create the following three styles:

- A tag style for the `` tag (specificity = 1)
- A class style named `.highlight` (specificity = 10)
- An ID style named `#logo` (specificity = 100)

Then, say your web page has this HTML: ``. If you define the same property—such as the `border` property—in all three styles, then the value from the ID style (`#logo`) always wins out.

NOTE A pseudo-element (like `::first-line` for example) is treated like a tag selector and is worth 1 point. A pseudo-class (`:link`, for example) is treated like a class and is worth 10 points. (See page 68 for the deal on these pseudo-things.)

Since descendent selectors are composed of several selectors—`#content p`, or `h2 strong`, for example—the math gets a bit more complicated. The specificity of a descendent selector is the total value of all of the selectors listed (see Figure 5-3).

selector	id	class	tag	total
<code>p</code>	0	0	1	1
<code>.byline</code>	0	1	0	10
<code>p.byline</code>	0	1	1	11
<code>#banner</code>	1	0	0	100
<code>#banner p</code>	1	0	1	101
<code>#banner .byline</code>	1	1	0	110
<code>a:link</code>	0	1	1	11
<code>p:first-line</code>	0	0	2	2
<code>h2 strong</code>	0	0	2	2
<code>#wrapper #content .byline a:hover</code>	2	2	1	221

FIGURE 5-3

When more than one style applies to a tag, a web browser must determine which style should “win out” in case style properties conflict. In CSS, a style’s importance is known as specificity and is determined by the type of selectors used when creating the style. Each type of selector has a different value, and when multiple selector types appear in one style—for example, the descendent selector `#banner p`—the values of all the selectors used are added up.

NOTE

Inherited properties don’t have any specificity. So even if a tag inherits properties from a style with a large specificity—like `#banner`—those properties will always be overridden by a style that directly applies to the tag.

The Tiebreaker: Last Style Wins

It’s possible for two styles with conflicting properties to have the same specificity. (“Oh brother, when will it end?” Soon, comrade, soon. The tutorial is coming up.) A specificity tie can occur when you have the same selector defined in two locations. You may have a `<p>` tag selector defined in an internal style sheet and an external style sheet. Or two different styles may simply have equal specificity values. In case of a tie, the style appearing last in the style sheet wins.

Here’s a tricky example using the following HTML:

```
<p class="byline">Written by <a class="email" href="mailto:jean@cosmofarmer.com">Jean Graine de Pomme</a></p>
```

In the style sheet for the page containing the above paragraph and link, you have two styles:

```
p .email { color: blue; }
.byline a { color: red; }
```

Both styles have a specificity of 11 (10 for a class name and 1 for a tag selector) and both apply to the `<a>` tag. The two styles are tied. Which color does the browser use to color the link in the above paragraph? Answer: Red, since it’s the second (and last) style in the sheet.

FREQUENTLY ASKED QUESTION

Get a Little Help

My head hurts from all of this. Isn't there some tool I can use to help me figure out how the cascade is affecting my web page?

Trying to figure out all the ins and outs of inherited properties and conflicting styles confuses many folks. Furthermore, doing the math to figure out a style's specificity isn't your average web designer's idea of fun, especially when there are large style sheets with lots of descendent selectors.

All current web browsers have built-in help in the form of an inspector. The fastest way to inspect an element on a page and all the CSS that affects it is to right-click (Control-click on a Mac) the element (the headline, link, paragraph, or image), and choose Inspect Element from the contextual menu. A panel will open (usually beneath the web page) showing the page's HTML, with your selected element's HTML highlighted. (To get this to work in Safari, you first need to turn on the Show Develop Menu option in the Preferences window→Advanced.)

On the right side of the panel, you'll see the styles applied to the element. There's usually a "computed" style—the sum total of all the CSS properties applied to the element through inheritance and the cascade or the element's "Frankenstyle." Below that you'll find the style rules that apply to the element, listed in order of most specific (at the top) to least specific (at the bottom).

In the listing of styles, you'll probably see some properties crossed out—this indicates that the property either doesn't apply to the element or that it's been overridden by a more specific style. For a couple of short tutorials on using Chrome's Developer's Tools for analyzing CSS, visit <https://developers.google.com/chrome-developer-tools/docs/elements-styles> and <http://webdesign.tutsplus.com/tutorials/workflow-tutorials/faster-htmlcss-workflow-with-chrome-developer-tools/>.

Now suppose the style sheet looked like this instead:

```
.byline a {color: red; }  
p .email { color: blue; }
```

In this case, the link would be blue. Since `p .email` appears after `.byline` in the style sheet, its properties win out.

What happens if you've got conflicting rules in an external and an internal style sheet? In that case, the placement of your style sheets (within your HTML file) becomes very important. If you first add an internal style sheet by using the `<style>` tag (page 45) and *then* attach an external style sheet farther down in the HTML by using the `<link>` tag (page 48), then the style from the external style sheet wins. (In effect, it's the same principle at work that you just finished reading about: *The style appearing last wins.*) The bottom line: Be consistent in how you place external style sheets. It's best to list any external style sheets first, and only use an internal style sheet when you absolutely need one or more styles to apply to a single page.

NOTE

Any external style sheets attached with the `@import` rule have to appear before internal styles within a `<style>` tag, and before any styles in an external style sheet. See page 48 for more information on external and internal style sheets.

TROUBLESHOOTING MOMENT

Overruling Specificity

CSS provides a way of overruling specificity entirely. You can use this trick when you absolutely, positively want to make sure that a particular property can't be overridden by a more specific style. Simply insert `!important` after any property to shield it from specificity-based overrides.

For example, consider the two following styles:

```
.nav a { color: red; }  
a { color: teal !important; }
```

Normally, a link inside an element with the class of `nav` would be colored red since the `.nav a` style is more specific than the `a` tag style.

However, including `!important` after a property value means that property always wins. So in the above example, all links on the page—including those inside an element with the `nav` class—are teal.

Note that `!important` works on an individual property, not an entire style, so you need to add `!important` to the end of each property you wish to make invincible. Finally, when two styles both have `!important` applied to the same property, the more specific style's `!important` rule wins.


Controlling the Cascade

As you can see, the more CSS styles you create, the greater the potential for formatting snafus. For example, you may create a class style specifying a particular font and font size, but when you apply the style to a paragraph, nothing happens! This kind of problem is usually related to the cascade. Even though you may think that directly applying a class to a tag should apply the class's formatting properties, it may not if there's a style with greater specificity.

You have a couple of options for dealing with this kind of problem. First, you can use `!important` (as described in the box above) to make sure a property *always* applies. The `!important` approach is a bit heavy-handed, though, since it's hard to predict that you'll never, ever, want to overrule an `!important` property someday. Read on for two other cascade-tweaking solutions.

Changing the Specificity

The top picture in Figure 5-4 is an example of a specific tag style losing out in the cascade game. Fortunately, most of the time, you can easily change the specificity of one of the conflicting styles and save `!important` for real emergencies. In Figure 5-4 (top), two styles format the first paragraph. The class style—`.intro`—isn't as specific as the `#sidebar p` style, so `.intro`'s properties don't get applied to the paragraph. To increase the specificity of the class, add the ID name to the style: `#sidebar .intro`.



However, simply tacking on additional selectors to make a style's properties "win" can lead to what's been called *specificity wars* where you end up with style sheets containing very long and convoluted style names like #home #main #story h1. In fact, as you'll read on page 114, you should try to avoid these types of styles and aim to keep your selectors as short as possible.

NOTE If you're into math, the `#sidebar p` style has a specificity of 101 (100 for the ID, and 1 for the tag selector), while the `.intro` style has a specificity of 10 (10 points for a class selector). Since 101 is greater than 10, `#sidebar p` takes precedence. Changing `.intro` to `#sidebar .intro` changes its specificity to 110.

Selective Overriding

You can also fine-tune your design by *selectively* overriding styles on certain pages. Say you've created an external style sheet named `styles.css` that you've attached to each page in your site. This file contains the general look and feel for your site—the font and color of `<h1>` tags, how form elements should look, and so on. But maybe on your home page, you want the `<h1>` tag to look slightly different than the rest of the site—bolder and bigger, perhaps. Or the paragraph text should be smaller on the home page, so you can wedge in more information. In other words, you still want to use *most* of the styles from the `styles.css` file, but you simply want to override a few properties for some of the tags (`<h1>`, `<p>`, and so on).

One approach is to simply create an internal style sheet listing the styles that you want to override. Maybe the `styles.css` file has the following rule:

```
h1 {
  font-family: Arial, Helvetica, sans-serif;
  font-size: 24px;
  color: #000;
}
```

You want the `<h1>` tag on the home page to be bigger and red. So just add the following style in an internal style sheet on the home page:

```
h1 {
  font-size: 36px;
  color: red;
}
```

In this case, the `<h1>` tag on the home page would use the font Arial (from the external style sheet) but would be red and 36 pixels tall (from the internal style).

TIP Make sure you attach the external style sheet *before* the internal style sheet in the `<head>` section of the HTML. This ensures that the styles from the internal style sheet win out in cases where the specificity of two styles are the same, as explained on page 114.

Another approach would be to create one more external style sheet—`home.css` for example—that you attach to the home page in addition to the `styles.css` style sheet. The `home.css` file would contain the style names and properties that you want to overrule from the `styles.css` file. For this to work, you need to make sure the `home.css` file appears *after* the `styles.css` file in the HTML, like so:

```
<link rel="stylesheet" href="css/styles.css"/>
<link rel="stylesheet" href="css/home.css"/>
```

TIP Another way to fine-tune designs on a page-by-page basis is to use different class names for the `<body>` tag of different types of pages—for example `.review`, `.story`, `.home`—and then create descendent selectors to change the way tags on these types of pages look. This technique is discussed on page 67.

Avoiding Specificity Wars

As mentioned on page 61, many web designers these days avoid ID selectors in favor of classes. One reason: ID selectors are very powerful, and, therefore, require more power to override. This often leads to specificity wars in which style sheets get loaded with unnecessarily long-winded and complicated selectors. This problem is best explained by example. Say, for instance, your page has this snippet of HTML:

```
<div id="article">
  <p>A paragraph</p>
  <p>Another paragraph</p>
  <p class="special">A special paragraph</p>
</div>
```

You decide that you want to color the paragraphs inside the article div red, so you create a descendent selector like this:

```
#article p { color: red; }
```

But you want that one paragraph with the class of special to be blue. If you simply create a class selector, you won't get what you want.

```
.special { color: blue; }
```

As you read on page 108, when determining which properties to apply to a tag, a web browser uses a simple mathematical formula to deal with style conflicts: browsers give an ID selector a value of 100, a class selector a value of 10, and a tag selector a value of 1. Because the selector `#article p` is composed of one ID and one element (a total of 101 specificity points), it overrides the simple class style—forcing you to change the selector:

```
#article .special {color: blue; }
```

Unfortunately, this change causes two more problems. First, it makes the selector longer, and second, now that blue color is applied only when the special class appears inside something with an ID of article. In other words, if you copy the HTML `<p class="special">A special paragraph</p>` and paste it elsewhere in the page, it will no longer be blue. In other words, the use of the ID makes your selectors both longer and less useful.

Now look what happens if you simply replace all IDs with classes. The previous HTML would change to:

```
<div class="article">
  <p>A paragraph</p>
  <p>Another paragraph</p>
  <p class="special">A special paragraph</p>
</div>
```

And you could change the CSS to this:

```
.article p { color: red; }  
p.special { color: blue; }
```

The first style—.article p—is a descendent selector worth 11 points. The second style p.special is also worth 11 points (one tag and one class) and means “apply the following properties to any paragraph with the special class.” Now if you cut that HTML and paste it anywhere else on the page, you’d get the blue styling you’re after.

This is just one example, but it’s not hard to find style sheets with ridiculously long selectors like #home #article #sidebar #legal p and #home #article #sidebar #legal p.special.

There’s basically no reason to use IDs. They don’t provide anything that you can’t have with a simple class selector or tag selector, and their powerful specificity can only lead you to unnecessarily complex style sheets.

NOTE

For a more detailed discussion of why you should avoid ID selectors, visit <http://csswizardry.com/2011/09/when-using-ids-can-be-a-pain-in-the-class>.

Starting with a Clean Slate

As discussed on page 96, browsers apply their own styles to tags: for example, <h1> tags are bigger than <h2> tags, and both are bold, while paragraph text is smaller and isn’t bold; links are blue and underlined; and bulleted lists are indented. There’s nothing in the HTML standard that defines any of this formatting: Web browsers just add this formatting to make basic HTML more readable. However, even though browsers treat all tags roughly the same, they don’t treat them identically.

For example, Safari and Firefox use the padding property to indent bulleted lists, but Internet Explorer uses the margin property. Likewise, you’ll find subtle differences in the size of tags across browsers and an altogether confusing use of margins among the most common web browsers. Because of these inconsistencies, you can run into problems where, for instance, Firefox adds a top margin, while Internet Explorer doesn’t. These types of problems aren’t your fault—they stem from differences in the built-in browser styles.

To avoid cross-browser inconsistencies, it’s a good idea to start a style sheet with a clean slate. In other words, erase the built-in browser formatting and supply your own. The concept of erasing browser styling is called *CSS reset*. This section gives you a working introduction.

In particular, there’s a core set of styles you should include at the top of your style sheets. These styles set a baseline for properties that commonly are treated differently across browsers.

Here’s a bare-bones CSS reset:

```
html, body, div, span, object, iframe, h1, h2, h3, h4, h5, h6, p, blockquote,
pre, a, abbr, acronym, address, big, cite, code, del, dfn, em, img, ins, kbd,
q, s, samp, small, strike, strong, sub, sup, tt, var, b, u, i, center, dl, dt,
dd, ol, ul, li, fieldset, form, label, legend, table, caption, tbody, tfoot,
thead, tr, th, td, article, aside, canvas, details, embed, figure, figcaption,
footer, header, hgroup, menu, nav, output, ruby, section, summary, time, mark,
audio, video {
    margin: 0;
    padding: 0;
    border: 0;
    font-size: 100%;
    vertical-align: baseline;
}

article, aside, details, figcaption, figure, footer, header, hgroup, menu,
nav, section {
    display: block;
}

body {
    line-height: 1.2;
}

ol {
    padding-left: 1.4em;
    list-style: decimal;
}

ul {
    padding-left: 1.4em;
    list-style: square;
}

table {
    border-collapse: collapse;
    border-spacing: 0;
}
```

NOTE

The above CSS reset is adapted from Eric Meyer's well-known and influential CSS reset, which you can find at <http://meyerweb.com/eric/tools/css/reset>.

The first style is a very long group selector (page 84) that takes the most common tags and *zeros them out*—removing all the padding and margins, setting their base text size to 100%, and removing bold text formatting. This step makes your tags look pretty much identical (see Figure 5-5), but that's the point—you want to start at zero and then add your own formatting so that all browsers apply a consistent look to your HTML.

The second selector (`article`, `aside`, `details`...) is another group selector that helps older browsers correctly display the new HTML5 tags. The third selector (`body`)

style sets a consistent line-height (space between lines in a paragraph). You'll learn about the line-height property in the next chapter.

NOTE

You don't have to type all this code yourself. You'll find a file named *reset.css* in the 05 tutorial folder at www.sawmac.com/css3 that contains a basic CSS reset file. Just copy the styles from this file and paste them into your own style sheets. Another approach to resets (discussed on page 551) is available in the Chapter 17 tutorial files inside the 17 folder.

The fourth and fifth styles (the o1 and u1 tag styles) set a consistent left margin and style (page 173 introduces list styling), and the last style makes adding borders to table cells easier (you'll learn why this style is useful on page 380).

Tutorial: The Cascade in Action

In this tutorial, you'll see how styles interact and how they can sometimes conflict to create unexpected results. First, you'll look at a basic page that has the CSS reset styles mentioned above plus a couple of other styles that provide some simple layout. Then, you'll create two styles and see how some properties are inherited and how others are overruled by the cascade. Then, you'll see how inheritance affects tags on a page and how a browser resolves any CSS conflicts. Finally, you'll learn how to troubleshoot problems created by the cascade.

To get started, you need to download the tutorial files located on this book's companion website at www.sawmac.com/css3. Click the tutorial link and download the files. All of the files are enclosed in a zip archive, so you'll need to unzip them first. (Go to the website for detailed instructions on unzipping the files.) The files for this tutorial are contained inside the folder named 05.

Resetting CSS and Styling from Scratch

First, take a look at the page you'll be working on.

1. **In a web browser, open the file named *cascade.html* located in the 05 tutorial folder (see Figure 5-5).**

The page doesn't look like much—two columns, one with a blue background and a lot of same-looking text. There are a few styles already applied to this file, so open the CSS up in a text editor and have a look.

2. **Using your favorite text or web page editor, open the file *styles.css* located in the 05 folder.**

This file is the external style sheet that the *cascade.html* file uses. It has several styles already in it—the first group is the CSS reset styles discussed on the previous page. They eliminate the basic browser styles, which is why all of the text currently looks the same. (You'll create your own styles to make this page look great soon.)




FIGURE 5-5
The basic “CSS reset” styles on this page eliminate the subtle differences in how different browsers display basic HTML tags. They also eliminate any difference between how the tags look. Your job is to take this empty canvas and style the tags so they look the way you want them to.

The last two styles—the class styles `.main` and `.sidebar`—create the two columns you see in Figure 5-5. The HTML is divided into two `<div>` tags, each with its own class. The class styles here essentially position the two divs so they appear side-by-side as columns (you’ll learn how to control page layout and create columns in Part 3).

You’ll first add a couple of styles to improve the page’s basic appearance and its top headline.

3. In the `styles.css` file, add these two styles at the bottom of the style sheet following the last `}` of the `.sidebar` style:

```
body {
    color: #B1967C;
    font-family: "Palatino Linotype", Baskerville, serif;
    padding-top: 115px;
    background: #CDE6FF url(images/bg_body.png) repeat-x;
    width: 800px;
    margin: 0 auto;
}
h1 {
    font-size: 3em;
    font-family: "Arial Black", Arial, sans-serif;
    margin-bottom: 15px;
}
```

The first style adds a background image and color to the page, and also sets a fixed width for the page. If you save this file and preview the `cascade.html` file in a web browser (see Figure 5-6), you'll notice that these attributes aren't inherited by the other tags—the same image, for example, isn't repeated behind the heading or paragraph tags.

The font-family and color properties, on the other hand, are inherited, so other tags on the page now use that font and have a brownish color. However, you'll see that although the top headline is the same color as the other text on the page, it uses a different font—here's the cascade in action. The h1 tag style doesn't have a color assigned to it, so that the heading inherits the brown color applied to the body tag. But, since the h1 tag style specifies a font family, it overrides the inherited font from the body tag style.




FIGURE 5-6

Inheritance and the cascade in action: the <h1> tag at the top of this page inherits its font color from the body tag style, but gets its size and font family from the specific h1 tag style.

Creating a Hybrid Style

In this example, you'll create two styles. One style formats all the second level headlines of the page; and another, more specific style reformats just those headings in the larger, main column of the page.

1. In the `styles.css` file, add the following style to the end of the style sheet:

```
h2 {
  font-size: 2.2em;
  color: #AFC3D6;
  margin-bottom: 5px;
}
```

This style simply changes the text color and increases the size of the h2 tag and adds a little bit of space below it. If you view the file in a web browser, you'll see that the h2 tags in the main column and the one h2 tag in the right sidebar now look alike.

Next, you'll create a style to just format the second-level headlines in the main column.

2. **Return to your web page editor and the `styles.css` file, click directly after the end of the new `<h2>` tag style, and press Enter (Return) to create an empty line.** Add the following style:

```
.main h2 {  
  color: #E8A064;  
  border-bottom: 2px white solid;  
  background: url(images/bullet_flower.png) no-repeat;  
  padding: 0 0 2px 80px;  
}
```

You've just created a descendent selector that formats all `<h2>` tags that appear *inside* of a tag with a class of `main` applied to it. The two columns of text on this page are enclosed in `<div>` tags with different class names applied to them. The larger, left-hand column has the class `main`, so this particular style will only apply to the `<h2>` tags in that div.

This style is similar to the one you created in the tutorial for Chapter 2 in Step 17 on page 52—it adds an underline and a simple flower icon to the headline. This style also specifies an orange color for the text.

3. **Save the style sheet and preview the page once again in a web browser (see Figure 5-7).**

You'll notice that all of the heading 2 tags (the two in the main column and one in the sidebar) are the same size, but the two in the main column also have the underline and flower icon.

Because the `.main h2` style is more specific than the simple `h2` style, if there are any conflicts between the two styles—the `color` property, in this case—the `.main h2` properties win out. So, although the second-level headlines in the main column get a blue text color from the `h2` style, the orange color from the more specific `.main h2` style wins out.

However, since the `.main h2` style doesn't specify a font size or bottom margin, the headlines in the main column get those properties from the `h2` style.

Overcoming Conflicts

Because of how CSS properties sometimes conflict when several styles apply to the same tag, you'll sometimes find your pages don't look exactly as you planned.

**FIGURE 5-7**

A tale of two styles: both the `h2` and `.main h2` styles apply to the second-level headlines in the left column of this page. However, the `.main h2` style applies to just those headlines inside the main (left) column. Also, since that style is more powerful than the basic `h2` tag style, it overrides any conflicts between the two styles, in this case, using an orange text color instead of the blue color of the `h2` tag style.

When that happens, you'll need to do a little work to find out why and rejigger your CSS selectors to make sure the cascade is working to produce the results you want.

1. Return to your web page editor and the `styles.css` file.

You'll now create a new style to format just the paragraphs in the main column of the page.

2. Add the following style to the end of the style sheet:

```
.main p {
  color: #616161;
  font-family: "Palatino Linotype", Baskerville, serif;
  font-size: 1.1em;
  line-height: 150%;
  margin-bottom: 10px;
  margin-left: 80px;
}
```

Preview the page in a web browser and you'll see that this new style changes the color, size, and font of the text, spreads the lines of text out (the `line-height` property), and adjusts the bottom and left margins of the paragraphs.

The page would look better if you highlighted the paragraph immediately following the headline—making it bigger and bolder can help make a more powerful message. The easiest way to style just that one paragraph is to create a class style and apply it to that paragraph.

3. Add one last style to the end of the style sheet:

```
.intro {  
  color: #6A94CC;  
  font-family: Arial, Helvetica, sans-serif;  
  font-size: 1.2em;  
  margin-left: 0;  
  margin-bottom: 15px;  
}
```

This style changes the color, font, and size, and adjusts the margins a bit. All you have to do is apply the class to the HTML.

4. Open the *cascade.html* file in your web page editor.

Locate the `<p>` tag that appears after `<h1>CSS: The Missing Manual</h1>` and directly below `<div class="main">`, and then add the following class attribute:

```
<p class="intro">
```

5. Preview the page in a web browser.

And...the paragraph is completely unchanged. What gives? Following the rules of the cascade, `.intro` is a basic class selector, while the `.main p` is a descendent selector composed of both a class and a tag name. These add up to create a more specific style, so its style properties overrule any conflict between it and the `.intro` style.

In order to make the `.intro` style work, you need to give it a little juice by making its selector more powerful.

6. Return to the *styles.css* file in your web page editor and change the name of the style from `.intro` to `p.intro`.

Make sure there's no space between the `p` and `.intro`. You've basically created a tie—`.main p`—is one class and one tag selector, and `p.intro` is one tag and one class. They both have a specificity value of 11, but because `p.intro` appears after `.main p` in the style sheet, it wins the battle, and its properties apply to the paragraph. (You could have created an even more specific style—`.main .intro`—to overcome the conflict.)

7. Preview the page in a web browser (see Figure 5-8).

Voila! The paragraph changes to blue, with bigger text, a different font, and no left margin. If you didn't have a clear understanding of the cascade, you'd be scratching your head wondering why that class style didn't work the first time around.

In this and the previous four chapters, you've covered the basics of CSS. Now, in Part Two, it's time to take that knowledge and apply it to real design challenges—making web pages look great.



FIGURE 5-8

Even in a simple page like this one, with just a handful of styles, the look of any one tag is often a combination of properties from various styles.

Applied CSS

CHAPTER 6:

Formatting Text

CHAPTER 7:

Margins, Padding, and Borders

CHAPTER 8:

Adding Graphics to Web Pages

CHAPTER 9:

Sprucing Up Your Site's Navigation

CHAPTER 10:

CSS Transforms, Transitions, and Animations

CHAPTER 11:

Formatting Tables and Forms



Formatting Text

Most websites still rely on words to get their messages across. Sure, people like to look at photos, movie clips, and animations, but it's the reading material that keeps 'em coming back. People are hungry for Facebook updates, news, gossip, how-to articles, recipes, FAQs, jokes, information lists, and even 140-character tweets. With CSS, you can—and *should*—make your headlines and body text grab a visitor's attention as compellingly as any photo.

CSS offers a powerful array of text-formatting options, which let you assign fonts, color, sizes, line spacing, and many other properties that can add visual impact to headlines, bulleted lists, and regular old paragraphs of text (see Figure 6-1). This chapter reveals all, and then finishes up with a tutorial where you can practice assembling CSS text styles and put them to work on an actual web page.

■ Using Fonts


The first thing you can do to make text on your website look more exciting is to apply different fonts to headlines, paragraphs, and other written elements on your pages. To apply a font to a CSS style, you use the `font-family` property and specify the font you wish to use. For example, say you want to use the Arial font for paragraphs on a page. You can create a `p` tag style and use the `font-family` property like this:

```
p {  
    font-family: Arial;  
}
```



FIGURE 6-1

Good web typography makes sites that are easy to read and enjoyable to look at. Using too many fonts or too many typographic flourishes often leads to confusing and difficult to understand web pages (top). Using different type sizes, subtle style choices, and only a couple font variations makes a page easy to scan, and fun to read (bottom).



Originally, the font-family property only worked if your site's visitors had the same font installed on their computers. In other words, using the above example, if someone visiting your site didn't have Arial font on his computer, the page's paragraphs would display with the web browser's default font (usually some variant of Times

New Roman). Because of this, web designers were limited to a handful of fonts that come preinstalled on most computers.

More recently, web browsers began supporting *web fonts*—fonts that the browser downloads and uses while viewing your site. Web fonts use the `font-family` property as well, but require an additional CSS command called the `@font-face` directive, which instructs a web browser to download the specified font. Web fonts open up many exciting design possibilities, letting you choose from a wild array of typefaces. But, as you'll learn on page 132, they also come with their own set of challenges.

In other words, as a web designer, you can choose to stick with the tried-and-true font method—selecting fonts from the basic set installed on most computers—or use web fonts for greater design choice (at the cost of more work). You're not limited to one approach or the other, either. Many web designers mix the two—using standard fonts in some cases (like the main body text of a page) and web fonts in other cases (to create eye-catching headlines, for instance).

Choosing a Common Font

When you use the `font-family` property to specify a font, visitors to your site won't necessarily see the font you choose—they must either have it installed on their computers already or, in the case of web fonts, temporarily download the font to view the site. Because you can't always know whether your preferred font is available to a particular visitor, it's common practice to specify not only your main font, but also a couple of back-up choices. If your viewer's computer has your first-choice font, then that's what she'll see. But when the first font isn't installed, the browser looks down the list until it finds a font that is. The idea is to specify a list of similar-looking fonts that are common to a variety of operating systems, like so:

```
font-family: Arial, Helvetica, sans-serif;
```

In this example, a web browser first looks to see if the Arial font is installed; if it is, then that font is used; if not, the browser next looks for Helvetica, and if that isn't installed, then it finally settles for a generic font—`sans-serif`. When you list a generic font type (like `sans-serif` or `serif`), the viewer's browser gets to choose the actual font. But at least you can define its basic character.

NOTE

In real life, when you put a CSS property into action, you must, of course, include all the other necessities of a complete style declaration block and style sheet, as described in Chapter 2: `p { font-family: Arial, Helvetica, sans-serif; }`, for example. When you see examples like `font-family: Arial, Helvetica, sans-serif;`, remember that's just the property in isolation, distilled down for your book-reading benefit.

Also, if the font's name is made up of more than one word, you must enclose it in quote marks:

```
font-family: "Times New Roman", Times, serif;
```

Here are some often-used combinations of commonly installed fonts organized by the type of font, including a generic font type at the end of each list.

■ **SERIF FONTS**

Serif fonts are best for long passages of text, as it’s widely believed that the serifs—those tiny “feet” at the end of a letter’s main strokes—gently lead the eye from letter to letter, making text easier to read. Examples of serif fonts are Times, Times New Roman, and Georgia.

- “Times New Roman”, Times, serif
- Georgia, “Times New Roman”, Times, serif
- Baskerville, “Palatino Linotype”, Times, serif
- “Hoefler Text”, Garamond, Times, serif

Examples of these fonts are in Figure 6-2.



FIGURE 6-2

Fonts don't always display the same on Mac (left) and Windows (right). The two systems come with different built-in fonts. In addition, anti-aliasing, which makes onscreen text look smoother, is better on the Mac than on Windows. Windows includes a technology called Clear Type, which can improve the look of text on a screen. The quality of text on Windows depends on which Clear Type settings your Windows computer has. You can learn more about Clear Type at www.microsoft.com/typography/cleartype.

■ **SANS-SERIF FONTS**

Sans-serif fonts are often used for headlines, thanks to their clean and simple appearance. Examples of sans-serif fonts include Arial, Helvetica, and Verdana. The text in this book is set in a sans-serif font.

- Arial, Helvetica, sans-serif
- Verdana, Arial, Helvetica, sans-serif

- Geneva, Arial, Helvetica, sans-serif
- Tahoma, “Lucida Grande”, Arial, sans-serif
- “Trebuchet MS”, Arial, Helvetica, sans-serif
- “Century Gothic”, “Gill Sans”, Arial, sans-serif

Examples of sans-serif fonts are shown in Figure 6-3.



FIGURE 6-3

Sans-serif fonts on Mac (left) and Windows (right). Some people believe that you should use only sans-serif fonts on web pages because they think the delicate decorative strokes of serif fonts don't display well on the coarse resolution of a computer screen. In the end, your aesthetic judgment is your best guide. Pick the fonts you think look best.

■ MONOSPACED AND FUN FONTS

Monospaced fonts are often used to display computer code like the CSS snippets you see throughout this book. Each letter in a monospaced font is the same width (like the ones manual typewriters used).

- “Courier New”, Courier, monospace
- “Lucida Console”, Monaco, monospace
- “Copperplate Light”, “Copperplate Gothic Light”, serif
- “Marker Felt”, “Comic Sans MS”, fantasy

Examples of these font lists are pictured in Figure 6-4.

■ ADDITIONAL FONTS TO CONSIDER

There are literally thousands of fonts, and every operating system ships with many more fonts than are listed here. However, here are a few fonts that are very common on both Macs and PCs, so you might want to give them a go:

- Arial Black
- Arial Narrow
- Impact




FIGURE 6-4
Monospaced fonts on Mac (left) and Windows (right). Courier is the most common monospaced font, but you're far from limited to it. Lucida Console is very common on Windows and Macs, and Monaco is installed on every Mac.

Be careful with Arial Black and Impact: They only have a single weight and don't include an italic version. Accordingly, if you use these fonts, make sure to set the font-weight and the font-style (coming up on page 141) to normal. Otherwise, if the text is bolded or italicized, the browser will make its best (read: ugly) guess at what the text should look like.

■ Using Web Fonts

The traditional way of using fonts in CSS is straightforward: just specify the font you want using the font-family property. However, you're limited to fonts your visitors likely to have installed on their computers. Fortunately, as mentioned earlier, all major browsers now support web fonts. With web fonts, browsers actually download the font from a web server and use it to display text on the web page.

The CSS part of web fonts is pretty basic and requires just two CSS commands:

- The @font-face directive is responsible for telling a web browser both the name of the font and where to download the font from. You'll learn how this CSS command works on page 137, but for now just keep in mind that this is how you tell a browser to download the font.
- The font-family property is used with web fonts in the same manner as the already installed fonts described on page 127. In other words, once the @font-face directive instructs the browser to download the font, you can then assign that font to any CSS style by using the font-family property.

In theory, web fonts aren't all that difficult to use. However, when you dig into the details, you'll need to understand a few unique requirements to use them properly.

Font File Types

Believe it or not, Internet Explorer has had support for web fonts since version 5 (released over 12 years ago!). Unfortunately, it required a unique and difficult method to create font formatting. That is, you couldn't just take a regular font from your computer, slap it up on a web server, and be done. Instead, you needed to take a regular font and convert it to EOT—Embedded Open Type—format. That's still true for versions up through IE 8.

There are still other font formats used for web fonts—some of which work in some browsers but not others. To make sure the largest number of visitors to your site can enjoy the fonts you specify, you'll need to provide those fonts in a variety of formats (you'll find the details on page 135).

Here's a list of the different font types and which browsers they work in.

- **EOT.** Embedded Open Type fonts work only in Internet Explorer. You need a special tool to convert a regular font to EOT format, but sites like FontSquirrel (page 135) can do this for you.
- **True Type and Open Type.** If you look in your computer's Fonts folder, you'll probably find .ttf (True Type) or .otf (Open Type) fonts. This is the font format most commonly used for computer fonts. You can use these for word processing and desktop publishing as well as for web pages. This font type has wide support in most web browsers: IE 9 and later, Firefox, Chrome, Safari, Opera, iOS Safari (version 4.2 and later), Android, and the Blackberry Browser.
- **WOFF.** Web Open Font Format files is a newer font format that's designed specifically for the Web. WOFF fonts are basically compressed versions of TrueType or Open Type fonts. That means WOFF fonts are generally smaller in file size and download more quickly than other fonts. WOFF format has wide browser support as well, including IE 9 and later, Firefox, Chrome, Safari, Opera, Blackberry browser, and iOS Safari version 5 and later. The most notable exception is Android. In other words, if you only use WOFF fonts, visitors on Android mobile devices or using IE 8 won't be able to download or display your fonts.
- **SVG.** Scalable Vector Graphic format isn't a font format, per se. It's actually a way to create vector graphics (graphics that can scale without losing quality). Support for SVG fonts is much more limited. Neither Internet Explorer nor Firefox support SVG. Another problem with SVG is that it produces files that are often twice the size of TrueType and three times the size of WOFF fonts. The only real benefit of SVG is that it's the only font format understood by older versions of iOS running Safari version 4.1 or earlier.

Fortunately, you don't have to select just one font type and ignore all other browsers. As you'll read on the next page, you can (and usually will) specify multiple formats and let the browser download the one that works for it. In addition, you can download a font that's already been converted to these four formats, or even convert a regular True Type font into these multiple formats.

NOTE A single font file contains just one weight and style for that font. In other words, if you want text to be bold, italic, or bold and italic, you must download separate font files for each variation of the font. Some fonts, especially fun display fonts, only include one variant and are best used for headlines or text where you won't need italic or bold versions. See page 129 for more information on different font weights and styles.

Legal Issues with Web Fonts

The second hurdle to using web fonts is a legal issue. Individuals and companies create and sell these fonts, like other software, to make their livelihood. When you upload a TrueType font to your web server for visitors to use while viewing your site, anyone can simply download the font and start using it on her own website or in her computer's word processing or page layout program. Most font companies don't like the idea of people pirating their creations, so many fonts have licenses that specifically prohibit their use on the Web.

In other words, even if you buy a font from Adobe, you can't simply start using it on your website. Many font companies are now offering different kinds of licenses (at different prices) to allow for use on the Web. This even applies to fonts that come supplied with your computer. You're allowed to use them with the programs you install on your computer, but you may not be allowed to place those same font files on your web server to use as a web font. If you don't know whether a font allows Web use, you're better off not using it and finding a font that can be used on the Web.

NOTE To sidestep any legal issues, you can use a font service like Google Fonts (page 146) or TypeKit, a commercial web font service from Adobe (see the box on page 153).

Finding Web Fonts

When looking for web fonts, you're confronted with two issues: finding fonts that are legal to use on the Web and finding fonts in all the font formats (EOT, WOFF, TrueType, and so on). While some font companies have begun to offer web licenses for fonts you purchase, there is a wide assortment of free fonts available for Web use. Here are a few of the many sources for free web fonts:

- **The League of Movable Type (www.theleagueofmoveabletype.com).** Composed of a group of designers, this site was one of the first to offer free, hand-crafted fonts for web use. Their font, League Gothic, is widely used on the Web.
- **Exljbris font foundry (www.exljbris.com).** Provides classic, free fonts by Jos Buivenga: Museo, Museo Sans, and Museo Slab.

- **Fontex.org** (www.fontex.org). Provides a large selection of free fonts, although not all of them are licensed for commercial use. If you plan on using one of the fonts on a commercial site (that is, not just your personal website), make sure you read the license agreement that accompanies the downloaded font.
- **The Open Font Library** (<http://openfontlibrary.org>). Over 152 free fonts (at the time of this writing) are available and all of them can be used on your websites (just don't use all 152 at once).
- **Font Squirrel** (www.fontsquirrel.com). A landmark site in the web font world offering over 800 fonts. In addition to offering just fonts, Font Squirrel provides what it calls “@font-face Kits” which are a collection of files including fonts in all the major font formats, and a CSS file that includes all the necessary @font-face syntax to load them (you'll learn how to use @font-face yourself on page 137). In addition, Font Squirrel offers an online tool for converting a TrueType or Open Type font to other font formats including EOT, SVG, and WOFF. You'll learn how to use this tool in the next section.
- **Google Fonts** (www.google.com/webfonts). Google provides a simple and free way to include web fonts on your sites. You'll learn how to use this service in depth on page 146.

Generating Multiple Font Formats

Most of the sites offering free fonts provide the font in a single format (usually TrueType (.ttf) or Open Type (.otf)). While many browsers support TrueType and Open Type, not all do. In addition, the newer WOFF format is supported by most browsers and has the advantage of being smaller in file size than TrueType. To make sure you supply fonts to as many browsers as possible, you need to use at least EOT, WOFF, and TrueType fonts. And if you're catering to iPhones running Safari version 4.1 or earlier, you'll need SVG fonts.

NOTE According to the web statistics site NetMarketShare, Safari 4.1 and earlier represent less than 2 percent of all mobile web browsers. You can read the article at www.netmarketshare.com/browser-market-share.aspx?qprid=2&qpcustomd=1.

Fortunately, Font Squirrel provides a very useful online tool to help generate the required font formats. The @font-face Generator located at www.fontsquirrel.com/fontface/generator provides a simple method for creating not only the proper fonts, but also a sample HTML file and a basic CSS style sheet.

To use Font Squirrel's @font-face Generator:

1. Locate a TrueType (.ttf) or Open Type (.otf) font.

Use one of the sites listed in the previous section, or find a font from another site. Just make sure that the font is licensed for use as a web font. If it's not, or you're not sure, then skip it and find another font.

2. **Go to the @font-face Generator at www.fontsquirrel.com/fontface/generator.**

It's a simple page with just a few options (see Figure 6-5).

3. **Click the Add fonts button (#1 in Figure 6-5).**

Your browser opens a "Select files" dialog box.

4. **Select one or more fonts from your computer and click the Open button.**

Your browser uploads the file or files to the Font Squirrel server.

5. **Select a conversion option (#2 in Figure 6-5).**

- **Basic** simply converts the font to EOT, WOFF, and SVG formats.
- **Optimal** is a better choice since it not only converts the font but also makes other enhancements to improve the performance and speed of the fonts.
- **Expert** lets you tweak every last setting for the conversion. For example, it lets you create a *subset* of the font—that is, just a handpicked set of characters. In other words, you could exclude from the font file certain characters you're not using, like the semicolon, exclamation mark, or letter Q.

In all likelihood, you'll want access to all characters, so it's best to stick with the Optimal.


6. **Turn on the "Yes, the fonts I'm uploading are legally eligible for web embedding" checkbox (#3 in Figure 6-5).**

As mentioned on page 134, fonts are intellectual property, and just slapping one up on a web server promotes software piracy. Make sure your fonts can be used on the Web; most of the ones listed in this section are.

7. **Click the Download Your Kit button (#4 in Figure 6-5).**

Depending on the number of fonts you're converting and their complexity, the download process may take a while. The Font Squirrel server needs to take the font and perform its magic to generate each font format. When it's done, you'll download a folder containing the various font format files, a demo file, a CSS file, and a few other miscellaneous files. The most important are, of course, the .eot, .ttf, .woff, and .svg font files.

Now that you've got the fonts you wish to use, it's time to learn how to use them with CSS's @font-face directive.

**FIGURE 6-5**

Unless you know what you're doing, stick with Font Squirrel's Optimal conversion setting. It generates all the font formats you'll need and makes a few other adjustments to make the fonts load faster and look better onscreen. But for ultimate control, choose the Expert option, and you'll see a list of nearly a dozen settings you can use to alter how the fonts are generated.

Using the @font-face Directive

Once you've downloaded the proper font files, it's time to use them. First, copy the files to the location on your computer where you keep the files for your website. Many web designers create a dedicated folder at the site root folder named `fonts`, `_fonts`, or `webfonts`. Alternatively, if you have a folder for your CSS files, you can place the font files there. It doesn't really matter where you put these files on your site, but it helps to be organized.

The secret to web fonts is a CSS command called the @font-face directive. This command at its most basic names the font and tells the browser where to find the font file for download. You place the @font-face directive in your style sheet, just like a regular style. For example, say you're using the League Gothic font. You have a True Type file named `League_Gothic-webfont.ttf` inside a fonts folder on your site. You'd instruct a browser to download this font by adding the @font-face directive to your style sheet like this:

```
@font-face {
  font-family: "League Gothic";
  src: url('fonts/League_Gothic-webfont.ttf');
}
```

The first property, `font-family`, you've seen before (page 127), but here it has a different purpose. When used inside an `@font-face` directive, `font-family` assigns a name to the font. You then use that font name when you want to apply that font to a style. For example, say you want to use the League Gothic font for all paragraphs on a page. You could then use this style:

```
p {
  font-family: "League Gothic";
}
```

NOTE You use one `@font-face` directive for each font you wish to use. If you have three fonts, you need three `@font-face` directives. It's a good idea to keep them grouped together and place them at the top of your style sheet, so a browser can begin downloading them immediately.

The second attribute—the `src` property—tells the browser where to look for the font file on the server. You place the path from the style sheet to the font file on the system inside quote marks and inside `url()`. The path works just like other HTML file paths—for instance, paths to images, links, and JavaScript files. For example, say you had a style sheet inside a folder named `_styles` and a font file named `my_font.ttf` inside a folder named `_fonts`. Both folders are in the root of your site. So the path from the style sheet to the font file is `../_fonts/my_font.ttf`. You'd write an `@font-face` directive for that font like this:

```
@font-face {
  font-family: "My Font";
  src: url('../_fonts/my_font.ttf');
}
```

You've probably noticed that in the examples above, there's only a single font file—a TrueType font. That makes it easy to see how `@font-face` works in general, before jumping into more detail. As discussed earlier, `@font-face` lets you specify multiple files with different font types. Unfortunately, due to browser bugs, the syntax for all that is a bit complicated. For example, say you want to use all the different font formats for League Gothic on your site. Here's how to rewrite the above code:

```
@font-face {
  font-family: 'League Gothic';
  src: url('fonts/League_Gothic-webfont.eot');
  src: url('fonts/League_Gothic-webfont.eot?#iefix') format('embedded-opentype'),
        url('fonts/League_Gothic-webfont.woff') format('woff'),
        url('fonts/League_Gothic-webfont.ttf') format('truetype'),
        url('fonts/League_Gothic-webfont.svg') format('svg');
}
```

This looks messy, and unfortunately, due to a bug in IE, it's unnecessarily complicated. Here's how it breaks down:

- Line 2 is the same as before. The `font-family` property supplies the name of the font; the same name you'll use when applying the font to your CSS styles.
- Line 3 is for Internet Explorer 9, but only when it's in Compatibility mode—a mode where IE 9 acts like it's IE 8. This weird feature was added to IE 9 so that websites designed to correctly accommodate the bugs in IE 8 and earlier would look OK in IE 9. A user has to purposely switch to compatibility mode in IE 9, so you're probably safe leaving this out.
- Line 4 begins a second `src` property, which according to the rules of the `@font-face` directive, can have multiple font type specified. The first font is the `.eot` font again, but this time you'll see that at the end of the `.eot` file, you need to add `?#iefix`. This is to accommodate yet more IE bugs—this time for IE 6–8. If you don't add that little bit to the URL following the `.eot`, then the font may not display in IE 8 or earlier correctly.

You'll also notice that after the URL there's some new code:

```
format('embedded-opentype')
```

This indicates the font format, and you add this after each URL for a different font format.

- Lines 5–7 simply identify additional font formats. This is actually just one property—the `src` property—split over several lines for greater readability. For each font type you specify for the `src` property, you add a URL, a format, and a comma (for all but the last font):

```
url('fonts/League_Gothic-webfont.woff') format('woff'),
```

NOTE

At the end of the list of files for the `src` property, you add a semicolon to note that you've reached the end of the `src` property (line 7 above). Don't forget this final semicolon, or the `@font-face` directive won't work.

Even though a browser may understand different types of fonts (for example, Chrome can use WOFF, TrueType, and SVG fonts), it won't download all the font files. Instead, as it reads through the list of font types, the browser downloads only the first one it understands. In other words, if Chrome encountered the above code, it would skip the `.eot` file since it doesn't understand that font format, but would download the `.woff` file. It would then skip the TrueType and SVG files entirely. That means the order in which you list the fonts is important. WOFF is generally preferred since it's a smaller file that downloads more quickly, while SVG is generally a much larger file, so you want to make sure that you list the fonts in the order of `.eot`, `.woff`, `.ttf`, and `.svg`.

NOTE The above `@font-face` syntax is the result of a lot of testing and troubleshooting on the part of many talented web professionals. You can read about its evolution on the following blog posts: <http://www.fontspring.com/blog/further-hardening-of-the-bulletproof-syntax>, <http://www.fontspring.com/blog/the-new-bulletproof-font-face-syntax>, and <http://paulirish.com/2009/bulletproof-font-face-implementation-syntax/>.

Creating Styles Using Web Fonts

The hardest part of web fonts is getting the font files in the proper format and setting up the `@font-face` directives. Once that's done, you use web fonts just as you would the preinstalled fonts discussed on page 129. In other words, when you create a new style, you simply use the `font-family` property and supply the name for the font you used in the `@font-face` directive. For example, in the previous code, the `@font-face` directive names the new font League Gothic (line 2 on page 138). This is the name you use when applying this font to a style. To make all `h1` tags use the League Gothic font, you could write this style:

```
h1 {
    font-family: 'League Gothic';
    font-weight: normal;
}
```

Notice that there's a new property—`font-weight`—listed here. Browsers normally display `<h1>` tags as bold. Most browsers will artificially bold a web font when a bold version is required. This results in an ugly boldface. Setting the `font-weight` to `normal` tells the browser to just use the League Gothic font “as-is,” and avoids trying to bold it. In the next section, you'll learn more about how to deal with font variants like bold and italic with web fonts.

It's also a good idea to include a list of backup, preinstalled fonts, in case the browser can't load the web font. This is the same technique described on page 129. For example:

```
h1 {
    font-family: 'League Gothic', Arial, sans-serif;
    font-weight: normal;
}
```

TIP You can use fonts that contain symbols and icons on a web page, too. So rather than creating a graphic of a warning sign (for example) and placing it inside a paragraph of text, you can use the `@font-face` directive to load a font containing the warning sign icon and just use a simple letter (mapped to the icon in the font). Here are a few resources on using icon fonts: <http://css-tricks.com/flat-icons-icon-fonts/>, <http://css-tricks.com/html-for-icon-font-usage/> and <http://css-tricks.com/examples/IconFont/>.

Dealing with Bold and Italic Variants

The common fonts installed on computers include variations in style and weight, so when you apply a `` tag in HTML, a web browser uses the bold version of that font; likewise, when you apply an `` tag to text, the browser uses an italicized

version of that font; and if you combine both tags, you'll see a bold and italic version of the font. These are actually different fonts contained in different font files. With the original method of using fonts in web pages (described on page 129), you never have to worry about these different fonts, since the browser uses the correct version automatically.

However, with web fonts, you need separate font files for each font variant. So, for body text you'll need at least a regular version of a font, a bold version, an italic version, and a bold/italic version. Keep this in mind when finding a web font for your site; some fonts only have a single weight and no italic version. This could be fine for a headline, but not much use for long paragraphs of text, which most likely will have some italic and bold text. In addition, you must create separate `@font-face` directives for each font variant.

You have two choices when working with italic/bold versions of web fonts. One method is easier to implement but doesn't work on Internet Explorer 8 or earlier (or IE 9 in compatibility mode); the other is more labor intensive but works on older versions of Internet Explorer.

■ THE EASY WAY TO ADD BOLD AND ITALIC

The easiest way to add bold and italic variants of your fonts is to add `font-weight` and `font-style` properties to the `@font-face` directive. Normally, the CSS `font-weight` property (page 163) tells a browser to display a font in bold, normal, or one of several other weights, while the `font-style` property (page 162) tells a browser to display a font as italic or normal. However, when used within the `@font-face` directive, `font-style` tells a browser to apply the font when the style asks for a particular variant of the font.

Say you have a font named PTSans. You start with the normal, non-bold, non-italic version of the font. The various font formats begin with PTSansRegular (PTSansRegular.eot, PTSansRegular.ttf, and so on). In your style sheet, you'd add this `@font-face` directive:

```
@font-face {  
  font-family: 'PTSans';  
  src: url('PTSansRegular.eot');  
  src: url('PTSansRegular.eot?#iefix') format('embedded-opentype'),  
       url('PTSansRegular.woff') format('woff'),  
       url('PTSansRegular.ttf') format('truetype'),  
       url('PTSansRegular.svg') format('svg');  
  font-weight: normal;  
  font-style: normal;  
}
```

Notice the following:

- You use a generic name for the font family—PTSans in line 2 above—instead of the specific name for that font file—PTSansRegular.

- The `font-weight` is set to `normal`, since this isn't a bold version of the font (line 8).
- The `font-style` is set to `normal`, since this isn't an italic version of the font (line 9).

NOTE The code examples here assume that the font files `PTSansRegular.eot`, `PTSansBold.eot`, and so on are in the same folder as the style sheet. If they were in different folders, you'd need to adjust the URL to accurately point to the location of the font files in relation to the style sheet.

Now, say you had an italicized version of the font—the file name begins with `PTSansItalic`. You'd then add this to your style sheet:

```
@font-face {
  font-family: 'PTSans';
  src: url('PTSansItalic.eot');
  src: url('PTSansItalic.eot?#iefix') format('embedded-opentype'),
       url('PTSansItalic.woff') format('woff'),
       url('PTSansItalic.ttf') format('truetype'),
       url('PTSansItalic.svg') format('svg');
  font-weight: normal;
  font-style: italic;
}
```

You use the same `font-family` name in line 2—`PTSans`. However, you change the `font-style` to `italic` (line 9). This tells the browser that the font you're specifying is the italic version of the `PTSans` font. You'd add similar `@font-face` directives for the bold and the bold/italic versions like this:

```
@font-face {
  font-family: 'PTSans';
  src: url('PTSansBold.eot');
  src: url('PTSansBold.eot?#iefix') format('embedded-opentype'),
       url('PTSansBold.woff') format('woff'),
       url('PTSansBold.ttf') format('truetype'),
       url('PTSansBold.svg') format('svg');
  font-weight: bold;
  font-style: normal;
}

@font-face {
  font-family: 'PTSans';
  src: url('PTSansBoldItalic.eot');
  src: url('PTSansBoldItalic.eot?#iefix') format('embedded-opentype'),
       url('PTSansBoldItalic.woff') format('woff'),
       url('PTSansBoldItalic.ttf') format('truetype'),
       url('PTSansBoldItalic.svg') format('svg');
  font-weight: bold;
  font-style: italic;
}
```

In other words, you need four `@font-face` directives to cover all variants of bold, italic, and regular text: notice that the `font-family` name is the same in each case; only the `src` properties change (to point to the different files) and the `font-weight` and `font-style` properties change.

The benefit of this method is that you can apply the regular font to text, apply `` and `` tags to your HTML, and let the browser worry about which font file to load and use. In this example, if you want to use the PTSans font on all your paragraphs, you'd simply add this style to your style sheet:

```
p {
  font-family: PTSans;
}
```

Then you can mark up your paragraph tags with HTML. For example, you might have a paragraph like this:

```
<p>When I was younger, I could remember <em>anything</em>, whether it had hap-
pened or <strong>not</strong> -- <strong><em>Mark Twain</em></strong></p>
```

When the web browser reads the style sheet (with the four `@font-face` directives and the `p` tag style), it would display most of the paragraph using the PTSansRegular font. However, the word “anything” contained inside the `` tags would use the PTSansItalic font; the word “not” inside the `` tags would use the PTSansBold font; and “Mark Twain” inside both `` and `` tags would use the PTSansBoldItalic font.

These directives even work for headlines. If you created a style to format all `h1` tags with PTSans, you could create this style:

```
h1 {
  font-family: PTSans;
}
```

With this style in place, a web browser would actually use the bold version of PTSans, since headlines are normally displayed in bold. (When you use this technique involving multiple variations of a font, you should not add `font-weight: normal;`, as described on page 140.)

Unfortunately, Internet Explorer 8 and earlier don't understand this method and will use the PTSansRegular font for all of the text. IE will create faux-italic and faux-bold for the `` and `` tags; that is, it will slant the PTSansRegular font on screen for italic, and make the PTSansRegular font thicker for bold. The resulting computer-generated bold and italic usually look pretty bad.

NOTE

This book's tutorial files include examples of both techniques for including bold and italic versions of fonts. Look inside the `webfonts-demo` folder. The file `webfonts.html` uses the technique outlined on page 140, while the `webfonts-ie-safe.html` file uses the technique described next.

■ ADDING BOLD AND ITALIC AND SUPPORTING INTERNET EXPLORER 8

If you're still supporting Internet Explorer 8 (or earlier), the previous solution to bold and italic won't work so well. You can get font variants to work in IE 8, but it requires a bit more work. To begin with, you still create four `@font-face` directives, one for each variant of the font. However, instead of giving them the same `font-family` name (PTSans, for example), you give each one its unique name (PTSansRegular, PTSansItalic, and so on). In other words, you'd rewrite the four `@font-face` directives like this:

```
@font-face {
  font-family: 'PTSansRegular';
  src: url('PTSansRegular.eot');
  src: url('PTSansRegular.eot?#iefix') format('embedded-opentype'),
       url('PTSansRegular.woff') format('woff'),
       url('PTSansRegular.ttf') format('truetype'),
       url('PTSansRegular.svg') format('svg');
}

@font-face {
  font-family: 'PTSansItalic';
  src: url('PTSansItalic.eot');
  src: url('PTSansItalic.eot?#iefix') format('embedded-opentype'),
       url('PTSansItalic.woff') format('woff'),
       url('PTSansItalic.ttf') format('truetype'),
       url('PTSansItalic.svg') format('svg');
}

@font-face {
  font-family: 'PTSansBold';
  src: url('PTSansBold.eot');
  src: url('PTSansBold.eot?#iefix') format('embedded-opentype'),
       url('PTSansBold.woff') format('woff'),
       url('PTSansBold.ttf') format('truetype'),
       url('PTSansBold.svg') format('svg');
}

@font-face {
  font-family: 'PTSansBoldItalic';
  src: url('PTSansBoldItalic.eot');
  src: url('PTSansBoldItalic.eot?#iefix') format('embedded-opentype'),
       url('PTSansBoldItalic.woff') format('woff'),
       url('PTSansBoldItalic.ttf') format('truetype'),
       url('PTSansBoldItalic.svg') format('svg');
}
```

Notice that each `@font-face` directive has its one family name—one that matches the font variant: PTSansRegular, PTSansItalic, PTSansBold, and PTSansBoldItalic.

In addition, notice that the `font-weight` and `font-style` properties used in the examples on pages 140–143 are gone. You don't need them here.

The hard part comes when it's time to apply the font. In the example on page 143, you merely applied the `font-family` to the style like this:

```
p {
  font-family: PTSans;
}
```

Now, unfortunately, you have to apply the different font names to the various tags—`p` for regular, `em` for italic, `strong` for bold, and a descendent selector to handle the case of bold and italic. So to get the different variants of the PTSans font to work, you need to create four styles, involving many lines of code, like this:

```
p {
  font-family: PTSansRegular;
  font-size: 48px;
  font-style: normal;
  font-weight: normal;
}

p em {
  font-family: PTSansItalic;
  font-style: normal;
  font-weight: normal;
}

p strong {
  font-family: PTSansBold;
  font-style: normal;
  font-weight: normal;
}

p strong em, p em strong {
  font-family: PTSansBoldItalic;
  font-weight: normal;
  font-style: normal;
}
```

First, notice there are four styles: the `p` style applies the PTSansRegular font; `p em` is a descendent selector that applies to an `` tag that's inside a `<p>` tag—that style applies the PTSansItalic font; `p strong` is another descendent selector, which applies the PTSansBold font to the `` tag when it appears inside a paragraph; finally, there's a group selector composed of two descendent selectors. The first descendent selector applies to an `` tag that's inside a `` tag that's inside a `<p>` tag; while the second applies to a `` tag inside and `` that's inside a `<p>`. You need both because you can nest `` tags inside of `` tags and vice versa. You could end up with HTML like this:

```
<p>  
  <em><strong>Hey!</strong></em>  
  , I'm talking to  
  <strong><em>you</em></strong>  
</p>
```

The single `p strong em` selector won't work for the "Hey!" above, since it's a `` tag inside an `` tag.

NOTE

In HTML5, the `` (for bold) and `<i>` (for italic) tags are back. You should use them merely for presentational purposes—when you want text to be italic, but not add any real emphasis to the meaning of the text. For example, the titles of books are often italicized, so using the `<i>` tag is recommended:

```
<i>CSS3: The Missing Manual</i>
```

Using `` would emphasize the text and cause screen readers to read the text aloud in a different way than other text. At any rate, if you intended to use `` and `<i>`, make sure you create styles that use the italic and bold variants of the font (again, you only need worry about that if you're using the IE 8—safe way of specifying italics, not if you're using the method discussed on page 141).

Another thing to notice is that you have to set the `font-weight` and `font-style` to `normal` for all these styles. If you don't, many browsers (not just Internet Explorer) will try to bold the already bolded font, and italicize the already italic version of the font (Firefox creates particularly bad fake bold text).

This second technique for supporting bold and italic variants is obviously a lot of work. It becomes even more work if you use more than one font with bold and italic versions on the same site. Which technique you use really depends on how important Internet Explorer 8 support is for you. At the time of this writing, IE 8 is still quite popular, ranging from 13% (http://gs.statcounter.com/#browser_version-ww-monthly-201108-201208) to 25% (<http://www.netmarketshare.com/browser-market-share.aspx?qprid=2&qpcustommd=0&qptimeframe=M>) of web browsers in use.

NOTE

Here's another approach to the problem of supporting bold and italic for IE 8. Try the first method (page 141), and see how it looks in IE 8. Some fonts, usually sans-serif fonts, don't always look that bad when IE does its faux italic and bold thing to them. You might find that the difference isn't that noticeable, and you can use the first method without much of a problem. Also, remember that IE 8's market share will continue to decline as people buy new computers, switch to Chrome or another browser, or upgrade their operating systems.

■ Discovering Google Web Fonts

If the instructions for using web fonts discussed in the previous section sound too daunting to you, there's an easier way—although one with fewer font options. In addition to search, maps, email, and all the many services it offers, Google provides an easy-to-use web fonts service. Rather than downloading fonts, converting them to

proper formats, and then placing them onto your web server, you simply include a single external style sheet link to Google that indicates which fonts you'd like to use. Google's server sends the proper fonts to the visitor's web browser. No muss, no fuss.

Your only responsibilities are finding the fonts you want to use on the Google Web Fonts site, copying the necessary code (which Google provides) and adding it to your web page, and creating CSS styles using those fonts. Start by visiting the Google Web Fonts site at www.google.com/webfonts (see Figure 6-6).




FIGURE 6-6

The Google Web Fonts site lists the fonts Google offers. Some fonts have multiple styles, such as bold, italic, thin, ultra-thin, and so on. To see all variants for a particular font, click the Show All Styles link in the left sidebar (circled). Each font also has three links: the first, "Quick Use" (#1) loads the Use panel described on page 150 and lets you quickly add the code necessary to use that font; the "Pop-out" link (#2) opens a new window with more information on the font as well as a specimen sheet demonstrating every letter in the font (it's a good way to see what the entire alphabet looks like and also to make sure that it has all the characters you need—such as unusual symbols or punctuation marks); lastly, the "Add to Collection" link (#3) adds the font to your collection. (If you want to use more than one font, then add them all to the collection.)

Finding and Selecting Fonts

You select the fonts you wish to use by creating a *collection*. It's as easy as finding a font you like and clicking the "Add to Collection" button (see Figure 6-6). To find a font, you can scroll down the main web fonts page and see examples of the available fonts, but with over 500 fonts to choose from, it might take you a while to locate one you like. If you have a specific look already in mind, like a bold sans-serif font for headlines, use one of the filtering options in the left side of the page (see Figure 6-7).

- **Search by name.** If you know the name of the font you're interested in, then just type the name (or part of the name) in the Search field (#1 in Figure 6-7). The page then filters the list of fonts to show you the ones that match.
- **Filter by category.** The category menu (#2 in Figure 6-7) lets you show fonts that match one, two, three, or four categories: Serif, Sans Serif, Display, and Handwriting. Just uncheck a box to hide that type of font, or turn on the box to show it. Display fonts are generally bold and stylish; they're not really good for long passages of text, but can make short headlines really jump out of the page. Handwriting fonts, or script fonts, look like someone wrote the text with a pen. They vary from elegant, wedding invitation-like scripts, to a hand-scrawled, "Give me the money if you want your cat back" ransom-note look.
- **Physical style.** Three sliders let you identify physical characteristics of fonts (#3 in Figure 6-7). The thickness slider lets you find fonts made of very thin lines (delicate lines that are often hard to read unless displayed at a large font size) to very thick lines (bold and chunky). The Slant slider identifies fonts with a "lean" to them: generally this means italic versions of fonts, but also is relevant for handwritten fonts, which generally have a pronounced lean toward the right. Finally, use the Width slider to find fonts that are either narrower or more spread-out. With wider fonts, you fit fewer letters on a single line but often make a bold statement in a headline.
- **Alphabet.** Lastly, the Script menu (#4 in Figure 6-7) lets you specify fonts for use with other languages. English and many European languages use the Latin alphabet, but if you need a font for Russian text, for example, you would choose Cyrillic. Pick the one that matches the language your text will appear in.

**FIGURE 6-7**

To help find the fonts that match your design, you can search Google's font directory, or filter down the list of fonts by specifying various criteria. If you try to use all of these filters, you'll most likely end up with no results. If so, click the "Reset all filters/search" link (circled) to return to the full list of Google web fonts.

TIP To see a showcase of some of the best fonts available from Google, check out <http://hellohappy.org/beautiful-web-type/>.

As you find fonts that you'd like to use, you can click the “Add to Collection” button (#1 in Figure 6-8). The collection is kind of like a shopping cart, so you can add fonts to it and remove fonts from it.




FIGURE 6-8

To see the fonts you've added to your collection, click the disclosure arrows (#2). You can remove a font from the collection by clicking the X (delete) button to the right of the font name (#3). The Review button (circled) lets you compare the fonts in your collection and retrieve more in-depth information. For example, you can see the complete character set for each font (that is, each letter and symbol), test drive a font by adding your own text and changing the font size, and even create an overlay comparison of all the fonts in your collection (if you're truly type obsessed).

Using Google Fonts

Once you've created a collection of fonts, you're ready to retrieve the code necessary to use them.

1. **At the bottom right of the Google Web Fonts screen (#1 in Figure 6-9), click the Use button.**

A page opens with several options as well as the code you need to copy.

2. **Choose the style you want to use (#2 in Figure 6-9).**

Some fonts include italic, bold, and other variants of the regular font. For body text, you'll usually want at least regular, italic, and bold. In the case of a headline, you can usually get away with just one font. You'll notice also that there's a “speed dial” on the right of this page. As you add more styles and fonts, the speed dial rotates clockwise indicating that it will take more time to download the fonts.

That's one drawback of web fonts. Since your site's visitors need to download them (as well as the web page, external style sheets, graphics, and other elements that make up your page), be careful not to go crazy and use too many fonts. Otherwise, people will have to wait a long time for the fonts to appear. The number on the dial indicates the number of milliseconds (on average) it will take to download the font files.

3. Optionally, choose the character sets you want.

This step isn't required and may not be available for all fonts. In addition, if you selected a character set other than Latin (see the last bullet point on page 148), then you may see other options besides Latin and Latin Extended. Latin Extended is a good choice if your text contains words in a language that uses particular accent characters like Turkish, Welsh, and Hungarian. For most Latin-based languages like French and Spanish, the normal Latin alphabet is all you need. You're better off not using the extended Latin if you don't need it, since using it adds file size and download time to the font.

NOTE To see a list of the extra characters available in Latin Extended visit http://en.wikipedia.org/wiki/Latin_Extended-A.

4. Copy the code in the “Add this code to your website” box (#3 in Figure 6-9).

You have three options here.

- **Standard** provides a `<link>` tag that points to an external style sheet (this is the same as linking to any external style sheet, as described on page 48). However, this is actually a special link that points to Google's web server and provides the information Google needs to deliver the proper fonts. For instance:

```
<link href='http://fonts.googleapis.com/css?family=Codystar:300,400|Gentium+Book+Basic:400,400italic' rel='stylesheet' type='text/css'>
```

Notice that at the end of the href attribute, the fonts and their styles are listed. In this example, the fonts are Codystar and Gentium. And Google will load several styles: 300 and 400 for Codystar and 400 and 400italic for Gentium. Those numbers are a way of indicating the weight (or thickness) of the font and are discussed in Step 6 on page 152.

NOTE If you're using HTML5, you can leave out the `"type='text/css'"` part of the `<link>` tag. It's not needed in HTML5.

- Another option is **@import**. Click the `@import` tab under step 3 on the web page (see Figure 6-9) to see the code needed to use the `@import` directive discussed on page 42. The benefit of this approach is that you can add `@import` to the beginning of another style sheet. For example, say you have

a single external style sheet for your site, and you've linked all the pages in your site to it. The standard `<link>` method requires you to add that code to every page on your site. However, with the `@import` method, you can add the code to your single external style sheet and you're done.

- Finally, you can choose a **JavaScript** approach. This book doesn't cover this method, since it requires a lot of code, and unless you know JavaScript really well, it's easy to make a mistake. In addition, it doesn't offer much benefit over the other options.

5. Paste the code on your site's web pages.

In the case of the `<link>` method described in the previous step, you must paste the code onto every page you wish to use the fonts on. If you're just beginning the process of building your site, this isn't such a big deal, but if you already have lots of pages, this may end up being quite a bit of work. In that case, consider the `@import` method: you can place the `@import` code at the top of your site's external style sheet, and then all the pages that link to that style sheet will also download the proper fonts.

NOTE The `@import` method can have a slight effect on your website's performance (that is, speed).

6. Create styles using the fonts.

Now that the fonts are loading, you can use them much like any other font. Just create a style, add the `font-family` property, and list the font. Google's Web Fonts page shows the font's name at the bottom of the Use page (#4 in Figure 6-9).

If you're using multiple styles of a font, then you also need to add the `font-weight` and `font-style` properties to the style. Google doesn't use the regular `normal` or `bold` keywords to indicate a font's weight. Instead it uses a numeric scale from 100 to 900. A value of 700 is bold, 400 is normal, and the other numbers indicate variations in thickness. For example, say you want to apply the regular italic version of the Gentium Book Basic font to the `` tag. You can write this style:

```
em {
  font-family: "Gentium Book Basic", serif;
  font-weight: 400;
  font-style: italic;}
```

1. Choose the styles you want:

CODYSTAR
 BOOK 300 **2**
 NORMAL 400
 Gentium Book Basic
 Normal 400
 Bold 700
 Bold 700 Italic

GRUMPY WIZARDS MAKE TOXIC BREW FOR THE EVIL QUEEN AND JACK
 GRUMPY WIZARDS MAKE TOXIC BREW FOR THE EVIL QUEEN AND JACK
 Grumpy wizards make toxic brew for the evil Queen and Jack
 Grumpy wizards make toxic brew for the evil Queen and Jack
 Grumpy wizards make toxic brew for the evil Queen and Jack
 Grumpy wizards make toxic brew for the evil Queen and Jack

Impact on page load time
 Tip: Using many font styles can slow down your webpage, so only select the font styles that you actually need on your webpage.

2. Choose the character sets you want:

Latin (latin) Latin Extended (latin-ext)

Tip: If you choose only the languages that you need, you'll help prevent slowness on your webpage.
[Read more on how to use subsets](#)

3. Add this code to your website:

Instructions: To embed your Collection into your web page, copy the code as the first element in the <head> of your HTML document.
[See an example](#)

4. Integrate the fonts into your CSS:

The Google Web Fonts API will generate the necessary browser-specific CSS to use the fonts. All you need to do is add the font name to your CSS styles. For example:

font-family: 'Codystar', cursive; **4**
 font-family: 'Gentium Book Basic', serif;

Instructions: Add the font name to your CSS styles just as you'd do normally with any other font.
 Example:
 h1 { font-family: 'Metropolis', Arial, serif; font-weight: 400; }

2 font families in your Collection [Choose](#) [Review](#) [Use](#) **1**

FIGURE 6-9

When you're ready to use the Google fonts that you've added to your collection, click the Use button in the bottom right (#1), the styles you want (#2), and the method you'd like to use to attach those fonts to a page. The most common way is to simply link to a style sheet that loads the fonts from Google's servers.

UP TO SPEED

TypeKit, a Google Alternative

Because of the technical and legal requirements to using web fonts, several companies have sprouted up that handle all the heavy lifting for you. Google Web Fonts is one example, but there are others. These *font services* let you select from a large collection of fonts hosted on their own web servers. In other words, you don't put the fonts on your server, you simply reference their servers by using either a snippet of CSS or JavaScript code. These services take care of sending the proper font format (EOT to IE 8 and earlier, for example) to your visitors' browsers.

A commercial service from Adobe, called TypeKit, also provides a wide selection of fonts, but for a fee. Because it's part of

Adobe (which makes fonts in addition to all the other software they create), you have access to a wide range of professionally created fonts. With TypeKit, you create individual *kits*, or collections of fonts, and assign them to a website. You then add a snippet of JavaScript code to each page on your site. This code connects with the TypeKit servers, and delivers the fonts you requested to your site's visitors. TypeKit is a commercial service, though it does offer a free, limited trial version. Depending on how many fonts you want access to and how many people visit your website each month, you can end up spending anywhere from \$24 a year to \$99 a year.

■ Adding Color to Text

Black-and-white is great for *Casablanca* and Woody Allen films, but when it comes to text, a nice skyline blue looks much sharper and classier than drab black. Coloring your text with CSS is easy. In fact, you've used the `color` property in a few tutorials already. You have several different ways to define the exact color you want, but they all follow the same basic structure. You type `color:` followed by a color value:

```
color: #3E8988;
```

In this example, the color value is a hexadecimal number indicating a muted shade of teal (more in a moment on what hexadecimal is).

Every graphics program from Fireworks to Photoshop to the GIMP lets you select a color using hexadecimal or RGB values. Also, the color pickers built into Windows and Mac let you use a color wheel or palette to select the perfect color and translate it into a hexadecimal or RGB value.

NOTE

If your color design sense needs some help, you can find lots of attractive, coordinated collections of colors as well as great color-related resources at www.colourlovers.com.

Hexadecimal Color Notation

The oldest color system used by web designers is hexadecimal notation. A color value—like `#6600FF`—actually contains three hexadecimal numbers—in this example 66, 00, FF—each of which specify an amount of red, green, and blue, respectively. As in the RGB color system described next, the final color value is a blend of the amounts of red, green, and blue specified by these numbers.

TIP

You can shorten the hexadecimal numbers to just three characters if each set contains the same two numbers. For example, shorten `#6600FF` to `#60F`, or `#FFFFFF` to `#FFF`.

■ RGB

You can also use the RGB—red, green, blue—method familiar in computer graphics programs. The color value consists of three numbers representing either percentages (0–100 percent) or numbers between 0–255 for each hue (red, green, and blue). So when you want to set the text color to white (perhaps to set it off from an ominous dark page background), you can use this:

```
color: rgb(100%,100%,100%);
```

or

```
color: rgb(255,255,255);
```

NOTE If all these numbers and digits have your head spinning, then you can always fall back on the classic HTML color keywords. (Just don't expect your site to win any awards for originality.) There are 17 colors—aqua, black, blue, fuchsia, gray, green, lime, maroon, navy, olive, orange, purple, red, silver, teal, white, and yellow. In CSS, you add them to your style like so: `color: fuchsia;` In addition, most browsers support 147 SVG colors (also called X11 colors), so if you really want to show off, start using colors like linen, chocolate, khaki, and whitesmoke. You can find these colors listed at https://developer.mozilla.org/en-US/docs/CSS/color_value.

■ RGBA

To add depth to a page, consider one of the newer color methods. RGBA stands for Red, Green, Blue, Alpha, and it works just like the RGB colors with the addition of an *alpha* channel. That is, you can specify a level of opacity so that the color isn't solid, but see-through (see Figure 6-10). To the RGB colors, you add one last number, a value between 0 and 1. A value of 0 makes the color invisible, while 1 renders the color totally opaque (that is, you can't see through it):

```
color: rgba(255, 100, 50, .5);
```

You can create interesting visual effects by placing RGBA colored text over background images. For example, you can make the images seep through the color of the text a little (by using a high value like .9) or a lot (by using a low value like .1).

TIP RGBA works particularly well with the `text-shadow` property discussed on page 166 and the `box-shadow` property discussed on page 210. Using RGBA, you can create even more subtle drop shadow effects by letting more of the background show through the shadow.

The downside? Internet Explorer 8 and earlier don't understand RGBA color. One solution is to declare a solid color first using hexadecimal notation, and then a second color property with RGBA color, like this:

```
color: rgb(255,100,50); /* for IE8 */
color: rgba(255,100,50,.5); /* for newer browsers */
```

All browsers interpret the first line; the second line overrides the first line, but only for browsers that understand RGBA color. In other words, IE 8 applies the first color declaration and ignores the second, while IE 9 and other browsers apply the RGBA color. You just won't get the transparency effect in IE 8. In addition, this technique doesn't work in IE 7, which simply ignores both lines and applies a black color. Fortunately, IE 7 usage is trending toward zero, so you probably don't need to worry about it. (To make the alpha transparency work in IE 7 and 8, see the note on page 156.)




FIGURE 6-10
RGBA colors aren't just for text. You can use RGBA color with any CSS property that accepts a color value, like the background color of the search box in the top-right of this image, or the color of the navigation buttons: Home, Archives, Authors, and so on.

NOTE

If you want to preserve the transparency effect for IE 7 and 8, you can. It just requires a bit of IE-only magic. Considering IE 7 is on its way out, you may not want to bother, but you can learn how at <http://css-tricks.com/rgba-browser-support>.

HSL AND HSLA

HSL stands for hue, saturation, and lightness (also sometimes labeled *luminance*). It's yet another way to specify color. It's not supported by Internet Explorer 8 or earlier, but works in all other browsers. If you're used to RGB or Hex colors, you may find the HSL syntax a bit unusual. Here's an example of a bright red color:

```
color: hsl(0, 100%, 50%);
```

You supply three values inside `hsl()`. The first is a degree value from 0 to 360, which maps to a circle of hues. If you remember the order of the colors in a rainbow—red, orange, yellow, green, blue, indigo, and violet (ROYGBIV)—then you've got a basic idea of the values you'll need to specify a color. Red is 0 (it's also 360, since that's one full rotation around a circle), yellow is around 50, orange around 100, green around 150, and so on. Each color is separated by around 51 degrees.

The second is the saturation, or how pure the color is. You specify saturation in a percentage from 0% to 100%. A value of 0% is no saturation at all, or a dull gray. In fact, no matter what hue you specify, 0% will produce the same gray hue. A value

of 100% is the pure color—bright and vibrant. The third value is the lightness value, specified in a percentage from 0% (completely black) to 100% (completely white). If you want to have a pure color, then you use a value of 50%.

HSL is supposed to be more intuitive than RGB or Hexadecimal color values, but if you don't find it easy to understand, you don't have to use it. Instead, use a program like Fireworks or Photoshop or an online color picker, each of which make picking an RGB or Hex value easy.

NOTE

If you're interested in using HSL, you'll find an easy-to-use HSL color picker at www.workwithcolor.com/hsl-color-schemes-01.htm.

Just as RGB has its companion format, RGBA, HSL supports opacity with the HSLA format. It works similarly to RGB described on page 155. You specify an opacity value from 0 (invisible) to 1 (totally opaque) to set the opacity value. This will create a bright red color with 50% opacity:

```
color: hsla(0, 100%, 50%, .5);
```

The examples in this book mostly stick with RGBA, but if you find HSL easier to understand, then use it!

■ Changing Font Size

Varying the size of text on a web page is a great way to create visual interest and direct your visitors' attention to important areas of a page. Headlines in large type sizes capture attention, while copyright notices displayed in small type subtly recede from prominence.

The font-size property sets text size. It's always followed by a unit of measurement, like so:

```
font-size: 1em;
```

The value and unit you specify for the font size (in this example, 1em) determine the size of the text. CSS offers a dizzying selection of sizing units: keywords, ems, exs, pixels, percentages, picas, points, and even inches, centimeters, and millimeters.

Units of measurement commonly used with printed materials—picas, points, inches, and so on—don't work well on web pages because you can't predict how they'll look from one monitor to the next. But you may have occasion to use points when creating style sheets for printer-friendly pages, as described on page 523. Only a few of the measurement units—pixels, keywords, ems, and percentages—make sense when you're sizing text for a computer monitor. The rest of this section explains how they work.

Using Pixels

Pixel values are the easiest to understand, since they're completely independent from any browser settings. When you specify, for example, a 36-pixel font size for an `<h1>` tag, the web browser displays text that's 36 pixels tall, period. Web designers cherish pixel values because they provide consistent text sizes across different types of computers and browsers.

To set a pixel value for the font-size property, type a number followed by the abbreviation `px`:

```
font-size: 36px;
```

NOTE

Don't include a space between the number and the unit type. For example, `36px` is correct, but `36 px` isn't.

UP TO SPEED

Pixels and Retina Displays

When Apple introduced the iPhone with Retina Display, iPhone owners rejoiced at the clarity and sharpness of the images. Apple's Retina Display provides its clear image by cramming more pixels into a square inch. While regular computer displays range from 72–100 pixels per inch, the new Retina Displays boast upward of 224 pixels per inch.

Apple has since added Retina Displays to iPads and laptops. Other tablet makers like Amazon are also jumping on the bandwagon, offering considerably more pixels per inch than older screens. What does this mean for web designers? Quite a bit. As you'll read in the box on page 473, these screens have considerable effect on images, and you'll need to do a bit of work to make great looking images for dense pixel displays.

When it comes to the pixels mentioned above, browsers on devices with Retina Displays actually multiply a pixel value by 2. That is, if you specify for text to be 16 pixels, a Retina Display-enabled web browser will actually use 32 pixels on the screen to draw the text. This is a good thing. If the browser only used 16 of its super-tiny pixels to display the text, then no one could read what you have to say.

In other words, although more dense displays are entering both the mobile and desktop computing world, they won't suddenly make the pixel-based type on your web pages appear microscopically small.

Using Keywords, Percentages, and Ems

Three ways of sizing text with CSS—keywords, percentages, and ems—work by either adding to or subtracting from the text size already on the viewer's browser screen. In other words, if you don't specify a text size using CSS, a web browser falls back on its pre-programmed settings. In most browsers, text inside a non-header tag is displayed 16 pixels tall—that's called the *base text size*.

Web surfers can adjust their browsers by pumping up or dropping down that base size; however, changing the base font size requires fiddling with the browser's preference settings, a step most folks won't bother with.

NOTE Most browsers have a *zoom* function that makes text, graphics, and the entire page smaller or larger. This setting doesn't really change the base text size as much as it magnifies the entire page. Ctrl++ (⌘++) on most browsers zooms in on a page, while Ctrl+ (⌘-) zooms out. Pressing the Ctrl (Control) key and using the scroll wheel on a mouse also lets you zoom in and out of a page.

When you resize text with CSS, the browser takes the base text size (whether it's the original 16 pixels or some other size the viewer ordered) and adjusts it up or down according to your keyword, em, or percentage value.

■ KEYWORDS

CSS provides seven keywords that let you assign a size that's relative to the base text size: `xx-small`, `x-small`, `small`, `medium`, `large`, `x-large`, and `xx-large`. The CSS looks like this:

```
font-size: large;
```

The medium option is the same as the browser's base font size. Each of the other options decreases or increases the size by a different factor. In other words, while each size change is supposed to be a consistent increase or decrease from the previous size, it isn't. Basically, `xx-small` is the equivalent of 9 pixels (assuming you haven't adjusted the base font size in your browser); `x-small` is 10 pixels, `small` is 13 pixels, `large` is 18 pixels; `x-large` is 24 pixels, and `xx-large` is 32 pixels.

Keywords are pretty limited: You have only seven choices. When you want more control over the size of your text, turn to one of the other font-sizing options discussed next.

■ PERCENTAGES

Like keywords, percentage values adjust text in relationship to the font size defined by the browser, but they give you much finer control than just `large`, `x-large`, and so on. Every browser has a pre-programmed base text size, which in most browsers is 16 pixels. You can adjust this base size in your browser's preferences. Whatever setting has been chosen, the base text size for a particular browser is equivalent to 100%. In other words, for most browsers, setting the CSS percentage to 100% is the same as setting it to 16 pixels.

Say you want to make a particular headline appear two times the size of average text on a page. You simply set the font size to 200%, like so:

```
font-size: 200%;
```

Or, when you want the text to be slightly smaller than the default size, use a value like 90% to shrink the font size down a bit.

The above examples are pretty straightforward, but here's where it gets a little tricky: Font size is an inherited property (see Chapter 4), meaning that any tags inside of a tag that has a font size specified inherit that font size. So the exact size of 100% can change if a tag inherits a `font-size` value.

For example, at the lower left of Figure 6-11, there's a `<div>` tag that has its font size set to 200%. That's two times the browser's base text size, or 32 pixels. All tags inside that `<div>` inherit that text size and use it as the basis for calculating their text sizes. In other words, for tags inside that `<div>`, 100% is 32 pixels. So the `<h1>` tag inside the `<div>` that has a font size of 100% displays at two times the base-text size for the page, or 32 pixels.




FIGURE 6-11

The three most common units for sizing text: pixels, ems, and percentages. Watch out for inherited text sizes when using ems or percentages, as explained on page 159. If you notice that some text on a page looks unusually large or small, then check to see if the offending text isn't inside a tag that inherits a font size from another tag.

■ **EMS**

Once you understand percentages, you know everything you need to understand ems. The two work exactly the same way, but many web designers use ems because of its roots in typography.

The word *em* comes from the world of printed (as in paper) typography, where it refers to the size of a capital letter M for a particular font. As it's worked its way into the Web world, an em in CSS no longer means the same thing as in typography. Think of it as referring to the base text size. That is, a value of 1em means the same thing as a value of 100 percent, as described in the previous section. You can even

say it the opposite way: A percentage value is just an em multiplied by 100: .5em is 50 percent, .75em is 75 percent, 3em is 300 percent, and so on.

For example, this CSS does the exact same thing as `font-size: 200%;`:

```
font-size: 2em;
```

NOTE As with pixel values, there's no space between the number and the word em. Also, even if you specify more than one em, you never add an s to the end: 2.5em, never 2.5ems.

When it comes to inheritance, ems also work just like percentage values. See the upper right of Figure 6-11 for an example. The bottom paragraph is set to .75em, which, since the <p> tag inherits the 2em (32 pixel) setting from the <div> tag, works out to .75 x 32, or 24 pixels. Inside the <p> tag are two other tags that also have a font-size setting of .75em. The innermost tag, a tag, is set to .75em or, in essence, 75 percent of its *inherited* size. There's a lot of math to this one: 32 pixels (inherited from the <div> tag) x .75 (inherited from the <p> tag) x .75 (inherited from the tag) x .75 (the tag's own font size). The result of this brainteaser is a text size of roughly 14 pixels.

WORKAROUND WORKSHOP

Untangling the Nest

Inherited font-size values can cause problems for nested lists. (See the bottom-right square of Figure 6-11.) If you create a style like `ul { font-size: 75% }`, then a nested list, which is a tag inside of another tag, is set to 75 percent of 75 percent—making the text in the nested list smaller than the rest of the list.

To get around this conundrum, create an additional descendent selector style like this: `ul ul {font-size: 100%}`. This style sets any ul tag inside of a ul to 100 percent: in other words, 100 percent of the surrounding ul tag's font size. In this example, it keeps any nested lists to 75 percent of the base text size.

There's another way to prevent this hall-of-mirrors, shrinking-text effect. CSS3 includes a new measurement unit named rem. No, it's not named after sleep patterns or a band. It stands for Root EM—meaning its value is based on the text size of the root element. In most cases this just means the base text size, so you can change the .75em shown in Figure 6-11 to this:

```
font-size: .75rem;
```

This style makes the font size .75 of the base text size, not the current font size (as is the case with ems). The root element in HTML is actually the html element you find at the beginning of a web page. When using rem values, you can set the base text size of the html element and then use rem units to set text to a size relative to that. For example, you can set the base text size to 20 pixels like this:

```
html {
    font-size: 20px;
}
```

Then use rem units to create fonts in relation to that 20-pixel base text size. For example, to then make all paragraphs 15 pixels in size, add this style.

```
p {
    font-size: .75rem;
}
```

You should be aware, however, that while most browsers now understand the rem unit, Internet Explorer 8 and earlier don't.

TIP You can make type stand out on a page in many different ways. Making certain words larger than others or making some text darker, lighter, or brighter visually sets them apart from the surrounding text. Contrast is one of the most important principles of good graphic design; it can help highlight important messages, guide a reader's eye around a page, and generally make understanding a page easier. For a quick overview of typographic contrast, check out this page: www.creativepro.com/article/dot-font-seven-principles-of-typographic-contrast.

■ Formatting Words and Letters

Although you'll spend a lot of time fine-tuning the color, size, and fonts of the text on your web pages, CSS also lets you apply other common text-formatting properties (like bold and italic) as well as some less common ones (like small caps and letter spacing).

NOTE CSS lets you combine multiple text properties, but don't get carried away. Too much busy formatting makes your page harder to read. Worst of all, your hard work loses its impact.

Italicizing and Bolding

Web browsers display type inside the `` and `<i>` tags in *italicized* type and text inside the ``, ``, `<th>` (table header), and header tags (`<h1>`, and so on) in **bold** type. But you can control these settings yourself—either turn off bold for a headline or italicize text that normally isn't—using the `font-style` and `font-weight` properties.

To italicize text, add this to a style:

```
font-style: italic;
```

Alternatively, you can make sure text *isn't* italicized, like so:

```
font-style: normal;
```

NOTE The `font-style` property actually has a third option—*oblique*—which works identically to *italic*.

The `font-weight` property lets you make text bold or not. In fact, according to the rules of CSS, you can actually specify nine numeric values (100–900) to choose subtle gradations of boldness (from super-extra-heavy [900] to nearly invisible-light [100]). Of course, the fonts you use must have nine different weights for these values to have any visible effect for your website's visitors. The only way to use the numeric values is with the web fonts discussed on page 132. In fact, Google Web Fonts (page 146) use the numeric values exclusively for specifying font weights.

NOTE When using web fonts, you'll find that making text bold and italic requires a few other steps. See page 140 for the details.

To make text bold:

```
font-weight: bold;
```

And to make text un-bold:

```
font-weight: normal;
```

NOTE

Since headlines are already displayed as bold type, you may want to find another way of highlighting a word or words that are strongly emphasized or bolded inside a headline. Here's one way:

```
h1 strong { color: #3399FF; }
```

This descendent selector changes the color of any `` tags (usually displayed as bold) that appear inside a `<h1>` tag.

Capitalizing

Capitalizing text is pretty easy—just hit the caps lock key and start typing, right? But what if you want to capitalize every heading on a page, and the text you've copied and pasted from a Word document is lowercase? Rather than retyping the headline, turn to the CSS `text-transform` property. With it, you can make text all uppercase, all lowercase, or even capitalize the first letter of each word (for titles and headlines). Here's an example:

```
text-transform: uppercase;
```

For the other two options, just use `lowercase` or `capitalize`.

Because this property is inherited, a tag that's nested inside a tag with `text-transform` applied to it gets the same uppercase, lowercase, or capitalized value. To tell CSS *not* to change the case of text, use the `none` value:

```
text-transform: none;
```

■ SMALL CAPS

For more typographic sophistication, you can also turn to the `font-variant` property, which lets you set type as `small-caps`. In small cap style, lowercase letters appear as slightly downsized capital letters, like so: POMP AND CIRCUMSTANCE. While difficult to read for long stretches of text, small caps lend your page an old-world, bookish gravitas when used on headlines and captions. To create small-cap text:

```
font-variant: small-caps;
```

Decorating

CSS also provides the `text-decoration` property to add various enhancements to text. With it, you can add lines over, under, or through the text (see Figure 6-12), or for real giggles, you can make the text blink like a No Vacancy sign. Use the `text-decoration` property by adding one or more of the following keywords: `underline`, `overline`, `line-through`, or `blink`. For example, to underline text:

```
text-decoration: underline;
```




FIGURE 6-12

The text-decoration property in action. If this is what the people at CSS headquarters call “decorations,” you’d best not ask for their design help on your next home remodel.

You can also combine multiple keywords for multiple effects. Here’s how to add a line over and under some text:

```
text-decoration: underline overline;
```

But just because you *can* add these not-so-decorative decorations to text, doesn’t mean you should. For one thing, anyone who’s used the Web for any length of time instinctively associates any underlined text with a link and tries to click it. So it’s not a good idea to underline words that aren’t part of a link. And `blink` is like a neon sign flashing “Amateur! Amateur! Amateur!” (That’s probably why most browsers don’t make text blink even if you ask for it.)

NOTE You can get a similar effect to underlining and overlining by adding a border to the bottom or top of an element (see page 298). The big advantage of borders is that you can control their placement, size, and color to create a more attractive design that doesn’t look like a link.

The `overline` option simply draws a line above text, while `line-through` draws a line right through the center of text. Some designers use this strike-through effect to indicate an edit on a page where text has been removed from the original manuscript.

Finally, you can turn off all decorations by using the `none` keyword like this:

```
text-decoration: none;
```


Why do you need a text-decoration property that removes decorations? The most common example is removing the line that appears under a link. (See page 297.)

Letter and Word Spacing

Another way to make text stand out from the crowd is to adjust the space that appears between letters or words (see Figure 6-13). Reducing the space between letters using the CSS letter-spacing property can tighten up headlines, making them seem even bolder and heavier while fitting more letters on a single line. Conversely, increasing the space can give headlines a calmer, more majestic quality. To reduce the space between letters, you use a negative value like this:

```
letter-spacing: -1px;
```

A positive value adds space between letters:

```
letter-spacing: .7em;
```

Likewise, you can open up space (or remove space) between words using the word-spacing property. This property makes the space between words wider (or narrower) without actually affecting the spacing between the letters inside a word:

```
word-spacing: 2px;
```

With either of these properties, you can use any type of measurement you'd use for text sizing—pixels, ems, percentages—with either positive or negative values.





FIGURE 6-13

Use word and letter spacing judiciously. Too much or too little of either can make text difficult, if not impossible, to read.

Unless you're going for some really far-out design effect—in other words, totally unreadable text—keep your values small. Too high a negative value, and letters and words overlap. To keep the message of your site clear and legible, use both letter and word spacing with care.

■ Adding Text Shadow

CSS3 includes one property that lets you add drop shadows to text to add depth and interest to headlines, lists, and paragraphs (see Figure 6-14).



The text-shadow property requires four pieces of information: the horizontal offset (how far to the left or right of the text the shadow should appear), the vertical offset (how far above or below the text the shadow should appear), the blurriness of the shadow, and the color of the drop shadow. For example, here's the text-shadow property that creates the effect at the top of Figure 6-14:

```
text-shadow: -4px 4px 3px #999999;
```

The first value—-4px—means “place the shadow 4 pixels to the left of the text.” (A positive value here would place the shadow to the right of the text.) The second value—4px—places the shadow 4 pixels below the text. (A negative value would place the shadow above the text.) The 3px value defines how blurry the shadow should be. A 0px value (no blur) results in a sharp drop shadow; the larger the value, the more blurry and indistinct the shadow. Finally, the last value is the drop shadow's color.

You can even add multiple drop shadows for more complex effects (see the bottom image in Figure 6-14): just add a comma followed by additional drop shadow values, like this:

```
text-shadow: -4px 4px 3px #666, 1px -1px 2px #000;
```

There's no limit (except good taste) to the number of shadows you can add this way. Sadly, this effect doesn't work in Internet Explorer 9 or earlier. It does, however, work

in all other current browsers (even IE 10). In other words, *don't* rely on this effect to make text readable. The bottom image in Figure 6-14 shows you what not to do: The text color is white and it's readable only because the drop shadows define the outline of the text. In Internet Explorer 9 and earlier, the text would be invisible—white text on a white background.

NOTE For some examples of beautiful ways to use text shadows, visit <http://webexpedition18.com/articles/css3-text-shadow-property/>.

■ Formatting Entire Paragraphs

Some CSS properties apply to chunks of text rather than individual words. You can use the properties in this section on complete paragraphs, headlines, and so on.

Adjusting the Space Between Lines

In addition to changing the space between words and letters, CSS lets you adjust the space between lines of text using the `line-height` property. The bigger the line height, the more space that appears between each line of text (see Figure 6-15).




FIGURE 6-15

The line-height property lets you spread a paragraph's lines apart or bring them closer together. The normal setting is equivalent to 120 percent, so a smaller percentage tightens up the lines (top), while a larger percentage pushes them apart (bottom).

■ LINE SPACING BY PIXEL, EM, OR PERCENTAGE

Just as with the `font-size` property, you can use pixels, ems, or percentages to set the size of line height:

```
line-height: 150%;
```

In general, percentages or ems are better than pixels, because they change according to, and along with, the text's `font-size` property. If you set the line height to 10 pixels and then later adjust the font size to something much larger (like 36 pixels), because the line height remains at 10 pixels, your lines then overlap. However, using a percentage (150% percent, say) means the `line-height` spacing adjusts proportionally whenever you change the `font-size` value.

The normal `line-height` setting for a browser is 120%. So, when you want to tighten up the line spacing, use a value less than 120%; and to spread lines apart, use a value greater than that.

NOTE

To determine the amount of space that appears between lines of text, a web browser subtracts the font size from the line height. The result—called *leading*—is the amount of space between lines in a paragraph. Say the font size is 12 pixels, and the line height (set to 150%) works out to 18 pixels. $18 - 12 = 6$ pixels, so the browser adds 6 pixels of space between each line.

■ LINE SPACING BY NUMBER

CSS offers one other measurement method specific to line height, which is simply a number. You write it like this:

```
line-height: 1.5;
```

There's no unit (like `em` or `px`) after this value. The browser multiplies this number by the font size to determine the line height. So if the text is `1em` and the `line-height` value is 1.5, then the calculated line height is `1.5em`. In most cases, the effect is no different from specifying a value of `1.5em` or `150%`. But sometimes this multiplication factor comes in handy, especially since nested tags inherit the `line-height` value of their parents.

For example, say you set the `line-height` property of the `<body>` tag to `150%`. All tags inside the page would inherit that value. However, it's not the percentage that's inherited; it's the *calculated* line height. So, say the font size for the page is set to 10 pixels; 150 percent of 10 is 15 pixels. Every tag would inherit a line height of 15 pixels, not 150 percent. So if you happened to have a paragraph with large, 36 pixel text, then its line height—15 pixels—would be much smaller than the text, making the lines squish together in a hard-to-read mess.

In this example, instead of using a `line-height` of `150%` applied to the `<body>` tag, you could have all tags share the same basic proportional line height by setting the `line-height` to `1.5`. Every tag, instead of inheriting a precise pixel value for line height from the `body` style, simply multiplies its font size by 1.5. So in the above example of a paragraph with 36-pixel text, the line height would be 1.5×36 or 54 pixels.

Aligning Text

One of the quickest ways to change the look of a web page is with paragraph alignment. Using the `text-align` property, you can center a paragraph on a page, align the text along its left or right edge, or justify both left and right edges (like the paragraphs in this book). Normally, text on a page is left aligned, but you may want to center headlines to give them a formal look. Languages that read from right to left, like Hebrew and Arabic, require right-alignment. To change the alignment of text, use any of the following keywords—`left`, `right`, `justify`, `center`:

```
text-align: center;
```

Justified text looks great on a printed page—mainly because the fine resolution possible with printing allows for small adjustments in spacing, and because most programs used to lay out printed material can hyphenate long words (thus attempting to equally distribute the number of characters per line). This prevents large, unsightly gaps or rivers of white space flowing through the paragraphs. Web pages are limited to much coarser spacing because of the generally low resolution of monitors, and because web browsers don't know how to hyphenate long words. So when you use the `justify` option, the space between words can vary significantly from line to line, making the text harder to read. When you want to use the `justify` option on your web pages, test it thoroughly to make sure the text is attractive and readable.

Indenting the First Line and Removing Margins

In many books, the first line of each paragraph is indented. This first-line indent marks the beginning of a paragraph when there are no spaces separating paragraphs. On the Web, however, paragraphs don't have indents but are instead separated by a bit of space—like the paragraphs in this book.

If you have a hankering to make your web pages look less like other web pages and more like a handsomely printed book, take advantage of the CSS `text-indent` and `margin` properties. With them, you can add a first-line indent and remove (or increase) the margins that appear at the beginnings and ends of paragraphs.

■ FIRST-LINE INDENTS

You can use pixel and em values to set the first-line indent like this:

```
text-indent: 25px;
```

or

```
text-indent: 5em;
```

A pixel value is an absolute measurement—a precise number of pixels—while an em value specifies the number of letters (based on the current font size) you want to indent.

TIP You can use negative text-indent values to create what’s called a *hanging indent*, where the first line starts further to the left than the other lines in the paragraph. (Think of it as “hanging” off the left edge.) You’ll usually use a negative text indent along with a position margin value, so that the negative text indent doesn’t stick outside the left side of a page, column, or layout box.

You can also use a percentage value, but with the text-indent property, percentages take on a different meaning than you’ve seen before. In this case, percentages aren’t related to the font size; they’re related to the width of the element containing the paragraph. For example, if the text-indent is set to 50%, and a paragraph spans the entire width of the web browser window, then the first line of the paragraph starts half the way across the screen. If you resize the window, both the width of the paragraph and its indent change. (You’ll learn more about percentages and how they work with the width of elements in the next section.)

POWER USERS’ CLINIC

A Shorthand Method for Text Formatting

Writing one text property after another gets tiring, especially when you want to use several different text properties at once. Fortunately, CSS offers a shorthand property called `font`, which lets you combine the following properties into a single line: `font-style` (page 162), `font-variant` (page 163), `font-weight` (page 162), `font-size` (page 37), `line-height` (page 167), and `font-family` (page 127). For example, consider the following declaration:

```
font: italic bold small-caps 18px/150%
    Arial, Helvetica, sans-serif;
```

It creates bold, italicized type in small caps, using 18px Arial (or Helvetica or sans-serif) with a line height of 150 percent. Keep these rules in mind:

- You don’t have to include every one of these properties, but you *must* include the font size and font family:
`font: 1.5em Georgia, Times, serif;`
- Use a single space between each property value. You use a comma only to separate fonts in a list like this: `Arial, Helvetica, sans-serif`.
- When specifying the line height, add a slash after the font size followed by the line-height value, like this:

`1.5em/150%` or `24px/37px`.

The last two properties must be `font-size` (or `font-size/line-height`) followed by `font-family`, in that order. All the other properties may be written in any order. For example, these two declarations are the same:

```
font: italic bold small-caps 1.5em Arial;
font: bold small-caps italic 1.5em Arial;
```

Finally, omitting a value from the list is the same as setting that value to normal. Say you create a `<p>` tag style that formats all paragraphs in bold, italics, and small caps with a line height of 2000 percent (not that you’d actually *do* that). You can then create a class style named, say, `.special-Paragraph` with the following font declaration:

```
font: 1.5em Arial;
```

When you apply this style to one paragraph on the page, then that paragraph would *not* inherit the italic, bold, small caps, or line height. Omitting those four values in the `.special-Paragraph` style is the same as writing this:

```
font: normal normal normal 1.5em/normal
    Arial;
```

■ CONTROLLING MARGINS BETWEEN PARAGRAPHS

Many designers hate the space that every browser throws in between paragraphs. Before CSS, there was nothing you could do about it. Fortunately, you can now tap into the `margin-top` and `margin-bottom` properties to remove (or, if you wish, expand) that gap. To totally eliminate a top and bottom margin, write this:

```
margin-top: 0;
margin-bottom: 0;
```

To eliminate the gaps between *all* paragraphs on a page, create a style like this:

```
p {
  margin-top: 0;
  margin-bottom: 0;
}
```

As with `text-indent`, you can use pixel or em values to set the value of the margins. You can also use percentages, but as with `text-indent`, the percentage is related to the *width* of the paragraph's containing element. Because it's confusing to calculate the space above and below a paragraph based on its width, it's easier to stick with either em or pixel values.

NOTE

Because not all browsers treat the top and bottom margin of headlines and paragraphs consistently, it's often a good idea to simply *zero out* (that is, eliminate) all margins at the beginning of a style sheet. To see how this works, turn to page 548.

For a special effect, you can assign a *negative* value to a top or bottom margin. For example a `-10px` top margin moves the paragraph up 10 pixels, perhaps even visually overlapping the page element above it. (See step 4 on page 190 for an example.)

Formatting the First Letter or First Line of a Paragraph

CSS also provides a way of formatting just a part of a paragraph by using the `:first-letter` and `:first-line` pseudo-elements (see Figure 6-16). Technically, these aren't CSS properties, but types of selectors that determine what part of a paragraph CSS properties should apply to. With the `:first-letter` pseudo-element, you can create an initial capital letter to simulate the look of a hand-lettered manuscript. To make the first letter of each paragraph bold and red you could write this style:

```
p:first-letter {
  font-weight: bold;
  color: red;
}
```

To be more selective and format just the first letter of a particular paragraph, you can apply a class style to the paragraph—.intro, for example:

```
<p class="intro">Text for the introductory paragraph goes here...</p>
```

Then you could create a style with a name like this: `.intro:first-letter`.

The `:first-line` pseudo-element formats the initial line of a paragraph. You can apply this to any block of text like a heading (`h2:first-line`) or paragraph (`p:first-line`). As with `:first-letter`, you can apply a class to just one paragraph and format only the first line of that paragraph. Say you want to capitalize every letter in the first line of the first paragraph of a page. Apply a class to the HTML of the first paragraph—`<p class="intro">`—and then create a style like this:

```
.intro:first-line { text-transform: uppercase; }
```




FIGURE 6-16

The `:first-letter` pseudo-element formats the first letter of the styled element, like the initial caps to the left. The `:first-line` selector, on the other hand, styles the first line of a paragraph. Even if your guest resizes the window (bottom), the browser still styles every word that appears on a paragraph's first line.

NOTE For some strange reason, neither Chrome nor the Safari web browser understands the `text-transform` property (page 163) when it's used with the `:first-line` pseudo-element. In other words, you can't use CSS to capitalize the letters of a paragraph's first line in Chrome or Safari.

Styling Lists

The `` and `` tags create bulleted and numbered lists, like lists of related items or numbered steps. But you don't always want to settle for the way web browsers automatically format those lists. You may want to swap in a more attractive bullet, use letters instead of numbers, or even completely eliminate the bullets or numbers.

Types of Lists

Most web browsers display unordered lists (`` tags) using round bullets, and numbered lists (`` tags) using...well...numbers. With CSS, you can choose from among three types of bullets—`disc` (a solid round bullet), `circle` (a hollow round bullet), or `square` (a solid square). There are also six different numbering schemes—`decimal`, `decimal-leading-zero`, `upper-alpha`, `lower-alpha`, `upper-roman`, or `lower-roman` (see Figure 6-17). You select all these options using the `list-style-type` property, like so:

```
list-style-type: square;
```

or

```
list-style-type: upper-alpha;
```




FIGURE 6-17

CSS provides many different ways to mark bulleted and numbered lists, from a handful of geometric shapes to many different numbering systems. If you feel like rushing a fraternity or sorority, you can also replace numbers with Greek letters— α , β , γ —using the `lower-greek` option. In fact, there are a number of other numbering schemes including Armenian, Georgian, Katakana, and other regional variations. You can find out about them at <https://developer.mozilla.org/en-US/docs/CSS/list-style-type>.

Most of the time, you use this property on a style that's formatting an `` or `` tag. Typical examples include an `ol` or `ul` tag style—`ul { list-style-type: square; }`—or a class you're applying to one of those tags. However, you can also apply the property to an individual list item (`` tag) as well. You can even apply different types of bullet styles to items within the same list. For example, you can create a style for a `` tag that sets the bullets to square, but then create a class named `.circle` that changes the bullet type to circle, like this:

```
li {list-style-type: square; }
.circle { list-style-type: circle; }
```

You can then apply the class to every other item in the list to create an alternating pattern of square and circular bullets:

```
<ul>
<li>Item 1</li>
<li class="circle">Item 2</li>
<li>Item 3</li>
<li class="circle">Item 4</li>
</ul>
```

Or, using the `nth-of-type` selector (page 78) you could skip the class name entirely:

```
li {list-style-type: square; }
li:nth-of-type(odd) { list-style-type: circle; }
```

At times you'll want to completely hide bullets, like when you'd rather use your own graphic bullets (see page 176). Also, when a site's navigation bar is a list of links, you can use an `` list, but hide its bullets (see the example on page 286). To turn off the bullets, use the keyword `none`:

```
list-style-type: none;
```

Positioning Bullets and Numbers

Web browsers usually display bullets or numbers hanging to the left of the list item's text (Figure 6-18, left). With CSS, you can control the position of the bullet (somewhat) using the `list-style-position` property. You can either have the bullet appear outside of the text (the way browsers normally display bullets) or inside the text block itself (Figure 6-18, right):

```
list-style-position: outside;
```

or

```
list-style-position: inside;
```

TIP You can adjust the space between the bullet and its text—increase or decrease that gap—by using the `padding-left` property. To use it, you create a style that applies to the `` tags. This technique works only if you set the `list-style-position` property to the `outside` option (or don't use `list-style-position` at all).




FIGURE 6-18

Using the `list-style-position` property, you can control the position of bullets and numbers in a list. The `outside` option (left) emphasizes the “listness” of your list. Use the `inside` option (right) if you need to maximize the width of your list.

In addition, if you don't like how web browsers indent a list from the left edge, then you can remove that space by setting both the `margin-left` and `padding-left` properties to 0 for the list. To remove the indent from all lists, you can create this group selector:

```
ul, ol {
  padding-left: 0;
  margin-left: 0;
}
```

Or, you can create a class style with those properties and apply it to a particular `` or `` tag. The reason you need to set both the padding and margin properties is that some browsers use padding (Firefox, Mozilla, Safari) and some use margin (Internet Explorer) to control the indent. (You'll learn more about the margin and padding properties in the next chapter.)

Browsers normally display one bulleted item directly above another, but you can add space between list items using the `margin-top` or `margin-bottom` properties on the particular list items. These properties work for spacing list items exactly the same way they work for spacing paragraphs, as explained on page 171. You just need to make sure that the style applies to the `` tags by creating a class style and applying it individually to each `` tag. Or, better yet, create an `` tag style or descendent selector. The style should *not* apply to the `` or `` tag. Adding margins to the top or bottom of those tags simply increases the space between the entire list and the paragraphs above or below it—not the space between each item in the list.

Graphic Bullets

If you're not happy with squares and circles for your bullets, create your own. Using an image-editing program like Photoshop or Fireworks, you can quickly create colorful and interesting bullets. Clip art collections and most symbol fonts (like Webdings) provide great inspiration.

TIP

For a listing of loads of sites with free icons and bullets, check out this page: www.cssjuice.com/38-free-icon-checkpoints/.

The CSS `list-style-image` property lets you specify a path to a graphic on your site, much as you specify a file when adding an image to a page by using the `src` attribute of the HTML `` tag. You use the property like this:

```
list-style-image: url(images/bullet.gif);
```

The term `url` and the parentheses are required. The part inside the parentheses—`images/bullet.gif` in this example—is the path to the graphic. Notice that, unlike HTML, you don't have to use quotation marks around the path (though you can, if you like).

FREQUENTLY ASKED QUESTION

Customizing List Bullets and Numbers

I'd like the numbers in my numbered lists to be bold and red instead of boring old black. How do I customize bullets and numbers?

CSS gives you a few ways to customize the markers that appear before list items. For bullets, you can use your own graphics, as described previously. You have two other techniques available: one that's labor intensive, but works on most browsers, and one that's super geeky, cutting edge, and doesn't work in Internet Explorer 7 or earlier.

First, the labor-intensive way. Say you want the numbers in an ordered list to be red and bold, but the text to be plain, unbolded black. Create a style that applies to the list—like a class style you apply to the `` or `` tags—with a text color of red and the font weight set to bold. At this point, everything in the list—text included—is red and bold.

Next, create a class style—.regularList, for example—that sets the font color to black and font weight to normal (that is, not bold). Then (and this is the tedious part), wrap a `` tag around the text in each list item and apply the class style to it. For example:

```
<li><span class="regularList">Item 1</span></li>
```

Now the bullets are bold and red and the text is black and normal. Unfortunately, you have to add that `` to every list item!

The cool, “I’m so CSS-savvy” way is to use what’s called *generated content*. Basically, generated content is just stuff that isn’t actually typed on the page but is added by the web browser when it displays the page. A good example is bullets

themselves. You don’t type bullet characters when you create a list; the browser adds them for you. With CSS, you can have a browser add content, and even style that content, before each `` tag. You read about generated content on pages 70-71, but just so you have the code at hand if you want to make regular bullets next to the list items red, add this CSS to your style sheet:

```
ul li {
    list-style-type: none;
}
ul li:before {
    content: counter(item, disc) " ";
    color: red;
}
```

And, if you wanted to make the items in a numbered list red, you can add this CSS:

```
ol li {
    list-style-type: none;
    counter-increment: item;
}
ol li:before {
    content: counter(item) ". ";
    color: red;
}
```

For a more in-depth explanation of styling numbered lists visit www.456bereastreet.com/archive/201105/styling_ordered_list_numbers/.

NOTE

When specifying a graphic in an *external* style sheet, the path to the image is relative to the style sheet file, not the web page. You’ll learn more about how this works in the box on page 244, as you start to use images with CSS.

While the `list-style-image` property lets you use a graphic for a bullet, it doesn't provide any control over its placement. The bullet may appear too far above or below the line, requiring you to tweak the bullet graphic until you get it just right. A better approach—one you'll learn in Chapter 8—is to use the `background-image` property. That property lets you very accurately place a graphic for your bulleted lists.

NOTE

As with the `font` property (see the box on page 170), there's a shorthand method of specifying list properties. The `list-style` property can include a value for each of the other list properties—`list-style-image`, `list-style-position`, and `list-style-type`. For example, `ul { list-style: circle inside; }` formats unordered lists with the hollow circle bullet on the inside position. When you include both a style type and style image—`list-style: circle url(images/bullet.gif) inside;`—web browsers use the style type `circle` in this example—if the graphic can't be found.

■ Tutorial: Text Formatting in Action

In this tutorial, you'll gussy up headlines, lists, and paragraphs of text, using CSS's powerful formatting options.

To get started, you need to locate the tutorial files on this book's companion website at www.sawmac.com/css3/. Click the tutorial link and download the files. All of the files are enclosed in a zip archive, so you'll need to unzip them first. (Go to the website for detailed instructions on unzipping the files.) The files for this tutorial are contained inside the folder named *06*.

Setting Up the Page


First, you'll get your style sheet started, add the `@font-face` directive to load some web fonts, and add styles to format the body text.

1. Launch your web browser and open the file *06→text.html* (see Figure 6-19).

It's not much to look at—just a collection of headlines, paragraphs and a lone bulleted list—but you'll turn it into something far better looking.

2. Open the file *text.html* in your favorite text editor.

Start by adding an internal style sheet to this file. (Yes, external style sheets are better, but it's perfectly OK to start your design with an internal sheet. See page 39.)

**FIGURE 6-19**

The page begins with nothing but basic, drab, HTML.

3. In the `<head>` of the web page, click directly after the closing `</title>` tag.

Hit Enter (Return), and then type:

```
<style>
```

```
</style>
```

Now that the basic style tags are in place, you'll add the CSS reset discussed on page 115. Instead of typing it all out, you'll just copy and paste the CSS from an external style sheet.

4. **Open the file *reset.css*.** Copy all the code from that file and paste it between the opening and closing `<style>` tags you added in Step 3.

If you preview the *text.html* file in a web browser now, you'll see that all of the text on the page (headlines, paragraphs, and so on) looks nearly the same—in other words, all the basic HTML formatting the browser applied has been removed, so you can start with a clean slate.

Next, you'll add the necessary `@font-face` directives to load four web fonts. Actually, they are all the same font—PTSans—but include the bold, italic, and bold-italic variants.

5. **Add the following code to the page:**

```
@font-face {
  font-family: 'PTSans';

  src: url('fonts/PTSansRegular.eot');
  src: url('fonts/PTSansRegular.eot?#iefix') format('embedded-opentype'),
        url('fonts/PTSansRegular.woff') format('woff'),
        url('fonts/PTSansRegular.ttf') format('truetype'),
        url('fonts/PTSansRegular.svg') format('svg');
  font-weight: normal;
  font-style: normal;
}

@font-face {
  font-family: 'PTSans';
  src: url('fonts/PTSansItalic.eot');
  src: url('fonts/PTSansItalic.eot?#iefix') format('embedded-opentype'),
        url('fonts/PTSansItalic.woff') format('woff'),
        url('fonts/PTSansItalic.ttf') format('truetype'),
        url('fonts/PTSansItalic.svg') format('svg');
  font-weight: normal;
  font-style: italic;
}

@font-face {
  font-family: 'PTSans';
  src: url('fonts/PTSansBold.eot');
  src: url('fonts/PTSansBold.eot?#iefix') format('embedded-opentype'),
        url('fonts/PTSansBold.woff') format('woff'),
        url('fonts/PTSansBold.ttf') format('truetype'),
        url('fonts/PTSansBold.svg') format('svg');
  font-weight: bold;
  font-style: normal;
}

@font-face {
  font-family: 'PTSans';
```



```
src: url('fonts/PTSansBoldItalic.eot');  
src: url('fonts/PTSansBoldItalic.eot?#iefix') format('embedded-opentype'),  
    url('fonts/PTSansBoldItalic.woff') format('woff'),  
    url('fonts/PTSansBoldItalic.ttf') format('truetype'),  
    url('fonts/PTSansBoldItalic.svg') format('svg');  
font-weight: bold;  
font-style: italic;  
}
```

NOTE

Yes, that's a lot of code. If you'd rather not type all of that, this chapter's examples include a file named *at-font-face.css*. You can open it, copy the code from there, and paste it into your style sheet. Go to www.sawmac.com/css3.

In a nutshell, you've created a new font family named PTSans. You'll be able to use it in any new styles you create. You're using the method described on page 141 to add the bold-italic variants of the font. This method means that whenever you apply a normal bolded tag to text (like a headline, or the `` tag), the browser will automatically swap in the bold version of the font. (This method doesn't work in IE 8, which artificially bolds and italicizes the text instead of swapping in the bold or italic versions of the font.)

Next, you'll create a style that defines some general properties for all text on the page.

6. After the four @font-face directives, press Enter, and type `html {`.

This is a basic tag selector that applies to the `<html>` tag. As discussed in Chapter 4, other tags inherit the properties of this tag. You can set up some basic text characteristics like font, color, and font size for later tags to use as their starting point.

7. Press Enter again, and then add the following two properties:

```
font-family: PTSans, Arial, sans-serif;  
font-size: 62.5%;
```

These two instructions set the font to PTSans (or Arial if the browser can't download PTSans), and the font size to 62.5 percent.

NOTE

Why set the page's base font to 62.5 percent? It just so happens that 62.5 percent times 16 pixels (the normal size of text in most web browsers) equals 10 pixels. With 10 pixels as a starting point, it's easy to compute what other text sizes will look like on the screen. For example, 1.5em would be 1.5 x 10 or 15 pixels. 2em is 20 pixels, and so on—easy multiples of ten. For more on this interesting discovery and more font-sizing strategies, visit <http://clagnut.com/blog/348/>.

8. Complete this style by pressing Enter and typing a closing bracket to mark the end of the style.

At this point, your completed style should look like this:

```
html {  
  font-family: PTSans, Arial, sans-serif;  
  font-size: 62.5%;  
}
```

Your style sheet is complete.

9. Save the page, and open it in a web browser to preview your work.

The text on the page changes font...it also gets really small. Don't worry, that's the 62.5 percent font size you set in Step 7. That's just the starting point for all text, and you'll easily increase the size of text by defining em sizes for the other tags.

Formatting the Headings and Paragraphs

Now that the basic text formatting is done, it's time to refine the presentation of the headlines and paragraphs.

1. **Return to your text editor and the `text.html` file.** Click at the end of the closing brace of the HTML tag selector in the internal style sheet, press Enter (Return) to create a new line, and then type `.main h1 {`.

This is a *descendent selector* (page 88). It provides more specific direction than a basic HTML tag selector. In this case, the selector tells the web browser “apply the following formatting to any `<h1>` tag inside another tag with the class name `main`.” If you look at the page's HTML, you'll see that there's a `<div>` tag with a class of `main` (`<div class="main">`). As you'll learn later, it's very common in CSS-based designs to group HTML tags inside of `<div>` tags. You can then position individual `<div>` tags to create columns and other complex page layouts. It's also common to use descendent selectors like this one to pinpoint your formatting choices by affecting just the tags in certain areas of the page.

2. **Hit Enter, and then type these three CSS properties:**

```
color: rgb(252,102,0);  
font-family: "Arial Black", Arial, Helvetica, sans-serif;  
font-size: 4em;
```

You've just changed the color of the `<h1>` tag as well as the font. This time, instead of using a web font, you're specifying a font that the visitor must have installed on their computer. Many computers have Arial Black, but if the one visiting this page doesn't, it will fall back to Arial or Helvetica or just a generic sans serif. You've also set the font size to `4em`, which for most browsers (unless the visitor has tweaked his browser's font settings) comes out to 40 pixels tall. That's all thanks to the `62.5%` size you set for the body back at Step 7. That smooth move made the base font size 10 pixels tall, so `4 x 10` comes out to 40 pixels. Next you'll add a text shadow to the headline.

3. Complete this style by hitting Enter, adding the code in bold below (don't forget the closing brace):

```
.main h1 {  
  color: rgb(252,102,0);  
  font-family: "Arial Black", Arial, Helvetica, sans-serif;  
  font-size: 4em;  
  text-shadow: 4px 3px 6px rgba(0,0,0,.5);  
}
```

Here, you've added a text shadow (page 166), which is offset 4 pixels to the right, 3 pixels below, and is feathered out 6 pixels. In addition, you're using the RGBA color (page 155) to set the shadow to black with 50 percent transparency.

4. Save the file and preview it in a web browser.

Next, spruce up the appearance of the other headings and paragraphs.

5. Return to your text editor and the *text.html* file.

Click after the closing brace of the `.main h1` tag, hit Enter, and add the following style:

```
.main h2 {  
  font: bold 3.5em "Hoefler Text", Garamond, Times, serif;  
  color: rgb(37,76,143);  
  border-bottom: 1px solid rgb(200,200,200);  
  margin-top: 25px;  
}
```

Here you have another descendent selector that only applies to `<h2>` tags inside another tag with the class `main` (you're probably getting the hang of these now). The `font` property used here is shorthand that combines the more long-winded `font-weight`, `font-size`, and `font-family` (see the box on page 170). In other words, this one line makes the headline bold, 3.5ems tall, and specifies a font.

In addition, this style adds a decorative border below the headline and a bit of space between the headline and the tag above it (in other words, it adds some space between the "CSS The Missing Manual" and the "Exploring Typographic Possibilities" headlines). You'll read more about borders and margins in the next chapter.

Time to tackle more headlines.

6. Add another style below the one you added in the last step:

```
.main h3 {  
  color: rgb(255,102,0);  
  font-size: 1.9em;  
  font-weight: bold;  
  text-transform: uppercase;  
  margin-top: 25px;  
  margin-bottom: 10px;  
}
```

This style dishes out some of the usual formatting—color, size, boldness—and also uses the `text-transform` property (page 163) to make all of the text in the `<h3>` headlines uppercase. Finally, it adds a bit of space above and below the headlines by using the `margin` properties.

Next, you'll improve the look of the paragraphs.

7. Add one more style to the page:

```
.main p {  
  font-size: 1.5em;  
  line-height: 150%;  
  margin-left: 150px;  
  margin-right: 50px;  
  margin-bottom: 10px;  
}
```

This style introduces the `line-height` property, which sets the spacing between lines. A percentage of 150 adds a little more space between lines in a paragraph than you'd normally see in a web browser. This extra breathing room gives the text a lighter, airier quality and makes the sentences a little easier to read (but only if you speak Latin).

The style also increases the font size to 1.5em (15 pixels for most browsers) and indents the paragraph from the left and right edges of the page. You'll notice that there's a lot of typing going on for the margin properties—fortunately, as you'll read on page 196 in the next chapter, there's a margin shortcut property that requires much less typing to control the four margins of an element.

Time to try out a more advanced selector type.


8. Add the following style to your style sheet:

```
.main p:first-line {  
  font-weight: bold;  
  color: rgb(153,153,153);  
}
```

The `:first-line` pseudo-element (page 172) affects just the first line of a paragraph. In this case, just the first line of text for each of the paragraphs inside the main div will be bold and gray.

9. Save the page and open it in a web browser to preview your work.

At this point, the page should look like Figure 6-20.



Formatting Lists

This page has a single bulleted list. The plan is to move the list over to the right edge of the page and have the text following it wrap around it. CSS makes this little trick easy.

1. **Return to your text editor and the `text.html` file.** Add the following style at the end of the page's internal style sheet:

```
.main ul {
  margin: 50px 0 25px 50px;
  width: 170px;
  float: right;
}
```

When formatting lists, you'll usually create styles for two different elements: the list itself (either the `` tag for bulleted lists or the `` tag for numbered lists) and the individual list items (the `` tag). This style controls the entire list.

There are a few things happening in this style. First, the *margin* property uses the shorthand method. This one line sets all four margins around the list, replacing the four individual margin properties (*margin-top*, *margin-right*, and so on). The four values are ordered like this: top, right, bottom, left. So for this style, 50 pixels of space get added above the list, 0 space on the right, 25 pixels on the bottom, and 50 pixels on the left.

The *width* property (discussed in detail on page 212) makes the entire list 170 pixels wide. If any particular list item has more text than will fit within that space, it wraps to another line. The *float* property is the real magic—in this case, *float: right* means move the list over to the right edge of the page. This property also causes the text following the list to wrap around the left side of the list. It's a cool trick, and you'll learn a lot more about floats on page 220.

You'll control the look of the individual list items next.

2. Add one more style to the internal style sheet in the *text.html* file:

```
.main li {  
  color: rgb(32,126,191);  
  font-size: 1.5em;  
  margin-bottom: 7px;  
}
```


Nothing new here: just changing the color and size and adding space below each list item. Time to check out your progress.

NOTE

If you want to add space between list items, you need to add top or bottom margins to the `` tag. Adding margins to the `` or `` tags simply adds space around the entire list.

3. Save the page and preview it in a web browser.

The page should now look like Figure 6-21.



Fine-Tuning with Classes

Sometimes you want even more control over how a style is applied. For example, while you might want most paragraphs in one section of the page to look the same, you might also want one or two paragraphs to have their own unique look. In this tutorial, the paragraph of text near the top of the page—“November 30 Rod Dibble”—contains some unique information—a publication date and author. You want it to stand out from the other paragraphs, so you'll add a class to the HTML and create a class style.

1. **Locate the HTML for that paragraph—`<p>november 30 Rod Dibble</p>`—and add `class="byline"` to the opening `<p>` tag.** The HTML should look like this:

```
<p class="byline">november 30 <strong>Rod Dibble</strong></p>
```

Now it's a simple matter of creating a class style that overrides the generic formatting of the other paragraphs on the page.

2. **In the internal style sheet near the top of the page, add a style for that paragraph:**

```
.main .byline {  
  font-size: 1.6em;  
  margin: 5px 0 25px 50px;  
}
```

This style tweaks the size and placement of just that one paragraph. Note that if you'd just named that style `.byline`—a basic class selector—it wouldn't work. Thanks to the rules of the cascade described in the last chapter, `.byline` is less specific (less powerful) than the `.main p` style you created in Step 7 on page 184, so it wouldn't be able to override the size and margins specified by `.main p`. However, `.main .byline` is more specific.

That paragraph still needs some work. It would be great if the name stood out more. The HTML in this case provides just the hook you need.

3. **Add another style to the style sheet:**

```
.main .byline strong {  
  color: rgb(32,126,191);  
  text-transform: uppercase;  
  margin-left: 11px;  
}
```

If you look at the HTML in Step 1 above, you'll see that the name—Rod Dibble—is inside a `` tag. The `` tag is used to emphasize text and mark it as important. But that doesn't mean you have to let it be bold, the way web browsers normally display that tag. Instead, this descendent selector targets the `` tag but only when it appears inside another tag with the class `.byline`, and only if all of that is inside yet another tag with the class `main`—whew, that's pretty specific.

This style turns the text blue, makes it uppercase, and adds a bit of space on the left side (nudging the name over just a bit from the “November 30” text).

Adding the Finishing Touches

For the last bit of design, you'll incorporate a few design touches that format the page and that main div so they both look better. Then you'll finish up with a cool bit of text formatting.

1. Return to your text editor and the *text.html* file.

First, you'll add a background color and image to the page.

2. Locate the `html` style near the top of the internal style sheet and add one new property so that it looks like this (changes are in bold):

```
html {  
  font-size: 62.5%;  
  font-family: Arial, Helvetica, sans-serif;  
  background: rgb(225,238,253) url(images/bg_body.png) repeat-x;  
}
```

The background property is a powerful tool for any web designer. You've already used it a couple of times in earlier tutorials; it lets you add color and insert and control the placement of an image to the background of any tag. You'll learn the ins and outs of this property on page 255, but for now this line changes the background color of the page to light blue and adds a dark blue stripe to the top of the page.

Next you'll spruce up the main div.

3. Add another style in between the `html` style and the `.main h1` style:

```
.main {  
  width: 740px;  
  margin: 0 auto;  
  padding: 0 10px;  
  border: 4px solid white;  
  background: transparent url(images/bg_banner.jpg) no-repeat;  
}
```

In other words, click after the closing `}` for the `html` style, hit Enter, and type the code above. You don't necessarily have to put the style in that spot for it to work, but for organizational purposes, putting the style that controls the div before the other styles that format tags inside that div makes sense.

The width property sets an overall width for this div (and the content inside it), essentially turning this page into a 740-pixel-wide document. The margin property values—`0 auto`—put 0 pixels of space above and below the div and set the left and right margins to auto, which centers the div in the middle of the browser window. The padding property adds space inside the box, pushing content inside the div away from the border line. Finally, you've placed an image into the background of the div.

Those last two styles didn't have anything to do with text formatting, but if you preview the page, you'll see that they make it look a lot better...except for those two top headlines. The first headline isn't bold enough, and the second should fall below the newly added graphic.

4. Add one last style right after the `.main h1` style:

```
.main h1 strong {  
  font-size: 150px;  
  color: white;  
  line-height: 1em;  
  margin-right: -1.25em;  
}
```

The HTML for the headline looks like this:

```
<h1><strong>CSS</strong> The Missing Manual</h1>
```

The “CSS” is enclosed inside `` tags, so this descendent selector formats only that text (in that sense, it’s like the style you added in Step 3 on page 188 that took advantage of a `` tag embedded within a paragraph). The text size is pumped way up, its color changed, and line height is adjusted so that it fits inside the top of the page. You’ll notice that the line height is set to 1em (as you read on page 160, an em is based on the current font size of the element), so in this case, the line height will translate to 150 pixels—that’s the font size of this style.

The one cool trick is the `margin-right` property, which is set to a negative value: `-1.25em`. Since a positive margin pushes elements away, a negative margin actually pulls elements on top of each other. In this case, the rest of the text in the headline—“The Missing Manual”—is scooted over 1.25 em, which is 1.25 times the font size (150 pixels), on top of the “CSS” text.

NOTE

Negative margins are perfectly legal (although tricky) CSS. They’re even used for some pretty advanced CSS layout, as described on page 199.

5. Save the file and preview it in a web browser.

It should look like Figure 6-22. You can compare your work to the finished *text.html* page located in the *06_finished* folder.

Congratulations! You’ve explored many of the text formatting properties offered by CSS and turned ho-hum HTML into an attractive, attention-getting design. In the next chapter, you’ll explore graphics, borders, margins, and other powerful CSS design options offered by CSS.




FIGURE 6-22

With a little CSS, you can turn plain text into a powerful design statement that helps guide readers through the information on your site.

Margins, Padding, and Borders

Every HTML tag is surrounded by a world of properties that affect how the tag appears in a web browser. Some properties—like borders and background colors—are immediately obvious to the naked eye. Others, though, are invisible—like padding and margin. They provide a bit of empty space on one or more sides of a tag. By understanding how these properties work, you can create attractive columns and decorative sidebars and control the space around them (what designers call *white space*) so your pages look less cluttered, lighter, and more professional.

Taken together, the CSS properties discussed in this chapter make up one of the most important concepts in CSS—the *box model*.

■ Understanding the Box Model

You probably think of letters, words, and sentences when you think of a paragraph or headline. You also probably think of a photo, logo, or other picture when you think of the `` tag. But a web browser treats these (and all other) tags as little *boxes*. To a browser, any tag is a box with something inside it—text, an image, or even other tags containing other things, as illustrated in Figure 7-1.

Surrounding the content are different properties that make up the box:

- **padding** is the space between the content and the content's border. Padding is what separates a photo from the border that frames the photo.
- **border** is the line that's drawn around each edge of the box. You can have a border around all four sides, on just a single side, or any combination of sides.

- **background-color** fills the space inside the border, including the padding area.
- **margin** is what separates one tag from another. The space that commonly appears between the tops and bottoms of paragraphs of text on a web page, for example, is the margin.

For a given tag, you can use any or all of these properties in combination. You can set just a margin for a tag or add a border, margins, *and* padding. Or you can have a border and margin but no padding, and so on. If you don't adjust any of these properties, then you'll end up with the browser's settings, which you may or may not like. For example, although browsers usually don't apply either padding or borders to any tags on a page, some tags like headings and paragraphs have a preset top and bottom margin.





FIGURE 7-1


The CSS box model includes the content inside a tag (for example, several sentences of text) plus padding, borders, and margins. The area within the border, which includes the content and padding, may also have a background color. Actually, the background color is drawn underneath the border, so when you assign a dashed or dotted border, the background color appears in the gaps between the dots or dashes.



NOTE As discussed on page 548, because different browsers apply different amounts of padding and margin to the same tags, it's best to “zero-out” padding and margin values for all tags. In other words, use a set of simple styles—called a CSS reset—to remove padding and margin from HTML tags. Then, when you create additional styles that add margin and padding, you can be assured that you'll have a consistent cross-browser presentation.

Controlling Space with Margins and Padding

Both margins and padding add space around content. You use these properties to separate one element from another—for example, to add space between a left-hand navigation menu and the main page content on the right—or to inject some white space between content and a border. You may want to move the border away from the edge of a photo (see Figure 7-2).



Padding and margin function similarly, and unless you apply a border or background color, you can't really tell whether the space between two tags is caused by padding or by a margin. But if you have a border around an element or a background behind it, then the visual difference between the two properties is significant. Padding adds space between the content and the border, and keeps the content from appearing cramped inside the box; it also includes the background area, so the space taken up by padding might be empty of content (like text or a photo), but it will still be filled with a background color or image. Margins, on the other hand, add white space (often called a *gutter*) between elements, giving the overall look of the page a lighter appearance.

You can control each side of the margin or padding for an element independently. Four properties control margin edges: `margin-top`, `margin-right`, `margin-bottom`, and `margin-left`. Similarly, four properties control padding: `padding-top`, `padding-right`, `padding-bottom`, and `padding-left`. You can use any valid CSS measurement to define the size of a margin or padding, like so:

```
margin-right: 20px;
padding-top: 3em;
margin-left: 10%;
```

Pixels and ems are commonly used and act just as they do with text (see page 160). A 20-pixel margin adds 20 pixels of space, and 3 ems of padding adds space equal to 3 times the font size of the styled element. You can also use percentage values, but they're tricky. (See the box below for the details.)

NOTE To remove all the space for a margin or padding, use 0 (`margin-top: 0` or `padding-bottom: 0`, for example). To remove space around all four edges of the browser window—to let a banner or logo or other page element butt right up to the edge without a gap—give the body tag a margin of 0 and a padding of 0: `margin: 0; padding: 0;`

POWER USERS' CLINIC

Margins, Padding, and Percentages

When you use percentages, web browsers calculate the amount of space based on the *width of the containing element*. On a simple web page, the containing element is the body of the page, and it fills the browser window. In this case, the percentage value is based on the width of the browser window at any given time. Say the window is 760 pixels wide. In that case, a 10% left margin adds 76 pixels of space to the left edge of the styled element. But if you resize the browser window, then that value changes. Narrowing the browser window to 600 pixels changes the margin to 60 pixels (10 percent of 600).

However, the containing element isn't always the width of the browser window. As you'll see in later chapters, when you create more sophisticated layouts, you can introduce new elements that help organize your page.

You may want to add a `<div>` tag to a page in order to group related content into a sidebar area. (You'll see an example of this in the tutorial on page 225.) That sidebar might have a specified width of 300 pixels. Tags inside the sidebar consider the `<div>` tag their containing element. So a tag in the sidebar with a right margin of 10% will have 30 pixels of empty space to its right.

To make matters more confusing, top and bottom percentage values are calculated based on the width of the containing element, not its height. So a 20% top margin is 20 percent of the width of the styled tag's container.

Margin and Padding Shorthand

You'll frequently want to set all four sides of a style's margin or padding. But typing out all four properties (`margin-right`, `margin-left`, and so on) for each style gets tedious. Fear not: You can use the shortcut properties named `margin` and `padding` to set all four properties quickly:


```
margin: 0 10px 10px 20px;  
padding: 10px 5px 5px 10px;
```

NOTE If the value used in a CSS property is 0, then you don't need to add a unit of measurement. For example, just type `margin: 0;` instead of `margin: 0px;`.

The order in which you specify the four values is important. It must be top, right, bottom, and left. If you get it wrong, you'll be in trouble. In fact, the easiest way to keep the order straight is to remember to stay out of **TRouBLE**—top, right, bottom, and left.

If you want to use the same value for all four sides, it's even easier—just use a single value. If you want to remove margins from all `<h1>` tags, you can write this style:

```
h1 {  
  margin: 0;  
}
```

Similarly, use shorthand to add the same amount of space between some content and its border:

```
padding: 10px;
```

NOTE When you're using the same value for both top and bottom and another value for both left and right, you can use two values. `margin: 0 2em;` sets the top *and* bottom margins to 0 and the left *and* right margins to 2 ems. Likewise, if the top and bottom margins (or padding) differ, but the left and right remain the same, you can use three values. For example, `margin: 0 2em 1em;` sets the top margin to 0, the left and right margins to 2 ems, and the bottom margin to 1 em.

Colliding Margins

When it comes to CSS, two plus two doesn't always equal four. You could run into some bizarre math when the bottom margin of one element touches the top margin of another. Instead of adding the two margins together, a web browser applies the larger of the two margins (Figure 7-3, top). Say the bottom margin of an unordered list is set to 30 pixels, and the top margin of a paragraph following the list is 20 pixels. Instead of adding the two values to create 50 pixels of space between the list and the paragraph, a web browser uses the *largest* margin—in this case 30 pixels. If you don't want this to happen, then use top or bottom padding instead (Figure 7-3, bottom).




FIGURE 7-3
 When two vertical margins meet, the smaller one collapses. Although the top headline has a bottom margin of 20 pixels, and the paragraph has a top margin of 15 pixels, a web browser adds only 20 pixels of space between the two elements. To get the full 35 pixels' worth of space that you want, use padding instead of margins, as shown in the bottom headline. Here, the heading has 20 pixels of bottom padding. Those 20 pixels get added to the 15-pixel top margin of the paragraph to form a 35-pixel gap.

Things get even weirder when one element's *inside* another element. This situation can lead to some head-scratching behavior. For example, say you add a “warning” box to a page (like a `<div>` tag to hold a warning message inside it). You add a 20-pixel top and bottom margin to separate the warning box from the heading above it and the paragraph of text below it. So far so good.

But say you insert a heading inside the warning box, and to put a little room between it and the top and bottom of the div, you set the heading's margin to 10 pixels. You may think you're adding 10 pixels of space between the heading and the top and bottom of the div, but you'd be wrong (Figure 7-4, top). Instead, the margin appears *above* the div. In this case, it doesn't matter how large a margin you apply to the headline—the margin still appears *above* the div.

NOTE In the lingo of CSS, this phenomenon is known as *collapsing margins*, meaning two margins actually become one.

You have two ways around this problem: Either add a small amount of padding around the `<div>` tag or add a border to it. Since border and padding sit *between* the two margins, the margins no longer touch, and the headline has a little breathing room (Figure 7-4, bottom).

NOTE Horizontal (left and right) margins and margins between floating elements don't collapse in this way. Absolutely and relatively positioned elements—which you'll learn about in Chapter 15—don't collapse either.

Removing Space with Negative Margins

Most measurements in CSS have to be a positive value—after all, what would text that’s *negative 20 pixels* tall (or short) look like? Padding also has to be a positive value. But CSS allows for many creative techniques using negative margins.




FIGURE 7-4

Holy shrinking margins, Batman! Top: Whenever vertical margins touch, even when one element is inside another element (like the <h2> tag inside this div), the margins collapse.

Bottom: To solve this dilemma, add a little padding or a border around the containing element (1 pixel of top and bottom padding on the <div>, in this case).

Instead of adding space between a tag and elements around it, a negative margin *removes* space. So you can have a paragraph of text overlap a headline, poke out of its containing element (a sidebar or other layout <div>), or even disappear off an edge of the browser window. And, hey, you can even do something useful with negative margins.

Even when you set the margins between two headlines to 0, there’s still a little space between the text of the headlines (thanks to the text’s line height, as described on page 168). That’s usually a good thing, since it’s hard to read sentences that bunch together and touch. But, used in moderation, tightening the space between two headlines can produce some interesting effects. The second headline of Figure 7-5 (the one that begins “Raise Tuna”) has a top margin of -10px applied to it. This moves the headline up 10 pixels so it slightly overlaps the space occupied by the headline above it. Also, the left and right borders of the “Extra! Extra!” headline actually touch the letters of the larger headline.

You can also use a negative margin to simulate negative padding. In the third headline of Figure 7-5, the one that begins with “The Extraordinary Technique,” a line appears directly under the text. This line is actually the *top* border for the paragraph that follows. (You’ll learn how to add borders on page 202.) But because that paragraph has a negative top margin, the border moves up and under the headline. Notice how

the descending tail for the letter Q in the headline actually hangs *below* the border. Since padding—the space between content (like that letter Q) and a border—can’t be negative, you can’t move a bottom border up over text or any other content. But you get the same effect by applying a border to the following element and using a negative margin to move it up.



FIGURE 7-5
In this example, to make the last paragraph’s top border look like it’s actually the bottom border for the headline above it, add a little padding to the paragraph. Around 5 pixels of top padding moves the paragraph down from the border, while 4ems of left padding indents the top border to extend to the left edge.

TIP You can actually use a negative top margin on the paragraph or a negative bottom margin on the headline. Both have the same effect of moving the paragraph up close to the headline.

Inline, Block, and Other Display Settings

Although web browsers treat every tag as a kind of box, not all boxes are alike. CSS has two different types of boxes—*block boxes* and *inline boxes*—that correspond to the two types of tags—block-level and inline tags.

A *block-level* tag creates a break before and after it. The `<p>` tag, for example, creates a block that’s separated from tags above and below. Headlines, `<div>` tags, tables, lists, and list items are other examples of block-level tags.

Inline tags don’t create a break before or after them. They appear on the same line as the content and tags beside them. The `` tag is an inline tag. A word formatted with this tag happily sits next to other text—even text wrapped in other inline tags like ``. In fact, it would look pretty weird if you emphasized a single word in the middle of a paragraph with the `` tag and that word suddenly appeared on its own line by itself. Other inline tags are `` for adding images, `<a>` for creating links, and the various tags used to create form fields.

In most cases, CSS works the same for inline boxes and block boxes. You can style the font, color, and background and add borders to both types of boxes. However,

when it comes to margins and padding, browsers treat inline boxes differently. Although you can add space to the left or right of an inline element using either left or right padding or left or right margins, you can't increase the height of the inline element with top or bottom padding or margins. In the top paragraph in Figure 7-6, the inline element is styled with borders, a background color, and 20 pixels of margin on all four sides. But the browser only adds space to the left and right sides of the inline element.




FIGURE 7-6

Adding top or bottom margins and padding doesn't make an inline element any taller, so you can run into some weird formatting. In the middle paragraph, the background and borders of a link overlap the text above and below. The background appears on top of the line before the styled inline text, but underneath the line following it because the browser treats each line as if it's stacked on top of the previous line. Normally, that isn't a problem since lines of text don't usually overlap. If you want top and bottom margins and padding to work for an inline element, you can use the `display:inline-block` instruction (bottom). This leaves the item inline, but treats it like a box so padding, margins, borders, and width and height are all applied (and obeyed). This even works in Internet Explorer 7, but only for normally inline elements like links, ``, ``, and `` tags; you should also add `vertical-align: middle` so that IE 7 displays the inline block the same as other browsers.

NOTE

One exception to the rule that inline elements don't get taller when padding or margins are added is the `` tag (even though it's an inline tag). Web browsers correctly expand the height of the image's box to accommodate any padding and margins you add.

At times, you may wish an inline element behaved more like a block-level element and vice versa. Bulleted lists present each item as its own block—each list item is stacked above the next. You may want to change that behavior so the list items appear side by side, all on a single line, as in a navigation bar (you can see an example of one in the box on page 307). Finally, you may want to treat an inline element like a block-level element. Maybe you want an image embedded in a paragraph to be on its own line, with space above and below.

Fortunately, CSS includes a property that lets you do just that—the `display` property. With it, you can make a block-level element act like an inline element:

```
display: inline;
```

Or you can make an inline element, like an image or link, behave like a block-level element:

```
display: block;
```

NOTE The `display` property has a myriad of possible options, some of which don't work in all browsers. The `inline-block` value works in current browsers (see Figure 7-6). Another value, `none`, works in most browsers and has many uses. It does one simple thing—completely hides the styled element so it doesn't appear in a web browser. With a dab of JavaScript programming, you can make an element hidden in this way instantly become visible, simply by changing its `display` back to either `inline` or `block`. You can even make an element with a `display` of `none` suddenly appear using CSS; you'll see an example of that on page 583.

■ Adding Borders

A border is simply a line that runs around an element. As shown back in Figure 7-1, it sits between any padding and margins you set. A border around every edge can frame an image or mark the boundaries of a banner or other page element. But borders don't necessarily have to create a full box around your content. While you can add a border to all four edges, you can just as easily add a border to just the bottom or any combination of sides. This flexibility lets you add design elements that don't necessarily feel like a border. For example, add a border to the left of an element, make it around `1em` thick, and it looks like a square bullet. A single border under a paragraph can function just like the `<hr>` (horizontal rule) by providing a visual separator between sections of a page.

You control three different properties of each border: `color`, `width`, and `style`. The color can be any of the CSS color values discussed starting on page 154, such as a hexadecimal number, a keyword, or an RGB (or RGBA) value. A border's width is the thickness of the line used to draw the border. You can use any CSS measurement type (except percentages) or the keywords `thin`, `medium`, and `thick`. The most common and easily understood method is pixels.

Finally, the `style` controls the type of line drawn. There are many different styles, and some look very different from browser to browser, as you can see in Figure 7-7. You

specify the style with a keyword. For example, `solid` draws a solid line and `dashed` creates a line made up of dashes. CSS offers these styles: `solid`, `dotted`, `dashed`, `double`, `groove`, `ridge`, `inset`, `outset`, `none`, and `hidden`. (None and hidden work the same way: They remove the border entirely. The none value is useful for turning off a single border. See the example on page 205.)



FIGURE 7-7

The appearance of border styles can vary greatly from browser to browser. The browsers pictured here are Internet Explorer 9 (top left), Chrome for Windows (top right), Firefox for Mac (bottom left), and Safari for Mac (bottom right).

Border Property Shorthand

If you've ever seen a list of the different border properties available in CSS, you may think borders are really complex. After all, there are 20 different border properties, which you'll meet in the following sections, plus a couple that apply to tables. But all these properties are merely variations on a theme that provide different ways of controlling the same three properties—color, width, and style—for each of the four borders. The most basic and straightforward property is `border`, which simply adds four borders:

```
border: 4px solid #FF0000;
```

The above style creates a solid, red, 4-pixel border. You can use this property to create a basic frame around a picture, navigation bar, or other item that you want to appear as a self-contained box.

NOTE

The order in which you write the properties doesn't matter: `border: 4px solid #FF0000;` works as well as `border: #FF0000 solid 4px;`

Formatting Individual Borders

You can control each border individually using the appropriate property: `border-top`, `border-bottom`, `border-left`, or `border-right`. These properties work just like the regular `border` property, but they control just one side. The following property declaration adds a 2-pixel, red, dashed line below the style:

```
border-bottom: 2px dashed red;
```

You can combine the `border` property with one of the edge-specific properties like `border-left` to define the basic box for the entire style but customize a single border. Say you want the top, left, and right sides of a paragraph to have the same type of border, but you want the bottom border to look slightly different. You can write four lines of CSS, like this:

```
border-top: 2px solid black;  
border-left: 2px solid black;  
border-right: 2px solid black;  
border-bottom: 4px dashed #333;
```

Or, you can achieve the same effect as the previous four lines of CSS with just two lines:

```
border: 2px solid black;  
border-bottom: 4px dashed #333;
```

The first line of code defines the basic look of all four borders, and the second line redefines just the look of the bottom border. Not only is it easier to write two lines of CSS instead of four, but it also makes changing the style easier. If you want to change the color of the top, left, and right borders to red, then you only have to edit a single line, instead of three:

```
border: 2px solid red;  
border-bottom: 4px dashed #333;
```

When you use this shortcut method—defining the basic look of all four borders using the `border` property and then overriding the look of a single border with one of the edge-specific properties like `border-left`—it's crucial that you write the code in a specific order. The more general, global border setting must come first, and the edge-specific setting second, like so:

```
border: 2px solid black;  
border-bottom: 4px dashed #333;
```

Because the `border-bottom` property appears second, it overrides the setting of the `border` property. If the `border-bottom` line came before the `border` property, then it would be cancelled out by the `border` property, and all four borders would be identical. The last property listed can overrule any related properties listed above it. This behavior is an example of the CSS cascade you read about in Chapter 5.

You can also use this shortcut method to turn off the display of a single border with the `none` keyword. Say you want to put a border around three sides of a style (top, left, and bottom) but no border on the last side (right). Just two lines of code get you the look you're after:

```
border: 2px inset #FFCC33;
border-right: none;
```

The ability to subtly tweak the different sides of each border is the reason there are so many different border properties. The remaining 15 properties let you define individual colors, styles, and widths for the border and for each border side. For example, you could rewrite `border: 2px double #FFCC33;` like this:

```
border-width: 2px;
border-style: double;
border-color: #FFCC33;
```

Since you're using three lines of code instead of one, you'll probably want to avoid this method. However, each border edge has its own set of three properties, which are helpful for overriding just one border property for a single border edge. The right border has these three properties: `border-right-width`, `border-right-style`, and `border-right-color`. The left, top, and bottom borders have similarly named properties—`border-left-width`, `border-left-style`, and so on.

You can change the width of just a single border like this: `border-right-width: 4px;`. One nice thing about this approach is that if you later decide the border should be solid, you need to edit only the generic border property by changing `dashed` to `solid`.

In addition, you can specify individual values for each side of the border by using the `border-width`, `border-style`, and `border-color` properties. For example, `border-width: 10px 5px 15px 13px;` applies four different widths to each (top, right, bottom, and left) side.

Imagine that you want to have a 2-pixel, dashed border around the four edges of a style, but you want each border to be a different color. (Perhaps you're doing a website for kids.) Here's a quick way to do that:

```
border: 2px dashed;
border-color: green yellow red blue;
```

This set of rules creates a 2-pixel dashed border around all four edges, while making the top edge green, the right edge yellow, the bottom edge red, and the left edge blue.

NOTE

You usually add padding whenever you use borders. Padding provides space between the border and any content, such as text, images, or other tags. Unless you want to put a border around an image, borderlines usually sit too close to the content without padding.

■ Coloring the Background

It's a cinch to add a background to an entire page, an individual headline, or any other page element. Use the `background-color` property followed by any of the valid color choices described starting on page 154. If you want, add a shockingly bright green to the background of a page with this line of code:

```
body { background-color: rgb(109,218,63); }
```

Alternatively, you can create a class style named, say, `.review` with the `background-color` property defined, and then apply the class to the body tag in the HTML, like so: `<body class="review">`.

NOTE

You can also place an image in the background of a page and control that image's placement in many different ways. You'll explore that in the next chapter. In addition, you can add a color gradient to the background of any element.

Background colors come in handy for creating many different visual effects. You can create a bold-looking headline by setting its background to a dark color and its text to a light color. Background colors are also a great way to set off part of a page like a navigation bar, banner, or sidebar.

And, don't forget about the RGBA color method described on page 155. With it, you can make the background partially transparent, letting underlying colors, textures, or images from other objects show through. For example, you can set the background color of the page to a tan color. Then, say you want a `<div>` tag inside that to be a lighter shade of that tan. Instead of placing a solid color in the background of that div, you can add the color white and then control the opacity of that color, so that various degrees of the tan color show through:

```
body {  
  background-color: rgb(247,226,155);  
}  
.special-div {  
  background-color: rgba(255,255,255,.75);  
}
```

NOTE

When you use background colors and borders, keep the following in mind: If the border style is either dotted or dashed (see Figure 7-7), the background color shows in the empty spaces between the dots or dashes. In other words, web browsers actually paint the background color *under* the borderline.

■ Creating Rounded Corners

As mentioned earlier, web browsers treat all elements as stark rectangular boxes. That becomes obvious when you put a border around a paragraph or div. Fortunately, you can soften the hard edges of those boxes by adding a rounded corner to your styles (see Figure 7-8). CSS3 introduces the `border-radius` property to let designers add curves to one or more corners of an element. At its simplest, the `border-radius` property accepts a single value, which it then applies to all four corners of an element:

```
.specialBox {  
  background-color: red;  
  border-radius: 20px;  
}
```

The browser uses the supplied radius value to draw a circle at each corner of the element. The value equals the distance from the center of the circle to its edge—its radius—as pictured in Figure 7-9. Pixels and ems are the most common measurements you'll use, but you can use percentages as well (though they behave a little differently than you might expect, as discussed in Figure 7-9).



FIGURE 7-8

CSS3 lets you apply rounded corners to any element. Make sure you have a background color or border on the element, or else you won't be able to see any of that awesome roundedness.


With a single value, the browser draws the same radius for each corner of the element. For example, the top-left image in Figure 7-8 uses the following declaration:

```
border-radius: 30px;
```

However, you're not limited to the same value for each corner. You can supply separate values for each corner by providing four values. For example, the top-right box in Figure 7-8 has four different corners. The declaration is:

```
border-radius: 0 30px 10px 5px;
```

The numbers start at the top-left of the box and work their way around clockwise. In other words, the first value (0 in the example in Figure 7-8) applies to the top-left, the second (30px) to the top-right, the third (10px) to the bottom-right, and the fourth (5px) to the bottom-left corner. You can also supply just two values, in which case, the first number applies to the top-left and bottom-right corners, while the second number applies to the top-right and bottom-left corners.



In addition to the perfectly round (that is, circular) corners you've seen so far, it's also possible to apply an elliptical corner, like the ones in the two bottom examples in Figure 7-8. An elliptical path requires two radius values: the first is the radius from the center of the path to one of the left or right edges, while the second number is the distance from the center of the path to one of the top or bottom edges. For example, to add corners like the one pictured in the bottom-left corner in Figure 7-8, you'd create this declaration:

```
border-radius: 40px/20px ;
```

The 40px value is the horizontal radius; the 20px value is the vertical radius. The slash between them lets a browser know that you're creating an elliptical path. You can make all four corners have different oblong shapes by providing four values for each radius of the ellipse. This is a bit confusing: you first provide the four values for the horizontal radius of each corner (starting in the top-left corner); then a forward slash (/) followed by four values for the vertical radius of each corner, like this:

```
border-radius: 40px 10px 20px 10px / 20px 30px 40px 20px;
```

To mix and match elliptical and circular corners you need to use this same syntax—circular corners will have the same horizontal and vertical radii:

```
border-radius: 10px 10px 20px 10px / 10px 30px 40px 10px;
```

Finally, if you want to go the longhand route, you can use separate properties to define the appearance of each corner. For example:

```
border-radius: 1em 2em 1.5em .75em;
```

can also be written as:

```
border-top-left-radius: 1em;  
border-top-right-radius: 2em;  
border-bottom-right-radius: 1.5em;  
border-bottom-left-radius: .75em;
```

NOTE Internet Explorer 8 and earlier don't understand the `border-radius` property, so they'll display square corners instead. In addition, version 3.2 of Safari for iOS, and version 2.1 of the Android Browser require the `-webkit-` vendor prefix like this: `-webkit-border-radius: 20px;`. See the box below for more.

UP TO SPEED

Vendor Prefixes

CSS is an always-evolving set of rules. Even as you build web pages today, there are smart people at the W3C (World Wide Web Consortium) working on new CSS properties, and other smart people adding support for new CSS properties in the web browsers they build. In fact, sometimes browser makers themselves come up with a new CSS property they think would be cool and add it to their browser. Other times, the W3C thinks up new CSS properties that the browser vendors slowly try to add to their browsers.

During this period when new CSS properties and standards are developing, browser manufacturers move cautiously. They don't want to completely commit to CSS properties that may change. Likewise, as they experiment with CSS properties of their own design, browser makers hesitate to claim that they've come up with an agreed-upon standard. To mark a CSS property as experimental or not-yet-completely agreed upon, a browser manufacturer uses a prefix before the property name. Each of the major browser makers has its own prefix:

- `-webkit-` is used by Chrome, Safari, and other WebKit-based browsers
- `-moz-` is used by Mozilla Firefox
- `-o-` is used by Opera
- `-ms-` is used by Microsoft Internet Explorer

When a property is in flux, a browser may support a vendor-prefixed version. For example, when the `border-radius`

property was first proposed, Firefox supported a `-moz-border-radius` property, while Safari supported the `-webkit-border-radius` property.

When a property requires a vendor prefix, you usually write several lines of code to create the same effect: one for each vendor, and finally one with the non-prefixed version like this:

```
-moz-box-sizing: border-box;  
-webkit-box-sizing: border-box;  
box-sizing: border-box;
```

Usually, if the W3C CSS Working Group adopts a property and finalizes enough of its details, vendors drop the extension. For example, now all major browsers simply support the `border-radius` property with no required vendor prefix. As you'll read throughout this book, the final details for some CSS3 properties are still being hammered out, so you may need to use a vendor prefix with them. This book will let you know when you need these prefixes and how to use them with a particular property.

■ Adding Drop Shadows

As you read on page 166, you can create subtle (or not so subtle) drop shadows to text to make it pop from the page. CSS3 includes the `box-shadow` property to add drop shadows to an element's bounding box so you can, for example, make a `<div>` appear to float above the page (see Figure 7-10). There are a few more options than with the `text-shadow` property. For example, you can make a shadow appear inside the box as at the bottom in Figure 7-10.

```
box-shadow: 4px 6px 8px rgba(0,0,0,.75);
```

```
box-shadow: 0 0 8px 2px rgba(0,0,0,.75);
```

```
box-shadow: -4px -6px 8px 2px rgba(0,0,0,.5),
            8px 6px 12px rgba(0,0,0,.5);
```

```
box-shadow: inset 0 0 8px 2px rgba(0,0,0,.75);
```

FIGURE 7-10


The CSS3 `box-shadow` property lets you add shadows to your elements to make them appear as though they're floating above the page. This property works in most current browsers including Internet Explorer 9. Unfortunately, IE 9 draws the shadows noticeably thinner than do other browsers. In addition, IE 8 and earlier simply ignore the property and won't draw any shadows on elements.

The basic syntax for the box-shadow property is pictured in Figure 7-11. The first value is a horizontal offset; that is, this value moves the shadow to the element's right or the left. A positive number moves the shadow to the right (Figure 7-10, top), and a negative number moves the shadow to the left.

The second value is the vertical offset—the position of the shadow either above or below the element. A positive element positions the shadow below the bottom edge of the box (Figure 7-10, top), while a negative value moves the shadow above the top edge of the box.

NOTE You must use pixels or ems for the drop shadow values. Percentages will not work.

The third value is the radius of the shadow. It determines how blurry and wide the shadow is. A value of 0 creates no blur, so the edges of the shadow are sharp. A large value creates more blur and a thicker shadow. Finally, the last value is the drop shadow's color. You can use any CSS color value, but RGBA values look particularly good since you can control the color's opacity to make it appear more translucent and shadow-like.



The box-shadow property includes two optional values: inset and a spread value. The inset keyword tells a browser to draw the shadow inside the box (Figure 7-10, bottom). Simply add inset as the first value of the box-shadow property to create an inset shadow:

```
box-shadow: inset 4px 4px 8px rgba(0,0,0,.75);
```

You can also add a *spread* as a fourth value (between the shadow radius and shadow color). The spread expands the shadow by the specified amount. In other words, if you add a spread value of 10px, a browser expands the shadow 10 pixels in each direction (basically making it 20 pixels wider and 20 pixels taller). The value also

dictates when the blur radius is applied. In other words, when you add a spread value, the blurring of the shadow doesn't begin until after the spread value is applied. This is particularly useful when you want to add a shadow around the entire element—what a lot of image-editing programs call *glow*.

NOTE The Android browser and older versions of Safari for the iPhone require the vendor-prefixed version of `box-shadow` to work; see the box on page 209 for more on vendor prefixes. In other words, to make a box shadow work in those browsers as well as all the new browsers, you need to add two declarations to a style:

```
-webkit-box-shadow: 2px 2px 10px #000000;  
box-shadow: 2px 2px 10px #000000;
```

For example, at the second-from-top box in Figure 7-10, both the horizontal and vertical offsets are set to 0; the shadow radius is 8px; and the spread is 2px. The spread value pushes the shadow outward 2 pixels on all four sides of the box; and then the 8 pixels of shadow radius extends the blurring another 8 pixels. You can even use the spread value to create a second, different-colored border around an existing border. Here's an example of that:

```
border: 10px solid rgb(100,255,30);  
box-shadow: 0 0 0 10px rgb(0,33,255);
```

Finally, you can even apply multiple shadows to a style (Figure 7-10, second from bottom). Just add a comma after the first set of shadow settings, and then add another shadow:

```
box-shadow: 10px 5px 8px #FF00FF,  
            -5px -10px 20px 5px rgb(0,33,255);
```

You can add as many shadows as you want (and as common design sense allows).

NOTE Unfortunately, there's a lot of variation in how browsers draw a box shadow. IE 9 for example creates a noticeably thinner shadow than other browsers. For a good visual comparison of how browsers draw box shadows, visit <http://thany.nl/apps/boxshadows/>.

■ Determining Height and Width

Two other CSS properties that form part of the CSS box model are useful for assigning dimensions to an object, such as a table, column, banner, or sidebar. The `height` and `width` properties assign a height and width to the content area of a style. You'll use these properties often when building the kinds of CSS layouts described in Part Three of this book, but they're also useful for more basic design chores like assigning the width to a table, creating a simple sidebar, or creating a gallery of thumbnail images (like the one described in the steps on page 278).

Adding these properties to a style is very easy. Just type the property followed by any of the CSS measurement systems you've already encountered. For example:

```
width: 300px;  
width: 30%;  
height: 20em;
```

Pixels are, well, pixels. They're simple to understand and easy to use. They also create an exact width or height that doesn't change. An *em* is the same as the text size for the styled element. Say you set the text size to 24px; an *em* for that style is 24px, so if you set the width to 2em, then it would be 2 x 24 or 48 pixels. If you don't set a text size in the style, the *em* is based on the inherited text size (see page 104).

NOTE

CSS3 introduces another measurement—the *rem*—which is based on the `font-size` of the `html` element. It works in all major browsers, except Internet Explorer 8 and earlier. See page 161 for more on the *rem* unit.

For the `width` property, percentage values are based on the percentage of the width of the style's containing element. If you set the width of a headline to 75% and that headline isn't inside any other elements with a set width, then the headline will be 75 percent of the width of the browser window. If the visitor adjusts the size of his browser, then the width of the headline will change. However, if the headline is contained inside a `<div>` (maybe to create a column) that's 200 pixels wide, the width of that headline will be 150 pixels. Percentage values for the `height` property work similarly, but are based on the containing element's height, instead of width.

Calculating a Box's Actual Width and Height

While the `width` and `height` properties seem pretty straightforward, there are a few nuances that can throw you for a loop. First of all, there's a difference between the value you set for a style's width and height and the amount of space that a web browser actually uses to display the style's box. The `width` and `height` properties set the width and height of the *content area* of the style—the place where the text, images, or other nested tags sit. (See Figure 7-1 for a refresher on where the content area sits within the overall box model.) The actual width—that is, the amount of screen real estate given by the web browser—is the total of the widths of the margins, borders, padding, and width properties, as illustrated in Figure 7-12.

Say you've set the following properties:

```
width: 100px;  
padding: 15px;  
border-width: 5px;  
margin: 10px;
```

When the width property is set, you always know how much room is allocated just for your content—the words and images that fill the space—regardless of any other properties you may set. You don't need to do any math because the value of the width property is the room for your content (in the previous example, 100 pixels). Of course, you *do* have to perform a little math when you're trying to figure out exactly how much space an element will take up on a web page. In the preceding example, the width that a web browser allocates for the style's box is 160 pixels: 20 pixels for the left and right margins, 10 pixels for the left and right borders, 30 pixels for the left and right padding, and 100 pixels for the width.




FIGURE 7-12

Calculate the actual width of a styled element's box by adding up its margin, border, padding, and width properties. The height occupied on the screen by the element is calculated in the same way—the total of the height property, the top and bottom margins, the top and bottom borders, and the top and bottom padding.

The general rule of thumb for setting heights on page elements is *don't!* A lot of budding CSS designers try to set heights on everything in an attempt to get pixel-perfect control. But unless you're totally sure of the exact dimensions of the content inside a tag, you can run into some unwanted results (see Figure 7-13). In this example, a pull-quote box used to highlight an interesting comment from an article has a set width and height of 100 pixels. When more text than fits into the 100-pixel height is added to the box, its contents spill out the bottom. Even if you make sure that the text you put inside a box with a fixed height fits, if a visitor increases the font size in her browser, the text might resize to a height larger than the box.

In other words, the height property is useful for controlling the height of a div containing images, for example, because you can correctly determine the height of the images; however, if you use the height for elements that have text, make sure to not only test your pages in the major browsers, but also test the page with different font sizes by increasing the font size in the web browser.

TIP The banner area of a page is another good candidate for a set height. Usually, the banner has limited content: a logo, search box, maybe some navigation buttons. Frequently, banners have a fair amount of white space (empty areas that help draw a visitor's attention to the key elements in the banner like the navigation bar), so specifying a height for a banner doesn't usually cause problems.




FIGURE 7-13

When you set the height of an element (like the right sidebar div here), but the content inside is taller than the element, browsers simply let the content spill out the bottom of the element below its edges.

Redefining Box Width with Box-Sizing

As mentioned on page 213, web browsers traditionally calculate the width of an element by adding together the border, padding, and width properties. Not only does this force you to (heaven forbid) do math to figure out an element's actual display width, it can cause other problems as well. This is especially true when you create float-based layouts using percentages. You'll learn the details of float layouts later in this book, but in a nutshell, CSS lets you place elements side-by-side using the `float` property, which lets you create multiple column layouts.

When using percentages with multiple columns, you can run into some weird problems. Say you have two columns (really, two tags, such as `<div>` tags), and you want each to be 50 percent of the width of the window. So you set the two columns to a width of 50%; however, the moment you add padding or a border to one of the columns, you'll increase its width to more than 50% (to be exact, it will be 50% plus the amount of left and right padding and the width of the left and right borders). In most cases, this will force the second column to drop *below* the first.

Fortunately, CSS3 offers a property that lets you change how a browser calculates the screen width (and height) of an element. The `box-sizing` property provides three options:

- The `content-box` option is the way browsers have always defined the screen width and height of an element, as described on page 213. That is, the browser adds the border widths and padding thicknesses to the values set for the width and height properties to determine the tag's onscreen width and height. Since this is the default behavior, you don't need to specify anything for `content-box`.
- The `padding-box` option tells a browser that when you set a style's width or height property, it should include the padding as part of that value. For example, say you give an element 20 pixels of left and right padding and set the width of the element to 100 pixels. The browser will consider the padding part of that 100-pixel value. In other words, the content area will be only 60 pixels wide (100 – 20 [left padding] – 20 [right padding]).
- The `border-box` value includes both the padding and the border thickness as part of the width and height values. This setting solves the problem of using percentage values for widths discussed above. In other words, with the `box-sizing` property set to `border-box`, when you set an element's width to 50%, for instance, that element will take up 50 percent of the space, even if you add padding and borders to that element.

If you don't like the standard way browsers calculate element widths and heights, go with the `border-box` value. (Unless, of course, you have some unusual reason why you'd want to include the padding but not the border as part of the calculation.) To use the `box-sizing` property, simply supply one of the three values from the list. For example:

```
box-sizing: border-box;
```

In addition, Firefox doesn't yet (at the time of this writing) support the standard property name, so you need to use the vendor-prefixed version (see the box on page 209); the same is true for older versions of Safari for iOS and Android (version 3 and earlier). To make sure the `box-sizing` setting works in all of those browsers as well, you should write three declarations like this:

```
-moz-box-sizing: border-box;
-webkit-box-sizing: border-box;
box-sizing: border-box;
```

In fact, many web designers are finding the `border-box` setting so useful that they create a universal selector (page 63) style to apply it to every element on a page:

```
* {  
  -moz-box-sizing: border-box;  
  -webkit-box-sizing: border-box;  
  box-sizing: border-box;  
}
```

As you'll read on page 467, using `border-box` is extremely helpful when creating CSS3's responsive web designs that resize to fit different device sizes (such as an iPhone, a tablet, and a desktop monitor).

NOTE

The `box-sizing` property even works in Internet Explorer 8 and newer, so it's supported in well over 95 percent of the browsers in use. Unfortunately, IE 7 doesn't understand this property, so if you use the `border-box` setting, IE 7 will ignore it and draw elements much wider (and taller) than in other browsers. If you still need to support IE 7, skip this property.

Controlling the Tap with the Overflow Property

When the content inside a styled tag is larger than the style's defined width and height, some weird things happen. As shown in Figure 7-13, browsers let the content spill out of the box (past the borders and often over other content).

Fortunately, you can control what a browser should do in this situation with the `overflow` property. `Overflow` accepts four keywords that control how content that overflows the edges of a box should be displayed:

- **visible.** This option is what browsers do normally. It's the same as not setting the property at all (Figure 7-14, top).
- **scroll.** Lets you add scroll bars (Figure 7-14, middle). It creates a kind of mini-browser window in your page and looks similar to old-school HTML frames, or the HTML `<iframe>` tag. You can use `scroll` to provide a lot of content in a small amount of space. Unfortunately, scroll bars *always* appear when you use this option, even if the content fits within the box.
- **auto.** To make scroll bars optional, use the `auto` option. It does the same thing as `scroll` but adds scroll bars only when needed.
- **hidden.** Hides any content that extends outside the box (Figure 7-14, bottom). This option is a bit dangerous—it can make some content disappear from the page—but it's a useful trick for float-based layouts (page 222).



FIGURE 7-14

The overflow property gives you three basic ways to deal with text that doesn't fit inside a box: visible displays the content anyway (top); scroll and auto add scroll bars (middle); and hidden just doesn't show anything that doesn't fit (bottom).

Maximum and Minimum Heights and Widths

In case you haven't yet realized it, CSS offers a lot of flexibility. In addition to the standard width and height properties, you'll find four variations:

- The **max-width** property, not surprisingly, sets the maximum width for an element. That element can be thinner than the setting, but it can't be any wider than that setting. This option comes in handy when you want your page to resize to fit different display widths but you don't want the page to get so wide that it's too hard to read on a really large monitor. For example, say you add this style to a page:

```
body {  
    max-width: 1200px;  
}
```

This style lets the page reflow to fit the width of smaller displays like smartphones and tablets. But on a really large desktop monitor, the page won't get wider than 1200 pixels, so the page can't grow unreadably wide.

- The **max-height** property works much like `max-width`, except it's for the element's height. As mentioned on page 214, however, it's usually best not to mess with the height of an element.
- The **min-width** property sets an element's minimum width. The element can stretch wider than the minimum width value, but it can never get thinner. If, for example, you notice that when you resize your browser window, the element's so thin that the layout falls apart, you can set a minimum width like this:

```
body {  
    min-width: 760px;  
}
```

If a visitor shrinks his browser window so it's only 500 pixels wide, then the browser will add a scrollbar rather than let the elements on the page get too narrow.

- The **min-height** property works like `min-width`, except for height. This property can solve the problem pictured in Figure 7-13. With a minimum height, you're telling a web browser to make the element at least a certain height. If the content inside the element is taller, then the browser will make the entire element taller as well.

You can use the minimum and maximum properties together as well. For example, if you want to make sure that a page is at least 760 pixels wide, but never expands to wider than 1200 pixels, you can use this style:

```
body {  
    min-width: 760px;  
    max-width: 1200px;  
}
```

Wrapping Content with Floating Elements

HTML normally flows from the top of the browser window down to the bottom, one headline, paragraph, or block-level element on top of another. This word-processor-like display is visually boring (Figure 7-15, top), but with CSS, you're far from stuck with it. You'll learn lots of new methods for arranging items on a web page in Part 3, but you can spice up your pages plenty with one little CSS property—`float`.

The `float` property moves an element to either the left or right. In the process, content below the floated element moves up and wraps around the float (Figure 7-15, bottom). Floating elements are ideal for moving supplemental information out of the way of the page's main text. Images can move to either edge, letting text wrap elegantly around them. Similarly, you can shuttle a sidebar of related information and links off to one side.





FIGURE 7-15

The regular flow of HTML is left to right, top to bottom, with one block-level element—headline, paragraph, div, and so on—stacked on top of the next. By letting you break up this uniformity, the `float` property is one of CSS's most powerful tools. Its uses range from simply moving an image to one side of a paragraph to providing complete layout control over banners, sidebars, navigation bars, and other page elements.



Although you can use floats in some complex (and confusing) ways, as you'll see in Chapter 13, the basic property is very simple. It takes one of three keywords—`left`, `right` or `none`—like so:

```
float: left;
```

- **left.** Slides the styled element to the left while content below wraps around the right side of the element.
- **right.** Slides the element to the right.
- **none.** Turns off the float and returns the object to its normal position.

Floated elements move to the left or right edge of their *containing element*. In some cases, this just means that the element moves to the left or right edge of the browser window. However if you float an element that's inside another tag with a set width or position on a web page, then the float will go to the left or right edge of that tag—the floated element's "container." For example, you may have a box on the page that's 300 pixels wide and is itself floated to the right edge of the browser window. Inside that box, you've got an image that floats to the left. That image slides to the left edge of that 300-pixel-wide box—not the left edge of the browser window.

You can even use the `float` property with an inline element, such as the `` tag. In fact, floating a photo to the left or right using CSS is a very common use of the `float` property. A web browser treats a floated inline element just like a block-level element, so you don't run into the problems with padding and margin that normally trouble inline elements (see page 200).

You can also float a block-level element like a headline or paragraph. A common technique is to float a `<div>` tag (or one of HTML5's new elements like `<article>`, `<section>`, or `<aside>`) containing other HTML tags and page content to create a kind of containing box. In this way, you can create sidebars, pull quotes, and other self-contained page elements. (You'll see an example of this in this chapter's tutorial.) When you float block-level elements, you should also set the `width` property for that element (in fact, CSS rules require setting the `width` for floated elements for all tags except images). This way, you can control how much horizontal space the block takes up and how much space is available for the content below it to move up and wrap around the block.

NOTE


The *source order*—the order in which you write your HTML—has a big impact on the display of floated elements. The HTML for the floated tag must appear *before* the HTML of any content that wraps around the floated element. Say you've created a web page composed of an `<h1>` tag followed by a `<p>` tag. Toward the end of that `<p>` tag, you've also inserted a photo using the `` tag. If you float that photo to the right, say, then the `<h1>` tag and most of the content inside that `<p>` tag will still appear above the photo; only content that follows the `` tag will wrap around the left side of the image.

Backgrounds, Borders, and Floats

To the consternation of many web designers, backgrounds and borders don't react to floated elements the same way content does. Say you float an element—a sidebar for example—to the right. The content below the sidebar moves up and wraps around it, just as it should. But if that content has a background or border set on it, then that background or border actually appears *underneath* the floated sidebar (Figure 7-16, left). In essence, a web browser wraps the text around the float, but not the border or background. Believe it or not, this is absolutely kosher and (according to the rules) how it's supposed to work. Of course, you may not want to follow these rules; you might want to have the border or background stop when it reaches the floated element (Figure 7-16, right). With a little CSS magic, you can do it.

First, you need to add one rule to the style that has background or borders running underneath the float. Once you locate the style, add this line: `overflow: hidden;`. The `overflow` property (page 217) makes any background or border that extends underneath the float disappear.

Another approach is to add a borderline around the floated element; when you make the borderline thick enough and match its color to the background color of the page, the border looks just like empty space—even though it's covering and hiding the background color and borderlines that are extending below it.



Stopping the Float

Sometimes you need a way to tell a tag to ignore a floated element. You may have a copyright notice that should always appear at the bottom of the browser window. If you have a particularly tall sidebar that's floated to the left side of the page, the copyright notice might actually be drawn up the page and wrap around the float. Instead of appearing at the bottom of the page, the copyright is sitting farther up the page next to the sidebar. You want the copyright notice part of your page to refuse to wrap around the floated element and instead drop below it.

Other problems occur when you have several floated items close together. If the floated items aren't very wide, they float up and next to each other, and if they're of varying heights they can get into an unattractive logjam (see Figure 7-17, top). In this case, the floated elements *shouldn't* float next to each other. CSS provides the `clear` property for just these types of problems.

The `clear` property instructs an element to *not wrap* around a floated item. By clearing an element, you essentially force it to drop down below the floated item. Also, you can control which type of float (left or right) is cleared or force a style to simply ignore both types of floats.

The `clear` property accepts the following options:

- **left.** The style will drop below elements that are floated left but will still wrap around right-floated objects.
- **right.** Forces a drop below right-floated objects but still wraps around left-floated objects.
- **both.** Forces a drop below both left- and right-floated elements.
- **none.** Turns off clearing altogether. In other words, it makes an item wrap around both left- and right-floated objects, which is how web browsers normally work.

In the case of a copyright notice that must appear at the bottom of the page, you'd want it to clear both left- and right-floated objects—it should always be below other content, and should never wrap to the left or right of any other item. Here's a class style that would do just that:

```
.copyright {  
  clear: both;  
}
```

Figure 7-17 shows how the `clear` property can prevent floated items of varying heights from clumping together. All three photos in that figure have a right float applied to them. In the top figure, the photo of the tomatoes (1) is the first image on the page and appears at the far right edge. The second image (2) obeys the float set on the first image and wraps up to the left of it. The last photo (3) is too wide to sit next to the second photo (2) but still tries to wrap around both (1) and (2). It gets stuck in the process.





FIGURE 7-17

Top: Sometimes you don't want an element to wrap around a floated object.

Bottom: Applying the `clear` property (in this case `clear: right`;) to each image prevents them from sitting next to each other. The `clear` applied to photo (2) prevents it from wrapping up next to image (1). Applying `clear: right` to photo (3) forces it to appear below photo (2).



Using `clear: right`; on the images prevents the photos from sitting next to each other (Figure 7-17, bottom). The `clear` applied to the second photo prevents it from wrapping up next to the first image, while the last image's right `clear` property forces it to appear below the second image.

NOTE This business of left floats, right floats, and how to clear them sounds complicated—and it is. This section gives you a basic introduction. You'll see the subject again in Chapter 13 and eventually learn how to use floats in more sophisticated ways.

Tutorial: Margins, Backgrounds, and Borders

In this tutorial, you'll explore elements of the CSS box model, adjust the spacing around objects on a page, add colorful borders to items on a page, and control the size and flow of page elements.

1. **To get started, you need to download the tutorial files located on this book's companion website at www.sawmac.com/css3/.** Click the tutorial link and download the files. (All of the files are enclosed in a zip archive. See detailed instructions for unzipping the files on the website.) The files for this tutorial are contained inside the *07* folder.

Controlling Page Margins and Backgrounds

You'll start with a very basic HTML file containing an internal style sheet with a basic CSS reset style. It's not much to look at right now (see Figure 7-18).

NOTE For a sneak preview of the final result, check out Figure 7-21.

2. **In your favorite text editor, open *07→sidebar.html*.**

There's already an internal style sheet added to this page containing the same set of styles discussed on page 116. The styles basically remove all margins, padding, and font size from the most common block-level elements and eliminate many of the cross-browser display problems you'll encounter related to these properties.

At a bare minimum, you should always include this set of styles in every style sheet you create. Probably the most important properties are the `margin` and `padding` settings in the first style. There's enough cross-browser weirdness related to those two properties that you should always zero these out and start fresh. You'll start with something simple: a background color.

3. **In the internal style sheet, click directly after the CSS comment `/* end reset styles */` and add a tag selector style:**

```
html {  
    background-color: rgb(253,248,171);  
}
```

This style adds a light yellow background color to the page. If you want to color the background of a web page, you can add the `background-color` property to either the `<html>` tag or the `<body>` tag. Next, you'll add some margins, borders, and other properties to the `<body>` tag.

NOTE

You may be used to using hexadecimal colors (like #FDF8AB) instead of RGB colors. You can use a tool like the online convertor at www.colorhexa.com/ to convert between the two. Using RGB is a good idea because RGBA colors, with their optional transparency (page 155), are so useful, and it's easier to just stick with one color model (RGB) instead of mixing two (RGB and hex).

4. Add another style to the internal style sheet:

```
body {  
  background-color: rgb(255,255,255);  
  border: 3px solid rgb(75,75,75);  
}
```

This style adds a white background color to the `<body>` tag and a 3-pixel dark gray border. Because the `<body>` tag sits inside the `<html>` tag, a web browser considers it to be “on top” of the `<html>` tag, so the white background will cover the yellow color you added in the previous step. Next you'll give the body tag a width and adjust its padding and margins.

TIP

Normally, if you add a background color property to the `<body>` tag, that color fills the entire browser window; however, if you also add a background color to the `<html>` tag, the body's background color fills only the area with content. To see this in action, just preview the web page after completing Step 4 above; then delete the `html` tag style, and preview the page again. A weird, but useful bit of CSS trivia.

5. Edit the body style you just created by adding five new properties (changes are in bold):

```
body {  
  background-color: rgb(255,255,255);  
  border: 3px solid rgb(75,75,75);  
  width: 760px;  
  margin-top: 20px;  
  margin-left: auto;  
  margin-right: auto;  
  padding: 15px;  
}
```

The width property constrains the body so that it's just 760 pixels wide: if a visitor's browser window is wider than 760 pixels, then he'll see the background color from the `html` style and a 760-pixel box with the white background of the body tag.




FIGURE 7-18
This web page is bare-bones HTML, with a single style that removes much of the built-in web browser styling. It'll look a lot better with a box model makeover.

The Amazing World of CSS

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt.

NOTE

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est.

Who Knew CSS Had Such Power?

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores.

Not Me!

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem.

Me Neither!

Sed ut perspiciatis unde omnis iste natus error sit voluptatem accusantium doloremque laudantium, totam rem aperiam, eaque ipsa quae ab illo inventore veritatis et quasi architecto beatae vitae dicta sunt explicabo. Nemo enim ipsam voluptatem quia voluptas sit aspernatur aut odit aut fugit, sed quia consequuntur magni dolores eos qui ratione voluptatem sequi nesciunt. Neque porro quisquam est, qui dolorem ipsum quia dolor sit amet, consectetur, adipisci velit, sed quia non numquam eius modi tempora incidunt ut labore et dolore magnam aliquam quaerat voluptatem. Ut enim ad minima veniam, quis nostrum exercitationem ullam corporis suscipit laboriosam.

Copyright 2010, The Lorem Ipsum Corporation

The `margin-top` property adds 20 pixels of space from the browser window's top edge—nudging the `body` tag down just a bit—while the left and right margin settings center the body in the middle of the browser window. “Auto” is just another way of telling a browser, “You figure it out,” and since that auto value is applied to both the left and right margins, a browser simply provides equal space on the left and right side.

NOTE

You could also use the margin shorthand property (page 186) to condense those three lines of margin settings to just one like this:

```
margin: 20px auto 0 auto;
```

Finally, to keep the content inside the <body> from touching the border line, 15 pixels of space are added to the inside of the body by using the padding property—in other words, the image and text is indented 15 pixels from all four edges. Next, you'll add a glow around the box using the box-shadow property.

6. Edit the body style you just created by adding one last property after the border but before the width (changes are in bold):


```
body {  
  background-color: rgb(255,255,255);  
  border: 3px solid rgb(75,75,75);  
  box-shadow: 0 0 15px 5px rgba(44,82,100,.75);  
  
  width: 760px;  
  margin-top: 20px;  
  margin-left: auto;  
  margin-right: auto;  
  padding: 15px;  
}
```

This style adds a glow to the box by creating a 15-pixel shadow placed directly behind the box (the 0 0 part at the beginning indicates that the shadow isn't offset to the left/right or top/bottom; it's simply in the background). The 5px value is the spread value (page 211), and it pushes the shadow out 5 pixels around all four edges. Finally, the rgba value sets the color to a dark blue that's only 75 percent solid (that is, you can see through to the background yellow).

Your style sheet is pretty far along, and you're ready to check the page.

7. Save the file and preview the page in a web browser.

You should see a white box with an image, a bunch of text, and a gray outline with a bluish glow floating in a sea of yellow (see Figure 7-19). The text needs some loving attention. You'll take care of that next.

**FIGURE 7-19**

Setting the left and right margins to auto for any element with a set width centers it. In this case, setting a width for the body and adding `margin-left: auto` and `margin-right: auto` places it smack dab in the center of the browser window. Unfortunately, there's no easy way to center an element vertically (with equal space above and below it) using CSS. There are a few tricks that crafty designers have come up with, though. If you're after vertically centered elements, check out www.vanseodesign.com/css/vertical-centering/.

Adjusting the Space Around Tags

Since the CSS reset styles pretty much stripped the text on this page of all formatting, you'll need to create styles to make the headings and paragraphs look great. You'll start with the `<h1>` tag at the top of the page.

1. **Return to your text editor and the `sidebar.html` file.** Click at the end of the closing brace of the body tag selector, press Enter (Return) to create a new line, and then add the following style:

```
h1 {  
  font-size: 2.75em;  
  font-family: Georgia, "Times New Roman", Times, serif;  
  font-weight: normal;  
  text-align: center;  
  letter-spacing: 1px;  
  color: rgb(133,161,16);  
  text-transform: uppercase;  
}
```

This style uses many of the text-formatting properties discussed in the previous chapter—the top headline is 2.75 ems tall (44 pixels in most browsers) and all uppercase, uses the Georgia font, and has a green color, with a little space between each letter. The `text-align` property makes sure the text is centered in the middle of the box. The real fun is adding a background color to really highlight the headline.

TIP Save the page and preview it in a web browser after each step in this tutorial. That way you'll get a better understanding of how these CSS properties affect the elements they format.

2. **Add one new property to the h1 tag style so that it looks like this (changes in bold):**

```
h1 {  
  font-size: 2.75em;  
  font-family: Georgia, "Times New Roman", Times, serif;  
  font-weight: normal;  
  text-align: center;  
  letter-spacing: 1px;  
  color: #85A110;  
  text-transform: uppercase;  
  background-color: rgb(133,161,16);  
}
```

If you preview the page now, you'll see that the headline has a light green background. When applied to a block-level element like a headline, the background fills the entire horizontal space available (in other words, the color doesn't just sit behind the text "The Amazing World of CSS," but extends all the way to the right edge of the box).

The headline text is a little cramped—the “T” that begins the headline touches the edge of the background. With a little padding, you can fix this.

3. Add another property to the h1 tag style so that it looks like this (changes in bold):

```
h1 {  
  font-size: 2.75em;  
  font-family: Georgia, "Times New Roman", Times, serif;  
  font-weight: normal;  
  text-align: center;  
  letter-spacing: 1px;  
  color: #85A110;  
  text-transform: uppercase;  
  background-color: rgb(133,161,16);  
  padding: 5px 15px 2px 15px;  
}
```

The padding shorthand property provides a concise way to add padding around all four sides of the content—in this case, 5 pixels of space are added above the text, 15 pixels to the right, 2 pixels to the bottom, and 15 pixels to the left.

There’s one other problem with the headline: Because of the padding added to the body tag (see Step 5 on page 226), the headline (including its background color) is indented 15 pixels from the left and right edges of the grey border surrounding the body. The headline would look better if its background color touched the grey border. No problem; negative margins to the rescue.

4. Add one last property to the h1 tag style so that it looks like this (changes in bold):

```
h1 {  
  font-size: 2.75em;  
  font-family: Georgia, "Times New Roman", Times, serif;  
  font-weight: normal;  
  text-align: center;  
  letter-spacing: 1px;  
  color: #85A110;  
  text-transform: uppercase;  
  background-color: rgb(133,161,16);  
  padding: 5px 15px 2px 15px;  
  margin: 0 -15px 20px -15px;  
}
```

Here, the margin shorthand sets the top margin to 0, the right margin to -15 pixels, bottom margin to 20 pixels, and the left margin to -15 pixels. The bottom margin just adds a bit of space between the headline and the paragraph that follows. The next trick is the use of negative values for the left and right margins. As mentioned on page 190, you can assign a negative margin to any element. This property pulls the element out toward the direction of the margin—in this case, the headline extends 15 pixels to the left and 15 pixels to the right, actually expanding the headline and pulling it out over the body tag's padding.

- 5. Now, you'll add some formatting of the <h2> tags.** Add the following style after the h1 tag style:

```
h2 {  
  font-size: 1.5em;  
  font-family: "Arial Narrow", Arial, Helvetica, sans-serif;  
  color: rgb(249,107,24);  
  border-top: 2px dotted rgb(141,165,22);  
  border-bottom: 2px dotted rgb(141,165,22);  
  padding-top: 5px;  
  padding-bottom: 5px;  
  margin: 15px 0 5px 0;  
}
```

This style adds some basic text formatting and a dotted border above and below the headline. To add a bit of space between the headline text and the lines, it puts a small bit of padding at the top and bottom. Finally, the margin property adds 15+ pixels above the headline and 5 pixels below it.

- 6. Save the file and preview the page in a web browser.**

The headlines are looking good (see Figure 7-20). Next, you'll create a sidebar on the right side of the page.

**FIGURE 7-20**

With just a few styles, you can add background colors, control margins throughout the page, and adjust the space between headlines and paragraphs.

Building a Sidebar

Sidebars are common elements in most types of print publications like magazines, books, and newspapers. They compartmentalize and highlight small chunks of information like a resource list, contact information, or a related anecdote. But to be effective, sidebars shouldn't interrupt the flow of the main story. They should, like the name says, sit unobtrusively off to one side, which you can easily make happen with CSS.

1. Return to your text editor and open the *sidebar.html* file.

First, you must isolate the region of the page that makes up the sidebar. The `<div>` tag is the perfect tool. You can enclose any amount of HTML into its own self-contained chunk by wrapping it in a `<div>` tag.

2. Scroll down the page into the HTML and click *before* the first `<h2>` tag (the one with the “NOTE” headline). Then type `<div class="sidebar">`, and press Enter (Return).

This HTML marks the beginning of the sidebar and applies a class to it. You'll create the `.sidebar` class style soon, but first you need to indicate the end of the sidebar by closing the `<div>`.

3. Click after the closing `</p>` tag that immediately follows the `<h2>` tag (this is the `</p>` that appears just before `<h2>Who Knew CSS Had Such Power?</h2>`. Press Enter, and then type `</div>`.

You've just wrapped a headline and paragraph inside a `<div>` tag. Next, you'll create a style for it.

4. Scroll back up to the page's style sheet, and add the following style below the `h2` style you created earlier:

```
.sidebar {  
  width: 30%;  
  float: right;  
  margin: 10px;  
}
```

This style sets the width of the content area (where the text appears) to 30 percent. You don't have to use an absolute value like pixels for widths. In this case, the sidebar's width is 30 percent of the width of the container. The `float` property moves the sidebar to the right side of the box, and the `margin` property adds 10 pixels of space around the sidebar.

If you preview the page in a browser, you'll see that the basic shape and placement of the sidebar are set, but there's one problem: The borders from the `<h2>` tags appear *underneath* the box. Even though the floated sidebar moves the text of the headlines out of the way, floats don't displace borders or backgrounds. Those just appear right under the floated sidebar. One way to fix this problem is to simply add a background color to the sidebar, so you can't see the `h2` borders. (There's another technique, as well, which you'll use in Step 8 on page 236.)

5. Add two other properties to the `.sidebar` style so it looks like this (changes in bold):

```
.sidebar {  
  width: 30%;  
  float: right;  
  margin: 10px;
```

```
background-color: rgb(250,235,199);  
padding: 10px 20px;  
}
```

These properties add a light orangish color to the sidebar and indents the text from the sidebar's edges so it won't touch the borders you're about to add.

6. Add two more properties to the `.sidebar` style so it looks like this (changes in bold):

```
.sidebar {  
width: 30%;  
float: right;  
margin: 10px;  
background-color: rgb(250,235,199);  
padding: 10px 20px;  
border: 1px dotted rgb(252,101,18);  
border-top: 20px solid rgb(252,101,18);  
}
```

Here's an example of the handy technique described on page 205. If you want most of the borders around an element to be the same, you can first define a border for all four edges—in this case a 1 pixel, dotted, orange line around the entire sidebar—and then supply new border properties for the specific edges you want changed—in this example, the top border will be 20 pixels tall and solid. This technique lets you use just two lines of CSS code instead of four (`border-top`, `border-bottom`, `border-left`, and `border-right`).

Next, you'll add rounded corners and a drop shadow to really make this sidebar stand out.

7. Finally, add two more properties to the `.sidebar` style so it looks like this (changes in bold):

```
.sidebar {  
width: 30%;  
float: right;  
margin: 10px;  
background-color: rgb(250,235,199);  
padding: 10px 20px;  
border: 1px dotted rgb(252,101,18);  
border-top: 20px solid rgb(252,101,18);  
border-radius: 10px;  
box-shadow: 5px 5px 10px rgba(0,0,0,.5);  
}
```

The `border-radius` property (page 207) lets you create rounded corners. In this case, the 10-pixel setting provides a prominent-looking curve. The `box-shadow` property here adds a drop shadow below and to the right of the box making it look as though it's floating above the page. You're almost done.

The headline inside the sidebar doesn't look quite right. It uses the same properties as the other `<h2>` tags (because of the `h2` tag style you created in Step 4). The border is distracting and the top margin pushes the headline down too much from the top of the sidebar. Fortunately, you can use a descendent selector to override those properties.

8. After the `.sidebar` style, in the internal style sheet, add a descendent selector:

```
.sidebar h2 {  
  border: none;  
  margin-top: 0;  
  padding: 0;  
}
```

Because of the `.sidebar`, this style is more powerful—that is, it has greater *specificity* as described on page 114—than the basic `h2` style. It erases the border from the original `h2` tag style, along with the top margin and all the padding. However, since this style doesn't have a font size, color, or font family, those properties from the `h2` style still apply—it's the cascade in action!

The page is looking good, but the borders on the `<h2>` tags still run up to and behind the sidebar. That just doesn't look good, but you can fix it easily.

9. Locate the `<h2>` style and add the `overflow` property, like so:

```
h2 {  
  font-size: 1.5em;  
  font-family: "Arial Narrow", Arial, Helvetica, sans-serif;  
  color: rgb(249,107,24);  
  border-top: 2px dotted rgb(141,165,22);  
  border-bottom: 2px dotted rgb(141,165,22);  
  padding-top: 5px;  
  padding-bottom: 5px;  
  margin: 15px 0 5px 0;  
  overflow: hidden;  
}
```

Setting the `overflow` property to `hidden` hides the borders that pass beyond the headline text and under the floating element.

10. Save the file and preview the web page in a browser.

The page should look like Figure 7-21.




FIGURE 7-21

A handful of CSS styles add design elegance to ho-hum HTML. Notice how the floated sidebar both attracts attention and moves it out of the way of the main body of text.

Going Further

To try out your newfound skills, try this exercise on your own: Create a `p` tag style to add some pizzazz to the paragraphs on the page—try out some margin settings, font color, and so on. Next, create a class style for formatting the copyright notice that appears at the bottom of the `sidebar.html` page (called, say, `.copyright`). In this style, add a border above the copyright notice, change its text color, shrink its font size, and change the type to uppercase. (Hint: Use the `text-transform` property discussed on page 163.) After you’ve created the style, add the appropriate class attribute to the `<p>` tag in the HTML.

Adding Graphics to Web Pages

No matter how much you gussy up your text or fiddle with borders and margins, nothing affects the appearance of your site more than the images you add to it. And once again, CSS gives you more image control than HTML ever dreamed of. You can work with graphics in CSS on two fronts: the `` tag and the `background-image` property (which lets you place an image in the background of any tag on a page).

This chapter delves into some of the creative ways you can deploy images with CSS. The best way to learn how to use graphics in CSS is to see them in action, so this chapter has three—count 'em, three—tutorials. By creating a photo gallery web page and using images for overall page styling, you'll be an image-slinging pro in no time.

■ Discovering CSS and the `` Tag

The venerable `` tag has been the workhorse of photo-heavy websites since the beginning of the World Wide Web. Even sites without photos use it to add logos, navigation buttons, and illustrations. While CSS doesn't have any properties specifically aimed at formatting images, you can take advantage of the CSS properties you've already learned to enhance your site's graphics. For example, the `border` property is a quick and simple way to frame an image or unify the look of a gallery of photos. Here's a rundown of the CSS properties most commonly used with images:

- **Borders.** Use one of the many `border` properties (page 202) to frame an image. You'll see an example of this in the tutorial on page 273. Since each border side can be a different color, style, and width, you've got lots of creative options.

- **Padding.** The padding property (page 195) adds space between a border and an image. By putting a little breathing room between a photo and its frame, padding simulates the fiberboard *mat* that’s used in traditional picture frames to surround and offset the image. And by setting a background color, you can even change the color of the mat.
- **Float.** Floating an image moves it to either the left or right edge of the page, or—if the image is contained in another layout element such as a sidebar—to the left or right edge of the image’s containing element. Text and other page elements then wrap around the image. You can even float multiple images to create a flexible, multi-row image gallery. You’ll see an example of this technique in the tutorial on page 272.
- **Margins.** To add space between an image and other page content, use the margin property. When you float an image, the text that wraps around it is usually uncomfortably close to the image. Adding a left margin (for right-floated images) or right margin (for left-floated images) adds space between text and the graphic.

In most cases, you won’t create a style for the `` tag itself. Formatting this tag is using too broad a brush, since it formats *all* images on your page—even those with very different functions, such as the logo, navigation buttons, photos, and even graphic ads. You wouldn’t, after all, want the same black frame around all of those images. Instead, you should use a class style, such as `.galleryImage` or `.logo`, to apply the style selectively.

Another approach is to use a descendent selector to target images grouped together in one section of a page. If you have a gallery of photos, you can place all the photos inside a `<div>` tag with a class name of `gallery`, and then create a style for just the images inside that `<div>`, like this: `.gallery img`.

■ Adding Background Images

The `background-image` property is the key to making visually stunning websites. Learn how to use it and its cousin properties, and you can make your site stand head and shoulders above the rest. For an example of the power of background images, check out www.csszengarden.com (Figure 8-1). The HTML for both the pages shown in Figure 8-1 is exactly the same; the most striking visual differences are accomplished by using different background images. How’s that for CSS power?

If you’ve built a few websites, you’ve probably used an image for the background of a page—perhaps a small graphic that repeats in the background of the browser window creating a (hopefully) subtle pattern. That time-honored HTML method used the `<body>` tag’s `background` attribute. But CSS does the same job better.

NOTE In the next few pages, you’ll meet three background image properties by learning the individual CSS code for each one. Later in the chapter, you’ll learn a shorthand method that’ll save you a lot of typing.





FIGURE 8-1

CSSzengarden.com showcases the power of CSS by demonstrating how you can transform a single HTML file into two utterly different-looking pages. The real secret to making each of the wonderful designs look unique is the extensive use of background images. (In fact, when you look at these pages' HTML code, you'll see there isn't a single tag in it.)



UP TO SPEED

GIFs, JPEGs, and PNGs: The Graphics of the Web

Computer graphics come in hundreds of different file formats, with a mind-numbing assortment of acronyms: JPEG, GIF, TIFF, PICT, BMP, EPS, and so on.

Fortunately, graphics on the Web are a bit simpler. Today's web browsers work with three main graphics formats: GIF, JPEG, and PNG, each of which provides good *compression*. Through clever computer manipulation, compression reduces the graphic's file size so it can travel more rapidly across the Internet. Which you choose depends on the image you wish to add to your page.

GIF (Graphics Interchange Format) files provide good compression for images that have areas of solid color: logos, text, simple banners, and so on. GIFs also offer single-color transparency, meaning that you can make one color in the graphic disappear, permitting the background of a web page to show through part of the image. In addition, GIFs can include simple animations.

A GIF image can contain a maximum of only 256 shades, however, which generally makes photos look *posterized* (patchy and unrealistically colored, like a poster). In other words, that radiant sunset photo you took with your digital camera won't look so good as a GIF. (If you don't need to animate an image, the PNG8 format discussed later is a better choice than GIF.)

JPEG (Joint Photographic Experts Group) graphics, on the other hand, pick up where GIFs leave off. JPEG graphics can contain millions of different colors, making them ideal for photos. Not only do JPEGs do a better job on photos, they also compress multicolored images much better than GIFs, because the JPEG compression algorithm considers how the human eye perceives

different adjacent color values. JPEG is the format many cameras use to save photos. When your graphics software saves a JPEG file, it runs a complex color analysis to lower the amount of data required to accurately represent the image. On the downside, JPEG compression makes text and large areas of solid color look blotchy.

Finally, the **PNG** (Portable Network Graphics) format includes the best features of GIFs and JPEGs, but you need to know which version of PNG to use for which situation. PNG8 is basically a replacement for GIF. Like GIF, it offers 256 colors and basic one-color transparency. However, PNG8 usually compresses images to a slightly smaller file size than GIF, so PNG8 images download a tiny bit faster than the same image saved in the GIF format. In other words, use PNG8 over GIFs.

PNG24 and PNG32 (which is basically PNG24 with alpha transparency) offer the expanded color palette of JPEG images, without any loss of quality. This means that photos saved as PNG24 or PNG32 tend to be higher quality than JPEGs. But before you jump on the PNG bandwagon, JPEG images do offer very good quality and a *much* smaller file size than either PNG24 or PNG32. In general, JPEG is a better choice for photos and other images that include lots of colors.

Finally, PNG32 offers one feature that no other format does: 256 levels of transparency (also called *alpha* transparency), which means that you can actually see the background of a web page through a drop shadow on a graphic, or even make a graphic that has 50 percent opacity (meaning you can see through it) to create a ghostly translucent effect.

The background-image property adds a graphic to the background of an element. To put an image in the background of a web page, you can create a style for the <body> tag:

```
body {
    background-image: url(images/bg.gif);
}
```

The property takes one value: the keyword `url`, followed by a path to the graphic file enclosed in parentheses. You can use an absolute URL like this—`url(http://www.cosmofarmer.com/image/bg.gif)`—or a document- or root-relative path like these:

```
url(../images/bg.gif) /* document-relative */
url(/images/bg.gif) /* root-relative */
```

As explained in the box on page 244, document-relative paths provide directions in relation to the style sheet file, *not* the HTML page you’re styling. These will be one and the same, of course, if you’re using an internal style sheet, but you need to keep this point in mind if you’re using an *external* style sheet. Say you’ve got a folder named *styles* (containing the site’s style sheets) and a folder named *images* (holding the site’s images). Both these folders are located in the site’s main folder along with the home page (Figure 8-2). When a visitor views the home page, the external style sheet is also loaded (Step 1 in Figure 8-2). Now, say the external style sheet includes a style for the `<body>` tag with the background image property set to use the graphic file *bg.gif* in the images folder. The document-relative path would lead from the style sheet to the graphic (Step 2 in Figure 8-2). In other words, the style would look like this:

```
body {
  background-image: url(../images/bg.gif);
}
```

This path breaks down like this: `../` means “go up one level” (that is, up to the folder containing the *styles* folder); `images/` means “go to the images folder”; and `bg.gif` specifies that file.




FIGURE 8-2

Document-relative paths are calculated in relation to the style sheet, not the web page being styled.

In the examples so far, the path isn’t enclosed in quotes as in HTML, but quotes are fine, too. In CSS, all three of the following code lines are kosher:

```
background-image: url(images/bg.gif);  
background-image: url("images/bg.gif");  
background-image: url('images/bg.gif');
```

UP TO SPEED

URL Types

In CSS, you need to specify a *URL* when you add a background image or attach an external style sheet by using the `@import` method (page 42). A URL or *Uniform Resource Locator* is a path to a file located on the Web. There are three types of paths: *absolute path*, *root-relative path*, and *document-relative path*. All three simply indicate where a web browser can find a particular file (like another web page, a graphic, or an external style sheet).

An absolute path is like a postal address—it contains all the information needed for a web browser located anywhere in the world to find the file. An absolute path includes `http://`, the hostname, and the folder and name of the file. For example: `http://www.cosmofarmer.com/images/bluegrass.jpg`.

A *root-relative* path indicates where a file is located relative to a site's top-level folder—the site's root folder. A root-relative path doesn't include `http://` or the domain name. It begins with a `/` (slash) indicating the root folder of the site (the folder the home page is in). For example `/images/bluegrass.jpg` indicates that the file `bluegrass.jpg` is located inside a folder named `images`, which is itself located in the site's top-level folder. An easy way to create a root-relative path is to take an absolute path and strip off the `http://` and the host name.

A *document-relative* path specifies the path from the current document to the file. When it comes to a style sheet, this means *the path from the style sheet to the specified file*, not the path from the current web page to the file.

Here are some tips on which type to use:

- If you're pointing to a file that's not on the same server as the style sheet, you *must* use an absolute path. It's the only type that can point to another website.
- Root-relative paths are good for images stored on your own site. Since they always start at the root folder, you can move the style sheet around without affecting the path from the root to the image on the site. However, they're difficult to use when first building your designs: You can't preview root-relative paths unless you're viewing your web pages through a web server—either your web server out on the Internet or a web server you've set up on your own computer for testing purposes. In other words, if you're just opening a web page off your computer using the browser's File→Open command, then you won't see any images placed using root-relative paths.
- Document-relative paths are the best when you're designing on your own computer without the aid of a web server. You can create your CSS files and then review them in a web browser simply by opening a web page stored on your hard drive. These pages will work fine when you move them to your actual, living, breathing website on the Internet, but you'll have to re-write the URLs to the images if you move the style sheet to another location on the server.

■ Controlling Repetition

If you use the `background-image` property by itself, the graphic always tiles, filling up the entire background of a web page. Fortunately, you can use the `background-repeat` property to specify how (or if at all) an image tiles:

```
background-repeat: no-repeat;
```

The property accepts four values: `repeat`, `no-repeat`, `repeat-x`, and `repeat-y`:

- **repeat** is the normal setting for background images that you want to display from left to right and top to bottom until the entire space is filled with a graphic (Figure 8-3).




FIGURE 8-3

Be careful when tiling images in the background of a web page. Choose an image without a lot of contrast that tiles seamlessly (left). An image with too much contrast (right), makes text hard to read.

- **no-repeat** displays the image a single time, without tiling or repetition. It's a very common option, and you'll frequently use it when placing images into the background of tags other than the body. You can use it to place a logo in the upper corner of a page or to use custom graphics for bullets in lists, to name a couple. (You'll see the bullet example in action in the tutorial on page 286.)
- **repeat-x** repeats an image horizontally along the x-axis (the horizontal width of the page, if your geometry is rusty). It's perfect for adding a graphical banner to the top of a web page (Figure 8-4, left) or a decorative border along the top or bottom of a headline. (See page 299 in the tutorial for an example of this effect.)
- **repeat-y** repeats an image vertically along the y-axis (the vertical length of the page). You can use this setting to add a graphic sidebar to a page (Figure 8-4, right) or to add a repeating drop shadow to either side of a page element (like a sidebar).

■ Positioning a Background Image

Placing and tiling a background image is just half the fun. With the `background-position` property, CSS lets you control the exact placement of an image in a number of ways. You can specify both the horizontal and vertical starting points for a graphic in three ways—keywords, exact values, and percentages.




FIGURE 8-4
Add graphic backgrounds to the banners and sidebars of a page by taking advantage of the tiling control offered by the `repeat-x` (left) and `repeat-y` (right) options.

Keywords

You get two sets of keywords to work with. The first one controls the three horizontal positions—`left`, `center`, `right`—and the second controls the three vertical positions—`top`, `center`, `bottom` (Figure 8-5). Suppose you want to place a graphic directly in the middle of a web page. You can create a style like this:

```
body {  
    background-image: url(bg_page.jpg);  
    background-repeat: no-repeat;  
    background-position: center center;  
}
```


To move that graphic to the top-right corner, just change the background position to this:

```
background-position: right top;
```


NOTE If you've decided to tile an image (by setting `background-repeat` to one of the values listed in the previous section), then the `background-position` property controls the *starting* point of the first tile. So, for example, if you use the `repeat` option, you'll still see the entire background filled by the image. It's just that the position of the *first* tile changes based on which `background-position` setting you used.

Keywords are really useful when you want to create vertical or horizontal banners. If you wanted a graphic that's centered on a page and tiled downwards in order to create a backdrop for content (Figure 8-6, left), then you'd create a style like this:

```
body {
  background-image: url(background.jpg);
  background-repeat: repeat-y;
  background-position: center top;
}
```



Likewise, using the bottom, center, or top keywords, you can position a horizontally repeating image by using repeat-x (Figure 8-4, left) in a particular place on the page (or within a styled element).



TIP You can actually add a background image to both the `<html>` and `<body>` tags. If you tile both images horizontally and place the `<body>` tag's image at the top and the `<html>` tag's image on the bottom, you can achieve the effect of two stripes cutting across the top and bottom of the page—no matter how tall the page is. And it works in all current browsers, even IE 6!

BROWSER BUG

Bottoming Out

When displaying an image in the background of a web page, most browsers don't always vertically position the image in the way you'd expect. For example, if you set the vertical position to `bottom`, the image doesn't always appear at the bottom of the browser window. This happens when the content on a page is shorter than the browser window is tall.

If the web page has only a couple of paragraphs of text and it's displayed on a really large monitor, most browsers treat the "bottom" as the bottom of the last paragraph, not the bottom of the browser window. If you run into this annoyance, then just add this style to your style sheet:

```
html { height: 100%; }
```


Precise Values

You can also position background images by using pixel values or ems. You use two values: one to indicate the distance between the image's left edge and the container's left edge, and another to specify the distance between the image's top edge and the style's top edge. (Put another way, the first value controls the horizontal position, the second value controls the vertical position.)

Say you want custom bullets for a list. If you add a background image to the `` tag, the bullets often don't line up exactly (see Figure 8-7, top). So you can just nudge the bullets into place by using the `background-position` property (Figure 8-7, bottom). If the list would look better with, say, the bullets 5 pixels farther to the right and 8 pixels farther down, then add this declaration to the style defining the background image:

```
background-position: 5px 8px;
```

You can't specify distances from the bottom or right by using pixel or em measurements, so if you want to make sure an image is placed in the exact bottom-right corner of the page or a styled element, then use keywords (`bottom right`) or percentages, as discussed next. However, you can use negative values to move an image off the left edge or above the top edge, hiding that portion of the image from view. You may want to use negative values to crop out part of a picture. Or, if the background image has lots of extra white space at the top or left edge, you can use negative values to eliminate that extra space.



Percentage Values

Finally, you can use percentage values to position a background image. Using percentages in this manner is tricky, and if you can achieve the effect you're after with the keyword or precise values discussed previously, then use them. But you have to use percentages to position an element in a spot that's proportional to the width of an element. For example, if you want to place a graphic three-quarters of the way across a headline and you don't know the width of the element.

As with pixel or em values, you supply two percentages: one to indicate the horizontal position and the second to indicate the vertical position. What the percentage is measuring is a little tricky. In a nutshell, a percentage value aligns the specified percentage of the image with the same percentage of the styled element. What?

The best way to understand how percentage values work is to look at a few examples. To position an image in the middle of a page (like the one shown in the center of Figure 8-8) you'd write this:

```
background-position:50% 50%;
```

This declaration places the point on the image that's 50 percent from its left edge directly on top of the point that's 50 percent from the left edge of the page (or whatever element you've styled with the background image). The declaration also aligns the point on the image that's 50 percent from its top with the point that's 50 percent from the top edge of the page or styled element. In other words, the center of the image is aligned with the center of the element. This means that, when using percentages, the exact point on the image that's being aligned can be a moving

target. (That’s because your styled element’s positioning percentages can change if your visitors resize their browsers.)

NOTE

Positioning an image vertically in the background of a page by using percentages won’t necessarily put the image in the correct spot if the page content doesn’t fill the entire height of the browser window. See the box on page 248 for the solution to this problem.

As with pixel and em values, you can specify negative percentage values, although the results can be hard to predict. You can also mix and match pixel/em values with percentage values. For example, to place an image that’s 5 pixels from the element’s left edge, but placed in the middle of the element’s height, you could use this:

```
background-position: 5px 50%;
```

NOTE

Although background images can raise the visual quality of your web pages, they usually don’t show up if your visitor prints the page. Most browsers *can* print out the backgrounds, but it usually requires extra work on your visitor’s part. If you plan to have your visitors print pages from your site, then you may want to keep using the tag to insert mission-critical images like your site logo or a map to your store.




FIGURE 8-8

Each of the four images pictured here have been positioned on this web page (represented by the large black box) by using percentage values. When using percentage values, first identify the “anchor point” on the image: 50% 50%, for example, is the center of the middle image. Next, identify the 50/50 point on the page itself: again, that would be directly in the center of the page. That spot is where the image’s anchor point gets placed. The three other images are all positioned in the same way.

Fixing an Image in Place

Normally, if there’s a background image on a web page and the visitor has to scroll down to see more of the page, the background image scrolls as well. As a result,

any pattern in the background of the page appears to move along with the text. Furthermore, when you have a nonrepeating image in the background, it can potentially scroll off the top of the page out of view. If you've placed the site's logo or a watermark graphic in the background of the page, then you may *not* want it to disappear when visitors scroll.

The CSS solution to such dilemmas is the background-attachment property. It has two options—`scroll` and `fixed`. `Scroll` is the normal web browser behavior; that is, it scrolls the background image along with the text and other page content. `Fixed`, however, keeps the image in place in the background (see Figure 8-9). So if you want to place your company's logo in the upper-left corner of the web page, and keep it there even if the viewer scrolls, then you can create a style like this:

```
body {
  background-image: url(images/logo.gif);
  background-repeat: no-repeat;
  background-attachment: fixed;
}
```

The `fixed` option is also very nice when using a repeating, tiled background. When you have to scroll, the page's text disappears off the top, but the background doesn't move: The page content appears to float gracefully above the background.




FIGURE 8-9

Looking for a way to nail down a site logo (like the CosmoFarmer 2.0 image) so when viewers scroll down the page the logo stays in place? Using the fixed option for the background-attachment property, you can lock a background image in place. That way, even if the page is very long and the visitor has to scroll down, the image remains visible on the web page (bottom).

Defining the Origin and Clipping for a Background

CSS3 adds the ability to tell a browser where the background image should begin in relation to the border, padding, and content of an element. For example, normally when you tile an image, it starts in the upper-left corner of the padding of an element (see the top, middle image in Figure 8-10). However, you can reposition that image's starting point, using the `background-origin` property. It takes one of three values:

- **border-box** places the image in the upper-left corner of the area assigned to the border (top-left in Figure 8-10).
- **padding-box** places the image in the upper-left corner of the area assigned to the padding (top-middle in Figure 8-10). This is normally where a browser places a background image.
- **content-box** places the image in the upper-left corner of the area assigned to the content (top-right in Figure 8-10).

Of course, this setting doesn't matter if there's neither a border nor any padding around an element; in addition, the effect can be very subtle, especially if you have a seamlessly tiling pattern.

NOTE

Neither the `background-origin` nor the `background-clip` properties work in Internet Explorer 8 and earlier. Since IE 8 is still a very popular browser, use these properties with caution.

However, it can be noticeable if you're not repeating an image. For example, if you choose the `no-repeat` option (page 245) and the background image appears only a single time, you could place that image in the upper-left corner of the content area (inside any padding) like this:

```
background-image: url(logo.png);  
background-repeat: no-repeat;  
background-origin: content-box;
```

In addition, the `background-origin` property can be used effectively with another new property—`background-clip`. The `background-clip` property limits the area where the background image appears. Normally, background images fill the entire area of an element including behind borders and padding areas (bottom-left in Figure 8-10). However, you can specify where the image appears with one of three values:

- **border-box** lets the image appear behind the content all the way behind any borders. You'll notice this only if you have borders with visible gaps like a dashed line (bottom-left in Figure 8-10). This is normally what browsers do, so there's no real reason to use this setting.
- **padding-box** limits any background to just the padding area and the element's content (bottom-middle in Figure 8-10). This is useful if you have a border that's dotted or dashed and you don't want the image to appear in the border's gaps.
- **content-box** limits the background to just the content area. The padding and the area behind the border will be free of any image (bottom-right in Figure 8-10).

By combining `background-origin` and `background-clip`, you can make sure that an image begins in the upper-left of the content area and appears only behind content like this:

```
background-origin: content-box;
background-clip: content-box;
```



Scaling Background Images

Unlike the HTML `` tag, you can't normally resize a background image. It's placed in the background at the size you created it. However, CSS3 adds a `background-size` property, which lets you control the size of a background image. You have the option of using values or keywords to set the size:

- Supply a height and width value to set the size of the image. You can use an absolute value like a pixel value:

```
background-size: 100px 200px;
```

This code sets the background image to 100 pixels wide and 200 pixels tall. You can also set the value of just the width or height and set the other to `auto`:

```
background-size: 100px auto;
```

In this case, the background image is 100 pixels wide, and the browser automatically sets the height to keep the aspect ratio of the image intact (so it isn't distorted). You can also use percentage values. If you want the image to scale to completely fit the background, you can use 100% for both settings (Figure 8-11, left):

```
background-size: 100% 100%;
```

- The contain keyword forces the image to resize to fit while maintaining the aspect ratio of the image (Figure 8-10, middle). Depending on the shape of the image and the element, the image is stretched to fit either the width or height of the element.

```
background-size: contain;
```

- The cover keyword forces the width of the image to fit the width of the element and the height of the image to fit the height of the element. This usually distorts the image by either squishing or stretching it to fit the element (Figure 8-10, right).

```
background-size: cover;
```

The background-size property almost always ends up resizing the original image: if the image is smaller than the elements, the browser scales the image up, usually resulting in noticeable pixilation and degradation of the image (as with the background images in Figure 8-11).

TIP Using the background-size property can be especially helpful when you're working with elements that are sized using percentages, such as the responsive designs discussed in Chapter 14. For example, if you put an image into the background of a banner that's 960 pixels when viewed on a desktop monitor but shrinks down to 480 when viewed on a phone, you can place a large background image in the banner and use this setting:

```
background-size: 100% auto;
```

This forces the web browser to resize the image to fit as the banner shrinks to a thinner size.



FIGURE 8-11

The background-size property is the only way to change the size of a background image. Keep in mind that while most browsers understand this property, the still widely used Internet Explorer 8 doesn't, so use it with care (or, if you don't care about IE 8, then use it with reckless abandon).

■ Using Background Property Shorthand

As you can see from the examples in the previous section, to really take control of background images you need to harness the power of several different background properties. But typing out `background-image`, `background-attachment`, and so on again and again can really take its toll on your hands. But there's an easier way—the background shorthand property.

You can actually bundle all the background properties (including the `background-color` property) into a single line of streamlined CSS. Simply type `background` followed by the values for `background-image`, `background-position`, `background-repeat`, `background-attachment`, and `background-color`. The following style sets the background to white and adds a nonrepeating fixed background image smack dab in the middle of the page:

```
body {  
    background: url(bullseye.gif) center center no-repeat fixed #FFF;  
}
```

You don't need to specify all the property values either. You can use one or any combination of them. For example: `background: yellow` is the equivalent of `background-color: yellow`. Any property value you leave out simply reverts to its normal behavior, so say you specify only an image:

```
background: url(image/bullseye.gif);
```

That's the equivalent of this:

```
background: url(image/bullseye.gif) scroll left top repeat transparent;
```

This behavior of resetting non-defined values to their default values can lead you to some unexpected results. For example, say you add these two declarations to a style:

```
background-color: yellow;  
background: url(image/bullseye.gif) no-repeat;
```

You may expect to see a single bull's-eye image sitting atop a yellow background color. But you won't, because a browser resets the `background-color` to transparent (invisible) when it encounters the background property with no color specified. To get around this predicament, you need to specify the `background-color` second, like this:

```
background: url(image/bullseye.gif) no-repeat;  
background-color: yellow;
```

In addition, when multiple styles apply to the same element, you can inadvertently end up wiping out background images. For example, say you want to add a background image to every paragraph on a page, so you create a style like this:

```
p {  
    background: url(icon.png) left top no-repeat rgb(0,30,0);  
}
```

You then decide you'd like the first paragraph after every Heading 2 to have a blue background, so you create this:

```
h2 + p {
  background: blue;
}
```

This second style uses the shorthand, which resets all the other background properties to their defaults. In the case of an image, the default is no image at all, so rather than simply adding a blue background to the paragraph and leaving the image in place, this style actually erases the image!

In other words, the background shorthand property can help you write less code, but it can also get you into trouble, so just keep this behavior in mind.

NOTE

You can use the newer CSS3 background properties—`background-size`, `background-origin`, and `background-clip`—in the background shorthand, but it's not necessarily a good idea. First, since IE 8 doesn't understand those properties, adding them to the background declaration will make IE 8 skip the other valid properties (in other words, it'll ignore all of your background settings). In addition, you need to put the properties in a specific order, and no browser (as of this writing) can handle both the `background-position` and `background-size` values together in a single declaration. To get around this, you can create one declaration with the common and accepted shorthand properties—`image`, `position`, `repeat`, `placement`, and `color`—and then add separate declarations after the shorthand declaration for the new CSS3 properties.

FREQUENTLY ASKED QUESTION

Finding Free Imagery

I'm not an artist. I can't draw, can't paint, don't even own a digital camera. Where can I find artwork for my site?

Thank goodness for the Web. It's the one-stop shop for creative geniuses who couldn't paint themselves into a corner if they tried. There are plenty of pay-to-download sites for stock photos and illustrations, but there are also quite a few completely free options. For photos, check out Morgue File (www.morguefile.com), which despite the grisly name has many wonderful photos supplied free of charge by people who love to take pictures. Stock.xchng (www.sxc.hu) is yet another excellent photographic resource. Open Photo (<http://openphoto.net>) also supplies images based on Creative Commons licenses, and you can use the search engine on the Creative Commons website to find images (and video and music) that can be used in personal and commercial projects: <http://search.creativecommons.org>. In addition, you can use Flickr (www.flickr.com/creativecommons) and Picasa Web Albums (<http://picasaweb.google.com>) to search for images that have

a Creative Commons license applied to them. (Although they don't cost money, not all photos on these sites can be used in commercial projects. Make sure you read the fine print for any photo you wish to use.)

If you're looking for bullets to add to lists, icons to supercharge your navigation bar, or patterns to fill the screen, there are plenty of sites to choose from. Some Random Dude (no, really, that's the name of the website) offers a set of 121 icons free of charge: www.somerandomdude.com/work/sanscons/. And if you're looking for interesting tiling patterns, check out the patterns on these sites: ColourLovers.com (www.colourlovers.com/patterns), Pattern4u (www.kollermedia.at/pattern4u), and Squidfingers (<http://squidfingers.com/patterns>). Or make your own tiled backgrounds with these online pattern creators: BgPatterns (<http://bgpatterns.com>), Stripe Generator 2.0 (www.stripegenerator.com), and PatternCooler (www.patterncooler.com).

■ Using Multiple Background Images

While one background image is fine, being able to layer multiple images in a background has its uses. For example, say you want to add a background image to a sidebar to make it look like a scroll (Figure 8-12). If you simply place a single image in the background, it might work at first (top-left in Figure 8-12), but if you add a lot of text inside that sidebar, it won't look so good (top-right in Figure 8-12). That's because the image is one size and it won't grow or shrink to accommodate the size of the sidebar.

Fortunately, CSS3 lets you add multiple images to the background of an element. In the scroll example, you can use three background images: one for the top of the scroll, one for the bottom of the scroll, and one for its text area. That last image is a seamlessly tiling image, so as the sidebar gets taller, the image simply tiles to fit the space.

Of course, you can use multiple images for simpler tasks as well. For example, say you want to add a colorful, richly textured image to the background of an element and you also add a two-color logo. As discussed in the box on page 242, JPEG is a better format when an image has lots of colors, while PNG8 is better for areas of solid color like a logo. In this case, you can have the best of both worlds by using a JPEG for the colorful background and a PNG8 for the logo.

For multiple background images, simply use the `background-image` property with a comma-separated list of images like this:

```
background-image: url(scrollTop.jpg),  
                 url(scrollBottom.jpg),  
                 url(scrollMiddle.jpg);
```

NOTE

In this example code, each URL is listed on its own line, but you don't have to do it that way. You could type this all out in one single (really long) line. However, most designers find it easier to read if you place each image on its own line and use spaces (or tabs) to indent the following lines to line up. Just keep in mind that you need a comma after each image specified, except the last, which requires the usual semicolon necessary to end a declaration.

Because background images normally tile, you'll usually need to include a `background-repeat` property as well (if you don't then the images would just tile one on top of the other hiding all images underneath.) You can add other background properties as well, with a similarly comma-separated set of values like this:

```
background-repeat: no-repeat,  
                 no-repeat,  
                 repeat-y;
```




FIGURE 8-12

Note that multiple background images don't work in Internet Explorer 8. See the box on page 259 for one way to use multiple background images with IE 8.

When using multiple values like this, the first value (no-repeat in this example) goes with the first image listed in the background-image property (*scrollTop.png*); the second goes with the second image listed, and so on. Because this can get confusing quickly, many web designers use the shorthand method to specify multiple images, like this:

```
background: url(scrollTop.jpg) center top no-repeat,
           url(scrollBottom.jpg) center bottom no-repeat,
           url(scrollMiddle.jpg) center top repeat-y;
```

NOTE Multiple background images lay on top of one another, like layers in an image-editing program. The order you list the background images in determines which image appears on top. The first image listed is on the element's top layer, the second the second layer, and the last on the bottom layer. In the preceding example code, the top of the scroll (*scrollTop.jpg*) is above the bottom of the scroll (*scrollBottom.jpg*), which in turn sits above the text area of the scroll (*scrollMiddle.jpg*).

POWER USERS' CLINIC

Faking Multiple Backgrounds

Internet Explorer 8 still is widely used (thanks to Windows XP). But because IE 8 doesn't support multiple images, you may feel like you should steer clear of them. There are, however, a couple of ways to fake multiple backgrounds. The simplest is to add individual background images to overlapping elements. For example, you can achieve the same scroll effect shown in Figure 8-12 by adding the middle, text area of the scroll to the background of the `<div>` tag, which creates that sidebar region. Then, add the top of the scroll to the background of the first element in the sidebar—in this case it's an `<h2>` tag with the text "Announcements." Finally, add the image of the bottom of the scroll to the bottom of the last element in the sidebar—in this case, an unordered list. The headline and the unordered list are both inside the sidebar div, and this lays on top of the `<div>`.

Another technique uses CSS generated content (page 595). Generated content is a way to add content before and/or after an element. You can add text, but you can also add images as well. The generated content sits above the element, so in the scroll example, you could add the top of the scroll to the `:before` pseudo class and the bottom of the scroll to the `:after` pseudo class, like this:

```
.sidebar {  
    background: url(scrollMiddle.jpg) center  
    top repeat-y;  
}  
.sidebar:before {  
    content: url(scrollTop.jpg);  
}  
.sidebar:after {  
    content: url(scrollBottom.jpg);  
}
```

To move the images around so they're not at the top or bottom of the element, you'll need to learn how to use absolute positioning so you can move the generated content around. You'll learn about absolute positioning in depth in Chapter 15. CSS3 multiple backgrounds let you add as many background images as you like. Using generated content, you're limited to just three images: the element's background and its before and after pseudo-classes. You'll use this generated content method to create multiple background images in the tutorial on page 290.

Utilizing Gradient Backgrounds

Gradients—smooth transitions of color from blue to red or black to white are common staples of any image-editing program. Creating subtle shifts from one similar color to another creates a kind of misty quality; Apple uses gradients on buttons and other user interface elements in their OS X and iPhone software. It used to be that you had to open Photoshop and create a huge image file with the gradient you were after. Now you can let the browser create gradients for you.

CSS3 supports background gradients—basically, images created on the fly by a web browser. In fact, you use the usual background-image property to create the gradient. You have several types of gradients to choose from.

Linear Gradients

The most basic type of gradient is a linear gradient. It moves in a straight line from one edge of an element to another, transitioning from one color to another (see Figure 8-13). In essence, you specify where to begin the gradient (at an element’s edge), the beginning color, and the ending color. For example, to create a gradient that starts out with black on the left edge of an element and then transitions to white on the far right of the element, you’d write this:

```
background-image: linear-gradient(left,black,white);
```

NOTE The syntax for linear gradients has changed many times in its history. Browsers have changed the syntax for linear gradients since this book was first written. The most important change is that the direction, for example “top left,” needs a “to” before it like this: `linear-gradient(to top left, black, white)`. You can read more about this new syntax at <https://developer.mozilla.org/en-US/docs/Web/CSS/linear-gradient>. Using an online gradient creation tool (like Colorzilla, which was discussed on page 269) is the best way to create cross-browser compatible gradients.

You can create a gradient by using any CSS color value (page 54), such as keywords like white or black, hexadecimal values like #000000, RGB values like `rgb(0,0,0)`, and so on. To identify the starting position, you can use left, right, top, or bottom. In fact, if you want a gradient that moves diagonally across the element, you can combine keywords. For example, to draw a gradient that travels from the top-left corner to the bottom-right corner changing from black to white, write this:

```
background-image: linear-gradient(top left,black,white);
```



FIGURE 8-13

Linear gradients let you bypass the old method of adding gradients to the background of an element: create the gradient as a graphic in Photoshop or Fireworks, and then use the background-image property to place that graphic in the background of the element.

You're not limited to keywords either. You can specify a degree value that specifies the direction of the gradient. Degrees are written with a number from 0 to 360 followed by `deg` like this: `0deg` (Figure 8-14). You'll need to do some trial and error to get the effect you want, but here's roughly how it works: `0deg` means start on the left and move to the right, whereas `45deg` begins in the bottom-left corner and moves the gradient 45 degrees up toward the top-right. For example, the gradient created in the bottom-left image in Figure 8-13 uses this declaration:

```
background-image: linear-gradient(45deg, rgb(0,0,0), rgb(204,204,204));
```

On a perfectly square element, `45deg` represents the bottom-left corner and is the same as using the keyword `bottom-left`. In other words this:

```
background-image: linear-gradient(45deg, rgb(0,0,0), rgb(204,204,204));
```

Is the same as this:

```
background-image: linear-gradient(bottom left, rgb(0,0,0), rgb(204,204,204));
```

However, on a rectangular image, these two declarations won't create the same gradients. That's because a browser draws an imaginary line through the middle of the element. The angle you specify is the angle of that line. For example, in the wide, rectangular element in Figure 8-14, `bottom`, a line drawn at 45 degrees through the middle doesn't actually run from the bottom-left to the top-right of the element. It runs somewhere between the left and middle of the bottom of the element up to a point between the middle and right edge at the top.




FIGURE 8-14

The degree value you supply for a linear gradient is used to create a line that passes through the middle of an imaginary point in the center of the element. The gradient is drawn along this line. The value dictates both where the gradient starts and the slope of the gradient.

■ COLOR STOPS

The gradients you've seen so far use only two colors, but you can add as many as you like. The additional colors are called *color stops*, and they let the background transition from one color to a second color, then from that second color to a third color, and so on, until the final color ends the gradient. To add color stops, simply add more color values to the gradient. For example, the bottom-right image in Figure 8-13 contains three colors: black to white to black:

```
background-image: linear-gradient(left, black, white, black);
```

Of course, you can use any color values (expressed as keywords, hexadecimal, or RGB) and even mix and match them, so you can even write the preceding line of code like this:

```
background-image: linear-gradient(left, black, rgb(255,255,255), #FFFFFF,  
HSL(0,0,0%));
```

Web browsers evenly spread out the colors, so in this example the far left starts out black; the background of the middle of the element is white; and then the far right of the element is black. However, you can place the different color stops at more specific locations in the background by adding a second value after the color.

TIP

You can get some really wild effects if you add the `background-position` property to an element with a gradient background. Essentially, you can change what the browser considers to be the starting point for the gradient. Try it out.

For example, say you want to start at a deep red, then quickly ramp up to a burnt orange about 10 percent into the element, stay at that orange color for most of the element, and then quickly ramp back down to deep red, like the top image in Figure 8-15. To do this, you'd use four color stops—red, orange, orange and red—and specify where the two white stops should be positioned:

```
background-image: linear-gradient(left, #900, #FC0 10%, #FC0 90%, #900);
```

Notice that the 10% applies to the second color (the orange): this tells the browser that it needs to get to this color at 10 percent of the width of the element. Likewise, the 90% indicates that the browser needs to stay at that orange color until it's 90 percent across the element, and then begin the transition to the deep red at the far right of the element.

NOTE

You don't have to use percentages to place color stops. You can use pixels or ems as well. However, percentages are more flexible and adapt as the width or height of an element changes. One exception is the repeating linear gradients discussed on page 265. Pixel values for stops are very useful for creating these types of tiled gradients.

You don't need to use any values for the first or last color, since the browser assumes that the first color starts at 0% and the last color ends at 100%. However, if you wanted to keep a solid starting color further into the element, you could provide a

value after the first color. For example, the bottom image in Figure 8-15 is created with this declaration:

```
background-image: linear-gradient(left, #900 20%, #FC0 30%, #FC0 70%, #900 80%);
```

Notice that the first color—#900—also has a position of 20%. This means that the first 20 percent of the element (from left to right) should be a solid red color. Then, at the 20 percent point, the gradient should begin transitioning to the orange color at 30 percent.



FIGURE 8-15

You can specify where the color stops appear in a linear gradient. In the top example, a dark red color transitions quickly from the left to an orange color at 10 percent of the width of the element. To create a large solid color area in the middle, you need two color stops with the same color value. Basically a gradient from one color to the same color is no gradient at all.



■ VENDOR PREFIXES AND INTERNET EXPLORER SUPPORT

As you read in the box on page 209, many of the newer CSS properties require a vendor prefix before the property name: `-webkit-` for Chrome and Safari, `-moz-` for Firefox, and `-o-` for Opera. This is true for gradients. Unfortunately, you have to write out declarations for each of the browsers. In other words, to get the simple gradient on page 262 to work in the different browsers, you have to write this code:

```
background-image: -webkit-linear-gradient(left,black,white);
background-image: -moz-linear-gradient(left,black,white);
background-image: -o-linear-gradient(left,black,white);
background-image: linear-gradient(left,black,white);
```

That's right, four times the work. To make matters worse, gradients are not supported in Internet Explorer 9 and earlier. If you do choose to use gradients, then you should provide a back-up color for IE 9 and earlier. Find a solid color that matches the general tone of your gradient and declare it first, followed by the gradient declarations, like this:

```
background-color: #FC0;
background-image: -webkit-linear-gradient(left, #900, #FC0, #900);
background-image: -moz-linear-gradient(left, #900, #FC0, #900);
background-image: -o-linear-gradient(left, #900, #FC0, #900);
background-image: linear-gradient(left, #900, #FC0, #900);
```

IE 9 will apply the background color, and since it doesn't understand linear gradients, it will skip the other declarations. Other browsers will apply the background color, but also create a gradient that covers the background color. If you're using RGBA colors with some level of transparency, then you won't want the background color to show through. In this case, use the background shorthand property instead, and the `background-color` will be overridden (thanks to the peculiar behavior of the background shorthand property discussed on page 255). So you can use this code for RGBA colors:

```
background-color: #FC0;
background: -webkit-linear-gradient(left, rgba(153,0,0,.5), #FC0,
    rgba(153,0,0,.5));
background: -moz-linear-gradient(left, rgba(153,0,0,.5),
    #FC0,rgba(153,0,0,.5));
background: -o-linear-gradient(left, rgba(153,0,0,.5), #FC0,
    rgba(153,0,0,.5));
background: linear-gradient(left, rgba(153,0,0,.5), #FC0, rgba(153,0,0,.5));
```

NOTE

As you can see, there's a lot of code involved in creating gradients. In addition, older versions of WebKit (Safari on Macs and iOS, and Android browsers) follow a different syntax entirely for linear gradients. Because of this, you'll probably want to use the online gradient creator tool discussed on page 269. It'll make your gradient-creation process a whole lot easier.

Repeating Linear Gradients

Normally, a linear gradient fills the entire element with the first color at one point and the last color at the opposite edge of the element. However, it's possible to create repeating gradients so you can create gradient patterns. In essence, you define a gradient with specified color stops; the browser draws the gradient, and then repeats that pattern, tiling it in the background of the element. For example, to get the repeating gradient of the left image in Figure 8-16, you can write this code:

```
background-image: repeating-linear-gradient(bottom left, #900 20px, #FC0 30px, #900 40px)
```

In cases like this, using pixel values for the color stops is very useful. In essence, the browser draws a gradient that starts at bottom-left; it starts with 20 pixels of deep red, then transitions to an orange at 30 pixels, and then goes back to deep red at 40 pixels. Once it's drawn that gradient, the browser simply tiles it in the background like a tiled image.

NOTE

There's plenty of room for experimentation with gradients. To see just a few of the amazing things that are possible, visit the CSS3 pattern gallery at <http://lea.verou.me/css3patterns/>, www.standardista.com/cssgradients/, and the amazing use of gradients to create flags of the world at www.standardista.com/CSS3gradients/flags.html.

You can even use repeating gradients to create solid stripes without any of the fancy and subtle transitions between colors. For example, the image on the right in Figure 8-16 is created with this declaration:

```
background-image: repeating-linear-gradient(45deg, #900 0, #900 10px, #FC0 10px, #FC0 20px);
```

Here, you start with deep red (#900) at the 0 point, and go to red again at the 10px point. Since you're transitioning between the same colors, the browser draws this as a solid color. Next, you transition to orange (#FC0) at 10 pixels. Since that's the same spot at which the red ends, that's not a subtle transition, the pattern just goes from red to orange. Finally, the transition goes to the same orange at 20 pixels, creating another solid line. Because this is a repeating linear gradient, the browser simply tiles that pattern to fill the background of the element.

Now the bad news. Repeating linear gradients work in most browsers, but not in older versions of Safari (prior to 5.1 or iOS 5) or in IE 9 and earlier. So it's a good idea to add a fallback background color; you also need to make sure that you include all the vendor-prefixed declarations, so the first repeat gradient would look like this:

```
background-color: #FC0;  
background: -webkit-repeating-linear-gradient(bottom left, #900 20px, #FC0  
30px, #900 40px)  
background: -moz-repeating-linear-gradient(bottom left, #900 20px, #FC0 30px,  
#900 40px)  
background: -o-repeating-linear-gradient(bottom left, #900 20px, #FC0 30px,  
#900 40px)  
background: repeating-linear-gradient(bottom left, #900 20px, #FC0 30px, #900  
40px)
```




FIGURE 8-16

You can create striped patterns using CSS3's repeating linear gradients.

Radial Gradients

CSS also provides a way of creating radial gradients—gradients that radiate outward in a circular or elliptical pattern (see Figure 8-17). The syntax is similar to linear gradients and at its most simple, you need only to provide a beginning color (the color at the middle of the gradient) and an ending color (the color at the end of the gradient). For example, the top-left image in Figure 8-17 is created with this code:

```
background-image: radial-gradient(red, blue);
```

This creates an elliptical shape that fits the height and width of the element, with the center of the gradient (the beginning red) in the center of the element.

You can also make circular gradients by adding a “circle” keyword before the colors. For example, the top-right image in Figure 8-17 is created with this code:

```
background-image: radial-gradient(circle, red, blue);
```

While a browser normally draws the center of a radial gradient in the center of the element, you can position the gradient's center by using the same positioning keywords and values you use for the `background-position` property (page 246). For example, in the middle-left image in Figure 8-17, the radial gradient begins 20 percent over from the left edge of the element and 40 percent from the top of the element. The positioning values go before the color and shape keyword, like this:

```
background-image: radial-gradient(20% 40%, circle, red, blue);
```

To dictate the size of the gradient, you can use one of four keywords:

- The **closest-side** keyword tells the browser to make the gradient extend from the center only as far as the side that's closest to the center. For example, in the middle-left image in Figure 8-17, the closest side to the center of the gradient is the top edge, so the radius of the circle travels from the center of the circle to this edge. This keeps the entire gradient within the element. Here is the code to produce this gradient:

```
background-image: radial-gradient(20% 40%, circle closest-side, red, blue);
```

When `closest-side` is applied to an elliptical gradient, both closest sides (that is, the top or bottom and the left or right sides) are used to calculate the x and y radii of the ellipse.

- The **closest-corner** keyword measures the width of the gradient from its center to the corner of the element that's closest (middle-right in Figure 8-17). This can mean that the gradient may overflow the element. For example, the circle drawn on top of the middle-right image in Figure 8-17 demonstrates the actual size of the gradient. Part of the gradient extends beyond the element:

```
background-image: radial-gradient(20% 40%, circle closest-corner, red, blue);
```

- The **farthest-side** keyword measures the radius of a circle from its middle to the side of the element that's farthest away. In the case of an elliptical gradient, it's the distance from the center to either the farthest top or bottom side and the farthest left or right side. Here is the code to produce the image in the bottom-left of Figure 8-17:

```
background-image: radial-gradient(20% 40%, circle farthest-side, red, blue);
```

- The **farthest-corner** keyword measures the radius of a circle from its middle to the corner of the element that's farthest away. Here is the code to produce the image in the bottom-right of Figure 8-17:

```
background-image: radial-gradient(20% 40%, circle farthest-corner, red, blue);
```




FIGURE 8-17
Radial gradients are elliptical (top-left) or circular (top-right) gradients. You can control the placement of the gradient within the background of the element, as well as control how large the gradient is.

As with linear gradients, you can use multiple color stops and set the placement of those color stops. For example, say you want a circular gradient that was composed of a bright red, an orange, and a yellow. You want the red to appear for a while before it transitions to orange, and then the orange lasts a while longer until the yellow appears at the end. You can use percentage values to dictate where the colors appear:

```
background-image: radial-gradient(20% 40%, circle, red 20%, orange 80%, yellow);
```

Of course, as with linear gradients you can use any valid CSS color values, so you can rewrite this code as:

```
background-image: radial-gradient(20% 40%, circle, rgb(255,0,0) 20%, rgb(255,165,0) 80%, #FFFF00);
```

As with linear gradients, Internet Explorer 9 and earlier won't know what you're talking about if you use a radial gradient, and neither will versions of Safari prior to 5.1 (and iOS 5). You should add a backup background color, and you'll need to add all the vendor prefixes as well. For example:


```
background-color: red;
background: -webkit-radial-gradient(20% 40%, circle, red 20%, orange 80%, yellow);
background: -moz-radial-gradient(20% 40%, circle, red 20%, orange 80%, yellow);
background: -o-radial-gradient(20% 40%, circle, red 20%, orange 80%, yellow);
background: radial-gradient(20% 40%, circle, red 20%, orange 80%, yellow);
```

Repeating radial gradients

As with linear gradients, you can create radial gradients that repeat—perfect for that bullseye look or when you wish to hypnotize your website visitors. You need to make sure you add either percentages or actual pixel or em values for the various color stops so the browser knows the size of a single radial gradient and can then repeat it. For example:

```
background-image: repeating-radial-gradient(circle, red 20px, orange 30px, yellow 40px, red 50px);
```

Note that to create a smooth-looking repeating radial gradient, you should end with the same color you start with (red, in this example). This provides a smooth color change back to the original color. If you don't (for example, if you just ended with the yellow color in the above code), then there's a sharp line where the last color ends and the first color of the repeated gradient begins.

TIP

Because web browsers treat linear- and radial-gradients simply as background images, you can use the other properties of background images, like `background-size`, `background-position`, and so on with them. In addition, you can have multiple, comma-separated gradients on a single style, just as you can have multiple background images (page 257). In fact, you can mix images with gradients in the same element.

■ Applying Easy Gradients with Colorzilla

The complexity of gradients and their limited browser support may have made you already decide to not use them in your CSS. Fortunately, there's an online tool that makes creating most types of gradients (except repeating gradients) a snap. It's the humbly named Ultimate CSS Gradient Generator (www.colorzilla.com/gradient-editor/), shown in Figure 8-18.

While this online tool is only a single web page, it has a lot of options. Here's one way to use it:

1. Start with a preset by selecting one of the gradients in the presets window (#1 in Figure 8-18).

You don't have to do this step, but building the gradient can go more quickly if you start with something close to what you're after.

2. From the Orientation menu, choose a gradient type (#2 in Figure 8-18).

This tool is limited to radial and linear gradients that go from top to bottom, left to right, top-left to bottom-right, bottom-left to top-right, or diagonal. However, once you've created the code, you can replace the keyword `angle` (top left, for example) with a degree (65deg, for example). Likewise, the tool creates elliptical radial gradients; if you want a circular gradient, just find `ellipse` and replace it with `circle` in the final CSS.

You can't create repeating linear gradients or repeating radial gradients with this tool.

3. To change the color and position of a color stop, click to select it (#3 in Figure 8-18).

Unless you like the preset colors, you'll need to edit each of the color stops.

4. To change the color of the color stop, click the color box (#4 in Figure 8-18).

A pop-up color picker appears. You can click to select a color, or if you know the color's RGB, hexadecimal, or HSL values, you can type it in. Click OK to select the new color and close the color picker.

5. Optionally, you can set the position of the color stop in the Location field to the right of the color box (#5 in Figure 8-18).

Type a percentage value, or, more easily, drag the color stop on the gradation bar (#3 in Figure 8-18).

NOTE To remove a color stop, select it from the gradation bar (#3 in Figure 8-18) and press the Delete button below it.

6. Add additional color stops by clicking below the gradation bar in the spot where you wish to add the color stop.

After you add a new color stop, change its color and position as desired (steps 4 and 5).

7. You can also alter the opacity of the gradient by making the beginning or end slightly or completely transparent. Select one of the stops above the gradation bar (#6 in Figure 8-18) and then adjust its opacity and position (#7 in Figure 8-18).

NOTE The Ultimate CSS Gradient Generator also attempts to make a gradient that works somewhat in IE 9 and earlier. Click the IE checkbox in the top-right preview box (see Figure 8-18) to see the effect, which uses a proprietary IE feature called *filters* to achieve a gradient. Unfortunately, IE can simulate only linear gradients that run either left to right or top to bottom, not radial gradients nor gradients at an angle.

8. Once you've created the gradient, point to the CSS box and click the Copy button when it appears (#8 in Figure 8-18).

This copies the CSS code to your computer's clipboard. You can then go to your text editor of choice and paste the code into the style to which you want to add a background gradient.

The Ultimate CSS Gradient Generator uses an IE-only feature to simulate a gradient for Internet Explorer versions 9 and earlier. In fact, it provides two fallbacks, one for IE 9 and one for earlier versions. The one for IE 9 uses another image technology—SVG or *scalable vector graphics*—to achieve its magic, and using it is a good idea. The one for earlier versions of IE uses a filter, which can't always simulate the gradient correctly and slows down IE's performance, so you're best off ignoring IE 8 and earlier. To do this:

1. Turn on the IE9 Support checkbox at bottom-right below the CSS code box (see Figure 8-18).

This adds the code to create a SVG gradient.

2. Copy the CSS code (Step 8 above) and paste it into your CSS.

3. Locate the IE filter code and delete it.

The last line of the code you copied looks something like this:

```
filter: progid:DXImageTransform.Microsoft.gradient( startColorstr='#3f4c6b',
endColorstr='#7ed6d3',GradientType=1 ); /* IE6-8 fallback on horizontal gradi-
ent */
```

If you really need to support IE 8, then leave this code in and test the gradient in IE 8 to make sure it displays correctly.

4. Finally, add a background-color property in the spot where you deleted the IE filter code; this is the color that will appear in the background for IE 8 and earlier.




FIGURE 8-18

The easiest way to get started with gradients is to use an online tool like the Ultimate CSS Gradient Generator (www.colorzilla.com/gradient-editor/). On the left, near the top of the page, you'll find a gallery of already created gradients. You can pick one of those as a simple starting point and adjust its colors and color stops to match your vision, or build your own gradient.

Tutorial: Enhancing Images

A photo gallery is a perfect example of an eye-catching web page. This tutorial brings together a variety of image styling techniques. You'll format images with frames and captions, create a photo gallery that's flexible enough to look great in a variety of window sizes, and use the box-shadow property (page 210) to create professional-looking drop shadows.

To get started, you need to download the tutorial files located on this book's companion website at www.sawmac.com/css3/. Click the tutorial link and download the files. All of the files are enclosed in a zip archive, so you need to unzip them first. (There are detailed instructions on the website.) The files for this tutorial are in the 08 folder.

Framing an Image

You'll be working on a basic web page from the fictional (just in case you thought it was real) website CosmoFarmer.com (Figure 8-19). In this case, there's already an external style sheet attached to the page, adding some basic text formatting.

1. Launch a web browser and open the file **08→01_image_ex→image.html**.




FIGURE 8-19

Before and after—CSS, that is. If you rely just on HTML, images take up lots of space (top). With a little CSS (bottom) you can nicely frame an image and move it out of the way.

2. Open the file *styles.css* in the *01_image_ex* folder in your favorite text editor.

This file is the external style sheet used by the *image.html* file. You'll start by adding a class style to this style sheet, and then applying a class to the `` tag in the HTML file.

3. Scroll to the bottom of the file and then type the following:

```
img.figure {  
  }  
}
```

The selector *img.figure* targets any `` tag with the *figure* class applied to it. You'll use this to selectively format only the images you want. (You could also just name the style *.figure*—the only difference is that that style would then apply to *any* tag with the class *figure*, not just images.)

4. Add float and margin properties to the style you just created, like so:

```
float: right;  
margin: 10px;
```

The right float moves the image to the right side of the page, letting the text move up and wrap around the photo's left edge. The margins give the photo a little breathing room and move it away from the text, the side of the page, and the headline above. Next, you'll add a border, a background color, and some padding to make the image look more like a real snapshot.

5. Add border, background color, and padding, so that the finished style looks like this:

```
img.figure {  
  float: right;  
  margin: 10px;  
  border: 1px solid #666;  
  background-color: #CCC;  
  padding: 10px;  
}
```

If you save this file and then preview the web page right now, you won't see a change, since the class style has no effect until you've added the class to a tag.

6. Save and close the *styles.css* file and open the *image.html* file. Locate the `` tag and add `class="figure"` so the tag looks like this:

```

```

Now that image takes on all of the formatting properties you defined for the *.figure* class style.

- 7. Preview the page in a web browser.** It should look like the bottom image in Figure 8-19.

A picture may be worth a thousand words, but sometimes you still need a few words to explain a picture. So in the next part of this tutorial, you'll add a caption below the photo.

You'll frequently want to add a caption to an image or photo to provide more information about the subject, where the photo was taken, and so on. Instead of just floating the image, as you did in the previous exercise, you want the caption text to float as well. The best way to float both is to wrap the image and the text in a container that's floated as a single unit. This method keeps the photo and its related text together. If you decide later that you want to change their layout—perhaps float them to the left—no problem: You simply change the formatting for the entire container.

Fortunately, HTML5 includes two new tags for just such a requirement: The `<figure>` tag is intended to enclose an image that's meant to be an illustrative figure. In addition, the `<figcaption>` tag can be used to enclose, you guessed it, a figure caption. First, you need to adjust some of the HTML.

NOTE

Because you're using some HTML5 tags now, you need to include the HTML5shiv JavaScript file to force IE 8 and earlier to recognize the `<figure>` and `<figcaption>` tags. See the box on page 24.

- 8. Return to your text editor and the *image.html* file.** Locate the `` tag in the code, and first remove the `class="figure"` that you added in Step 6, and add `<figure>` before that tag.

This marks the beginning of the container. Now you'll add the caption and close the `<figure>` to indicate the end of the container.

- 9. After the `` tag, add the code in bold below, so the HTML looks like this:**

```
<figure>

<figcaption>Figure 1: Creeping Bentgrass is best suited for outdoor use and
should be avoided by the indoor farmer.
</figcaption>
</figure>
```

- 10. Switch back to the *styles.css* file.** Scroll to the bottom of the file and delete the `img.figure` style you created earlier.

You'll add a new style for the figure element.

11. Add this style to the *styles.css* file:

```
figure {  
  float: right;  
  width: 222px;  
  margin: 15px 10px 5px 10px;  
}
```

You've already used the `float: right` property in the previous tutorial, and the `margin` adds a little white space around all four edges of the `<figure>` tag. But what's the *width* for, you ask? Although the photo has a set width (200 pixels), the caption paragraph doesn't. When you don't set a width, the paragraph makes the `<figure>` expand wider than the photo. In this case, you want the caption to be just as wide as the photo and its frame.

The 222-pixel value comes from a little math used to calculate the entire area taken up by the photo on the page: While the photo is only 200 pixels wide, the 10 pixels of left and right padding as well as the image's 1-pixel left border and 1-pixel right border make the entire width of the photo equal to 222 pixels from border to border (see page 213 for a refresher on how to calculate the width of an element). Next, you'll add the formatting for the image.

12. Add this style to the *styles.css* file:

```
figure img {  
  border: 1px solid #666;  
  background-color: #CCC;  
  padding: 10px;  
}
```

This descendent selector affects any `` tag *inside* a `<figure>` tag. Since you're using a descendent selector here, you don't need to add a class to the `` tag. Next, you'll style the caption.

13. Add the following style to the *styles.css* style sheet:

```
figcaption {  
  font: bold 1em/normal Verdana, Arial, Helvetica, sans-serif;  
  color: #333;  
  text-align: center;  
}
```


This style uses some of the properties you learned about in Chapter 6 to create a center-aligned, bold, and gray caption using the Verdana font. Fortunately, the font shorthand property in the first line lets you roll four different properties into a single style declaration.

To make the caption stand out even more, add a background color and border.

14. Add three properties to the figcaption style, like so:

```
figcaption {
  font: bold 1em/normal Verdana, Arial, Helvetica, sans-serif;
  color: #333;
  text-align: center;
  background-color: #e6f3ff;
  border: 1px dashed #666;
  padding: 5px;
}
```

The purpose of the background-color, border, and padding properties should be clear—to create a colored box around the caption. Now it's time to preview your work.

15. Save both the *image.html* and *styles.css* files and preview the *image.html* file in a web browser.**16. Now you see one reason why it's easier to develop a design using an internal style sheet—you need to work in and save only one file instead of two.** The page should look like Figure 8-20. (You can find a completed version of this page in the *08_finished*→*01_image_ex* folder.)**FIGURE 8-20**

With the use of a containing `<figure>` tag, a right float, and a little style, it's easy to add captions to photos.

■ Tutorial: Creating a Photo Gallery

Folks used to rely on the HTML `<table>` tag to create rows and columns for holding the pictures in a photo gallery. But you can achieve the same effect with a little CSS and far less HTML.

1. Open the file `08→02_gallery_ex→gallery.html`.

First, a quick review of the HTML used to construct the photo gallery. The page contains six photos and photo captions. Each photo and caption is contained in a `<figure>`. The photo itself is an `` tag and the caption is inside a `<figcaption>` tag.

```
<figure>
  
  <figcaption>Figure 6: The dandelion: scourge of the apartment farmer.
</figcaption>
</figure>
```

NOTE

Because you're using some HTML5 tags, you need to include the HTML5 `HTML5shiv` JavaScript file to force IE 8 and earlier to recognize the `<figure>` and `<figcaption>` tags. See the box on page 24.

2. Locate the `<link>` tag near the top of the file, place your cursor *after* that tag, and then press **Enter (Return)** to create a new blank line.

The `<link>` tag attaches an external style sheet containing some basic formatting.

3. Add an internal style sheet.

 Then add two new styles, as follows:

```
<style>
figure img {
  border: 1px solid #666;
  background-color: #FFF;
  padding: 4px;
}

figcaption {
  font: 1.1em/normal Arial, Helvetica, sans-serif;
  text-align: center;
  margin: 10px 0 0 0;
}
</style>
```

These two styles add a border to each image in the gallery, and set the font, alignment, and margins of the captions. The first is a descendent selector to target just the images inside the figures.

Next, place the photos side by side.

NOTE

When you insert the internal style sheet, make sure to place it in the page's head section, after the link tag and before the IE conditional comment, which attaches the *HTML5shiv* JavaScript file (page 24).

4. Add the following style to the internal style sheet you just created:

```
figure {  
  float: left;  
  width: 210px;  
  margin: 0 10px 10px 10px;  
}
```

This style floats each photo/caption pair to the left. In effect, it places the photos side-by-side until there's no more room in the row. The browser then drops the next photos down a row, until all of the photos are displayed one row on top of the next. The width is the *total* width of the photo plus padding and borders. In this example, it's 200 pixels for the photo, 8 pixels for left and right padding, and 2 pixels for left and right borders.

NOTE

In this fictitious photo gallery, each picture is the same width. In the real world, you may have pictures of varying sizes. See the box below for a trick that lets you arrange rows of pictures of different widths. Using different height images won't work (as you'll see in Step 5). When you've got images with differing heights, stick with HTML tables.

POWER USERS' CLINIC**When One Width Doesn't Fit All**

It's a breeze to set up a photo gallery—like the one in this tutorial—when the photos are conveniently all the same width. But what if you have photos of differing widths? One solution is to create a style for each different width and apply a class to the `<figure>` tag for the particular image. (That's tons of work, so it would pay to do some photo editing work to standardize your photos to just a handful of different widths first.)

For example: `<figure class="w300">`.

Then create a class style, for example `.w300`, and set the width to the width of the image (in this case, 300) plus 10 to cover the padding and borders: `.w300 { width: 310 };`

5. Save the file and preview the *gallery.html* page in a web browser. It should look like the left image in Figure 8-21.

Adjust the width of your browser window to make it thinner and wider and watch how the images reflow into the space. Aha—something's not quite right. The second row of images has two empty spaces where photos should be. This problem occurs because the caption for the second image on the first line is taller than the other captions on the line. Images that jump down to another row bump into that caption and can't get by it. (You can read more about this `float` property snafu on page 425.) Fortunately, there's a simple fix to this dilemma.

6. Return to your text editor and the *gallery.html* file. Locate the figure style. Remove the `float:left` and add `display: inline-block; vertical-align: top`. The finished style should look like this:

```
figure {
    display: inline-block;
    vertical-align: top;
    width: 210px;
    margin: 0 10px 10px 10px;
}
```

The `display: inline-block` property (page 308) treats each image/caption pair as a block (a box with height and width) but also as an inline element (so the blocks can sit side-by-side). In addition, the `vertical-align: top` makes sure that each `<figure>` tag aligns to the top of all the other `<figure>` tags in a row.

7. Save the file and preview the page in a web browser. See the right side of Figure 8-21.

If you resize the browser window, the gallery reformats itself. With a wider window you can fit four or even five images on a row, but if you make it smaller you'll see only one or two images per row.




FIGURE 8-21

Floating elements next to each other is one way to simulate the column and row appearance of a table. But it doesn't work well if the elements are of varying heights (left). Using `display: inline-block` is another way to force elements to sit side-by-side (right) without the nasty dropping behavior pictured in the left image.

Adding Drop Shadows

Your gallery looks good, but you can make it even more impressive. Adding drop shadows under each photo lends the page an illusion of depth and a realistic 3-D quality. But before you fire up Photoshop, you'll be glad to know there's no need to add individual drop shadows. Instead, you can make CSS automatically add a shadow to any image you want. Before CSS3 (and in previous editions of this book), you had to go through an elaborate process to add drop shadows to the images in this gallery, adding extra divs around the images and using two background graphics, and it still didn't look like a perfect drop shadow. Fortunately CSS3 makes it so easy, you'll wrap this tutorial up in three steps.

1. In a text editor, return to the *gallery.html* file you've been working on.

You'll update the `img` style you created before.

2. Add `box-shadow: 2px 2px 4px rgba(0,0,0,.5);` at the end of the figure `img` style so it looks like this (changes in bold):

```
figure img {  
  border: 1px solid #666;  
  background-color: #FFF;  
  padding: 4px;  
  box-shadow: 2px 2px 4px rgba(0,0,0,.5);  
}
```

You learned about the `box-shadow` property back on page 210. Here you've added a shadow that extends 2 pixels to the right of the image, 2 pixels below the image, and which spreads out 4 pixels. Using an RGBA color (page 155), you can set the shadow to 50 percent transparent black color.

3. Save the file and preview the page. It should look like Figure 8-22.

Each image has its own drop shadow, and you didn't even have to open Photoshop!

You can find a completed version of this tutorial in the *08_finished*→*02_gallery_ex* folder.




FIGURE 8-22
Adding drop shadows to photos gives a page a 3-D look and increases the visual appeal of any photo gallery. Fortunately, using CSS you can easily add a drop shadow to any picture without even touching Photoshop.

■ Tutorial: Using Background Images

The CSS *background-image* property is the secret weapon of modern web design. It can turn a ho-hum, text-heavy web page into a dazzling swirl of imagery (see Figure 8-23). Since you can use it to add an image to the background of any HTML tag, the designs you can create are limited only by your imagination. The drop shadow example in the previous tutorial is just one example of creative background image use. Other common background image frills include applying a page background and adding custom bullets to unordered lists. You'll explore some of these common tasks in this tutorial.

Adding an Image to the Page Background

Whether it's an intricate pattern, a logo, or a full-screen photograph, images appear in the background of many web pages. In fact, adding an image to the background of a page is probably the most common application of the `background-image` property.

1. In your text editor, open the file `08→03_bg_ex→bg_images.html`.

This page is a basic two-column layout: a very simple page, with some text formatted on a white background (Figure 8-23, left). To start, you'll add a background image to the page. The page has an external style sheet with the basic formatting, but to avoid having to wade through all the styles in that file, you'll add an internal style sheet for the steps in this tutorial.

2. Click between the opening and closing `<style>` tags. Add the following style:

```
body {  
    background-image: url(images/bg_page.png);  
    background-repeat: repeat-x;  
    background-color: #FFF;  
}
```

The first line of code points to the image—`bg_page.png`—you want to display on the page. The file is stored in the `images` folder. This graphic is a gradient that starts as light blue at the top and fades to white at the bottom. The graphic isn't as tall as the page content, so without further instructions, it would tile over and over across and down the page. At a certain point down the page, that light blue would reappear and fade once again downward to white. To prevent this unsightly snafu, you've set the `background-repeat` property so that the image tiles from left to right in order to fit any width of browser window, but doesn't tile *down* the page. The last line of code sets the page's background color to match the end of the gradient, so the image fades seamlessly into the page's background color.

You might think that using a linear gradient would be a lot better than using a gradient image. In some cases, that's true. However, when adding a linear gradient to the background of a page, the web browser literally has to redraw that background gradient every time you resize the browser window, causing a noticeable slowing down of the page rendering and making the page feel slow. In addition, because linear gradients don't work in IE 9 or earlier without some additional code, you'll stick with a background image for now.

NOTE

Using background property shorthand, you can condense the three lines of code from Step 2 into a single line of CSS: `background: url(images/bg_page.png) repeat-x #FFF`.

3. Save the file and preview it in a web browser.

The background graphic's blue gradient drips down the page. Not bad looking, but the blue also appears in the text's background. You can make the text pop by giving its background a different color.

4. Return to your text editor and the *bg_images.html* file. Add another style for the <div> containing the content of the page:

```
.wrapper {
    background-color: #FFF;
}
```




FIGURE 8-23
Using background images, you can make an already well-organized page (left) look much spiffier (right). Since you can add images to the background of any tag on a page, the possible placement of graphics on a page are nearly limitless.

The wrapper div is a fixed width, centered in the middle of the page, containing all of the page's text. This style gives it a white background, but with the help of an image, you can do better than that.

5. Edit the style you created in Step 4 by adding a background image:

```
.wrapper {
    background-color: #FFF;
    background-image: url(images/bg_main.jpg);
    background-position: left top;
    background-repeat: no-repeat;
}
```

These three lines of code add a background image to the top-left of the <div>; the no-repeat option for the background-repeat property means the image only appears a single time. If you save the file and preview it in a web browser, you'll now see the picture of a hand acting like it's holding the page. Very cool. The only problem is the text is too far up, covering up the image. You'll next push down the top headline and the left sidebar.

6. Add two more styles to the internal style sheet:

```
.banner {
    margin-top: 48px;
}
.announcement {
    margin-top: 115px;
}
```


The first line just adds a bit of padding, pushing down the banner containing the headline until it just touches the top of the white page, while the second style moves the left sidebar down enough to clear the picture of the hand. The page should now look like Figure 8-24.




FIGURE 8-24

CSS lets you combine a background color and a background image, which comes in really handy in this example. The main text area has a white background color that helps separate the text from the fading gradation in the page's background. In addition, a graphic of a hand holding a piece of paper adds depth to the design.

Replacing Borders with Graphics

The border property is a useful tool in your design arsenal, but the limited number of border styles CSS offers can get boring. A hand-drawn line with a little texture would catch your visitors' attention better than a plain, straight one. You can skip the border property and add any kind of line you want as a background image—easy as pie. In this part of the tutorial, you'll replace the underline below each `<h2>` tag in the main text area with a custom graphic that looks like a hand-drawn line.

1. **Return to your text editor and the `bg_images.html` file.** Add a style for the `<h2>` tags inside the main `<div>` tag:

```
.main h2 {
  background-image: url(images/underline.png);
  background-repeat: no-repeat;
}
```

The `background-image` property specifies which graphic to use in the background of `<h2>` tags inside any tag with a class of `main`, whereas the `no-repeat` value makes sure the graphic only appears a single time.

If you preview the file now, you'll see that the underline doesn't exactly line up. In fact, it isn't *under* at all. It's above the headlines!

2. Add the following style declaration to the `.main h2` style below the `background-repeat` property:

```
background-position: left bottom;
```

You've changed the graphic's starting location so it appears at the left edge and bottom of the `<h2>` tags. If you preview the page now, though, you may not notice much improvement. The underline runs *into* the headline text.

But there's an easy fix. Since the `bottom` value used here puts the graphic at the bottom of the block created by the `<h2>` tag, you need only to increase the overall height of the block to move the line down a bit. You'll do this with a little bottom padding.

NOTE

CSS3 provides a means of using images for borders. Unfortunately, it's a bit complex and doesn't work on Internet Explorer 9 or earlier. Since you can achieve a similar effect in this example by using a background image, in this tutorial you'll go that route. However, if you want to learn more about border images, visit www.css3files.com/border.

3. Edit the `.main h2` style one last time, so that it looks like this:

```
.main h2 {  
  background-image: url(images/underline.png);  
  background-repeat: no-repeat;  
  background-position: left bottom;  
  padding-bottom: 7px;  
}
```

Padding, as you'll recall from page 195, is the space between the border (the edge of the background as well) and the content. It also increases the overall height of the box—in this case, by adding 7 pixels of bottom padding. Now, the line graphic is placed at the bottom of the `h2` block, but in the empty space created by the bottom padding.

4. Save the file and preview the page in a web browser.

Each `<h2>` tag has the hand-drawn underline. Next you'll tackle the sidebar box, making it look a little less boxy and jazzing up the bulleted lists.

Using Graphics for Bulleted Lists

The average bullet used for unordered lists is a black dot—not very inspiring. But you can use the `background-image` property to replace those drab bullets with any image you want. The first step is to hide the bullets that normally appear beside list items.

1. **Return to your text editor and the `bg_images.html` page.** Add a style for formatting the list items in the left sidebar.

```
.announcement li {  
  list-style: none;  
}
```

The bulleted list is inside a `<div>` with a class of `announcement`, so this descendent selector targets just the list items (`` tags) inside that div. The style removes the bullet. Now add the graphic.

NOTE You can just as well apply `list-style: none;` to a style affecting the `` or `` tags to remove bullets from *each* list item.

2. **Add the following two properties to the `.announcement li` style:**

```
background-image: url(images/bullet.png);  
background-repeat: no-repeat;
```

You've seen these two properties before. They add an image to the background and turn off repeating so that the graphic appears only once.

If you preview the page, you'll see that the bullets currently overlap the list text and the list items are a little jammed together (Figure 8-25, left). A little padding and margin will fix this.

3. **Add two more properties to the `.announcement li` style:**

```
padding-left: 25px;  
margin-bottom: 10px;
```

The left padding adds empty space, effectively moving the text out of the way in order to display the new bullet icon. The bottom margin adds just a bit of breathing room between each list item (Figure 8-25, middle).

There's just one final flaw. The bullet image is a tad too high on the line, causing the tip of the icon to stick out too far above the text. But you can easily fix that with the `background-position` property.

4. **Finish this style by adding `background-position: 0px 4px;`** The completed style should look like this:


```
.announcement li {  
  list-style: none;  
  background-image: url(images/bullet.png);  
  background-repeat: no-repeat;  
  background-position: 0 4px;  
  padding-left: 25px;  
  margin-bottom: 10px;  
}
```

This last style declaration positions the bullet icon to the far left (that's the 0) and 4 pixels from the top (4px) of the list item. It moves the icon down just a smidgen, enough to make the bullet look perfect.

NOTE As discussed on page 178, this kind of exact positioning is precisely why you should use the background property instead of the list-style-image property for adding graphic bullets to your lists.

5. Save the file and preview the page in your browser.

The list should now have 3-D tabs with red exclamation marks instead of dreary black circles (Figure 8-25, right).



Giving the Sidebar Personality

At this point, the sidebar looks pretty good. The text is nicely formatted, and the bullets look great, but the sidebar gets a little lost in the sea of white. Adding a background image can make the sidebar stand out in a whimsical way. You could use a single image—the scroll image pictured in the right image of Figure 8-23—in the background of the <div> tag, but in order to make sure the text fits exactly on the scroll, you'd have to limit the amount of content you put in the sidebar. Too much text and it won't fit on top of the single image (top-left in Figure 8-12), too little, and there will be too much empty space on the graphic.

A more flexible approach would let the image grow as the sidebar acquires more content (bottom-right in Figure 8-12). As discussed on page 257, there are multiple ways to achieve this effect. You can put the background part of the scroll (where the text appears) as a repeating background image in the div, then place a background image for the top of the scroll in the headline at the top of the div, and a background image in the bottom of the list item at the bottom of the div. In fact, that's the method used in previous editions of this book. However, now that most browsers support CSS3 multiple backgrounds, you can use them instead. It's a lot simpler, and it doesn't require three different styles to work.

1. **Return to your text editor and the `bg_images.html` file.** Locate the .announcement style you added in Step 6 on page 284 and add one additional property:

```
.announcement {  
  background: url(images/scroll_top.jpg) no-repeat center top,  
             url(images/scroll_bottom.jpg) no-repeat center bottom,  
             url(images/scroll_middle.jpg) repeat-y center top;  
  margin-top: 115px;  
}
```

Yes, that's only one property—the background property—but it has three different images. The order in which you list these images is important, since they stack on top of each other. In this case, the first image is the top of the scroll; it only appears once (*no-repeat*) at the top and center. The second image is the bottom of the scroll; it also only appears once, but at the bottom of the div. Finally, the middle part of the scroll—*scroll_middle.jpg*—will be layered underneath the other two images (since it appears last in the list), and it's repeated along the y-axis (up and down), so if the `<div>` gets taller, the image simply tiles to fill the space.

If you preview the page, you'll see a few problems. First, the text appears on top of the rolled up top and bottom parts of the scroll. A little padding will fix that.

- 2. Update the `.announcement` style to add top and bottom padding.** Make the changes listed in bold below:

```
.announcement {  
  background: url(images/scroll_top.jpg) no-repeat center top,  
             url(images/scroll_bottom.jpg) no-repeat center bottom,  
             url(images/scroll_middle.jpg) repeat-y center top;  
  padding: 70px 0 60px 0;  
  margin-top: 115px;  
}
```

Another problem is that the bulleted list sticks out on both the left and right sides of the sidebar image. To make the bulleted list fit on the scroll, you need to add some left and right margin.

- 3. Locate the `.announcement li` style you created earlier and add two properties to the end so it looks like this:**

```
.announcement li {  
  list-style: none;  
  background-image: url(images/bullet.png);  
  background-repeat: no-repeat;  
  background-position: 0 4px;  
  padding-left: 25px;  
  margin-bottom: 10px;  
  margin-left: 30px;  
  margin-right: 40px;  
}
```

These properties move both the left and right edges of each bulleted item in enough to clear the edges of the background image.

4. Save the file and preview it in a web browser.

The page should look like the right image in Figure 8-23—in all current browsers except Internet Explorer 8. That browser doesn't support multiple background images.

Getting the Scroll to Appear in IE 8

While Internet Explorer 8 doesn't support multiple images, you can fake it, especially if you only need two or three background images. Using generated content (page 595), you can add text or images before and after any element on a page. In this case, you can add the top of the scroll before the div, and the bottom of the scroll after the div.

If you're not so worried about supporting IE 8, you can skip this step, but if you want to see how to make this work in IE 8 and later as well as all other current browsers, read on.

1. Edit the `.announcement` style so there's only a single background image (the middle of the scroll) and no padding:

```
.announcement {  
    background: url(images/scroll_middle.jpg) repeat-y center top;  
    margin-top: 115px;  
}
```

You won't need the padding, since the other images will take up room above and below the div. Next, you'll add the top of the scroll as a before element to the div.

2. Add the following style below the `.announcement` style:

```
.announcement:before {  
    content: url(images/scroll_top.jpg);  
}
```

As mentioned on page 70, the `:before` pseudo-element lets you add content before a tag. This could be text, or (as in this case) an image. Now for the bottom of the scroll.

3. Add the following style below the `:before` style you just added:

```
.announcement:after {  
    content: url(images/scroll_bottom.jpg);  
}
```

This adds the bottom of the scroll after the div. Well, it doesn't really go after the div, it goes on top and the div expands to fit it. In fact, if you preview the page, you'll see a little bit of the background of the div (the scroll) show underneath the curved bottom of the scroll. You'll fix that with a little more CSS magic.

4. Edit the style you just created by adding two more lines of code (bolded below):

```
.announcement:after {  
  content: url(images/scroll_bottom.jpg);  
  position: relative;  
  bottom: -5px;  
}
```

You're jumping ahead a bit here, since you won't learn about the `position` property in depth until Chapter 15, but in a nutshell, you're moving the bottom of the scroll down 5 pixels to cover up the background of the div.

Now the page should look like the righthand image in Figure 8-23, and just like the one you created in the earlier part of this tutorial with multiple images. You'll find both pages in the *08_finished/03_bg_ex* folder: *bg_images.html* and *bg_images_ie8.html*.

5. Lastly, add:

```
<meta http-equiv="X-UA-Compatible" content="IE=edge">
```

To the `<head>` area of the page. Above the `<title>` is a good place. This code isn't always necessary, but IE8 can be set to display using "IE7-mode" which won't work. Adding this `<meta>` tag forces IE8 to really display the page as IE8.

Sprucing Up Your Site's Navigation

It's safe to say that without links there'd be no Web. The ability to be on one page, then click something onscreen and suddenly see a page on a computer half a world away is what makes the Web so useful. Links are also how your visitors navigate their way around your website. That's why web designers agonize over making their links look good and work properly.

In this chapter, you'll learn how to style links to make them stand out from other text. You can also make your links provide visual cues so your site's visitors can see where they are—and where they've been. You'll learn how to use CSS to create onscreen buttons and navigation bars just like the pros use. And in the tutorial section, you'll get some hands-on experience creating a full set of navigation features that work in all browsers.

■ Selecting Which Links to Style

As always in CSS, you have to select something before you can style it. For links, you need to tell CSS not only *what* you want to style, but also *when* you want that style to apply. Web browsers keep track of how a visitor interacts with links, and then displays that link differently depending on the link's status, or *state*. When you use a CSS link selector, you can target a specific link state as well.

Understanding Link States

Most browsers recognize four basic link states: an unvisited link, a link that's been visited already (meaning the URL is stored in the browser's history), a link that the visitor's mouse is poised over, and a link that's being clicked. As described in

Chapter 3, CSS gives you four pseudo-class selectors to accompany these states—`:link`, `:visited`, `:hover`, and `:active`. Using them, you can apply different formatting to each state, so there's no doubt in your visitor's mind whether he's been there or done that.

NOTE

Browsers also recognize a pseudo-class called `:focus`. Links get `:focus` when mouse-averse visitors use the keyboard to tab to them. This pseudo-class is also fun to use with form text fields, as you'll see in the forms tutorial on page 395.

Suppose you want to change the text color for an unvisited link from boring browser blue to vivid orange. Add this style:

```
a:link { color: #F60; }
```

Once someone has clicked that link, its state changes to `visited`, and its color changes to the purple used by most browsers. To change that color to deep red, use this style:

```
a:visited { color: #900; }
```

TIP

When you want to provide a style that applies to all link states—for example, use the same font and font size for all link states—then style the HTML `<a>` tag by creating a generic selector. You can then use the specific link state styles—`a:visited`, for example—to change the color or in some other way customize the look of just that state.

WORD TO THE WISE

Limits on Visitation

Due to privacy concerns, browsers have begun to place severe limits on which CSS properties you can apply to the `:visited` pseudo class. As it turns out, some nefarious types have figured out how to use JavaScript to read changes in the style of `:visited` links to determine sites people had visited. For example, by loading a new background image for visited links, you can determine whether a visitor has been to Paypal.com,

eBay.com, BankofAmerica.com, or not-safe-for-work.com. Because of that potential problem, you're limited to styling the `color`, `background-color`, and `border-color` of visited links—and only if you've already given the normal states of those links a color, background color, or border color. In other words, you can't do much with the `:visited` pseudo-class any longer.

The `:hover` pseudo-class offers many creative possibilities; you'll learn quite a few later in this chapter. It lets you completely alter the look of a link when a visitor moves her mouse over it. If you've used cumbersome JavaScript to make graphic buttons change when a mouse hovers over them, you'll love being able to create the same effect with CSS alone. But to start with a simple example, this style changes the color of a link as a mouse passes over it:

```
a:hover { color: #F33; }
```

TIP Be careful when adding CSS properties to the `:hover` pseudo-class. Properties that change the size of the hovered element might affect other elements around it. For example, if you increase the font size of a hovered text link, when moused over, the link text will grow, pushing other elements out of the way. The effect can be jarring.

And finally, if you're one of those obsessive-compulsive designers who leave no design stone unturned, you can even change the look of a link for the few milliseconds when a visitor is actually clicking it. Here's how:

```
a:active {color: #B2F511; }
```

In most cases, you'll probably have a generic `a` style, `:visited`, and `:hover` styles in your style sheets. For maximum design control you may want to style all the different states. But for that to work, you must specify the links in a particular order: `link`, `visited`, `hover`, and `active`. Use this easy mnemonic to remember it: **LoVe/HaTe**. So here's the proper way to add all four link styles:

```
a:link { color: #F60; }  
a:visited { color: #900; }  
a:hover { color: #F33; }  
a:active {color: #B2F511; }
```

If you change the order, the hover and active states won't work. For example, if you put `a:hover` before `a:link` and `a:visited`, then the color change won't take effect when hovering.

NOTE Why does the order matter? That would be thanks to our friend the cascade (see Chapter 5). All those styles have the same specificity, so the order in which they appear in the code determines the style that wins out. A link can be both *unvisited* and *hovered over*. So if the `a:link` style comes last in the code, then it wins, and the color from `a:hover` never gets applied.

Targeting Particular Links

The styles in the previous section are basic `<a>` tag styles. They target certain link states, but they style *all* links on a page. What if you want to style some links one way and some links another way? A simple solution is to apply a class to particular link tags. Say you have a bunch of links within the body of an article, some of which point to sites that you want to highlight (for example, links to websites belonging to your friends, business associates, or sponsors). You may want to identify these links so people know they're special and are more likely to click them. In this case, you can apply a class to these external links, like this:

```
<a href="http://www.hydroponiconline.com" class="sponsor">Visit this great  
resource</a>
```

To style this link in its own way, you'd create styles like this:

```
a.sponsor { font-family: Arial, sans-serif; }
a.sponsor:link { color: #F60; }
a.sponsor:visited { color: #900; }
a.sponsor:hover { color: #F33; }
a.sponsor:active {color: #B2F511; }
```

Leaving off the `a` and only specifying the class works too:

```
.sponsor { font-family: Arial, sans-serif; }
.sponsor:link { color: #F60; }
.sponsor:visited { color: #900; }
.sponsor:hover { color: #F33; }
.sponsor:active {color: #B2F511; }
```

Now only those links with a class of “sponsor” will get this formatting.

NOTE

These examples change only the links' colors, but that's just to make it simple for demonstration purposes. You can use *any* CSS property to format links (except `:visited` links, as explained in the box on page 294). As you'll see in the next section, you have lots of creative ways to style links.

Grouping links with descendent selectors

If a bunch of links appear together in one area of a page, you can also save time by using *descendent selectors*. Say you have five links that lead to the main sections of your site. They represent your main navigation bar, and so you want to give them a distinctive look. Just wrap those links in the HTML5 `<nav>` tag. Now you have an easy way to identify and format just those links:

```
nav a { font-family: Arial, sans-serif; }
nav a:link { color: #F60; }
nav a:visited { color: #900; }
nav a:hover { color: #F33; }
nav a:active {color: #B2F511; }
```

Alternatively, you can use a `<div>` tag (if you're not quite ready for HTML5 tags) and add a class to that div: `<div class="mainNav">`:

```
.mainNav a { font-family: Arial, sans-serif; }
.mainNav a:link { color: #F60; }
.mainNav a:visited { color: #900; }
.mainNav a:hover { color: #F33; }
.mainNav a:active {color: #B2F511; }
```

Using descendent selectors, it's easy to style links differently for different areas of a web page. (See page 553 in Chapter 17 for a thorough discussion of the power of descendent selectors.)

TIP It's very common to use bulleted lists to present links (you'll see an example of this technique on page 304). In this case, you can add an ID or class to the `` tag for the list—`<ul class="mainNav">`, for example—then create descendent selectors like `.mainNav a:link` to style them.

Styling Links

Now that you know how to create a selector that targets links, how should you style them? Any way you want! There aren't any CSS properties intended just for links. You have access to all CSS properties, so you're limited only by your imagination. Just make sure your links look like links. Not that they need to be blue and underlined, but links must look different from non-link text so visitors know they can click them.

If you make a link look like a button—adding a border, including a background, and making it change color when moused over—most people will understand they can click it. Or, use a linear gradient (page 260) to add texture and depth to a link. Likewise, links that appear in long passages of text should look clearly distinct. You can make links stand out by bolding the text, keeping the traditional underline, coloring the background, or adding a hover style. You can even add a graphic (like an arrow) that provides a clear visual cue that clicking the text takes you somewhere else.

TIP Unless you set an `` tag's `border` attribute to 0, Internet Explorer adds a border around linked images. To prevent this from happening, add this basic style to your style sheets: `img { border: none; }`.

Underlining Links

Since the beginning of the Web, vibrant blue, underlined text has signaled, "Click here to go there." But that underline and color are often the first two things a designer wants to change. Underlines are such a common way to mark a link that they're boring (#1 in Figure 9-1). Fortunately, you can do several things to eliminate or improve on the standard underline, while still ensuring that your links are identifiable:

- **Remove the underline entirely.** To eliminate the regular underline, use the `text-decoration` property and the none value:

```
a {text-decoration: none;}
```

Of course, removing the underline completely can confuse your visitors. Unless you provide other visual cues, your links look exactly the same as all the other text (#2 in Figure 9-1). So if you go this route, then make sure you highlight the links in some other way, like making link text bold (#3 in Figure 9-1), coloring the background, adding an informative graphic, or making the link look like a button (page 305).

- **Underline when mousing over.** Some designers remove underlines for all links, highlight them in some other way, and then add the underlines back when the visitor moves his mouse over the link (#4 in Figure 9-1). To do so, simply remove the underline for links, and then reintroduce it using the `:hover` pseudo-class:

```
a {
  text-decoration: none;
  background-color: #F00;
}
a:hover {
  background-color: transparent;
  text-decoration: underline;
}
```




FIGURE 9-1

You have plenty of ways to make the boring line (1) under links more exciting. Start by removing the link entirely (2, 3) and replacing it only when the visitor mouses over the link (4). Better yet, create a more stylized link by using the border property (5) or a background image (6).

- **Use a bottom border.** You can't control the color, width, or style of a regular link underline. It's always a solid, 1-pixel line in the same color as the link text. For greater variety, use the `border-bottom` property instead (#5 in Figure 9-1). Hiding the normal underline and adding a dashed-line border looks like this:

```
a {
  text-decoration: none;
  border-bottom: dashed 2px #9F3;
}
```

You can alter the style, width, and color of the border. To put more space between the text and the border, use the padding property.

- **Use a background image.** You can customize the look of links even further by using a graphical line. For example, #6 in Figure 9-1 uses a graphic that looks like a hand-drawn line. There's a similar technique for underlining headlines in the Chapter 8 tutorial (page 285). Start by creating an underline graphic using a program like Fireworks or Photoshop, which have brush tools that simulate the look of a crayon, felt-tip marker, or whatever. Next, create a style for the link that removes the normal underline and adds a background image. Make sure the graphic repeats horizontally and is positioned at the bottom of the link. You may also need to add a little bottom padding to position the line. Here's an example:

```
a {
  text-decoration: none;
  background: url(images/underline.gif) repeat-x left bottom;
  padding-bottom: 5px;
}
```

Creating a Button

You can also make links look like the buttons in the dialog boxes and toolbars you see in desktop programs. Buttons look great in navigation bars, but you can also use them for any small (one- or two-word) links on your pages. Your main allies in this task are the `border`, `background-color`, and `padding` properties. With them, it's easy to create a wide range of boxy-looking buttons (see Figure 9-2).

Say you added a class to a link that you'd like to style as a button: `Free Donuts Here!`. To add a basic black outline around this link (like the top-left image in Figure 9-2), you'd create this style:


```
a.button {
  border: solid 1px #000;
}
```

You can get fancier by adding a background color as well, like so:

```
a.button {
  border: solid 1px #000;
  background-color: #333;
}
```

NOTE

In these examples, both `a.button` or `.button` would work for style names. In the case of `a.button`, the style only applies to `<a>` tags with the class `button`, while `.button` applies to any tag with that class name. If you want to make sure the style only applies to a particular tag, then add the tag name to the beginning. Adding the tag name is also a helpful reminder when looking over your CSS code—it provides a valuable clue as to what the style is intended to format. When you see `a.button`, it's clear that the style is aimed at particular links.



Mind you, all four borders don't need to be the same width, type, or color. You don't even have to have four borders. One common design technique is to add a beveled look to a button using four different border colors, as shown at top right in Figure 9-2. Creating the beveled look isn't difficult, but you need to remember what makes something look three-dimensional—the light source. Imagine a light shining on one of the four sides; that side is the lightest, while the side opposite is the darkest (since the raised button is blocking the light and putting that side into a “shadow”). The other two sides should have shades in between the “lit” and “shadow” borders. Here's the CSS used to create the beveled design in the top-right corner of Figure 9-2:


```

a.button {
  background: #B1B1B1;
  color: #FFF;
  font-weight: bold;
  border-width: 4px;
  border-style: solid;
  border-top-color: #DFDFDF;
  border-right-color: #666;
  border-bottom-color: #333;
  border-left-color: #858585;
}

```

Keep in mind that you can (and probably should) create a `:hover` state for your buttons as well. That way, your buttons can react when a visitor moves her mouse over the link, providing useful visual feedback. In the case of a beveled button, reversing the various colors—make a dark background lighter, a light border darker, and so on—is very effective.

Using linear gradients and rounded corners, box and text shadows can really add depth to a button. For example, the button in the bottom middle of Figure 9-2 is created with this code:

```

1. background-color: #ee432e;
2. background-image: -webkit-linear-gradient(top, #ee432e 0%, #c63929 50%,
   #b51700 50%, #891100 100%);
3. background-image: -moz-linear-gradient(top, #ee432e 0%, #c63929 50%,
   #b51700 50%, #891100 100%);
4. background-image: -o-linear-gradient(top, #ee432e 0%, #c63929 50%, #b51700
   50%, #891100 100%);
5. background-image: linear-gradient(top, #ee432e 0%, #c63929 50%, #b51700
   50%, #891100 100%);
6. border: 1px solid #951100;
7. border-radius: 5px;
8. box-shadow: inset 0px 0px 0px 1px rgba(255, 115, 100, 0.4), 0 1px 3px
   #333333;
9. padding: 12px 20px 14px 20px;
10. text-decoration: none;
11. color: #fff;
12. font: bold 20px/1 "helvetica neue", helvetica, arial, sans-serif;
13. text-align: center;
14. text-shadow: 0px -1px 1px rgba(0, 0, 0, 0.8);

```

Line 1 sets a deep red background color; this color is provided for browsers that don't understand linear gradients (IE 9 and earlier as well as other older browsers). Lines 2–5 set up a linear gradient for various browsers. Line 6 adds a simple border, while

line 7 creates the rounded corners and line 8 adds a subtle inset shadow and a second drop shadow below the button; in other words, it applies two drop shadows, which is perfectly legal, as described on page 211. Line 9 adds padding to provide space around the button text and the button border, while line 10 removes the underline that normally appears below links. The last lines set properties for the text in the button including its color, font, alignment, and text shadow.

TIP Creating great looking buttons often involves piling on the CSS properties (as you can tell from the above code). If you need a little help creating all that code, check out the CSS3 Button generator <http://css3button.net>. To see other great examples of CSS3 buttons, visit <http://hellohappy.org/css3-buttons/> and <http://webdesignerwall.com/tutorials/css3-gradient-buttons>.

Using Graphics

Adding graphics to links is one of the easiest and most visually exciting ways to spruce up your site's navigation. There are any number of possible techniques and designs, but none of the good ones involve an HTML `` tag. Instead, you can easily add attractive and informative imagery to any link using the CSS `background-image` property. You can see several examples in Figure 9-3. (You'll also learn more advanced techniques for using images to create graphical buttons and rollovers starting on page 314.)




FIGURE 9-3

Even a simple graphic can enliven a link and make its purpose clearer. A globe icon (bottom left) is one way to indicate an external link.

If you need a refresher on `background-image` and related properties, flip back to page 240. Meanwhile, here are a few things to keep in mind when you use images with links:

- **Don't forget no-repeat.** Normally a background graphic tiles repeatedly in the background. With many graphics, that effect looks awful for links (top right, Figure 9-3). Unless you're using a subtle pattern like a gradient fill, remember to set the repeat option to stop the tiling like this: `background-repeat: no-repeat;`

- **Control placement with background-position.** To place an image accurately in the background, use the `background-position` property (page 246). When you want to place an image on the far-right edge of a link but centered vertically on the line, use this CSS: `background-position: right center`.

For more accurate placement, use a specific value such as pixels or ems. These units of measurement make it easy to scoot a graphic a couple of pixels away from the left edge of the link. By combining these units with a percentage value, you can easily center a graphic vertically within a link but place it an exact amount away from the left edge: `background-position: 10px 50%`;

TIP In positioning background images, the first value is the horizontal placement (left to right); the second is vertical placement (top to bottom).

Unfortunately, there's no way to exactly place an image from the right or bottom edges. So if you want to move an image in from the right edge a bit, then you have two options: First, in your image-editing program, you can add empty space to the right edge of the graphic. The amount of empty space you add should be equivalent to how much you want to indent that graphic from the right. Once you've created the graphic, use the `background-position` property to place the graphic on the right edge of the element: for example, `background-position: right top`; Or you can use percentage values: `background-position: 90% 75%`; places the point that lies 90 percent from the left edge of the image on top of the point 90 percent from the left edge of the styled element. As you can imagine, this method doesn't provide complete accuracy, so you'll need to experiment a little. (See page 249 for more on how percentage positioning works.)

- **Padding gives you room.** If you're using an image or icon to mark a link, then make sure to add padding on the side the image is on to move the link text out of the way. For instance, the third example in Figure 9-3 has 30 pixels of left padding to prevent the word "Home" from overlapping the picture of the house, while a little right padding makes room for the globe in the bottom-left image.

NOTE Since the `<a>` tag is an inline element, adding top and bottom padding (or, for that matter, top and bottom margins) has no effect. See page 200 for the reason why. You can, however, turn a link into a block-level element (`display: block`) so it can accept top and bottom padding and margins, or use the `inline-block` setting (`display: inline-block`). You'll see both of these techniques later in this chapter.

- **Use the pseudo-classes.** Don't forget the `:hover` and `:visited` pseudo-classes. They can add great dynamic effects and provide helpful feedback about your links. You can swap in a *different* background graphic for any of these pseudo-classes. So you could, for example, have a dim light bulb graphic in the background of a normal link but change that graphic to a lit bulb when the mouse travels over it.

Should you decide to use a graphic for a link's `:hover` state, keep in mind that browsers don't download the graphic until your visitor's mouse actually hovers over the link, so there'll be a noticeable delay before the graphic appears. Once the graphic is downloaded, however, the delay goes away. See page 313 for a technique to prevent this awkward problem.

■ Building Navigation Bars

Every site needs good navigation features to guide visitors to the information they're after—and help them find their way back. Most sites are organized in sections, such as Products, Contact Info, Corporate Blog, and so on. This structure lets visitors know what information to expect and where they can find it. Much of the time, you find links to a site's principle sections in a *navigation bar*. CSS makes it easy to create a great-looking navigation bar, rollover effects and all.

Using Unordered Lists

At heart, a navigation bar is nothing more than a bunch of links. More specifically, it's actually a *list* of the different sections of a site. Back in Chapter 1, you learned HTML's mission is to provide meaningful structure to your content. Accordingly, you should always use a tag that's appropriate to the meaning of that content. For a list of items, that's the `` or unordered list tag—the same one you use to create bulleted lists. It doesn't matter whether you want your list to have *no* bullets or to stretch horizontally across the top of the page: You can do all that by styling the `` tag with CSS. Figure 9-4 shows an example.



FIGURE 9-4

Using CSS, you can bend ordinary HTML `` tags to your will and turn them into either vertical or horizontal navigation bars. To paraphrase a classic movie line, “We don’t need no stinkin’ bullets.”

The HTML for a nav bar is straightforward. There's a single link inside each individual list item. Also, you need a way to style just that unordered list. (You don't want *actual* lists of items to look like navigation bars.) Applying a class or id to the `` tag is a good approach:

```
<ul class="nav">
<li><a href="index.html">Home</a></li>
<li><a href="news.html">News</a></li>
<li><a href="reviews.html">Reviews</a></li>
</ul>
```

The CSS varies a bit depending on whether you want a horizontal or vertical navigation bar. In either case, you need to do two things:

- **Remove the bullets.** Unless the navigation bar is supposed to look like a bulleted list, remove the bullets by setting the `list-style-type` property to `none`:

```
ul.nav {
  list-style-type: none;
}
```

- **Eliminate padding and margins.** Since browsers indent list items from the left, you need to remove this added space as well. Some browsers do the indenting using padding, and others use margin, so you need to set both to 0:

```
ul.nav {
  list-style-type: none;
  padding-left: 0;
  margin-left: 0;
}
```

These two steps essentially make each list item look like any plain old block-level element, such as a paragraph or headline (except that a browser doesn't insert margins between list items). At this point, you can begin styling the links. If you want a vertical navigation bar, read on; for horizontal nav bars, see page 307.

Vertical Navigation Bars

A vertical navigation bar is just a bunch of links stacked one on top of the next. Removing the bullets, left margin, and padding (as explained in the previous section) gets you most of the way there, but you need to know a few additional tricks to get things looking right:

1. Display the link as a block.

Since the `<a>` tag is an inline element, it's only as wide as the content inside it. Buttons with different length text (like Home and Our Products) are different widths. The staggered appearance of different width buttons stacked on top of each other doesn't look good, as you can see in #1 in Figure 9-5. In addition, top and bottom padding and margins have no effect on inline elements. To get around these limitations, style the link as a block element:

```
ul.nav a {
  display: block;
}
```

The block value not only makes each button the same width, but it also makes the entire area of the link clickable. That way, when your visitors click areas where there's no link text (like the padding around the link), they still trigger the link.

2. Constrain the width of the buttons.

Making links block-level elements also means they're as wide as the tag they're nested in. So when they're just sitting in a page, those links stretch the width of the browser window (#2 in Figure 9-5). You have several ways to make them a little narrower. First you can just set the width of the `<a>` tag. If you want each button to be 8 ems wide, for example, then add that to the width property:




FIGURE 9-5

In just a few easy steps, you can turn an unordered list of links into an attractive navigation bar.

```
ul.nav a {
  display: block;
  width: 8em;
}
```

Setting a width for any of the tags that wrap around those links—such as the `` or `` tags—also works.

If the button text occupies only one line, you can also center the text vertically so there's equal space above and below the link text. Just add a height to the link *and* set its `line-height` property to the same value:

```
a {  
  height: 1.25em;  
  line-height: 1.25em;  
}
```

NOTE You may not need to set an explicit width if the nav bar is inside a page layout element that itself has a width. As you'll read in Part Three, it's easy to create a sidebar that hugs the left (or right) edge of a page. The sidebar has a set width, so plopping the unordered list nav bar inside it automatically constrains the width of the buttons.

Now that all this busywork is out of the way, you can style the buttons to your heart's content. Add padding, background colors, margins, images, or whatever tickles your artistic fancy. If you want to spread the buttons out so they don't touch, then add a bottom (or top) margin to each link.

Horizontal Navigation Bars

CSS lets you turn a set of stacked list items into a side-by-side presentation of links, like the one shown back in Figure 9-4. This section shows you two common ways to create a horizontal navigation bar from a list. The first—using the `display: inline` property—is easy, but it usually leads to a small gap between buttons. There's a way around this, but it involves fussing with your HTML. If you want a horizontal nav bar where buttons touch, then turn to the floated `` method described on page 310.

WORKAROUND WORKSHOP

When Borders Bump

In a vertical navigation bar, if the buttons touch, you'll see a double border between two buttons. In other words, the bottom border from one button touches the top border of the next button.

To get around this, add the border to only the *top* of each link. That way, you'll get just one border line where the bottom from each button touches the top from the next.

This workaround, however, leaves the entire nav bar borderless below the last link. To fix that problem, you can either create a

class with the correct bottom border style and apply it to the last link, or better yet, add a bottom border to the `` tag that encloses the nav bar. (You'll see this trick in action in this chapter's tutorial beginning on page 324.)

The same holds true when you have horizontal links. In this case the right and left borders of adjacent buttons touch. Just turn off the left borders on the buttons and add a left border to the containing tag—the `` tag, for example.

Whichever method you use, start by removing the bullets and left space from the `` tag, as illustrated in #1 in Figure 9-6.




FIGURE 9-6

Creating a horizontal menu from an unordered list of links requires just a few steps. However, using the inline and inline-block method results in a noticeable gap between the buttons (circled). The reason for this gap is described at the bottom of page 309.

■ USING DISPLAY: INLINE AND DISPLAY: INLINE-BLOCK

The simplest method of creating a horizontal navigation bar involves changing the display property of the list items from block to inline. It's easy to do using CSS.

- 1. Create a style for the unordered list to remove any padding, margins, and bullets.**

```
ul.nav {
  margin-left: 0px;
  padding-left: 0px;
  list-style: none;
  border-bottom: 1px dashed #000;
}
```

In this case, you've also added a bottom border, which will appear under the buttons (see #1 in Figure 9-6).

- 2. Make the list items inline elements.**

Inline elements don't create a line break before or after them as block-level elements do. Setting the display property of the tags to inline makes them appear one beside the other (#2 in Figure 9-6).

```
.nav li { display: inline; }
```

You need to make sure you don't have too many buttons, though. If they don't all fit side by side, some will drop down below the first row.

NOTE You could also use `inline-block` for the above style, but only if you don't care about Internet Explorer 7, which only lets you apply `inline-block` to inline elements like links, not to block-level elements like the `` tag.

3. Style the links.

You can remove the underline beneath the links and add a border around them instead. You can also add background color or a background image to provide visual depth. Add padding if you need more room around each link's text. If you want some space between each button, then apply a right margin. The following style gives links a button-like appearance, as shown in #3 in Figure 9-6:

```
.nav a {
  display: inline-block;
  border: 1px dashed #000;
  border-bottom: none;
  padding: 5px 15px 5px 15px;
  background-color: #EAEAEA;
  text-decoration: none;
  color: #333;
}
```

First, you need to set the `display` property of the links to `inline-block`. This makes sure that top and bottom padding and margins are obeyed (as described on page 200, normally inline elements ignore top and bottom padding and margins as well as width and height values). Then you can style the buttons to your heart's content. Here, you've added a border to the links and removed the bottom border so it doesn't double up on the bottom border applied to the unordered list.

TIP You can make the buttons all equal in size by setting the width of the links.

To make this horizontal nav bar appear in the center of the page, add `text-align: center;` to the `` tag's style. In fact, this is one benefit of this technique over the float technique described next—when you use `inline` and `inline-block`, you can center your nav bar, which you can't do with floats.

You will, however, notice that the buttons don't touch (see the circled area in Figure 9-6). That has to do with the way web browsers treat the white space between the `` tags. For example, take this example HTML:

```
<ul class="nav">
  <li><a href="index.html">Home</a></li>
  <li><a href="news.html">News</a></li>
  <li><a href="reviews.html">Reviews</a></li>
</ul>
```

Web browsers treat any white space (a tab, carriage return, or space character) between a closing `` and the next `` as a space. There are a couple of ways to remove this space:

- Put the closing `` and opening `` on the same line like this:

```
<ul class="nav">
<li><a href="index.html">Home</a></li><li>
<a href="news.html">News</a></li><li>
<a href="reviews.html">Reviews</a></li>
</ul>
```

This kind of code isn't normally written this way, and a program like Dreamweaver definitely wouldn't write it this way. To remove the space, you have to get in and change the code by hand.

- Add a negative right margin to the list items. For example, you could change the `li` style in Step 2 above to this:

```
.nav li {
    display: inline;
    margin-right: -5px;
}
```

The negative margin value basically pulls the following list item over 5 pixels to close up the gap between the buttons. The problem with this technique is that the exact value you use will vary depending upon the size of the text—5 pixels may or may not work—so you'll need to experiment to get the proper value.

■ USING FLOATS FOR HORIZONTAL NAVIGATION

Another more popular technique is to float the list items. This method also places the links side-by-side. In addition, this technique doesn't suffer from the spacing problem of the inline method.

NOTE

Nav bars made up of floated elements are hard to center horizontally in the middle of a page. When you need to do that, the `inline` method described on page 308 is better.

1. Float the list items.

Adding a left float to the `` tags removes them from the normal top-down flow of elements:

```
.nav li { float: left; }
```

The floated list items (along with their enclosed links) slide right next to each other, just like the images in the photo gallery tutorial on page 278. (You can just as easily float them right if you want those buttons to align to the right edge of the screen or containing sidebar.)

FREQUENTLY ASKED QUESTION

Pop-up Menus

How do I create those cool pop-up menus that display a sub-menu of links when someone rolls his mouse over a button?

Navigation bars that have multiple levels of menus that pop up or slide out are extremely popular. They're a perfect way to cram a lot of link options into a compact navigation bar. You can create them in a couple of ways.

First, there's the CSS-only approach. You can find a basic tutorial on the process at <http://line25.com/tutorials/how-to-create-a-pure-css-dropdown-menu>. For a spiffy CSS menu that uses CSS transitions to animate the appearance and disappearance of the drop-down menus, check out www.red-team-design.com/css3-animated-dropdown-menu.

If you're not the do-it-yourself type, or if you're just in a hurry, you can use the free Pure CSS Menu generator—a wizard-like web page that produces the necessary HTML and CSS for you: <http://purecssmenu.com>.

The one disadvantage to the CSS approach is that the sub-menus disappear instantly if your visitor's mouse strays. You can hope that all your visitors have excellent reflexes, or you can try a different approach: Use CSS to style the buttons and JavaScript to control the actions of the submenu. For a very simple JavaScript menu, try the jQuery Navigation Plug-in at <https://github.com/dansdom/plugins-navigation>.

2. Add display: block to the links.

Links are inline elements, so width values (as well as top and bottom padding and margins) don't apply to them. Making a browser display the links as block elements lets you set an exact width for the button and add a comfortable amount of white space above and below each link:

```
ul.nav a { display: block; }
```

3. Style the links.

Add background colors, borders, and so on.

4. Add a width.

If you want the nav buttons to have identical widths, set a width for the `<a>` tag. The exact width you use depends on how much text is in each button. Obviously for a link like Corporate Philosophy, you need a wider button.

If you want each button to be simply the width of the text inside, don't set a width. You can, however, add left and right padding to give the text some breathing room.

TIP

To center the text in the middle of the button, add `text-align: center;` to the links' style.

5. Add overflow: hidden to the tag style.

If it has a border, background color, or image, you should need to “contain the float”—that is, the floated list items inside the will appear to pop out of the bottom of the list (and outside the tags border or background color).

```
ul.nav {  
    overflow: hidden;  
}
```

Here are the styles required to create the navigation bar pictured in Figure 9-7. Notice that the buttons are the same width, and the button text is centered.

```
.nav {  
    margin: 0px;  
    padding: 0px;  
    list-style: none;  
    border-bottom: 3px solid rgb(204,204,204);  
    overflow: hidden;  
}  
  
.nav li {  
    float: left;  
}  
  
.nav a {  
    width: 12em;  
    display: block;  
    border: 3px solid rgb(204,204,204);  
    border-bottom: none;  
    border-radius: 5px 5px 0 0 ;  
    padding: 10px;  
    margin-right: 5px;  
    background-color: rgb(95,95,95);  
    background-image: -webkit-linear-gradient(rgb(175,175,175), rgb(95,95,95));  
    background-image: -moz-linear-gradient(rgb(175,175,175), rgb(95,95,95));  
    background-image: -o-linear-gradient(rgb(175,175,175), rgb(95,95,95));  
    background-image: linear-gradient(rgb(175,175,175), rgb(95,95,95));  
    text-decoration:none;  
    color: white;  
    text-align: center;  
    font-family: Arial, Helvetice, sans-serif;  
    font-weight: bold;  
}
```



Heading for this page

FIGURE 9-7

Floating list items let you create equal-width buttons for a navigation bar like this one. You can see the actual CSS that created this bar on the facing page.

FREQUENTLY ASKED QUESTION

Where to Get Navigation Bar Help

I've never made a nav bar before, but I really want my site to have one. I just don't think I can put it all together on my own. Is there something that walks me through the whole process for the first time?

Yes. In fact, there's a tutorial in this very chapter that shows you step by step how to create a navigation bar. Just flip to page 324.

Online, you can find tutorials, plus tools that do some of the work for you.

For more information on turning ordinary lists into extraordinary navigation elements, visit the step-by-step list tutorial at: <http://css.maxdesign.com.au/listtutorial>.

You can also find loads of cool list-based navigation designs at <http://css.maxdesign.com.au/listamatic>.

Finally, if you just don't want to bother creating your own, then try the List-O-Matic wizard at www.accessify.com/tools-and-wizards/developer-tools/list-o-matic. This site is for certain information, like fonts and colors, and can create the CSS you need for list-based navigation. It even lets you create submenus (a.k.a. drop-down menus).

■ CSS-Style Preloading Rollovers

In the bad old days, making a graphical link change to another graphic when moused over required JavaScript. With CSS, you can achieve similar effects with the `:hover` pseudo-class and a background image. However, there's one problem with the CSS method: Unless your visitor has already downloaded the rollover graphic, there's a noticeable delay while the browser sucks down the new graphic and displays it. The delay happens only the first time the visitor hovers over the link, but still, waiting for graphics to load is very 20th century.

The JavaScript solution can avoid this problem thanks to a technique called *preloading*, which automatically downloads the rollover graphic well before it's needed. But CSS doesn't give you that option, so you need to enlist another clever maneuver called *CSS Sprites*, which utilizes a single graphic to create different states for the same button.

NOTE

CSS Sprites are used widely by companies like Yahoo and Google, not just for rollover effects but also to optimize the download speed of websites. You can learn more about them at <http://coding.smashingmagazine.com/2009/04/27/the-mystery-of-css-sprites-techniques-tools-and-tutorials/>.

Here's how to implement the method:

- 1. In your favorite image-editing program, create one image with different versions of the button.**

You might create a regular state, a rollover state, and maybe even a “you are here” state. Place the images one on top of the other, with the regular link image on top and the rollover image below.

NOTE

Fireworks CS6 has a built-in tool for creating CSS sprites. There are also many online tools to help you create them: SpritePad (<http://spritepad.wearekiss.com>) is one example.

- 2. Measure the distances from the top of the entire graphic to the top of each image.**

In Figure 9-8 (top), the rollover image's top edge is 39 pixels from the top of the graphic.

- 3. Create a CSS style for the regular link.** Include the image in the background and place it at the left top of the style (Figure 9-8, middle).

Your style may look something like this:


```
a { background: #E7E7E7 url(images/pixy.png) no-repeat left top; }
```

- 4. Create the `:hover` style.**

Here's the trick: Use the `background-position` property to shift the graphic *upwards*, so the first image disappears and the rollover image becomes visible (Figure 9-9, bottom).

```
a:hover { background-position: 0 -39px; }
```

Besides preventing the dreaded download delay, this technique helps you keep your navigation graphics organized in a single file.



NOTE Some websites take this technique to the extreme. Yahoo, Amazon, and Google (among many others) often put together dozens of little images into a single file and display only the portion of the file containing the desired button. You can see an example from Amazon here: www.flickr.com/photos/mezzoblue/3217540317. Sites with millions of daily viewers benefit from complex sprites, since it's easier and faster for a web server to send a single (albeit bigger) image file than dozens of smaller files.

On a more manageable level, the website of one well-known designer uses a single graphic to manage the 15 different buttons on her navigation bar. You can read about her technique at http://veerle-v2.duoh.com/blog/comments/the_xhtml_css_template_phase_of_my_new_blog_part_2/. You can also see this technique in action in this chapter's tutorial, in Step 8 on page 320.

■ Styling Particular Types of Links

Web designers link to all sorts of things: other web pages on their sites, web pages on other sites, Adobe Acrobat files, Word documents, and zip archive files, to name a few. To help guide your site's visitors, you might want to supply clues to let them know where a link leads before they click it. Advanced selectors are a great way to do just that.

Links to Other Websites

You can easily create a style that identifies links to other websites using an attribute selector. As you read on page 72, attribute selectors let you style HTML tags that have a particular attribute—for example, an `` tag with the `alt` attribute set to *Our Company*. You can also style tags whose attributes *begin* with certain values. Any link that points outside your site must be an absolute URL (see the box on page 244), meaning it must begin with `http://`—for example, `http://www.yahoo.com`. So to create a style that only affects links using an absolute URL, you use this selector:

```
a[href^='http://']
```

The `^=` translates to “begins with,” so this selector matches links like ``, ``, and so on.

You could style these any way you’d like, but one common technique is to add a small image next to the link—an icon indicating an external link. You’ll see this in action on page 321 of this chapter’s tutorial.

If you happen to use absolute links to point to other pages in *your* site, then you’ll need to add another style to “turn off” the styling—otherwise, you’ll end up highlighting those links as external links, when in reality they’re just links within your site. This second style just uses a more detailed version of the selector listed above. For example, if your site is located at `www.mysite.com`, then you can create a selector that applies to those links like this: `a[href^='http://www.mysite.com']`. Putting this all together, if you want to add a globe icon next to external links, but not for links within your site, you can create these two styles:

```
a[href^='http://'] {
    background: url(images/globe.png) no-repeat center right;
    padding-right: 15px;
}

a[href^='http://www.mysite.com'] {
    background: none;
    padding-right: 0;
}
```

NOTE

If you want to get really fancy with your CSS, you can combine the attribute selector with the CSS3 `:not()` selector to create a single style that will affect all absolute URLs *except* ones pointing to your own site:

```
a[href^='http://']:not(a[href^='http://www.mysite.com'])
```

This crazy-looking selector translates to “select all links that begin with `http://`, but *not* the ones that begin with `http://www.mysite.com`.” The downside of this technique is that Internet Explorer 8 and earlier don’t understand the `:not()` selector.

Email Links

Email links are another special kind of link. Normally, email links look just like any other link—blue and underlined. However, they don't act like any other link. Clicking one launches a visitor's email program, and some people find starting up a new program while browsing a website really distracting, so let 'em know it's for email.

The same basic technique described for external links above applies. Since all email links begin with `mailto:`, you can create a selector like the following to create a style to format just email links:

```
a[href^='mailto:']
```

You'll see an example of this in action in the tutorial on page 321.

Links to Specific Types of Files

Some links point to files, not other web pages. You often see a company's annual report online as a downloadable PDF file or a zip archive of files (like the tutorials for this book) on a website. Links to those types of files usually force the browser to download the file to the visitor's computer, or, for PDF files, launch a plug-in that lets you view the file within the browser. It can be a real drag to click a link, only to find out that it's actually started a 100MB download!

You can identify specific file types in much the same way as external links or email links. But instead of looking for specific information at the beginning of the link's URL, you can find it at the end. For example, a link to a PDF document might look like this ``, while a link to a zip archive could look like this: ``. In each case, the specific file type is identified by an extension at the end of the URL—.pdf or .zip.

CSS provides an attribute selector that lets you find attributes that end with specific information. So to create a style for links to PDF files, use this selector:

```
a[href$='.pdf']
```

`$=` means “ends in,” so this selector means “select all links whose href attribute ends in .pdf.” You can create similar styles for other types of files as well:

```
a[href$='.zip'] /* zip archive */  
a[href$='.doc'] /* Word document */
```

You'll see examples of this technique in the tutorial on page 323.

■ Tutorial: Styling Links

In this tutorial, you'll style links in a variety of ways, like adding rollovers and background graphics.

To get started, download the tutorial files from this book's companion website at www.sawmac.com/css3. Click the tutorial link and download the files. All the files are enclosed in a zip archive, so you need to unzip them first. (You'll find detailed instructions on the website.) The files for this tutorial are contained inside the *09* folder.

Basic Link Formatting

1. **Launch a web browser and open the file *09→links→links.html*.**

This page contains a variety of links (circled in Figure 9-9) that point to other pages on the site, links to pages on other websites, and an email address. Start by changing the color of the links on this page.

2. **Open *links.html* in a text editor and place your cursor between the opening and closing `<style>` tags.**

The page already has an external style sheet attached to it with some basic formatting, plus the `<style>` tags for an internal style sheet.

NOTE

As you've done before, you'll put the styles for this exercise into an internal style sheet for easy coding and previewing. When done, it's best to move the styles to an external style sheet.

3. **Add a new style to the internal style sheet:**

```
<style>
a {
  color: #207EBF;
}
</style>
```

This style is about as generic as it gets. It will apply to all `<a>` tags on the page. It's a good place to start, since it sets up the overall look of links for the page. You'll add more styles that will let you pinpoint links in specific areas of the page. Now, time to remove that boring old underline beneath the link.

4. **Add `text-decoration: none;` to the style you just created.**

This removes the underline, but also makes the link less visible on the page. Remember: you should always do something to make links stand out and seem clickable to your site's visitors.




FIGURE 9-9
Here's a basic web page with links in their standard browser configuration—underlined and blue (or purple, if they're links to previously visited pages). In this case, some links point to other pages on the site, some point to other sites, and one is an email address. In this tutorial, you'll style each of these links differently.

5. Add font-weight: bold; to the a style.

Now links appear in bold (other text may appear bold, too). Next you'll replace the underline, but you'll do it a bit more creatively, using a border instead of the text-decoration property.

6. Add a border declaration to the style, so it looks like this:

```
a {
  color: #207EBF;
  text-decoration: none;
  font-weight: bold;
  border-bottom: 2px solid #F60;
}
```

The links really stand out, and using a border instead of the normal underline applied to links lets you change the line's color, size, and style (Figure 9-10). Now you'll change the look of visited links.

7. Add a `:visited` pseudo-class style for visited links:

```
a:visited {  
  color: #6E97BF;  
}
```

This style changes the look of visited links to a lighter, grayer shade of the main link color—a subtle way to draw attention away from an already visited page. If you preview the page, click one of the links (try one in the middle part of the page) and then return to the `links.html` page. You should see the link get lighter in color. You'll also notice that it stays bold and continues to have the orange underline you assigned to the `a` style in Step 6. That's the cascade in action (Chapter 5)—the `a:visited` style is more specific than a plain `a` selector, so its color property overrides the color assigned by the `a` style.

Time to take it a step further by adding a rollover effect, so the link's background changes color when the mouse moves over it.

8. Add a `:hover` pseudo-class style to the style sheet:

```
a:hover {  
  color: #FFF;  
  background-color: #6E97BF;  
  border-bottom-color: #6E97BF;  
}
```

This pseudo-class applies only when the mouse is over the link. The interactive quality of rollovers lets visitors know the link does something (Figure 9-10).



FIGURE 9-10

With a couple of styles, you can change the look of any link. With the `:hover` pseudo-class, you can even switch to a different style when the mouse moves over the link.

Adding a Background Image to a Link

The email link at the bottom of the page looks no different than the other links on the page (Figure 9-11, top). You have other plans for that `mailto` link, however. Since it points to an email address, clicking it doesn't take a visitor to another page, but instead launches an email program. To provide a visual cue emphasizing this point, you'll add a cute little email icon.

1. Add a descendent selector to the internal style sheet of the `links.html` file:

```
a[href^="mailto:"] {  
  color: #666666;  
  border: none;  
  background: url(images/email.gif) no-repeat left center;  
}
```

This is an advanced attribute selector, which selects any links that begin with `mailto:` (in other words, it selects email links). The `border: none` setting removes the underline defined by the `a` style you created in Step 6—you're going for a subtle look here. The `background` property adds an image on the left edge of the link. Finally, the `no-repeat` value forces the graphic to appear just a single time. Trouble is, the graphic lies directly underneath the link, so it's hard to read the text (circled in the middle image in Figure 9-11).

2. Add 20 pixels of left padding to the *attribute* style you just created:

```
padding-left: 20px;
```

Remember that padding adjusts the space between content and its border. So adding some left padding moves the text over 20 pixels but leaves the background in place. One last touch: move the entire link a little away from the copyright notice.

3. Add 10 pixels of left margin to the style, so it finally ends up like this:

```
a[href^="mailto:"] {  
  color: #666666;  
  border: none;  
  background: url(images/email.gif) no-repeat left center;  
  padding-left: 20px;  
  margin-left: 10px;  
}
```

This small visual adjustment makes it clear that the icon is related to the link and not part of the copyright notice (Figure 9-11, bottom).



FIGURE 9-11

Just a few subtle touches can help make a link's purpose obvious. In this case, a plain link (top) becomes clearly identifiable as an email link (bottom).

Highlighting Different Links

At times you may want to indicate that a link points to another website. In this way, you can give your visitors a visual clue that there's additional information elsewhere on the Internet or warn them that they'll exit your site if they click the link. Also, you may want to identify links that point to downloadable files or other non-web-page documents.

On the web page you're working on, the right-hand "Resources" sidebar contains different types of links that you'll highlight with icons—a different icon for each type of link. First, you'll set up a basic style that applies to all of those links.

1. Add this style to the `links.html` internal style sheet:

```
.resources a {  
    border-bottom: none;  
}
```

Since all of the links you want to format are inside a `<div>` with the class `resources`, the descendent selector `.resources a` targets just those links. This style gets rid of the underline that the generic link style added.

Next, you'll add an icon next to external links.

2. Add another style at the end of the *links.html* internal style sheet:

```
.resources a[href^='http://'] {  
  background: url(images/globe.png) no-repeat right top;  
}
```

This is a descendent selector style that uses the advanced attribute selector discussed on page 317. Basically, it targets any link that begins with *http://* (but only those that are also inside the element with the class *resources*). As with the email link style you created earlier, this style adds a background image. It places the image at the right side of the link.

However, this style has a similar problem as the email link style—the image sits underneath the link's text. Fortunately, the solution is the same—just add some padding to move the image out of the way of the text. In this case, though, instead of adding left padding, you'll add right padding (since the icon appears on the right side of the link). In addition, since every link in the resources box will have a similarly sized icon, you can save some code by adding the padding to the *.resources a* style you created in Step 1.

3. Edit the *.resources a* style so that it looks like this:

```
.resources a {  
  border-bottom: none;  
  padding-right: 22px;  
}
```

If you save the page and preview it in a web browser, you'll see small globe icons to the right of the bottom two links in the sidebar. Time to format the other links.

4. Add three more styles to the internal style sheet:

```
.resources a[href$='.pdf'] {  
  background: url(images/acrobat.png) no-repeat right top;  
}  
  
.resources a[href$='.zip'] {  
  background: url(images/zip.png) no-repeat right top;  
}  
  
.resources a[href$='.doc'] {  
  background: url(images/word.png) no-repeat right top;  
}
```

These three styles look at how the href attribute ends; identifies links to either Adobe Acrobat files (.pdf), zip archives (.zip), or Word documents (.doc); and assigns a different icon in each case.

5. Finally, add a hover state for the resources links:

```
.resources a:hover {
  color: #000;
  background-color: rgba(255,255,255,.8);
}
```

This style both changes the color of the text and adds a background color (see Figure 9-12).

You can find a finished version of this tutorial in the [09_finished/links/links.html](#) file.



FIGURE 9-12

Using advanced attribute selectors, you can easily identify and style different types of links—external links, links to PDF files, Word docs, and zip files.

Tutorial: Creating a Navigation Bar

In this exercise, you'll turn a plain old list of links into a spectacular navigation bar, complete with rollover effects and a “You are here” button effect.

1. In a text editor, open [09](#)→[nav_bar](#)→[nav_bar.html](#).

As you can see, there's not much to this file yet. There's an internal style sheet with the basic reset styles discussed on page 115, and one rule setting up some basic properties for the <body> tag. The HTML consists of an unordered list with six links. It looks like example #1 in Figure 9-13. Your first step is to add some HTML so you can target your CSS to format the links in this list.

2. Locate the opening tag and add `class="mainNav"` to it, so it looks like this:

```
<ul class="mainNav">
```

The class attribute identifies this list as the main navigation area. Use this class to build descendent selectors to format only these links—and not just any old link on the page.




FIGURE 9-13
While it may feel like a lot of steps, transforming a plain unordered list of links into a sophisticated navigation bar requires only a few styles.

3. Below the body style in the internal style sheet, add a new style:

```
.mainNav {
  margin: 0;
  padding: 0;
  list-style: none;
}
```

This style applies only to a tag with an class of mainNav—in this case, the tag. It removes the indent and bullets that browsers apply to unordered lists, as shown in #2 in Figure 9-13. Next, you'll start formatting the links.

4. Add a descendent selector to format the links in the list:

```
.mainNav a {
  color: #000;
  font-size: 11px;
  text-transform: uppercase;
  text-decoration: none;
}
```

This style defines the basic text formatting for the links. It sets the color and font size, makes all letters uppercase, and removes the line usually found underneath links (#3 in Figure 9-13). Now start making the links look like buttons.

5. To the `.mainNav` a style, add the following border and padding properties:

```
border: 1px dashed #999;  
padding: 7px 5px;
```

If you preview the file now, you'll see a few problems (#4 in Figure 9-13): The borders overlap and the boxes aren't the same width. That's because the `<a>` tag is an inline element, so the width of the box is just as wide as the text in the link. In addition, top and bottom padding don't add any height to inline boxes, so the borders overlap. (See page 200 for a discussion of inline boxes.) You can fix these problems by changing how a browser displays these links.

6. Add `display: block;` to the `.mainNav` a style.

You've changed the basic display of the `<a>` tag so it acts like a paragraph or other block-level element, with the links neatly stacked one on top of the other. The only problem now is that they also extend the full length of the browser window—a little too wide for a button. You can fix this by constraining the width of the `` tag's style.

7. In the internal style sheet, locate the `.mainNav` style and add `width: 175px;` to it:

```
.mainNav {  
  margin: 0;  
  padding: 0;  
  list-style: none;  
  width: 175px;  
}
```

With the list's width now set to 175 pixels, the links still expand, but they're limited to the width of their container (the `` tag). In many cases, you'll have a list of links inside some layout element (like a sidebar) that already has a set width, so you'll be able to skip this step. (You'll learn how to add sidebars in Part Three.)

Now for the fun part.

8. Add background properties to the `.mainNav` a style, like so:

```
.mainNav a {  
  color: #000;  
  font-size: 11px;  
  text-transform: uppercase;  
  text-decoration: none;  
  border: 1px dashed #999;  
  padding: 7px 5px;  
  display: block;  
  background-color: #E7E7E7;  
  background-image: url(images/nav.png);  
  background-repeat: no-repeat;  
  background-position: 0 2px;  
}
```

These lines add a gray background color to the links and a non-repeating image at the left edge of each button (#5 in Figure 9-13). You still have a couple of things to fix: The link text overlaps the icon, and the border between each button is 2 pixels thick. (Technically, the borders are still just 1 pixel thick, but the bottom and top borders of adjoining links are creating a 2-pixel line.)

TIP Using the background shorthand property, you can write the code in Step 8 like this: `background: #E7E7E7 url(images/nav.png) no-repeat 0 2px;`

9. Remove the bottom border and adjust the padding for the `.mainNav` a style, so it looks like this:

```
.mainNav a {  
  color: #000;  
  font-size: 11px;  
  text-transform: uppercase;  
  text-decoration: none;  
  border: 1px dashed #999;  
  border-bottom: none;  
  padding: 7px 5px 7px 30px;  
  display: block;  
  background-color: #E7E7E7;  
  background-image: url(images/nav.png);  
  background-repeat: no-repeat;  
  background-position: 0 2px;  
}
```

The text of each link sits clear of the icon and the borders look great...except for one thing. The last link's bottom border is now gone. (Sometimes CSS feels like two steps forward, one step back!) But you have a few ways to fix this snafu. One way is to create a class style with the proper `border-bottom` setting and then apply it to just that last link. But it would be easier to apply a bottom border to the `` tag containing the list of links. (Since there's no padding on that tag, there's no space separating the top of the `` from the top of that first link.)

10. Add a bottom border to the `.mainNav` style so that it looks like this:

```
.mainNav {  
  margin: 0;  
  padding: 0;  
  list-style: none;  
  width: 175px;  
  border-bottom: 1px dashed #999;  
}
```

There you have it: A basic navigation bar using borders, padding, background color, and images (#6 in Figure 9-13).

Adding Rollovers and Creating “You Are Here” Links

Now it's time to add some interactive and advanced features to this nav bar. First, you'll add a rollover effect to the buttons in your main navigation bar. That way, the buttons change to show your visitor which button she's about to click.

It's also considerate to let your visitor know which page of your site she's on. Using the same HTML nav bar you already have, you can make this bit of interactivity happen automatically. You simply make the button's format change to match the page's section. Sounds simple, but it does require a little planning and setup, as you'll see in the following steps.

The rollover effect is easy, so get that out of the way first:

1. In the `nav_bar.html` file, add the following style to the end of the style sheet:

```
.mainNav a:hover {
    font-weight: bold;
    background-color: #B2F511;
    background-position: 3px 50%;
}
```

This style sets the button's hover state. It makes the text inside the button bold, and changes the background color to a vibrant green. In addition, it uses the CSS Sprites technique discussed on page 314. The same image is used as in Step 8 on page 326—however, that image actually holds three different icons (see Figure 9-14). In this case, the image is centered within the button, displaying the middle icon in the file.

Now, moving the mouse over any of the buttons instantly changes its look. (Open the page in your web browser and try it yourself.)




FIGURE 9-14

With some basic CSS, it's easy to create interactive rollover effects for navigation buttons. You can even automatically highlight the section of the site in which the current page is located. To speed up the download of your navigation bar graphics, you can use the CSS Sprites method described on page 314. Basically, you use one image (circled at top right) and adjust its position for different states of each button (bottom row).

Next, make your navigation bar more informative by highlighting the button that matches the section in which the page is located. To do so, you need to identify two things in the nav bar's HTML: the section a page belongs to and the section each link points to. For this example, assume that the page you're working on is the home page.

NOTE Alternatively, you can create a class style that changes the appearance of a link and apply it to the link representing the page's section. For a horoscope page, you'd apply the class to the Horoscope link in the nav bar: `Horoscopes`.

2. Locate the `<body>` tag, and then add `class="home"`, like so:

```
<body class="home">
```

Now that you know what section this page belongs to, you can use a descendent selector to create special CSS rules that apply only to tags on pages within the Features section. Next, you need to identify the section each link applies to, which you accomplish by adding some classes to those links.

3. In the nav bar's HTML code, locate the Home link, and then add `class="homeLink"` so the tag looks like this:

```
<a href="/index.html" class="homeLink">Home</a>
```

This class identifies this link, providing the information you need to create a style that applies only to that link.

You need to add a class to the other links in the navigation bar as well.

4. Repeat Step 3 for each of the other links using the following classes: `featureLink`, `expertLink`, `quizLink`, `projectLink`, and `horoscopeLink`.

You're done with the HTML part of this exercise. Now it's time to create some CSS. Because you've provided classes to identify the different links, it's easy to create a descendent selector to highlight the Home link.

5. Add another style to the page's style sheet:

```
.home .homeLink {  
  background-color: #FFFFFF;  
  background-position: 97% 100%;  
  padding-right: 15px;  
  padding-left: 30px;  
  font-weight: bold;  
}
```

You've seen all these properties before. Again, you're using the CSS Sprites method to adjust the position of the background image. This time, the image is moved over to the right 97 percent (that is, the point 97 percent across the image is matched up with the point 97 percent across the button), and the bottom of the image is placed at the bottom of the button. In other words, it displays the

icon at the bottom of the image (see Figure 9-14). See page 249 for a discussion of how percentage values work with background-images.

The most interesting part is the selector—.home .homeLink. It's a very specific selector that applies only to a link with a class of homeLink that's *also* inside a <body> tag with a class of home. If you change the class of the page to quiz, for example, the link to the Home page is no longer highlighted.

Preview the page in a browser to see the effect: The Home link now has a white background and a paperclip icon. To make this work for the other links, you need to expand this selector a little...OK, make that a *lot*.

6. Edit the selector for the style you just added, like so:

```
.home .homeLink,  
.feature .featureLink,  
.expert .expertLink,  
.quiz .quizLink,  
.project .projectLink,  
.horoscope .horoscopeLink  
{  
  background-color: #FFFFFF;  
  background-position: 97% 100%;  
  padding-right: 15px;  
  padding-left: 30px;  
  font-weight: bold;  
}
```

Yes, that's a lot of CSS. But your setup work here has a big payoff. This style now applies to every link in the nav bar, but only under certain conditions, which is exactly how you want it to behave. When you change the class attribute of the <body> tag to quiz, the link to the Quiz gets highlighted instead of the link to the Features section. Time to take your work for a test drive.

NOTE This long-winded selector is an example of the group selector discussed on page 62.

7. Change the class attribute of the <body> tag to feature like this:

```
<body class="feature">
```

Preview the page, and wham! The Feature link is now highlighted with a white background and a paperclip icon (Figure 9-14). The secret at this point is to just change the class in the <body> tag to indicate which section of the site a page belongs to. For a horoscope page, change the class to class="horoscope" in the <body> tag.

NOTE

Ready to take this design further? Try adding a rollover effect to complement the style you created in Step 6. (Hint: Use the `:hover` pseudo-class as part of the selector like this: `.quiz .quizLink:hover`.) Also try adding a different graphic for the Home link. (You have a `home.png` file in the images folder to use.)

To see the completed version of this navigation bar, see the file `09_finished→nav_bar→nav_bar_vertical.html`.

From Vertical to Horizontal

Suppose you want a horizontal navigation bar that sits at the top of the page. No problem—you did most of the hard work in the last part of this tutorial. Just modify that page a little to spread the buttons along a single line. (You'll use the `nav_bar.html` file you just completed, so if you want to keep the vertical nav bar, then save a copy of the file before proceeding.)

- 1. Make sure you've completed all the steps above to create the vertical navigation bar, and have the file `nav_bar.html` open in your text editor.**

Now you'll see how easy it is to change the orientation of a navigation bar. Start by cleaning up some of the work you already did. You need to remove the width you set for the `` tag in Step 7 on page 326. That width prevented the nav buttons from spanning the entire length of the page. But since the `` needs to spread out much wider to contain the side-by-side buttons, this width has to go.

- 2. Find the `.mainNav` style, and then remove the `width: 175px;` declaration.**

And now it's time for the big secret of horizontal nav bars—placing the buttons side by side.

- 3. Add a new style to your style sheet (directly below the `.mainNav` style is a good spot):**

```
.mainNav li {  
    float: left;  
    width: 12em;  
}
```

This style applies to the `` tag (the list items that hold each link). The first declaration floats the tag to the left. In this way, each `` tag attempts to wrap around to the right side of the previous `` tag. Also, setting the width of the `` tag defines the width of each button. Here, a value of 12 ems provides enough space to contain the longest link name—Horoscopes. When you're working with longer links, you need to increase this value.

If you preview the page now, you'll see the basics are complete. All that's left are some cosmetic enhancements (see the circled areas of #1 in Figure 9-15). First, the bottom border you created in Step 10 on page 327 runs the entire length of the `` tag—wider than the navigation buttons themselves. Even stranger, that bottom border is no longer on the bottom—it's on top of the navigation buttons! In addition, since the buttons sit side by side, their left and right borders combine to make a 2-pixel border between each button. You'll fix that problem now.




FIGURE 9-15

Changing a vertical stack of navigation buttons into the much shorter, side-by-side format of a horizontal navigation bar only takes a couple of steps. Most of your effort involves tweaking styles for cosmetic considerations such as borders and background image placement.

4. In the `.mainNav` a style, change `border-bottom: none;` to `border-left: none;`

This change removes the left border so that the borders don't double up between buttons and at the same time adds a border to the bottom of each button. But that `` tag's bottom border is still on top of the buttons, and now the nav bar is missing a border on the far-left button (see circled areas of #2 in Figure 9-15). No problem—just change the border on the `` tag.

5. Locate the `.mainNav` style and change `border-bottom: 1px dashed #999999;` to `border-left: 1px dashed #999999;`

If you preview the page now, you'll see that the border above the buttons is gone, but there's still no left border (#3 in Figure 9-15). You're witnessing one of the complications of using floats. That is, floating the list items removes them from the normal flow of the document, so web browsers no longer see them as part of the `` tag, and the `` tag shrinks down to nearly no height—that's the reason the `ul`'s bottom border appeared on top as well. (If this whole scenario sounds confusing, it is. That's why there's an entire section of Chapter 13 dedicated to dealing with the issue—see page 425 for the details.)

Fortunately, while the problem is complex, the solution is simple. Add one CSS property to the bulleted list.

6. Add one more property to the end of the `.mainNav` style (changes are in bold):

```
.mainNav {  
  margin: 0;  
  padding: 0;  
  list-style: none;  
  border-left: 1px dashed #999;  
  overflow: hidden;  
}
```

The `overflow: hidden` forces the unordered list to expand. Why does this property work? See the detailed coverage on page 222. Finally, that paperclip aligned to the right edge of the “You are here” button looks funny (#4 in Figure 9-15). You’ll switch its position to the left edge of the button.

7. Locate the “You are here” style you created in Step 6 on page 330. (It’s the one with the crazy, long-winded selector.) Change its background position from `97% 100%` to `3px 100%`. The style should now look like this:

```
.home .homeLink,  
.feature .featureLink,  
.expert .expertLink,  
.quiz .quizLink,  
.project .projectLink,  
.horoscope .horoscopeLink  
{  
  
  background-color: #FFFFFF;  
  background-position: 3px 100%;  
  padding-right: 15px;  
  padding-left: 30px;  
  font-weight: bold;  
}
```

Preview the page, and you’ll find a fully functional horizontal navigation bar (#5 in Figure 9-15).

To see the finished version, open the file *09_finished→nav_bar→nav_bar_horizontal.html*.

NOTE You may want to center the text inside each button. If so, you need to do two things: Add `text-align: center;` to the `.mainNav` a style and adjust that style’s `left-padding` until the text looks absolutely centered.

CSS Transforms, Transitions, and Animations

For the short history of the web, designers have had few options for adding animation to their websites. The humble, goofy-looking animated GIF provides basic animation within an image. Adobe's Flash program lets you create complex animations, and even games and web applications, but its learning curve is steep, and it can't interact with the other HTML on your page, like the images, headlines, and paragraphs that make up most web content. JavaScript lets you animate anything on a web page, but at the cost of learning a full-fledged programming language. Fortunately, CSS3 provides a way to move, transform, and animate any HTML element on a page, without resorting to any of those other technologies.

■ Transforms

CSS3 introduces several properties that transform a web page element, by either rotating it, scaling it, moving it, or distorting it along its horizontal and vertical axes (a process called *skewing*). You can use a transform, for example, to provide a slight tilt (rotation) to a navigation bar, or make an image get twice as big when a visitor mouses over it. You can even combine multiple transformations for some wild visual effects.

The basic CSS property to achieve any of these changes is the CSS transform property. You use this property by supplying the type of transformation you want and a value indicating how much to transform the element. For example, to rotate an element, you supply the keyword `rotate`, followed by the number of degrees to turn it:

```
transform: rotate(10deg);
```

The above declaration rotates the element 10 degrees clockwise.


CSS transforms are relatively new and, for that reason, aren't supported in all browsers. While Internet Explorer 9, Safari, Chrome, Firefox, and Opera support 2D transforms, Internet Explorer 8 and earlier don't. What's more, you need to use vendor prefixes for all current browsers. So, to get the above code working, you need to rewrite it like this:

```
-webkit-transform: rotate(10deg);
-moz-transform: rotate(10deg);
-o-transform: rotate(10deg);
-ms-transform: rotate(10deg);
transform: rotate(10deg);
```

NOTE

Earlier in this book, you've seen other CSS3 properties that require vendor prefixes (`-webkit-linear-gradient`), for example. Thus far, you haven't encountered the `-ms-` prefix, which stands for Microsoft and is aimed at Internet Explorer. Internet Explorer 9 doesn't understand a lot of CSS3 properties, so you don't usually need vendor prefixes for that browser. Internet Explorer 10 (which may be available when you read this) isn't going to use vendor prefixes for most of the CSS3 properties discussed in this book. However, IE 9 *does* understand the `transform` property, so you need to use the `-ms-transform` property to get any transformation to work in that browser.

One strange feature of CSS transforms is that they don't affect other elements around them. In other words, if you rotate an element 45 degrees, it may actually overlap elements above, below, or to the side. Web browsers actually start by setting aside the space the element would normally take up (before the transformation), and then they transform the element (rotate it, enlarge it, move it, or skew it). This process is readily apparent when you increase the size of an element by using a `transform scale` function (page 338). If you increase an element's size two times, the browser enlarges the transformed element but doesn't move any of the surrounding content out of the way, usually causing parts of the page to overlap (Figure 10-1). In other words, the web browser preserves all the other parts of the page just as they would appear if the element wasn't enlarged.

**FIGURE 10-1**

Get out of my way...or not. Transformed elements are pretty much ignored by other elements around them. Enlarging the <div> here (the big square) simply makes it overlap the headline above and below it. The box in the middle, with the dotted outline, represents the div before it was scaled up by two.

Rotate

The transform property's rotate function is easy to understand: you give it a degree value from 0 to 360, and the browser rotates that element the specified number of degrees around a circle (see Figure 10-2). To specify a degree value, use a number followed by deg. For example, to rotate an element 180 degrees, add this declaration:

```
transform: rotate(180deg);
```


NOTE

To save space, these examples don't include all the vendor-prefixes here, but when you put this code into a style sheet, you need to add the `-webkit-transform`, `-moz-transform`, `-o-transform`, and `-ms-transform` properties as well.

You can even use negative numbers to rotate the element counter-clockwise. For example, the element in the top middle of Figure 10-2 is rotated 45 degrees counter-clockwise like this:

```
transform: rotate(-45deg);
```

The value `0deg` provides no rotation, while `360deg` is one complete rotation, and `720deg` is two complete rotations. Of course, looking at an element that's been rotated once, twice, or three times will look just like an element that hasn't been rotated at all (top-left and bottom-right in Figure 10-2), so you're probably wondering why'd you ever use a value of 360 or higher. CSS3 provides a mechanism for animating changes in CSS properties. So, for example, you can make a button spin around four times when a visitor mouses over it by starting with an initial rotation of `0deg` and adding a `:hover` style for that button that has a rotation of `1440deg`. You'll learn how to do this on page 339.




Scale

You can also resize an element, making it bigger or smaller using the `scale` function (see Figure 10-3). For example, to make an element twice as big, you add this declaration:

```
transform: scale(2);
```

The number you supply inside the parentheses is a scaling factor—a number that's multiplied by the element's current size. For example, 1 is no scaling, .5 is half the current size, while 4 is four times the current size. In other words, a number between 0 and 1 shrinks an element, while a number larger than 1 makes it bigger (a value of 0 actually renders the element invisible on the page).



The element and everything inside it is scaled by this number. For example, if you scale a `<div>` tag up by a factor of two, not only would that `div` be twice as wide and tall, but also the text inside would be twice as big, as would any images inside it.

Of course, you may be wondering why you'd ever use this. After all, you could just as easily increase or decrease the width and height of the element, using the CSS width and height properties, and you can scale text size up or down using the `font-size` property. The most common use for `scale` is to make a visual change to an element dynamically on the page. For example, mousing over a button may make that button momentarily bigger. You could achieve this effect with the `:hover` state.

For example, say you have a link on a page with the `.button` class applied. You can create a simple style like this to format that button:

```
.button {
  font: .9em Arial, Helvetica, sans-serif;
  border-radius: .5em;
  background-color: rgb(34,255,23);
  border: 1px solid rgba(0,0,0,.5);
  padding: .5em;
}
```

To really emphasize that button, you can make it get slightly bigger when a visitor mouses over it, like this:

```
.button:hover {
  -webkit-transform: scale(1.2);
  -moz-transform: scale(1.2);
  -o-transform: scale(1.2);
  -ms-transform: scale(1.2);
  transform: scale(1.2);
}
```

When the visitor mouses off the button, the transform is removed and the button returns to its regular size. On page 345, you'll even learn how you can animate this change in size by using CSS transitions.

TIP

You can use a similar idea for images. Display a gallery of small images, and then add a `:hover` style to them so that when a visitor mouses over the image, it grows larger. To make this look good, you should insert the final, enlarged version of the image inside the HTML, but set its size smaller by using either CSS or the `` tag's `width` and `height` properties.

You can even scale the horizontal and vertical dimensions separately. To do this, supply two values separated by a comma inside the parentheses; the first number is the horizontal scale, and the second is the vertical scale. For example, to make an element half as wide but twice as tall, use this declaration:

```
transform: scale(.5,2);
```

You can see the effect at bottom left in Figure 10-3.

CSS3 also provides separate functions for horizontal and vertical scaling: `scaleX` scales along the horizontal axis, while `scaleY` scales vertically. For example, to make an element twice as tall without changing its width, you'd write this:

```
transform: scaleY(2);
```

NOTE

Again, to save space, this example shows only the un-prefixed version of the transform property. For this to work in all browsers, you'll need to add the proper prefix `-webkit`, `-moz`, and so on.

But to make an element three-and-a-half times as wide, but not taller or shorter, you'd use:

```
transform: scaleX(3.5);
```

There's another visual trick that scaling offers: the ability to flip an element upside down and backwards. No one's quite sure what branch of mathematics the W3C used to come up with this system, but if you use a negative number with `scale`, you actually flip an element around. For example, here's how to flip an element upside down and left to right:

```
transform: scale(-1);
```

This produces the image pictured in Figure 10-4, left. You can also flip the element on only one axis. In the middle image in Figure 10-4, the image is flipped only on its horizontal axis. Flipping the element along its vertical axis produces the middle image:

```
transform: scale(-1,1);
```

It produces the effect of a mirror held to the side of the element, or like you've flipped the element over and are looking through its back. What fun!





FIGURE 10-4

There's no end to the ways you can use CSS to confuse and enrage your website's visitors. The box at left is flipped on the horizontal axis, the box in the middle is flipped on the vertical axis, and at right it's flipped both ways. Of course, if you want to create a tribute site to Leonardo DaVinci (www.mos.org/sln/Leonardo/LeonardoRightToLeft.html), creating a mirror image of all the text on a page may be just the thing!

Translate

The `transform` property's `translate` function simply moves an element from its current position a set amount left or right and up or down. By itself, it's really not that useful. As you read on page 335, when a web browser transforms an element, it doesn't rearrange the page; it lays the page out as if the element had no transformation. Accordingly, when you move a `div` or other tag, using the `translate` function, the browser leaves an empty space where the tag would normally appear,

and then draws the element in its new position (see Figure 10-5). If you simply want to position an element on the page, you can use absolute or relative positioning as described in Chapter 15.



However, `translate` does come in handy when you want to make subtle movements in response to a hover or click. For example, in many user interface designs, when you click a button, it moves slightly down and to the left, simulating the look of a real 3D button being pressed into a keypad. You can simulate this effect using the `translate` function and the `:active` state of a link:

```
.button:active {
  -webkit-translate(1px, 2px);
  -moz-translate(1px, 2px);
  -o-translate(1px, 2px);
  -ms-translate(1px, 2px);
  translate(1px, 2px);
}
```

The `translate` function takes two values: the first specifies the horizontal movement and the second the vertical movement. In this example, clicking an element with the `.button` class moves that element one pixel to the right and two pixels down. Use a negative number for the first value to move the element to the left; use a negative number for the second value to move the element up.

You're not limited to pixel values either. Any valid CSS length value—`px`, `em`, `%`, and so on will work.

CSS3 also provides two additional functions for moving an element just to the left or right—`translateX`—and up or down—`translateY`. For example, to move an element up .5 ems, use the `translateY` function like this:

```
transform: translateY(-.5em);
```

The real fun with the translate function is when used with CSS transitions. With the CSS transition, you can then animate the movement of the element, so that it travels across the screen. You'll learn how to do that on page 345.

Skew

Skewing an element lets you slant it on its horizontal and vertical axes: this can give an element a three-dimensional feel (see Figure 10-6). For example, to slant all the vertical lines so that they lean to the left 45 degrees (as in the first image in Figure 10-6), you'd write this code:

```
transform: skew(45deg, 0);
```

To do the same along the Y axis (middle image in Figure 10-6), you'd write this:

```
transform: skew(0,45deg);
```

You can skew an element on both axes at once. For example, here is the code used to produce the third image in Figure 10-6:

```
transform: skew(25deg,10deg);
```

The first value is a degree value from 0deg to 360deg, proceeding in a counter-clockwise direction from the top of the element. For example, in the first image in Figure 10-6, the 45 degrees are represented by a line drawn from the center of the element and rotated 45 degrees counter-clockwise (bottom-left).




FIGURE 10-6

The skew function is one way to simulate a 3D look. However, as you'll see in the box on page 345, CSS3 actually offers a better way to simulate three dimensions, with 3D transforms.

NOTE

Remember to add browser-prefixed versions of the transform property to your finished CSS: `-webkit-transform`, `-moz-transform`, and so on.

The second value is also a degree value from 0deg to 360deg. But this one proceeds in a clockwise position from the right of the element. So the middle image in Figure 10-6 shows a 45-degree slant of all of the horizontal lines.

TIP Visit <http://westciv.com/tools/transforms/index.html> to play with an online tool for visualizing CSS transforms.

As with translate and scale, CSS3 offers separate functions for the X and Y axes: skewX and skewY.

NOTE CSS3 provides yet another transformation method called a *matrix*. A matrix is an array of numbers, as used in advanced algebra. They're pretty mind-bending and not at all intuitive unless you're Stephen Hawking. But if you want to learn how they work, visit <http://dev.opera.com/articles/view/understanding-the-css-transforms-matrix/> for as lucid an explanation as possible.

Multiple Transformations

You're not limited to just a single transformation. You can both scale an image and skew it; rotate it and translate it; or use any of the four different transform functions simultaneously. Simply add additional functions to the transform property, each separated by a space. For example, here's how you can rotate an element 45 degrees and enlarge it to twice its normal size:

```
transform: rotate(45deg) scale(2);
```

Here's an example with all four transformations applied at the same time:

```
transform: skew(45deg,0deg) scale(.5) translate(400px,500px) rotate(90deg);
```

The order in which you place the transform functions is the order in which the browser applies these effects. For example, in the second example, the element is first skewed, then scaled, then translated, and finally rotated. The order doesn't really matter unless you're using translate. Since translate actually moves the element, if you place it before a rotate, for example, the browser first moves the element and then rotates it. Since the element moved first, the point around which it rotates has changed. On the other hand, if you rotate it first, you're then moving the rotated element a certain amount from its center (which is now in a new location).

Origin

Normally, when you apply a transformation to an element, the web browser uses the center of the element as the transformation point. For example, when you rotate an element, the browser rotates it around its center point (Figure 10-7, left). However, CSS3 lets you change that transformation point, using the transform-origin property. It works just like the background-position property (page 246); you can supply keyword values, absolute values in pixels, and relative values in ems and percentages.

For example, to rotate a div around its top-left point (Figure 10-7, middle), you can use the `left` and `top` keywords, like this:

```
transform-origin: left top;
```

You can also use pixel values:

```
transform-origin: 0 0;
```

Or percentages:

```
transform-origin: 0% 0%;
```

Likewise, to rotate an element around its bottom-right corner (Figure 10-7, right), use the `right` and `bottom` keywords:

```
transform-origin: right bottom;
```


Which is also equivalent to:

```
transform-origin: 100% 100%;
```

When using pixel, em, or percentage values, the first number is the horizontal position, and the second is the vertical position.

NOTE

The `transform-origin` property has no effect on elements that are only moved using the `translate` function.



POWER USERS' CLINIC

3D Transforms

CSS3 also offers a much more complex type of transformation. 3D transforms let you simulate a three-dimensional space on the flat screen of a monitor, tablet, or phone.

For a short introduction to 3D transforms, visit <http://coding.smashingmagazine.com/2012/01/06/adventures-in-the-third-dimension-css-3-d-transforms/> and <http://blogs.msdn.com/b/ie/archive/2012/02/02/css3-3d-transforms-in-ie10.aspx>. To see some great examples of 3D transforms in action, visit these sites:

- One of the first examples of the power of 3D Transformations, Apple's Morphing Power Cubes page (www.webkit.org/blog-files/3d-transforms/morphing-cubes.html) demonstrates a rotating cube, which you can change into a rotating set of tiles.
- Another great demo from Apple, the Horizontal 3D picture gallery (<https://developer.apple.com/safaridemos/showcase/gallery/>) lets you flip, carousel-like, through a series of photos.
- Snow Stack: Use left and right arrow keys to send an endless gallery of photos shooting by: <http://www.satine.org/research/webkit/snowleopard/snowstack.html>.
- The 2011 BeerCamp website (<http://2011.beercamp.com>) provides an innovative way to navigate by moving pages “forward” and “backward” through space.

Transitions

While transforms can be fun (especially the rotate function), they really bring your page to life when coupled with a CSS3 transition. A *transition* is simply an animation from one set of CSS properties to another set over a specific amount of time. For example, you can make a banner rotate 360 degrees over the course of two seconds.

To make a transition work, you need a few things in place:

- **Two styles.** One style represents the beginning look of the element—a red nav button, for example—while the second style is the ending look—a blue nav button. The web browser will take care of the process of animating the change between the two styles (changing the button from red to blue, for example).
- **The transition property.** CSS3 adds the transition property—the secret sauce that makes the animation possible. In general, you apply the transition property to the original style, the style that defines the look of an element before the animation begins.
- **A trigger.** The trigger is the action that causes the change between the two styles. With CSS, you can use several pseudo-classes to trigger an animation. The most common is the `:hover` pseudo-class. With it, you can animate the change between an element's normal appearance and how it looks when a visitor mouses over it. You'll see an example of that in just a minute. In addition,

you have `:active` (when the mouse is clicked on an element), `:target` (when an element is the target of link), and `:focus` (when a link is tabbed to, or a form field is clicked into or tabbed to). Beyond that, you can use JavaScript to dynamically change the style of any tag (see the box on page 351).

When the trigger no longer applies—when the visitor mouses off a navigation button, for example—then the browser returns the tag back to its previous style *and* animates the entire process. In other words, you only need to set a transition to an element once, and the browser takes care of animating from one style to another and back to the original style.

A web browser can't animate every single CSS property, but you still have a long list of properties to choose from. In addition to the `rotate`, `scale`, `translate`, and `skew` transformations you just read about, you can also animate `color`, `background-color`, `border-color`, `border-width`, `font-size`, `height`, `width`, `letter-spacing`, `line-height`, `margin`, `opacity`, `padding`, `word-spacing`; the positioning properties—`top`, `left`, `right`, and `bottom`—which you'll learn about in Chapter 15; and many other properties. You can find a complete list at www.w3.org/TR/css3-transitions/#animatable-properties.

NOTE

CSS3 transitions work in most browsers. Unfortunately, when it comes to Internet Explorer, only version 10 and later understand CSS transitions. Because of this, it's best to use transitions simply as a way to add visual excitement. Mostly, this is just fine: IE 9 and earlier will, in most cases, be able to switch between two styles (for example, show a `hover` style) without animating that change.

Adding a Transition

The heart of CSS transitions are four properties that control which properties to animate, how long the animation takes, the type of animation used, and an optional delay before the animation begins. Here's a simple example. Say you want a navigation button's background color to change from orange to blue when a visitor mouses over it. First, you start with the two styles needed to switch between these two colors. For example, you can apply a class of `.navButton` to the link and then create two styles, like this:

```
.navButton {
    background-color: orange;
}

.navButton:hover {
    background-color: blue;
}
```

These styles will work in any browser; hovering over the nav button will change its background from orange to blue. However, the change is instantaneous. To make the color animate over one second, add two new properties to the `.navButton` style, like this:

```
.navButton {
  background-color: orange;
  transition-property: background-color;
  transition-duration: 1s;
}

.navButton:hover {
  background-color: blue;
}
```

The `transition-property` specifies which properties to animate. You can specify a single property (as in the above example), use the keyword `all` to animate all CSS properties that change, or use a comma-separated list to specify more than one (but not all) properties. For example, say you create a `:hover` style so the text color, background color, and border color all change. You list out all three of those properties like this:

```
transition-property: color, background-color, border-color;
```

Or, to make it simple, use the `all` keyword like this:

```
transition-property: all;
```

In most cases, using `all` works well, since every CSS change is animated, which creates a pleasing visual effect.

To specify how long the animation takes to complete, use the `transition-duration` property. This property takes either a value in seconds or milliseconds (thousandths of a second). For example, to make a transition take half a second to complete, you can use either:

```
transition-duration: .5s;
```

Or:

```
transition-duration: 500ms;
```

It's even possible to set separate timings for each animated property. For example, when a visitor mouses over a button, you may want the text color to change rapidly, the background color to change a little more slowly, and the border color to change really slowly. To do so, you need to list the animated properties, using `transition-property` and then list the times, using `transition-duration`, like this:

```
transition-property: color, background-color, border-color;
transition-duration: .25s, .75s, 2s;
```

The order in which you list the times must match the order you list the properties. So, in the above example, `.25s` goes with the `color` property, `.75s` with the `background-color` property, and the `2s` with the `border-color` property. If you move the properties around, then their timing changes.

Unfortunately, like many CSS3 properties, transitions require vendor prefixes to work. In other words, the `.navButton` example above won't work in most browsers until you add the proper vendor prefixes, so you need to rewrite that style like this:

```
.navButton {
  background-color: orange;
  -webkit-transition-property: background-color;
  -moz-transition-property: background-color;
  -o-transition-property: background-color;
  transition-property: background-color;
  -webkit-transition-duration: 1s;
  -moz-transition-duration: 1s;
  -o-transition-duration: 1s;
  transition-duration: 1s;
}
```

You don't need an `-ms` vendor prefix for Internet Explorer since IE 9 and earlier don't understand transitions, and IE 10 understands the non-prefixed versions of the transition properties.

NOTE

As of this writing, current versions of Firefox and Opera no longer require vendor prefixes for transitions. But to make sure your animations still work in older versions of those browsers, it's best to keep using the `-moz` and `-o` vendor prefixes for the time being.

Transition Timing

To have a working, animated transition, you only need to set `transition-property` and `transition-duration`. However, you can control the rate of the animation by using the `transition-timing-function` property. This property can be a little confusing: it doesn't control how long the animation takes (that's what the `transition-duration` property is for). Instead it controls the speed *during* the animation. For example, you can begin the animation slowly and then quickly complete it, creating an effect where the background color changes almost imperceptibly at first and then quickly completes its color change.

The `transition-timing-function` property can take one of five keywords: `linear`, `ease`, `ease-in`, `ease-out`, and `ease-in-out`. If you don't specify a timing function, the browser uses the `ease` method, which begins the animation slowly, speeds up in the middle, and slows down at the end, providing a more organic change. The `linear` option provides a steady change along the entire length of the animation. No option is really any better than the other, they just provide different looks, so try them out to see which one you like best.

To use it, simply add the `transition-timing-function` property and the method you'd like to use:

```
transition-timing-function: ease-in-out;
```

Of course, as with all of these transition properties, you need to add vendor prefixes as well. So to get this line of code to work in as many browsers as possible, you'll need to rewrite it as:

```
-webkit-transition-timing-function: ease-in-out;  
-moz-transition-timing-function: ease-in-out;  
-o-transition-timing-function: ease-in-out;  
transition-timing-function: ease-in-out;
```

NOTE

It's a lot easier to see the different timing functions than to describe them. Visit www.the-art-of-web.com/css/timing-function/ to see an excellent side-by-side comparison of the five timing methods.

You can also use what's called a cubic-bezier value for the `transition-timing-function` property. The Bezier curve plots the progress of the animation over time (see Figure 10-8). If you've used a drawing program like Adobe Illustrator, you're probably familiar with Bezier curves. By adjusting two control points you can control how the line curves: the steeper the line, the faster the animation, the flatter the line, the slower. For example, the Bezier curve pictured in Figure 10-8 starts off steep (the animation begins quickly), then flattens in the middle (the animation slows down), and then grows steep again (the animation rapidly progresses to its final state). To create this kind of animation, add this line of code:

```
transition-timing-function: cubic-bezier(.20, .96, .74, .07);
```

Cubic Bezier curves aren't something you can come up with off the top of your head. You're better off using one of the many online tools for creating and testing different timing functions. Matthew Lein's Ceaser tool is one of the best: <http://matthewlein.com/ceaser/>.

As with the `transition-duration` property, you can apply different timings to different properties.

Ceaser CSS EASING ANIMATION TOOL


Tweet

1. Choose an easing type and test it out with a few effects.
2. If you don't quite like the easing, grab a handle and fix it.
3. When you're happy, snag your code and off you go.

Now that we can use CSS transitions in all the modern browsers, let's make them pretty. I love the classic Penner equations with Flash and jQuery, so I included most of those. If you're anything like me, you probably thought this about the default easing options: "ease-in, ease-out...yawn." The mysterious cubic-bezier has a lot of potential, but was cumbersome to use. Until now. Also, touch-device friendly!

*If you are anything like me, we should be friends @matthewlein

Note: Bugfixes have landed, so the newest Webkit now supports values above 1 and below 0. For the time being, I am including fallback code for older Webkit that is clamped between 0 and 1 when needed.



Code snippets, short and long-hand:

```
-webkit-transition: all 500ms cubic-bezier(0.580, 0, 1.000, 1); /* older webkit */
-webkit-transition: all 500ms cubic-bezier(0.580, -0.600, 1.000, 1.560);
-moz-transition: all 500ms cubic-bezier(0.580, -0.600, 1.000, 1.560);
-ms-transition: all 500ms cubic-bezier(0.580, -0.600, 1.000, 1.560);
-o-transition: all 500ms cubic-bezier(0.580, -0.600, 1.000, 1.560);
transition: all 500ms cubic-bezier(0.580, -0.600, 1.000, 1.560); /* custom */

-webkit-transition-timing-function: cubic-bezier(0.580, 0, 1.000, 1); /* older webkit */
-webkit-transition-timing-function: cubic-bezier(0.580, -0.600, 1.000, 1.560);
-moz-transition-timing-function: cubic-bezier(0.580, -0.600, 1.000, 1.560);
-ms-transition-timing-function: cubic-bezier(0.580, -0.600, 1.000, 1.560);
-o-transition-timing-function: cubic-bezier(0.580, -0.600, 1.000, 1.560);
transition-timing-function: cubic-bezier(0.580, -0.600, 1.000, 1.560); /* custom */
```

If this saves you time, or blows your mind, consider making a [Donation](#) to keep these projects alive.

FIGURE 10-8

Creating a cubic Bezier curve lets you create a wide range of interesting timing functions for your animations. You can make them start really slowly and end quickly, or vice versa. The online Ceaser tool makes creating cubic Bezier curves a breeze: just grab the control handle on the bottom-left point and drag to change the slope of the line, and then drag the control point on the top-right point. The steeper the line, the faster the progress of the animation at that stage. In this example, the line starts off relatively flat, meaning the animation will move slowly at first, then ramps up steeply at the end, meaning the animation will quickly progress to the finish at the end of the transition's duration.

POWER USERS' CLINIC

Using JavaScript to Trigger Transitions

CSS3 transitions are easy-to-use animations built right into web browsers (at least most web browsers). You can create complex effects simply by defining a set of CSS properties to begin with, and a set of CSS properties to end with, and then step out of the way and let the web browser handle the rest.

Unfortunately, you're limited to just a handful of CSS selectors for triggering those transitions. Most commonly, you'll use the `:hover` pseudo-class to make an element change when moused over. You can also use the `:focus` pseudo-class on a form element to make it animate when a user clicks inside it (for example, you can make a multi-line text area grow in height when focused, then shrink to just a few lines when a visitor clicks out of it).

For example, CSS doesn't have a `:click` pseudo-class, so if you want to trigger a transition when someone clicks on an element, you can't do it with CSS. Likewise, if you want to hover over one element but trigger an animation on another element, you're out of luck...if you're only using CSS. But CSS

transitions work anytime a CSS property changes, even if you change the CSS property using JavaScript.

JavaScript is a programming language that lets you add interactivity to web pages, build dynamic user interfaces, and loads of other things. But you can also use JavaScript to simply add or remove a class from an element, or change any CSS property you'd like. Using JavaScript, you can add a class to an image when a visitor clicks a "Show bigger image" link. That new class simply scales up the image (using the `scale` transform discussed on page 367). By adding a transition to the image, you'll have an instant animation.

JavaScript is a big topic worthy of its own book... there just so happens to be *JavaScript & jQuery: The Missing Manual* by this author that's worth a read. But if you want to get started with the simplest way to use CSS transitions triggered by JavaScript, read this short tutorial: <http://www.creativebloq.com/css3/get-more-out-your-css-transitions-jquery-3126395>.

Delaying a Transition's Start

Finally, you can prevent a transition from animating right away with the `transition-delay` property. For example, if you want to wait a half second before the animation begins, you can add this code:

```
transition-delay: .5s;
```

And, of course, this property requires vendor prefixes, so to get this code to work in most browsers, you'd need to write:

```
-webkit-transition-delay: .5s;  
-moz-transition-delay: .5s;  
-o-transition-delay: .5s;  
transition-delay: .5s;
```

Most of the time, you won't want to use a delay for all properties, since it kind of undermines the transition's potential for interactivity. After all, it's more like a cruel trick to make your visitors wait a second before they see any visual changes when they mouse over your button. However, if you're animating several properties, you may want to make one property wait until the others finish before its animation starts. For example, say you have a button whose background color and text color you want to change, and then have its border color change suddenly after the other two properties have finished. Here's how you might do that:

```
.navButton {
  color: black;
  background-color: #FF6603;
  border: 5px solid #660034;
  transition-property: color, background-color, border-color;
  transition-duration: 1s, 1s, .5s;
  transition-delay: 0, 0, 1s;
}

.navButton:hover {
  color: white;
  background-color: #660034;
  border-color: #FF6603;
}
```

As with the `transition-duration` property, you can specify different delay values for each property. The order in which you list the times must match the order of the properties listed for `transition-property`. For instance, in the preceding code, there's no delay for the transition between the color and background color, but there's a one-second delay before the border color changes.

TIP

Usually you put the transition properties into the starting style (for example, `.navButton` on page 348), not the final style (`.navButton:hover`). However, here's a trick for use with CSS drop-down menus (see the box on page 313). One problem with drop-down menus in CSS is that they usually disappear very quickly if you accidentally mouse off the menu. However, you can make the menu appear quickly but disappear slowly using the `transition-delay` property. To do so, you add the following code to the original style:

```
transition-delay: 5s;
```

Then add no delay to the `:hover` style:

```
transition-delay: 0;
```

It's somewhat counterintuitive, but this code basically makes the `:hover` transition happen immediately, with no delay. But to return to the regular style (where the menu disappears) takes 5 seconds. During that time, a visitor has enough time to move his errant mouse back over the menu before it disappears.

Transition Shorthand

Writing out all the different properties—`transition-property`, `transition-duration`, `transition-timing-function`, and `transition-delay`—can get pretty tiring. Especially when you consider you need to also create vendor-prefixed versions of each of those as well. Fortunately, there's a faster way to create transitions—the `transition` property.

This property bundles all of the other properties into one. To use it, simply list the property, duration, timing function, and delay in a space-separated list. For example, to animate all CSS properties for one second using the `ease-in` timing function, with a half-second delay, write the following:

```
transition: all 1s ease-in .5s;
```

You need to list either `all` or a single CSS property and a duration, but the timing function and delay are optional. By default, the timing function is `ease` and there's no delay. So if you simply want to animate the transition of all CSS properties for one second, then write this:

```
transition: all 1s;
```

If you only want to animate the change in the background color, then list that property:

```
transition: background-color 1s;
```

You can only list a single CSS property here, so if you wish to animate multiple CSS properties (but not all), then you can write a comma-separated list of space-separated transition properties. Take the example from page 347, where the `border-color` property is animated separately from the `color` and `background-color`. You can rewrite that code like this:

```
transition: color 1s, background-color 1s, border-color .5s 1s;
```

To make the code easier to read, many web designers put each transition on a separate line, like this:

```
transition: color 1s,  
           background-color 1s,  
           border-color .5s 1s;
```

This is perfectly legal as long as you remember to separate them with a comma and end the whole shebang with a semicolon. And, of course, you need to create vendor-prefixed versions as well:

```
-webkit-transition: color 1s,  
                  background-color 1s,  
                  border-color .5s 1s;  
-moz-transition: color 1s,  
               background-color 1s,  
               border-color .5s 1s;
```

```
-o-transition: color 1s,  
              background-color 1s,  
              border-color .5s 1s;  
transition: color 1s,  
           background-color 1s,  
           border-color .5s 1s;
```

■ Animations

CSS3 provides another, more feature-rich mechanism for creating animations. With CSS transitions, you can only animate from one set of CSS properties to another. CSS3 *animations* let you animate from one set of properties to another set and so on. In addition, you can have an animation repeat, pause when a visitor mouses over it, and even reverse itself once the animation reaches its end.

CSS3 animations are a bit more complicated than transitions, but they have the added benefit of not necessarily needing a trigger to begin the animation. While you can add an animation to a `:hover` state so the animation plays when the mouse hovers over an element, you can also have an animation start when the page loads. This effect lets you draw attention to a banner or logo by animating it across the page when a visitor first enters your site.

NOTE

CSS3 animations, like transitions, don't work in Internet Explorer 9 or earlier. They're well supported in most other current browsers, however.

The first step in creating an animation is creating a set of keyframes. In animation, a *keyframe* is a single frame of an animation that dictates how the scene looks. Suppose the first keyframe shows a ball on one side of a soccer field. By adding a second keyframe, you can define an ending point for the animation—like the ball inside the goal on the other side of the soccer field. A web browser then provides the animation between the two keyframes by drawing all of the intermediate steps—the ball travelling across the field on its way to the goal.

If you're thinking transitions use a similar idea, you're right. In a transition, you define two styles and let the browser animate the change from one style to another. In this way, you could think of each of those styles as a keyframe. However, CSS3 animations let you define *multiple* keyframes, so you can create much more complex animated effects: a soccer ball traveling from one side of the field, to a player, to another player, and then into the goal, for example.

There are two steps in creating an animation:

1. **Define the animation.** This involves setting up keyframes that list the CSS properties to animate.

- 2. Apply the animation to an element.** Once defined, you can apply the animation to any number of elements on a page. You can even set up separate timings, delays, and other animation properties for each element. So you can use the same animation with slightly different settings multiple times on a page.

Defining Keyframes

The first step is to set up your keyframes. The syntax involved may look kind of strange, but here's the basic structure:

```
@keyframes animationName {
  from {
    /* list CSS properties here */
  }

  to {
    /* list CSS properties here */
  }
}
```

You start with `@keyframes`, followed by a name. The name is what you call the animation. You'll end up using that name later when you apply the animation to an element on the page, so make it descriptive, like “fadeOut” or “fadeIn.”

NOTE

The term `@keyframes` isn't a CSS property, it's called an *at rule*. Other *at rules* in CSS include the `@import` statement for loading an external style sheet from another style sheet (page 42), and `@media` to define styles for different types of media such as a printer (page 523) or different screen sizes and resolutions (page 547).

You then add at least two keyframes. In the current example, the keywords `from` and `to` are used to create the beginning keyframe (`from`) and the final keyframe (`to`). Inside each keyframe you add one or more CSS properties—just as if you were creating a style. In fact, you can think of each keyframe as just a CSS style filled with one or more CSS properties. For example, say you want to create an animation that fades an element into view. You could start with an opacity value of 0 (invisible), and end with a value of 1 (fully visible):

```
@keyframes fadeIn{
  from {
    opacity: 0;
  }

  to {
    opacity: 1;
  }
}
```

You're not limited to just two keyframes either. You can use percentage values to define multiple keyframes. The percentage represents where in the overall length of the animation the change should occur. For example, say you want to create an effect where the background of an element changes from yellow to blue to red. You can write this:

```
@keyframes backgroundGlow {
  from {
    background-color: yellow;
  }

  50% {
    background-color: blue;
  }

  to {
    background-color: red;
  }
}
```

In this case, the blue background will appear halfway through the animation. If you want the yellow to last longer and the blue to appear after three-quarters of the animation is complete, use 75% instead of 50%. You can continue to add additional keyframes this way (for example, at 25%, 66%, and so on).

NOTE You can replace the `from` keyword with 0% and the `to` keyword with 100%.

Nor are you limited to a single CSS property. You can place any number of animatable properties (page 346) inside each keyframe—`background-color`, `opacity`, `width`, `height`, and so on:

```
@keyframes growAndGlow {
  from {
    background-color: yellow;
  }

  50% {
    transform: scale(1.5);
    background-color: blue;
  }

  to {
    transform: scale(3);
    background-color: red;
  }
}
```


In the above example, not only does the background color cycle through three colors, it also scales up in size until it's three times its original size.

You can also get pretty tricky with the percentage values by adding multiple percentage values for one set of CSS properties. This is useful in a couple of cases: first, it's good if you want to animate to a certain point, pause, and then continue. For example, say you'd like to begin with a yellow background color for a `<div>` tag. Then you'd like to change that color to blue, stay at blue for a while, and then finish with a red color. In other words, you want a sort of pause in the middle while the background color stays constant before changing again. You can do that with this code:

```
@keyframes glow {
  from {
    background-color: yellow;
  }

  25%, 75% {
    background-color: blue;
  }

  to {
    background-color: red;
  }
}
```

Notice the 25%, 75% in line 5. That means 25% of the way through the animation, the background color of the element should be blue. However, it should be blue 75% of the way through as well. In other words, from the 25% mark to the 75% mark, the background will remain solid blue, before finally turning red. If this animation ran for 4 seconds, then for the middle 2 seconds of the animation, the element's background would remain solid blue.

You can also use percentages when you want to use the same set of CSS properties for different parts of the animation. For example, say you want to animate the background color again, but this time go from yellow to blue to orange to blue to orange to red. Blue and orange appear twice, so instead of writing their background-color properties multiple times, you can instead do this:

```
@keyframes glow {
  from {
    background-color: yellow;
  }

  20%, 60% {
    background-color: blue;
  }

  40%, 80% {
    background-color: orange;
  }
}
```

```
    to {
      background-color: red;
    }
  }
}
```

In this case, the background color will turn blue at the 20% mark, orange at the 40% mark, then blue again at the 60% mark, and orange one last time at the 80% mark before finally turning red.

One downside of CSS3 animations is that they require vendor-specific prefixes (like a lot of CSS3 properties). In other words, you need to repeat your keyframes for *each* browser. So to write this simple fade-in animation so it'll work in as many browsers as possible, you have to write this:

```
@-webkit-keyframes fadeIn {
  from {
    opacity: 0;
  }
  to {
    opacity: 1;
  }
}

@-moz-keyframes fadeIn{
  from {
    opacity: 0;
  }
  to {
    opacity: 1;
  }
}

@-o-keyframes fadeIn{
  from {
    opacity: 0;
  }
  to {
    opacity: 1;
  }
}

@keyframes fadeIn{
  from {
    opacity: 0;
  }
}
```

```
    to {  
      opacity: 1;  
    }  
  }  
}
```

Notice the two hyphens—one between the @ and the vendor prefix and one between the vendor prefix and the word `keyframes`.

NOTE You don't need the `-ms-` vendor prefix for Internet Explorer in this case. IE 9 and earlier don't understand CSS animations anyway, and IE 10 supports the `@keyframes` syntax without a prefix.

Applying an Animation

Once you've completed a set of keyframes, the animation is ready. However, to make it work, you need to apply it to an element on your page. You can add an animation to any style for any element on a page. If you simply add the animation to a style that applies immediately to an element—for example, an `h1` tag style—the animation will apply when the page loads. You can use this technique to add an introductory animation to a page that makes a logo zoom into place in the page's upper-left, or make a particular box of content glow to draw attention to it.

In addition, you can apply an animation to one of the pseudo-classes, including `:hover`, `:active`, `:target`, or `:focus` to make an animation run when a visitor mouses over a link, for example, or clicks into a form field. Finally, you can apply the animation to a class style and use JavaScript to dynamically apply that class in response to a visitor clicking a button or some other page element (see the box on page 351).

CSS3 provides a handful of animation-related properties to control how and when an animation plays back (as well as a shorthand version that encompasses all the individual properties). At a minimum, to get an animation running, you need to supply the name you gave the original animation (in the `@keyframes` rule as discussed on page 355), and a duration for the animation.

Here's a simple example. Say you want a div with an important announcement to fade into view when the page loads. You've given that div a class name of `announcement`: `<div class="announcement">`.

1. Create the fade-in animation with the `@keyframes` rule:

```
@keyframes fadeIn {  
  from { opacity: 0; }  
  to { opacity: 1; }  
}
```

TIP If you're only animating a single property, it can be easier to read to if you put the keyframes on a single line:

```
from { opacity: 0; }
```

However, if you're animating many properties, it's easier to read (and type) if you spread that code over several lines:

```
from {
  opacity: 0;
  color: red;
  width: 50%;
}
```

2. Apply that animation to the style for the <div> tag:

```
.announcement {
  animation-name: fadeIn;
  animation-duration: 1s;
}
```

The `animation-name` property simply tells the browser which animation to use. It's the same name you provided when you created the animation in Step 1. The `animation-duration` property sets the time the animation takes from start to finish. In this example, these are the only two animation properties listed, but you can (and probably will) put other non-animation properties in the style as well. For example, in the real world, you'd probably add properties such as `width`, `background-color`, `border`, and so on to this `.announcement` style.

NOTE Putting the animation's name inside of quotes—`'fadeIn'`—isn't technically required, and it's not done in this example, but doing so can prevent any conflicts that might arise if you use a CSS keyword for an animation name.

As with the `@keyframes` rule, each of the animation properties require vendor-specific prefixes, so the above `.announcement` style would need to be written like the following to work in as many browsers as possible:

```
.announcement {
  -webkit-animation-name: fadeIn;
  -webkit-animation-duration: 1s;
  -moz-animation-name: fadeIn;
  -moz-animation-duration: 1s;
  -o-animation-name: fadeIn;
  -o-animation-duration: 1s;
  animation-name: fadeIn;
  animation-duration: 1s;
}
```

It may seem a bit of a pain to define the animation in one place with the `@keyframes` rule and then apply it in another (the style); however, once you've defined the animation, you're free to use it any number of times in any number of styles. For example, you can create a generic fade-in type of animation and apply it to different elements. What's more, you can control the animation independently for each style—for example, make the header fade in over the course of half a second, but make another page element fade in for five seconds.

In addition, you can apply more than one animation to an element. Say you create one animation named `fadeIn` to make an element fade in and another animation named `blink` to make the background color blink wildly. To apply both animations to the element, you provide a comma-separated list of names like this:

```
animation-name: fadeIn, blink;
```

To give the animations separate timings, provide a list of comma-separated times:

```
animation-name: fadeIn, blink;
animation-duration: 1s, 3s;
```

The order in which you place the times applies to the animation name in the same order. For example, the first animation gets the first time listed. In the above example, `fadeIn` takes one second to complete, while `blink` takes three seconds.

You can apply several other useful animation properties as well. Read on.

Timing the Animation

You've already seen that the `animation-duration` property lets you control an animation's length. As with transitions, you can use milliseconds (750ms, for example) or seconds (.75s, for example) to specify the duration.

As with transitions, you can also set a specific type of timing function to control the rate of the animation throughout that duration. For example, you can start the animation slowly and end it quickly, using a cubic-Bezier curve (page 349) or using one of the built-in keyword methods: `linear`, `ease`, `ease-in`, `ease-out`, `ease-in-out`. These work the same as the `transition-timing-function` property discussed on page 348.

You can use the `animation-timing-function` to control the entire animation or just specific keyframes. For example, to apply the `ease-out` timing function for the `fadeIn` animation presented earlier (Step 1 on page 359), add the timing function to the `.announcement` style (Step 2 on page 360):

```
.announcement {
  animation-name: fadeIn;
  animation-duration: 1s;
  animation-timing-function: ease-out;
}
```

However, you can also control the timing function for the animation between keyframes. For example, say you create an animation that has three keyframes with three different background colors. The web browser will animate from one color

to another and then to a third. Perhaps you want it to slowly move from the first to the second color using a cubic Bezier curve, and then move in a uniform time from the middle to the end. You can do that by adding two timing functions, one to the first keyframe (which controls the animation from keyframe 1 to 2), and one at the second keyframe to control the animation from keyframe 2 to 3:

```
@keyframes growAndGlow {
  from {
    background-color: yellow;
    animation-timing-function: cubic-bezier(1, .03, 1, .115);
  }

  50% {
    transform: scale(1.5);
    background-color: blue;
    animation-timing-function: linear;
  }

  to {
    transform: scale(3);
    background-color: red;
  }
}
```

You can also delay the beginning of the animation using the `animation-delay` property. It works the same as the `transition-delay` property for transitions (page 351), and simply waits a specific number of milliseconds or seconds before the animation begins. For example, if you want to wait one second before the “announcement” div fades into view, you can rewrite that `.announcement` class like this:

```
.announcement {
  animation-name: fadeIn;
  animation-duration: 1s;
  animation-delay: 1s;
}
```

Adding a delay to an animation is a great way to catch people’s attention and add surprise to a page.

NOTE

The `animation-timing-function` and `animation-delay` properties require vendor prefixes, so make sure you add the appropriate `-webkit-animation-timing-function`, `-moz-animation-timing-function`, and so on to your animated styles.

Finishing the Animation

With CSS, you can control a few additional aspects of an animation, including whether to repeat an animation, which direction the animation runs if it's animated more than once, and also how the browser should format the element when the animation is complete.

Transitions are animations that only run once—mouse over a button and the button grows, for example. Animations, however, can run once, twice, or continuously, thanks to the `animation-iteration-count` property. If you want an animation to run 10 times (fade in and out 10 times, perhaps), add this code to the style you're animating:

```
animation-iteration-count: 10;
```

Normally a browser only plays the animation once, and if that's all you're after, then leave off this iteration count property. If you want the animation to play continuously, the `animation-iteration-count` property accepts one keyword: `infinite`. So to run the `fadeIn` animation an infinite number of times on the announcement div, you can create this style:

```
.announcement {  
  animation-name: fadeIn;  
  animation-duration: .25s;  
  animation-iteration-count: infinite;  
}
```

That, however, would annoy your visitors to no end, so please don't do it. However, you could use a style like this for a simple “pulsing” effect where a “sign up today” button gently glows (by animating the `box-shadow` property discussed on page 210).

Normally, when an animation runs more than once, a web browser literally starts the animation over from the beginning. So if you animated a background color from yellow to blue and repeated it twice, the browser would show a yellow box turning blue, and then suddenly the yellow box would return and then animate to blue once again. This effect can be pretty jarring. In this case, it would look better if, for the second time through the animation, the browser simply reversed the effect. That's how transitions work: for example, when you mouse over an element, the browser animates the transition from the regular state to the rollover state. When you move the mouse off the element, the browser simply reverses the animation to return to the regular state. To make an animation move forward on odd runs and backward on even runs, use the `animation-direction` property and the `alternate` keyword. For example, to make an element fade out and then back in again, you can create an animation called `fadeOut`, like this:

```
@keyframes fadeOut {  
  from { opacity: 1; }  
  to { opacity: 0; }  
}
```

Then, play that animation twice, reversing its direction on the second time:

```
.fade {  
  animation-name: fadeOut;  
  animation-duration: 2s;  
  animation-iteration-count: 2;  
  animation-direction: alternate;  
}
```

This code tells the web browser to run the `fadeOut` animation on any element with the class of `fade`. The animation should run for two seconds and then repeat. Because of the `alternate` value for `animation-direction`, the animation will fade out the first time (go from totally opaque—an opacity of 1—to invisible—an opacity of 0), but will run backwards the second time (from 0 to 1 opacity), which makes it fade back into view.

TIP

To have an animation run a number of times but end up back at the beginning state, use an even number of iterations and set the `animation-direction` property to `alternate`.

No matter how many times you have a web browser run an animation, once the animation is completed, the browser displays the animated element in its original, pre-animation state. For example, say you animate an image so it slowly grows to twice its size. Once the animation is completed, the web browser snaps the image back down to its original size, creating a jarring visual effect. Fortunately, you can tell the browser to keep the animated element formatted the same as when the animation ended by setting the `animation-fill-mode` property to `forwards`.

```
animation-fill-mode: forwards;
```

Apply this property to the element you're animating, along with the `animation-name`, `animation-duration`, and other animation properties.

Animation Shorthand

As you can see, there are a lot of animation properties, and writing all of them out in addition to all of the vendor-prefixed versions is a recipe for carpal tunnel syndrome. While you still need vendor-prefixed versions, you can simplify things by using the `animation` shorthand property. This single property combines `animation-name`, `animation-duration`, `animation-timing-function`, `animation-iteration-count`, `animation-direction`, `animation-delay`, and `animation-fill-mode` into a single property. For example, you can take this code:

```
.fade {  
  animation-name: fadeOut;  
  animation-duration: 2s;  
  animation-timing-function: ease-in-out;
```



```

animation-iteration-count: 2;
animation-direction: alternate;
animation-delay: 5s;
animation-fill-mode: forwards;
}

```

And rewrite it like this:

```

.fade {
  animation: fadeOut 2s ease-in-out 2 alternate 5s forwards;
}

```

That's one line of code instead of seven! You should list the property values in the order used above: name, duration, timing function, count, direction, delay, and fill-mode. In addition, make sure each value is separated by a space. Only the name and duration are actually required. The other values are optional.

If you want to apply more than one animation to an element, simply use comma-separated lists of animation properties. For example, to apply two animations (say `fadeOut` and `glow`) to the `.fade` style, write this:

```

.fade {
  animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,
            glow 5s;
}

```

Of course, in real usage you'd need to use vendor prefixes as well:

```

.fade {
  -webkit-animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,
                    glow 5s;
  -moz-animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,
                  glow 5s;
  -o-animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,
                glow 5s;
  animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,
             glow 5s;
}

```

In general, you should opt to use the animation shorthand—it's much more concise and gentler on your fingers and the keyboard.

Pausing an Animation

CSS3 includes another animation property—`animation-play-state`—to control an animation's playback. It accepts only one of two keywords: `running` or `paused`. To pause an animation, simply apply this declaration to a style:

```

animation-play-state: paused;

```

There's only one way to really apply that using CSS, however—a pseudo-class. As with transitions, you need some kind of trigger to pause an animation. One way to do this is to pause any animation when a visitor mouses over the animation. Here's an example using the `.fade` class style:

```
.fade {  
  animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,  
           glow 5s;  
}
```

This code runs two animations—`fadeOut` and `glow`—on any element with the `fade` class applied to it. Say you want to let visitors pause this animation simply by mousing over it. You'd only need to add one more style:

```
.fade:hover {  
  animation-play-state: paused;  
}
```

Of course, you'll need all the vendor prefixed versions as well. A more powerful way to pause an animation would be to dynamically apply the `animation-play-state` property to the element using JavaScript. In this way, you can create a complex animation and add a Pause button that pauses the animation when clicked. See the box on page 351 for more on JavaScript and CSS animations.

Animating on Hover

So far, the animations you've seen here would all run when the page loads. You have a few other options, including several pseudo-classes and using JavaScript, to trigger a CSS animation. The most common pseudo-class for animation is `:hover`. With it, you can run an animation when a visitor mouses over any element; for example, you can make a logo do fancy gymnastics, move off the page, and then move back again.

To animate an element when a visitor's mouse hovers over it, start by creating an animation with the `@keyframes` rule (Step 1 on page 359). Then, create a `:hover` pseudo-class for whatever element you wish to animate. In that style, you simply add the animation properties (Step 2 on page 360). Now the animation runs only when the visitor hovers over the element.

■ Tutorial

In this exercise, you'll add transformations, animation, and transitions to a banner.

To get started, download the tutorial files from this book's companion website at www.sawmac.com/css3. Click the tutorial link and download the files. All the files are enclosed in a zip archive, so you need to unzip them first. (You'll find detailed instructions on the website.) The files for this tutorial are contained inside the **10** folder.

1. In a text editor, open **10→banner.html**.

The page includes a banner with a logo graphic, headline, and set of navigation buttons (see Figure 10-9). First, you'll add a transformation so that when a visitor mouses over a button it scales up in size.




FIGURE 10-9

A normal, static banner just waiting to come to life with animation, transformations, and transitions.

2. Locate the opening and closing `<style>` tags near the top of the page and add the following rule to the style sheet:

```
nav a:hover {
  -webkit-transform:scale(1.2);
  -moz-transform: scale(1.2);
  -o-transform: scale(1.2);
  -ms-transform: scale(1.2);
  transform: scale(1.2);
}
```

The buttons on the page are contained inside an HTML5 `nav` element. This descendant selector targets links inside the `<nav>` tag in their hover state (that is, when a visitor mouses over the link). The style applies the `scale` function (page 338) to make the button slightly larger. Unfortunately, you need to add five lines of code so it'll work in Safari, Chrome, Firefox, Opera, and Internet Explorer 9, as well as future browsers that won't require a vendor prefix.

NOTE

To make the steps in this tutorial easier to follow, you're putting the styles inside an internal style sheet in the web page. However, if you'd prefer, you can add this code to the external style sheet that's already applied to this page. (It's called `styles.css` and it's in the same folder as the web page.)

3. Save the page and preview it in a web browser. Mouse over the links below the headline.

When you mouse over a button, it grows larger, almost popping off the page (Figure 10-10). Very cool, but it would look even better if you added an animation to the effect.

NOTE

Internet Explorer 8 and earlier don't understand transforms, so you won't see any effect in those browsers.

Transitions and Animations

Home

Gallery

Story

About Us

FIGURE 10-10

Pop goes the button. By adding a scale transformation to a button's hover state, you can make it almost pop off the page. The enlarged button doesn't affect any of the content around it (for example, it doesn't push the other buttons out of the way). This is a unique aspect of all CSS transformations.

4. Add another style before the `nav a:hover` style you just created:

```
nav a {
  -webkit-transition: all .5s;
  -moz-transition: all .5s;
  -o-transition: all .5s;
  transition: all .5s;
}
```

Again, you need to add the vendor prefixed versions. (IE 9 doesn't understand transitions, and since IE 10 understands the non-prefixed version, you don't need a `-ms-transition` property.) Here, you're instructing the web browser to animate all changes to the CSS properties of the `<a>` tags inside the `<nav>` element, and to make the animation last `.5s`. To make things more interesting, you'll add a background color to the hover state.

5. Locate the `nav a:hover` style and add `background-color: red`, so the finished style looks like this:

```
nav a:hover {
  background-color: red;
  -webkit-transform: scale(1.2);
  -moz-transform: scale(1.2);
  -o-transform: scale(1.2);
  -ms-transform: scale(1.2);
  transform: scale(1.2);
}
```

If you save the page and preview it now, you'll see that not only do the buttons grow larger when hovered over, they also fade to red. But now you'll add separate timings to these transitions, so the button first grows larger and then turns red.

6. Change the `nav a` style to include two transitions, one for the transformation and the other for the background color, like this (changes are in bold):

```
nav a {  
  -webkit-transition: -webkit-transform .5s,  
                      background-color 1s ease-in .5s;  
  -moz-transition: -moz-transform .5s,  
                  background-color 1s ease-in .5s;  
  -o-transition: -o-transform .5s,  
                background-color 1s ease-in .5s;  
  transition: transform .5s,  
             background-color 1s ease-in .5s;  
}
```

The first part—`transform .5s`—informs the browser that you want to animate any changes in the `transform` property over the course of half a second. The second part—`background-color 1s ease-in .5s`—indicates that you wish to animate the background color change over the course of one second, using the `ease-in` timing method (page 361), but wait half a second before starting. That `.5s` at the end is important since it matches the `.5s` of the `transform` animation. In other words, the browser will wait until the `transform` transition is complete before changing the background color.

7. Save the page and preview it in a web browser.

Mouse over a button. First, the button gets larger. Keep the mouse over the button, and it then turns red. You can of course, tweak with the timing—for example, remove the delay for the `background-color` transition, and the color change will begin at the same time as the size change. However, since the color change lasts for one second, it will continue after the button has reached its final size.

Adding an Animation

Now, it's time to try out CSS3 animations. You'll begin by simply spinning and scaling the logo image. The first step in creating a CSS animation is to use the `@keyframes` rule to set up the keyframes of the animation. This example starts you off with a simple animation and just two keyframes.

TIP

Because CSS animations require a fair amount of code, it's a good idea to start by using only the vendor-prefix for the browser you most often use. Test the page in that browser, and once you've perfected the animation, then add the code for the other browsers.

1. Add the following style to the page's internal style sheet, after the `nav a:hover` style:

```
@-webkit-keyframes logo {  
  from {  
    -webkit-transform: rotate(0) scale(.5);  
  }  
  
  to {  
    -webkit-transform: rotate(-720deg) scale(1);  
  }  
}
```

This example uses the WebKit syntax, which means it'll work in Chrome and Safari. If you're using Firefox as your main browser, replace `@-webkit-keyframes` with `@-moz-keyframes`. (Use `@-o-keyframes` for Opera; for IE 10, skip the prefixes.)

This code is telling the browser that it should start the element with no rotation—`rotate(0)`—and at half its size—`scale(.5)`. It should then animate the change from that to the animation's "to" state—in this case rotating it `-720` degrees, which is three counter-clockwise rotations—and scaling it back up to its normal size. In other words, this animation will spin an element and make it grow.

Now, you need to apply it to any element on the page.

2. Create a new style after the one you just added:

```
.logo {  
  -webkit-animation: logo 1s;  
}
```

The logo in the banner has a class of `logo` applied to it, so this class selector adds an animation to it. The `animation` property can take many values, but you only need the name and duration. Here, you're specifying the animation you created in the last step—`logo`—and telling a web browser to make the animation last one second.

3. Save the file and preview it in Chrome or Safari (or whatever browser you used the prefix for).

The logo should spin, grow in size, and then stop. If it doesn't, double-check your code and make sure you're previewing the page in the proper browser. If all goes according to plan, this animation should look great, but it would be even better if it moved in from off the page and then stopped in its proper spot in the banner. To do that, you'll simply animate the element's position on the page.

4. Edit the @keyframes rule so it looks like this (addition in bold):

```
@-webkit-keyframes logo {
  from {
    -webkit-transform: rotate(0) scale(.5);
    left: 120%;
  }
  to {
    -webkit-transform: rotate(-720deg) scale(1);
    left: 0;
  }
}
```

Here, you begin the logo's position to the right of the banner and navigation buttons at the edge of the screen (basically you're placing the logo's left edge 1.2x the width of the banner). To get this to work, you need to take advantage of the CSS `position` property. You'll learn about it in-depth in Chapter 15, but for now you just need to know that CSS gives you the power to position any element anywhere in the browser window—even outside the browser window. The final keyframe places the logo at the 0 position, where it normally would appear on the page at the left side of the banner.

5. Save the page and preview it in Chrome or Safari.

Looking good. But you can still do better. Add another keyframe so the logo rolls into place and then rotates in the opposite direction as it gets bigger.

6. Change the code you added in Step 4 to look like this:

```
@-webkit-keyframes logo {
  from {
    -webkit-transform: rotate(0) scale(.5);
    left: 120%
  }
  50% {
    -webkit-transform: rotate(-720deg) scale(.5);
    left: 0;
  }
  to {
    -webkit-transform: rotate(0) scale(1);
  }
}
```

Now you have three keyframes: one at the beginning, another right in the middle, and a third at the end. The browser will animate the properties as they change from frame 1 to frame 2 to frame 3.

The first keyframe is the same as from Step 4: the logo is unrotated, half its size, and placed off to the right side. The second keyframe keeps the logo at the same size, rotates it three times, and moves it to the left side of the banner. Finally, once the logo is in the place, the browser scales it up while rotating it back from the -720 degree position to the 0 degree position; in other words, the logo now spins three times clockwise.

7. Save the page and preview it in Chrome or Safari.

The logo should roll in from the right side of the banner to the left, stop, grow, and spin clockwise. If it's not working, double-check your code with that from above. Unfortunately, the animation's a bit too fast. That's an easy fix.

8. Edit the `.logo` style so the animation lasts for three seconds instead of one:

```
.logo {
  -webkit-animation: logo 3s;
}
```

Now for the tedious part—getting it to work in other browsers by adding all the vendor prefixes. You'll tackle the `@keyframes` rule first.

9. Add vendor-prefixed versions for the `@keyframes` rule, so your code looks like this:

```
@-webkit-keyframes logo {
  from {
    -webkit-transform: rotate(0) scale(.5);
    left: 120%
  }

  50% {
    -webkit-transform: rotate(-720deg) scale(.5);
    left: 0;
  }

  to {
    -webkit-transform: rotate(0) scale(1);
  }
}

@-moz-keyframes logo {
  from {
    -moz-transform: rotate(0) scale(.5);
    left: 120%
  }

  50% {
    -moz-transform: rotate(-720deg) scale(.5);
    left: 0;
  }
}
```



```
    }  
    to {  
      -moz-transform: rotate(0) scale(1);  
    }  
  }  
}  
  
@-o-keyframes logo {  
  from {  
    -o-transform: rotate(0) scale(.5);  
    left: 120%;  
  }  
  
  50% {  
    -o-transform: rotate(-720deg) scale(.5);  
    left: 0;  
  }  
  
  to {  
    -o-transform: rotate(0) scale(1);  
  }  
}  
  
@keyframes logo {  
  from {  
    transform: rotate(0) scale(.5);  
    left: 120%;  
  }  
  
  50% {  
    transform: rotate(-720deg) scale(.5);  
    left: 0;  
  }  
  
  to {  
    transform: rotate(0) scale(1);  
  }  
}
```

That's a lot of code, and, unfortunately, that's what you have to do at this point to use CSS animations. At some point, in a beautiful future, all the browsers will use the single non-prefixed `@keyframes` rule and a non-prefixed `transform` property. But, at this point, you're stuck typing all this code.

Fortunately, adding the `@keyframes` rule is the hardest part. Adding the animation to the `.logo` style isn't nearly as much work.

10. Edit the .logo style by adding three new lines:

```
.logo {  
  -webkit-animation: logo 3s;  
  -moz-animation: logo 3s;  
  -o-animation: logo 3s;  
  animation: logo 3s;  
}
```

11. Save the page and check it out in Firefox, Chrome, Safari, and Opera.

The logo should roll along the page and enlarge on all of those browsers. Of course, in Internet Explorer 9 and earlier, you won't see any animation. However, the logo will still be correctly placed and the page will look just fine. You'll find a finished version of this tutorial in the *10_finished* folder.

To take this further, add an animation that makes one of the navigation buttons glow when the mouse is positioned over it. (Hint: create an animation that cycles through different box shadow. Use the `inset` value to add the shadow inside the box as described on page 211. Then add that animation to the `nav a:hover` style so it only plays when the mouse hovers over a button.)




FIGURE 10-11

Books can do a lot, but they can't, unfortunately, show you the amazing animation that you just created. Here's what the page should look like when the animation has run its course and you mouse over the Home button.

Formatting Tables and Forms

The formatting powers of CSS go way beyond text, images, and links. You can make tables of information like schedules, sports scores, and music playlists easier to read by adding borders, backgrounds, and other visual enhancements. Similarly, you can use CSS to organize the elements of a form to help your visitors through the process of ordering items, signing up for your newsletter, or using your latest web application.

This chapter shows you how to display tables and forms with HTML and how to lay out and style them using CSS. In two tutorials at the end of the chapter, you'll create a table and a form, using the tricks you've learned along the way.

■ Using Tables the Right Way

HTML tables have seen a lot of use in the short history of the Web. Originally created to display data in a spreadsheet-like format, tables became a popular layout tool. Faced with HTML's limitations, designers got creative and used table rows and columns to position page elements like banner headlines and sidebars. As you'll see in Part Three of this book, CSS does a much better job of laying out web pages. You can concentrate on using (and formatting) tables for their original purpose—displaying data (Figure 11-1).




FIGURE 11-1
You can do all of your page layout and design with CSS and use tables for what they were intended—displaying rows and columns of information. CSS created the attractive fonts, borders, and background colors in this table about indoor lawn mowers, but the underlying structure is all thanks to HTML.

HTML (and XHTML) has a surprising number of tags dedicated to table building. This chunk of HTML creates the very simple table pictured in Figure 11-2.

```
<table>
<caption align="bottom">
  Table 1: CosmoFarmer.com's Indoor Mower Roundup
</caption>
<colgroup>
  <col class="brand" />
  <col class="price" />
  <col class="power" />
</colgroup>
<thead>
<tr>
  <th scope="col">Brand</th>
```

```

<th scope="col">Price</th>
<th scope="col">Power Source</th>
</tr>
</thead>

<tbody>
<tr>
<td>Chinook Push-o-matic Indoor Mower</td>
<td>$247.00</td>
<td>Mechanical</td>
</tr>

<tr>
<td>Sampson Deluxe Apartment Mower</td>
<td>$370.00</td>
<td>Mechanical</td>
</tr>
</tbody>

</table>

```

Even with only three rows and three columns, the table uses nine unique HTML tags: <table>, <caption>, <colgroup>, <col>, <thead>, <tbody>, <tr>, <th>, and <td>. In general, more HTML isn't a good thing, and you don't need all of these tags: you can get away with just the <table>, <tr>, and <td> tags (and usually <th> as well). However, a table's various tags give you lots of useful hooks to hang CSS styles on. The headers of each column—the <th> tags—can look different from other table cells if you create a <th> tag style, and you can use the <colgroup> tag as an easy way to set the width of a table column. This saves you the hassle of having to create lots of classes—like .tableHeader—and then apply them by hand to individual table cells. In the next section, you'll see examples of how you can use these different tags to your advantage.

Brand	Price	Power Source
Chinook Push-o-matic Indoor Mower	\$247.00	Mechanical
Sampson Deluxe Apartment Mower	\$370.00	Mechanical

Table 1: CosmoFarmer.com's Indoor Mower Roundup

FIGURE 11-2

Data tables, like this one, usually have headers created with the <th> tag. Header cells announce what type of information appears in a row or column. Price tells you that you'll find the cost of each lawn mower listed in the cells below. The actual data presented in a table is enclosed in <td> tags.

NOTE

For an in-depth article on the HTML used to create tables, visit www.456bereastreet.com/archive/200410/bring_on_the_tables.

■ Styling Tables

You can use many of the CSS properties you've read about to dress up the appearance of a table and its contents. You can use the *color* property, for example, to set a table's text color, just like anywhere else. You'll find a few properties, however, that are particularly useful with tables, as well as a couple aimed specifically at formatting tables.

Because tables are composed of several HTML tags, it helps to know which tag to apply a particular CSS property to. Applying padding to a `<table>` tag, for example, has no effect. The next few sections cover CSS properties for formatting tables and which HTML tags they get along with.

Adding Padding

As you read on page 195, padding is the space between an element's border and its content. You can use padding to provide a little space between the edges of a paragraph's text and its border. When it comes to tables, the borders are the *edges* of a cell, so padding adds space around any content you've placed inside of a table cell (see Figure 11-2). It works a lot like the old `cellpadding` attribute—which is no longer valid in HTML5—with the added benefit that you can individually control space between a cell's content and each of its four edges.

You apply padding to either a table header or a table cell tag, but *not* to the `<table>` tag itself. So, to add 10 pixels of space to the inside of all table cells, use this style:

```
td, th { padding: 10px; }
```

You can also control the spacing separately for each edge. To add 10 pixels of space to the top of each table data cell, 3 pixels to the bottom of that cell, and 5 pixels on both the left and right sides, create this style:

```
td {  
  padding-top: 10px;  
  padding-right: 5px;  
  padding-bottom: 3px;  
  padding-left: 5px;  
}
```

Or, use the padding shortcut property:

```
td {  
  padding: 10px 5px 3px 5px;  
}
```

TIP If you place an image into a table cell using the `` tag and notice that there's unwanted space below the image, then set its `display` property (page 202) to `block`. For more information, see http://developer.mozilla.org/en/docs/Images,_Tables,_and_Mysterious_Gaps.

Adjusting Vertical and Horizontal Alignment

To control where content is positioned *within* a table cell, use the `text-align` and `vertical-align` properties.

`text-align` controls horizontal positioning and can be set to `left`, `right`, `center`, and `justify` (see Figure 11-3). It's an inherited property. (See Chapter 4 for more on inheritance.) When you want to right align the contents of all table cells, create a style like this:

```
table { text-align: right; }
```

This property comes in handy with `<th>` tags, since browsers usually center align them. A simple style like `th { text-align: left; }` makes table headers align with table cells.





Table cells have a height as well. Web browsers normally align content vertically in the middle of a table cell (see the middle example in Figure 11-4). You can control this behavior by using the `vertical-align` property. Use one of these four values: `top`, `baseline`, `middle`, or `bottom`. `top` pushes content to the top of the cell, `middle` centers content, and `bottom` pushes the bottom of the content to the bottom of the cell. `Baseline` works just like `top`, except the browser aligns the baseline of the first line of text in each cell in a row (Figure 11-4). Unless you're a real perfectionist, you won't even notice the subtlety of the `baseline` option. More importantly, neither will your visitors. Unlike `text-align`, the `vertical-align` property isn't inherited, so you can use it only on styles that apply directly to `<th>` and `<td>` tags.

NOTE So far, the table formatting you've learned applies to *all* your tables. When you want to style individual tables (or table cells), change the selector you use. To apply a special design to a certain table, give it a class name—`<table class="stocks">`—and create descendent selectors like `.stocks td` or `.stocks th` to uniquely format individual cells. If you want to style a particular cell differently than other cells in a table, then apply a class to the tag—`<td class="subtotal">`—and create a class style to format that cell.



Creating Borders

The CSS border property (page 202) works pretty much the same with tables as with other elements, but you need to keep a couple of things in mind. First, applying a border to a style that formats the `<table>` tag outlines just the table, not any of the individual cells. Second, applying borders to cells (`td { border: 1px solid black; }`) leaves you with a visual gap between cells, as shown in Figure 11-5, top. To gain control of how borders appear, you need to understand how web browsers normally draw tables cells and the CSS border-collapse property.

- **Controlling the space between table cells.** Unless instructed otherwise, browsers separate table cells by a couple of pixels. This gap is really noticeable when you apply a border to table cells. CSS gives you the border-spacing property to control this space. Apply this property to the table itself, and if you wish to remove the space that browsers normally place between cells, then set the border-spacing property to 0:

```
table {
  border-spacing: 0;
}
```


Of course, if you like space between the cells, then add space:

```
table {  
  border-spacing: 2px;  
}
```

- **Eliminating double borders.** Even if you eliminate the cell spacing of a table, borders applied to table cells double up. That is, the bottom border of one cell adds to the top border of the under-hanging cell, creating a line that's twice as thick as the border setting (Figure 11-5, middle). The best way to eliminate this (and eliminate cell spacing at the same time) is to use the `border-collapse` property. It accepts two values—`separate` and `collapse`. The `separate` option is normally how tables are displayed, with the cell spaces and doubled borders. Collapsing a table's borders eliminates the gaps and doubled borders (Figure 11-5, bottom). Apply the `collapse` value to a style formatting a table, like so:

```
table { border-collapse: collapse; }
```

NOTE If you set the `border-collapse` property to `collapse`, `border-spacing` has no effect.

- **Rounded corners.** You can use the `border-radius` property (page 207) to add rounded corners to table cells (but not to tables themselves). For example, if you want to outline table cells and give them rounded corners, you can create this style:

```
td {  
  border: 1px solid black;  
  border-radius: 5px;  
}
```

Note that if you set the `border-collapse` property to `collapse`, then browsers ignore any `border-radius` you've set for table cells; they'll just draw regular square corners.

NOTE You can even apply the `box-shadow` property (page 210) to tables and to cells. If you apply it to a table, the shadow will appear outside the entire table, but if you apply the shadow to individual cells, then each cell will have its own drop shadow.

Styling Rows and Columns

Adding stripes, like the ones in Figure 11-6, is a common table design technique. By alternating the appearance of every other row of data, you make it easier for people to spot the data in each row. Fortunately, CSS does offer a way to do that. Using the `nth-of-type` selector, which you read about on page 78, you can add different backgrounds to odd and even rows:

```
tr:nth-of-type(odd) { background-color: red; }  
tr:nth-of-type(even) { background-color: blue; }
```

If you don't want to apply the same background to the odd rows of all of your tables, simply add a class name to the table you wish to target (products, for a table with product information, for example), then use a descendent selector like this:

```
.products tr:nth-of-type(odd) { background-color: red; }
.products tr:nth-of-type(even) { background-color: blue; }
```

Brand	Price	Power Source	Mini-Review
Chinook Push-o-matic Indoor Mower	\$247.00	Mechanical	The latest model of the Chinook mower is a big improvement over last year's model. It's smooth gliding action is perfect for even massively over grown sod. Its handling around corners is superb -- perfect for those tight areas around sofas and coffee tables.
Sampson Deluxe Apartment Mower	\$370.00	Mechanical	In our battery of 7 mowing tests, the Sampson scored 9 or above on each. The fine blades turn even large weeds into tiny cuttings, perfect for composting or salad garnishes.

Table 1: CosmoFarmer.com's Indoor Mower Roundup

Brand	Price	Power Source	Mini-Review
Chinook Push-o-matic Indoor Mower	\$247.00	Mechanical	The latest model of the Chinook mower is a big improvement over last year's model. It's smooth gliding action is perfect for even massively over grown sod. Its handling around corners is superb -- perfect for those tight areas around sofas and coffee tables.
Sampson Deluxe Apartment Mower	\$370.00	Mechanical	In our battery of 7 mowing tests, the Sampson scored 9 or above on each. The fine blades turn even large weeds into tiny cuttings, perfect for composting or salad garnishes.

Table 1: CosmoFarmer.com's Indoor Mower Roundup

Brand	Price	Power Source	Mini-Review
Chinook Push-o-matic Indoor Mower	\$247.00	Mechanical	The latest model of the Chinook mower is a big improvement over last year's model. It's smooth gliding action is perfect for even massively over grown sod. Its handling around corners is superb -- perfect for those tight areas around sofas and coffee tables.
Sampson Deluxe Apartment Mower	\$370.00	Mechanical	In our battery of 7 mowing tests, the Sampson scored 9 or above on each. The fine blades turn even large weeds into tiny cuttings, perfect for composting or salad garnishes.

Table 1: CosmoFarmer.com's Indoor Mower Roundup

FIGURE 11-5

Browsers normally insert space between each table cell. (You probably won't notice this extra space unless you've added a border, as shown here at the top.) If you set the border-spacing to 0 to remove the extra space, you're left with double border lines where adjoining borders touch (middle). The border-collapse property solves both dilemmas (bottom).

You're not limited to colors either. You can use background images (see page 240) or even linear gradients (page 260) to create more sophisticated looks like the slight gradation in the table header row of Figure 11-6. (You'll see a similar example of this in the tutorial on page 393.) You can use a descendent selector to target cells in that row as well. This technique is great for when you style all of the cells in one column with their own look: `<td class="price">`, for example.

NOTE

The nth-of-type selector isn't supported in Internet Explorer 8 or earlier.

Formatting columns is a bit trickier. HTML provides the `<colgroup>` and `<col>` tags to indicate groups of columns and individual columns, respectively. You include one `<col>` tag for each column in the table and can identify them with either a class or ID. (See the HTML code on page 376.) Only two sets of properties work on these tags: `width` and the background properties (`background-color`, `background-image`, and so on). But they can come in mighty handy. When you want to set the width of all of the cells in a column, you can skip any HTML attributes and just style the column, using a style applied to the `<col>` tag. For example, say you have this bit of HTML: `<col class="price">`. You can add this style to a style sheet to set the width of each cell in that column to 200 pixels:

```
.price { width: 200px; }
```




FIGURE 11-6

Alternating the background color from row to row in a table makes it easier to quickly identify the data for each row.

To highlight a column, you can use the background properties. Again, assume you have a `<col>` tag with a class of `price` applied to it:

```
.price { background-color: #F33; }
```

Keep in mind, however, that backgrounds for columns appear under table cells, so if you set a background color or image for `<td>` or `<th>` tags, the column's background won't be visible.

NOTE Typically, web browsers display the border and background color of any empty table cell. If you want to hide those empty cells, CSS lets you. Just add `empty-cells: hide` to a style applied to a table:

```
table {  
    empty-cells: hide;  
}
```

One caveat, however: If you set the `border-collapse` property (page 380) to `collapse`, browsers ignore the `empty-cells` property and show the borders and backgrounds of even empty cells.

■ Styling Forms

Web forms are the primary way visitors interact with a website. By supplying information on a form, you can join a mailing list, search a database of products, update your personal profile on Facebook, or order that Star Wars Lego set you've had your eye on.

There's no reason your forms need to look like all the others on the Internet. With a little CSS, you can style form fields to share the same formatting as other site elements like fonts, background colors, and margins. There aren't any CSS properties specific to forms, but you can apply just about any property in this book to a form element.

The results, however, can be mixed (see Figure 11-7). Browsers vary in how they handle the styling of form elements. The next section tells you which properties work best with which form tags and also lists which browsers interpret them properly.

UP TO SPEED

Staying True to Form

Quite apart from the varying browser support for CSS-styled forms, there are good reasons to tread lightly when altering the look of universally recognized interface elements like submit buttons and pull-down menus. Most web surfers are already very familiar with how forms look and work. The generic look of a submit button is the same from site to site. When people see it, they instantly know what that button does and how to use it. If you alter the look of a form *too* much, you may make it harder for visitors to fill out your form correctly.

Adding a dotted border to a form field can turn an easily recognizable text field into an easily skipped box. (See the examples at bottom right and bottom center of Figure 11-7.) If that text box is intended to capture email addresses for your newsletter, you may lose a few visitors who skip right over it. At the very least, make sure people can recognize the forms on your sites as forms.



FIGURE 11-7
Browsers vary in how they handle the styling of form fields. Internet Explorer 9 (top) doesn't support rounded corners or drop shadows on a text area (see the Text area in the Borders panel at right). Nor does it understand the linear gradient applied to the Submit button in the middle Backgrounds panel. The differences between Chrome (second from top), Firefox (second from bottom), and Safari (bottom) aren't nearly so drastic, but there are still a few visual inconsistencies between them. The best you can do is design your forms carefully and not expect them to look the same on every browser.

HTML Form Elements

A variety of HTML tags help you build forms. You can format some of them (like text fields) more successfully than others (radio buttons). Here are a few common form tags and the types of properties they get along with:

- **Fieldset.** The `<fieldset>` tag groups related form questions. Most browsers do a good job of displaying background colors, background images, and borders for this tag. However, Internet Explorer lets the background flow up and over the top line of the fieldset. (Look at the middle panel of the top image in Figure 11-7.) Padding places space from the edges of the fieldset to the content inside it. Although Internet Explorer unfortunately ignores top padding, you can simulate it by adding a top `margin` to the first element inside the fieldset.
- **Legend.** The `<legend>` tag follows the HTML for the `<fieldset>` tag and provides a label for the group of fields. The legend appears vertically centered on the top borderline of a fieldset. If the form elements for collecting a shipping address appear inside the fieldset, you might add a legend like this: `<legend>Shipping Address</legend>`. You can use CSS to change the `<legend>` tag's font properties, add background colors and images, and add your own borders.
- **Text fields.** The `<input type="text">`, `<input type="password">`, and `<textarea>` tags create text boxes on a form. These tags give you the most consistent cross-browser CSS control. You can change the font size, font family, color, and other text properties for text boxes, as well as add borders, background colors, and images. You can set the width and height of these fields using the CSS `width` and `height` properties.
- **Buttons.** Form buttons—like `<input type="submit">`—let your visitors submit a form, reset its contents, or set off some other action. Most browsers let you go wild with text formatting, borders, backgrounds, drop shadows, and rounded corners. You can also align the button's text to the left, middle, or right using the `text-align` property. Linear gradients (page 260) look especially good on buttons.
- **Drop-down menus.** Drop-down menus created by the `<select>` tag also give you a fair amount of styling control. Most other browsers also let you set the font, font size, background color, image, and borders. However, backgrounds and background images aren't always added to the drop-down menu when it expands to show all of the menu's options.
- **Checkboxes and radio buttons.** Most browsers don't allow formatting of these elements. Opera, however, lets you set a background color that appears *inside* the box or button. Internet Explorer adds a background color *around* the box or button. Because browsers vary widely in how they treat these elements, it's best to leave them alone.

POWER USERS' CLINIC

Attribute: The Ultimate Form Field Selector

When it comes to styling forms, tag styles just don't cut the mustard. After all, text boxes, radio buttons, checkboxes, password fields, and buttons all share the same HTML tag—`<input>`. While a width of 200 pixels makes sense for a textbox, you probably don't want your checkboxes to be that big, so you can't use the `<input>` tag to format width. For now, the most cross-browser-friendly way of formatting only text fields would be to add a class name to each text field—like `<input type="text" class="textfield" name="email">`—and then create a class style to format it.

However, you can take advantage of the attribute selector (page 72) to fine-tune your form styling without resorting to classes.

An attribute selector targets an HTML tag based on one of the tag's attributes. The `type` attribute is responsible for

determining what kind of form element the `<input>` tag produces. The `type` value for a form text field is `text`. To create a style that makes the background color of all single-line text fields blue, you'd create this selector and style:

```
input[type="text"] {  
    background-color: blue;  
}
```

Changing `text` in the above example to `submit` creates a style for submit buttons only, and so on.

All current browsers, even Internet Explorer 7, understand attribute selectors, so feel free to use them to style your forms with precision.

Laying Out Forms Using CSS

All it takes to create a form is adding a bunch of labels and other form elements to a web page. Visually, though, you may end up with a chaotic mess (see Figure 11-8, left). Forms usually look best when the questions and form fields are organized into columns (Figure 11-8, right).

You can achieve this effect in a couple of ways. The easiest approach is with an HTML table. Although form labels and fields aren't strictly table data, they lend themselves beautifully to a row/column format. Just put your labels ("First Name," "Phone Number," and so on) in one column and form fields in a second column.

Using CSS, you can also create a two-column form like Figure 11-8 (with the added benefit of less HTML code). Here's the basic approach:

1. Wrap each label in a tag.

The obvious choice for a tag is `<label>`, since it's designed to identify form labels. But you can't *always* use `<label>` tags for all labels. Radio buttons usually have a question like "What's your favorite color?" followed by separate `<label>` tags for each button. So what tag do you use for the question? In this case, you must resort to wrapping the question in a `` tag: `What's your favorite color?`. Then add a class to each of these tags—``—and also add the class to just those `<label>` tags you want to appear in the left-hand column (in Figure 11-8, that would be the labels for "First name," "Last name," and so on, but not the `<label>` tags for the radio buttons).

NOTE Visit www.htmldog.com/guides/htmladvanced/forms for a quick overview on the <label> tag.




FIGURE 11-8
The different shapes and sizes of text boxes, radio buttons, and other form objects don't naturally align well with text, often causing an ungainly zigzag pattern. This form isn't just ugly; it's hard to read (left). The solution is to organize your forms into columns (right), using either an HTML table or CSS styles.

2. Set the display property to inline-block, and set a width.

Normally the <label> and tags are inline elements, which normally ignore many of the settings available to block elements, including width, height, and text-align. However, if you make the label an inline-block, it can still sit next to (that's the "inline" part) the form field. The width value should provide enough space to accommodate the entire label on one line if possible. You can create a class style that looks something like this:

```
.label {
    display: inline-block;
    width: 20em;
}
```

The width and inline-block settings turn the labels into little evenly sized blocks and provide a clean left edge to which all the form fields align.

3. Adjust the style.

Just a couple more enhancements complete the job. You want to set the vertical-align property (page 379) to top, so the top of the label text aligns with the top of the form field. You also should align the label text to the right, so each label appears next to each form field. Finally, by adding a little bit of right margin, you can create a nice gutter of white space between the labels and form fields.


```
.label {
  float: left;
  width: 20em;
  vertical-align: top;
  text-align: right;
  margin-right: 15px;
}
```

At this point, you've got yourself a simple, neat form. You can make other enhancements if you wish, like making the labels bold and a different color. The tutorial that starts on the next page provides a step-by-step example of this technique.

POWER USERS' CLINIC

Form Pseudo-Classes

There are a handful of pseudo-classes aimed at styling forms. The `:focus` pseudo-class lets you create a selector that changes the way a text field looks when a visitor clicks or tabs inside it (this is called giving the field *focus*). You can use this to change the size, background color, font, and other CSS properties of the field. You'll see an example of it in action in the tutorial on page 395.

The `:checked` pseudo-class works with radio buttons and checkboxes. It's intended to let you style those elements, but web browsers generally keep a tight visual rein on these fields, and most CSS properties do not apply. However, if you want to give them a try, you can simply create a style named `:checked` and add some CSS properties to it. Realize it will only apply to the radio buttons and checkboxes of a form. If you want to style a particular checkbox when it's checked, you can create a class style:

```
.special:checked
```

And then apply that class to just that checkbox:

```
<input type="checkbox" class="special" ...
```

Form elements can also be enabled or disabled. When disabled, the field can't be changed: for example, you can't type into

a disabled text field, or turn on a disabled checkbox. You can only change the state of a form element (from disabled to enabled, for example) using JavaScript, so you'll need to learn that to really take advantage of the `:enabled` or `:disabled` pseudo-classes. However, they can come in handy. For example, say you have an order form with both "billing" and "shipping" address fields. If you added a "same as billing address" checkbox next to the shipping address fields, a visitor can click this box. Using JavaScript, you can disable the shipping address fields so no one accidentally types into them. To make it clear that the user can't fill them out, you can change their style so they look "dimmed" or grayed out, like this:

```
:disabled {
  background-color: #333;
}
```

There are even more pseudo-classes intended to work with some of HTML5's special form features like built-in form validation or other special properties. To learn about these, visit <http://html5doctor.com/css3-pseudo-classes-and-html5-forms/>. Keep in mind, though, that many browsers don't yet support these HTML5 form features.

Tutorial: Styling a Table

HTML is great for building tables, but you need CSS to give them style. As you can see on page 375, it takes quite a bit of HTML to construct a simple table. Lucky for you, this book comes with a prebuilt HTML table for you to practice your CSS on. In this tutorial, you'll format the table's rows, columns, and cells, and give it an attractive font and background color.

To get started, download the tutorial files located on this book's companion website at www.sawmac.com/css3/. Click the tutorial link and download the files. All the files are enclosed in a zip archive, so you need to unzip them first. (Go to the website for detailed instructions.) The files for this tutorial are in the `11→table` folder.

1. Launch a web browser and open the file `11→table→table.html`.

This page contains a simple HTML table. It has a caption, a row of table headers, and nine rows of data contained in table cells (Figure 11-9). In addition, the `<col>` tag is used three times to identify the three columns of data. As you'll see in a bit, `<col>` is a handy tag to style, since it will let you set the width of all cells in a column.

`<table class="inventory">`

Table 1: Current Inventory ← `<caption>`

Product	Price	Rating
Vitae Quam Lorem	\$19.95	★★★★★
In Tempus Velit	\$14.55	★★★
Lorem Ipsum Dolor Sat	Priceless	★★★★★
Quis Felis Fringilla	\$29.95	★★
Nunc Sem Pharetra	\$75.99	★★★
Vel Faucibus Elit	\$82.00	★
Non Adipiscing Vitae	\$1.95	★★★★
Aenean Orci Ante	\$17.95	★★★★
Venenatis Non Adipiscing	\$44.00	★★★★★

`<col id="product">`
 `<col id="price">`
 `<col id="rating">`

FIGURE 11-9

Formatting a table with borders, background colors, and other CSS properties not only makes a drab HTML table (top) look great, but also makes the table's data easier to read (bottom).

Table 1: Current Inventory

PRODUCT	PRICE	RATING
Vitae Quam Lorem	\$19.95	★★★★★
In Tempus Velit	\$14.55	★★★
Lorem Ipsum Dolor Sat	Priceless	★★★★★
Quis Felis Fringilla	\$29.95	★★
Nunc Sem Pharetra	\$75.99	★★★
Vel Faucibus Elit	\$82.00	★
Non Adipiscing Vitae	\$1.95	★★★★
Aenean Orci Ante	\$17.95	★★★★
Venenatis Non Adipiscing	\$44.00	★★★★★

2. Open *table.html* in a text editor.

You'll start by creating a style that sets the table's width and text font. This table has a class of `inventory` applied to it, so you can use a class selector to format just this one table.

NOTE There's already an external style sheet attached to this page, but you'll add your new styles to an internal style sheet.

3. Click between the opening and closing `<style>` tags, and then add the following style:

```
.inventory {  
  font-family: "Trebuchet MS", Arial, Helvetica, sans-serif;  
  width: 100%;  
  margin-top: 25px;  
}
```

Unless you set the width of a table, it grows and shrinks to fit the size of the content inside it. In this case, you've set a 100 percent width, so the table stretches to fit the entire width of its container. (In this case, it's the `<body>` tag itself, with a set width and auto left and right margins to center it in the browser window.) Setting the font family in the `<table>` uses inheritance to give all of the tags inside the table the same font—`<caption>`, table headers (`<th>`), table cells (`<td>`), and so on. Finally, the `margin-top` property scoots the table down from the headline above it.

Next you'll style the table's caption.

4. Add another style below the table style you just created:

```
.inventory caption {  
  text-align: right;  
  font-size: .85em;  
  margin-bottom: 10px;  
}
```

This descendent selector only affects the `<caption>` tag that appears inside another tag with the class of `inventory` (that's the `<table>` on this page). A `<caption>` tag indicates what a table is about. In this case, it shouldn't be the focus of attention, so you've kept the text small and moved it to the right edge, out of the way. The bottom margin adds a bit of space between the caption and the table.

When you read information across a table row, it's easy to lose track of which row you're looking at. Good visual guides are essential. Adding borders around the cells, which you'll do next, visually delineates the information.

5. Add the following group style to the internal style sheet:

```
.inventory td, .inventory th {  
    font-size: 1.1em;  
    border: 1px solid #DDB575;  
}
```

This group selector formats the table header (<th>) and table cell (<td>) tags of this table with larger type and draws a border around each header and each cell. Browsers normally insert space between each cell, so at this point there are small gaps between the borders (Figure 11-10, circled). Between the gaps and the borders, the whole table looks too boxy. You'll fix that next.

6. Add the border-collapse property to the table style you created in Step 3 so that it looks like this:

```
.inventory {  
    font-family: "Trebuchet MS", Arial, Helvetica, sans-serif;  
    width: 100%;  
    margin-top: 25px;  
    border-collapse: collapse;  
}
```

The border-collapse property removes the spacing between cells. It also merges borders that touch, which prevents thick, unattractive borders. Without border-collapse, the bottom border of a table header and the top border of the table cell would double up to make a two-pixel border.

If you preview the table now, you'll see the data is better organized visually, but the information in each cell looks a little cramped. Add some padding to fix that.

7. Add padding to the group selector you created in Step 5:

```
.inventory td, .inventory th {  
    font-size: 1.1em;  
    border: 1px solid #DDB575;  
    padding: 3px 7px 2px 7px;  
}
```

Although the top, table-header row stands out because of its boldface text, there are a few things you can do to make it stand out even more and improve its appearance.

8. Create a new style below the .inventory td, .inventory th style for formatting just table head cells:

```
.inventory th {  
    text-transform: uppercase;  
    text-align: left;  
    padding-top: 5px;  
    padding-bottom: 4px;  
}
```

This style is a perfect example of effective cascading. The group selector `td`, `th` defines common formatting properties between the two types of cells. By introducing this `th`-only style, you can further tweak the look of *just* the table headers. For example, the `padding-top` and `padding-bottom` settings here override those same settings defined in the selector in Step 7. However, since you don't override the left or right padding settings, the `<th>` tags will retain the seven pixels of left and right padding defined in Step 7. This style also turns all of the text to uppercase and aligns it to the left edge of the table cell.

The table headers still don't have enough oomph, and the table seems to recede into the background of the page. A background graphic can provide the necessary boost.

Product	Price	Rating
Vitae Quam Lorem	\$19.95	★★★★★
In Tempus Velit	\$14.55	★★★
Lorem Ipsum Dolor Sat	Priceless	★★★★★
Quis Felis Fringilla	\$29.95	★★
Nunc Sem Pharetra	\$75.99	★★★
Vel Faucibus Elit	\$82.00	★
Non Adipiscing Vitae	\$1.95	★★★★
Aenean Orci Ante	\$17.95	★★★★
Venenatis Non Adipiscing	\$44.00	★★★★★

Product	Price	Rating
Vitae Quam Lorem	\$19.95	★★★★★
In Tempus Velit	\$14.55	★★★
Lorem Ipsum Dolor Sat	Priceless	★★★★★
Quis Felis Fringilla	\$29.95	★★
Nunc Sem Pharetra	\$75.99	★★★
Vel Faucibus Elit	\$82.00	★
Non Adipiscing Vitae	\$1.95	★★★★
Aenean Orci Ante	\$17.95	★★★★
Venenatis Non Adipiscing	\$44.00	★★★★★

FIGURE 11-10

A browser's normal display of a table inserts space between each cell (top). It also lets borders double up where cells touch. Setting the `border-collapse` property to collapse solves both problems (bottom).

9. Edit the `th` style by adding a linear gradient to the background and changing the text color:

```
.inventory th {
  text-transform: uppercase;
  text-align: left;
  padding-top: 5px;
  padding-bottom: 4px;
  background: rgb(229,76,16);
  background: -webkit-linear-gradient(rgb(229,76,16), rgb(173,54,8));
  background: -moz-linear-gradient(rgb(229,76,16), rgb(173,54,8));
  background: -o-linear-gradient(rgb(229,76,16), rgb(173,54,8));
}
```

```
background: linear-gradient(rgb(229,76,16), rgb(173,54,8));
color: white;
}
```

You start by simply adding an RGB color to the background; that way, Internet Explorer 9 and earlier (which don't understand gradients) at least have a solid color. The next three lines add the vendor-prefixed versions of the linear gradient, while the second-to-last line is the official `linear-gradient` syntax. Finally, the text color is changed to white.

When tables have lots of data stuffed into many rows and columns, it's sometimes hard to quickly identify which data belongs to each row. Thankfully, you can use the `nth-of-type` selector to quickly target alternating rows.

10. Add one more style to the web page's internal style sheet:

```
.inventory tr:nth-of-type(even){
  background-color: rgba(255,255,255,.1);
}

.inventory tr:nth-of-type(odd){
  background-color: rgba(229,76,16,.1);
}
```

As you can read on page 78, the `nth-of-type` selector is used to select child elements that follow a numeric pattern; for example, every fifth paragraph. In this case, the first style selects every even `<tr>` tag, while the second selects every odd `<tr>` tag.

Finally, you'll adjust the width of the cells that fall under the Price and Rating columns. One technique is to meticulously add class names to those cells and create a class style with a set width. A better approach, however, is to take advantage of the `<col>` tag, which lets you assign a class or ID to a column's worth of cells. As you can see in Figure 11-9, those two columns have an ID of price and rating. You can easily set the width for these two columns with one group selector.

11. Add one more style to the web page's internal style sheet:

```
#price, #rating {
  width: 15%;
}
```

Preview the page in a web browser to see the results. Your page should look like the bottom image in Figure 11-9. You'll also find the completed exercise in the [11_finished→table](#) folder.

Tutorial: Styling a Form

This tutorial gives you some practice using CSS to organize a form and make it more attractive. If you open `11→form→form.html` in a web browser, then you'll see it contains a simple form for subscribing to the fictitious website, CosmoFarmer.com (Figure 11-11). The form asks several questions and uses a variety of form elements for input, including text boxes, radio buttons, and a pull-down menu.

As subscription forms go, it looks fine, but a little bland. In the steps on the following pages, you'll spruce up the fonts, line up the questions and boxes better, and add a few other improvements.

1. Open the file `form.html` in a text editor.

There's already an external style sheet attached to this page, but you'll add your new styles to an internal style sheet. Start by increasing the size of the type in the form to make it more readable.

2. Click between the opening and closing `<style>` tags, and then add the following style:

```
.subform {  
  font-size: 1.2em;  
  color: white;  
  font-family:Tahoma, Geneva, sans-serif;  
}
```

The subscription form has a class of `subform` applied to it, so this style sets the text size, color, and font for all text between the opening and closing `<form>` tags.

Time to work on the layout. To better align the form elements, you'll create the appearance of two columns—one for the questions (labels) and another for the answers (form fields).



Reader Subscription Form

What is your name?

What is your email address?

Rate your apartment farming skills Novice Intermediate Advanced

Where did you hear about us?

Any additional comments?

FIGURE 11-11

While the HTML `<table>` tag is a common way to organize the questions of a form, you can also use CSS to make a disorganized jumble of labels and form fields (like the ones pictured here) and make a form's layout clearer and more attractive.

3. Add another style to the internal style sheet:

```
.subform .label {  
  display: inline-block;  
  width: 200px;  
  vertical-align: top;  
}
```

This descendent selector identifies any element with a class of `.label` within this form. The style changes the labels from inline elements (which won't accept width values) to `inline-block` elements. The width setting sets the label area to 200 pixels wide, while the vertical align setting makes sure the label text aligns with the top of the form fields next to them. As a result, when you apply this style to each of the questions in the form, you create an even-width column. But in order to see the effect, you must first apply the class to the appropriate page elements.

4. In the page's HTML, locate this code `<label for="name">` and add `class="label"`, so the tag looks like this:

```
<label for="name" class="label">
```

You must do the same for each question in the form, so...

5. Repeat Step 4 for the following pieces of HTML code: `<label for="email">`, `<label for="refer">`, `<label for="comments">`.

There's one additional question on the form—*Rate your apartment farming skills*. It isn't inside a `label` tag, since its purpose is to introduce a series of radio buttons, each of which has its own label. You need to add a `` tag to this text so you can apply the `label` style to it.

6. Find the text *Rate your apartment farming skills*, and then wrap it in a `` tag with a class of `label`, like so:

```
<span class="label">Rate your apartment farming skills</span>
```

Now the questions appear to be in a single column (Figure 11-12, top). But they'd look better if they stood out more and lined up with the corresponding form fields.

7. Edit the `.subform .label` style you created in Step 4, so it looks like this:

```
.subform .label {  
  display: inline-block;  
  width: 200px;  
  vertical-align: top;  
  text-align: right;  
  margin-right: 10px;  
  font-weight: bold;  
  color: rgba(255,255,255,.5);  
}
```


Preview the page in a web browser. The form should look like the bottom image in Figure 11-12.

The form is shaping up, but that Subscribe button looks out of place over at the left edge. You'll align it with the other form elements next.

Reader Subscription Form

What is your name?

What is your email address?

Rate your apartment farming skills Novice Intermediate Advanced

Where did you hear about us?

Any additional comments?

Reader Subscription Form

What is your name?

What is your email address?

Rate your apartment farming skills Novice Intermediate Advanced

Where did you hear about us?

Any additional comments?

FIGURE 11-12

Sometimes small and subtle changes can make a form more readable. Making the questions on the form bold and aligning them with their corresponding form elements (bottom figure) immediately improves the look of the form.

8. Add another style to the internal style sheet.

```
.subform input[type="submit"] {  
    margin-left: 220px;  
}
```

Since submit buttons are created by adding `type="submit"` to an `<input>` tag, you can simply use an attribute selector (page 72) to target them. This frees you from having to create a class style and applying it to the submit button.

Most browsers let you style buttons in other ways, too, so...

9. Edit the Submit button style by adding a few more properties:

```
.subform input[type="submit"] {  
  margin-left: 220px;  
  padding: 10px 25px;  
  font-size: 1em;  
  color: white;  
}
```

Padding adds space between the text inside the button and the edges of the button, while the `font-size` and `color` properties affect the text on the button. Now you can get more creative and add a gradient to the button.

10. Edit the Submit button style again:

```
.subform input[type="submit"] {  
  margin-left: 220px;  
  padding: 10px 25px;  
  font-size: 1em;  
  color: white;  
  background: rgb(0,102,153);  
  background: -webkit-linear-gradient(rgba(255,255,255,.1) 40%,  
  rgba(255,255,255,.5));  
  background: -moz-linear-gradient(rgba(255,255,255,.1) 40%,  
  rgba(255,255,255,.5));  
  background: -o-linear-gradient(rgba(255,255,255,.1) 40%,  
  rgba(255,255,255,.5));  
  background: linear-gradient(rgba(255,255,255,.1) 40%, rgba(255,255,255,.5));  
}
```

Here you set a standard background color (for IE 9 and earlier) followed by a linear gradient. There are two color stops. The first color runs from the top to 40 percent of the way into the button, then the gradient begins (for a recap of gradients and color stops, turn to page 262).

Finally, you'll tweak the look just a bit. You'll remove the standard border, round the corners, and add a glow around the box.

11. Edit the Submit button style one last time (changes in bold):

```
.subform input[type="submit"] {  
  margin-left: 220px;  
  padding: 10px 25px;  
  font-size: 1em;  
  color: white;  
  background: rgb(0,102,153);  
  background: -webkit-linear-gradient(rgba(255,255,255,.1) 40%,
```

```

rgba(255,255,255,.5));
  background: -moz-linear-gradient(rgba(255,255,255,.1) 40%,
rgba(255,255,255,.5));
  background: -o-linear-gradient(rgba(255,255,255,.1) 40%,
rgba(255,255,255,.5));
  background: linear-gradient(rgba(255,255,255,.1) 40%, rgba(255,255,255,.5));
  border: none;
  border-radius: 5px;
  box-shadow: 0 0 4px white;
}

```

Setting the border to none removes the border browsers normally draw around the button, while the `border-radius` property (page 207) rounds the button's corners. Finally, by adding a drop shadow with no horizontal or vertical offset (that's the `0 0` part), you can add a glow to an element. In this case, it looks like a slight white glow coming from behind the button.

NOTE You can take this button design even farther. Try creating a rollover style for it—`.subform input[type="submit"]:hover`—and change the background color. You can even animate that transition using the information you learned in the previous chapter!

You've got the text labels and Subscribe button looking great, but why stop there? Time to jazz up the form fields. Begin by changing their font and background colors.

12. Add a style for the form's Select menu:

```

.subform select {
  font-size: 1.2em;
}

```

This just pumps the text size up a bit. You could choose a font, add a background color, and make other changes. However, some browsers (like Safari) don't really let you style the drop-down menus much, so make sure you test out any style changes you make to drop-down menus.

Now it's time to change the text fields.

13. Create a new group selector for styling the three text boxes in the form:

```

.subform input[type="text"], .subform textarea {
  border-radius: 5px;
  border: none;
  background-color: rgba(255,255,255,.5);
  color: rgba(255,255,255,1);
  font-size: 1.2em;
  box-shadow: inset 0 0 10px rgba(255,255,255,.75);
}

```

This group style selects all input elements with the type of text as well as the multiline text boxes (the `<textarea>` tag). This adds various properties that you should be familiar with by now, like `border-radius`, `background-color`, `font-size`, and `box-shadow`). The text boxes look a little small, so you'll set their widths and add a little bit of padding.

14. Edit the style you just created by setting a width and padding (changes in bold):

```
.subform input[type="text"], .subform textarea {
  font-size: 1.2em;
  border-radius: 5px;
  border: none;
  background-color: rgba(255,255,255,.5);
  color: rgba(255,255,255,1);
  font-size: 1.2em;
  box-shadow: inset 0 0 10px rgba(255,255,255,.75);
  width: 500px;
  padding: 5px;
}
```

You can make your form easier for your visitors to fill out by highlighting the active form element with the special `:focus` pseudo-class (page 70). You'll add that in the next step.

15. At the end of the internal style sheet, add one last style for the pull-down menu and the three text fields:

```
.subform input[type="text"]:focus, .subform textarea:focus {
  background-color: white;
  color: black;
}
```

Preview the page in a web browser. It should now look like Figure 11-13 You can find a completed version of this tutorial in the [11_finished→form](#) folder.




FIGURE 11-13

Using the `:focus` pseudo-class, you can make your forms more interactive by highlighting form fields the visitor uses. Here, you can see you're about to type in the Comments field because of its white background color.

CSS Page Layout

CHAPTER 12:

Introducing CSS Layout

CHAPTER 13:

Building Float-Based Layouts

CHAPTER 14:

Responsive Web Design

CHAPTER 15:

Positioning Elements on a Web Page



Introducing CSS Layout

CSS leads a double life. As great as it is for formatting text, navigation bars, images, and other bits of a web page, its truly awesome power comes when you're ready to lay out entire web pages. While HTML normally displays onscreen content from top to bottom, with one block-level element stacked after another, CSS lets you create side-by-side columns and position images or text anywhere on the page (even layered on top of other page elements), so you can create much more visually interesting web pages.

There's a lot to CSS layout. The next three chapters cover the most important CSS techniques in detail. This chapter provides a brief overview of the principles behind CSS layout and a handful of useful guidelines for approaching your own layout challenges.

■ Types of Web Page Layouts

Being a web designer means dealing with the unknown. What kind of browsers do your visitors use? Are they viewing your site on an Android phone or an iPad? The biggest issue designers face is creating attractive designs for different display sizes. Monitors vary in size and resolution: from 15-inch, 640 x 480 pixel notebook displays to 30-inch monstrosities displaying, oh, about 5,000,000 x 4,300,000 pixels. Not to mention the petite displays on mobile phones, and the small- to mid-range screens of tablets.

Web layouts offer several basic approaches to this problem. Nearly every page design you see falls into one of two types—*fixed width* or *liquid*. Fixed-width designs give you the most control over how your design looks but can inconvenience some

of your visitors. Folks with really small monitors have to scroll to the right to see everything, and those with large monitors end up with wasted space that could be showing more of your excellent content. In addition, smartphone owners need to pinch and zoom to get to the content they're after. Liquid designs, which grow or shrink to fit browser windows, make controlling the design more challenging but offer the most effective use of the browser window. A recent innovation—*responsive web design*—seeks to solve the problem of wildly varying screen widths, but at the cost of added complexity.

- **Fixed Width.** Many designers prefer the consistency of a set width, like the page in Figure 12-1, top. Regardless of the browser window's width, the page content's width remains the same. In some cases, the design clings to the left edge of the browser window, or, more commonly, it's centered in the middle. With the fixed-width approach, you don't have to worry about what happens to your design on a very wide (or small) monitor.

Many fixed-width designs are below 1,000 pixels wide, letting the window and the space taken up by scrollbars and other parts of the browser's "chrome" fit within a 1024 x 768 pixel monitor. A very common width is 960 pixels. Many websites are fixed width, but that's changing, thanks to the widespread adoption of smartphones and tablets, which are often much narrower than the average fixed-width web page design.

NOTE

For examples of fixed-width designs, visit www.alistapart.com, espn.go.com, or www.nytimes.com.

- **Liquid.** Sometimes it's easier to roll with the tide instead of fighting it. A liquid design adjusts to fit the browser's width—whatever it may be—by assigning percentage widths instead of absolute pixel values. Your page gets wider or narrower as your visitor resizes the window (Figure 12-1, middle). While this type of design makes the best use of the available browser window real estate, it gives you the additional challenge of making sure your design looks good at different window sizes. On very large monitors, these types of designs can look ridiculously wide, creating very long, difficult to read lines of text.

NOTE

For an example of a liquid layout, check out <http://maps.google.com>.

- **Responsive web design (RWD).** This new technique, championed by web designer Ethan Marcotte, offers another way to address the problem presented by the wildly different screen sizes of smartphone, tablet, and desktop web browsers. Instead of presenting a single layout for all devices, responsive web design compensates for different browser widths by changing its presentation. For example, a responsive web page may shrink down from a wide, multicolumn layout for desktop monitors to a single-column layout for smartphones. In this

way, responsive web design is very much like liquid layouts—the design uses percentages to grow or shrink in response to the width of the browser window. However, it goes one step further by using some tricky CSS—called media queries—to send different designs to different-width browsers, letting you create very different looking layouts depending on the device viewing the page.

In the tutorials at the end of next chapter, you'll create a fixed-width design and a liquid design. In Chapter 13, you'll dive into the techniques for creating responsive web designs.

NOTE The `max-width` and `min-width` properties offer a compromise between fixed and liquid designs. See page 219.



FIGURE 12-1
 You have several ways to deal with the uncertain widths of web browser windows and browser font sizes. You can simply ignore the fact that your site's visitors have different resolution monitors and force a single, unchanging width for your page (top), or create a liquid design that flows to fill whatever width window it encounters (middle). A responsive design literally reformats itself depending upon the browser window width. The Boston Globe (www.bostonglobe.com) site, for example, goes from one column (left), to two columns (middle), to three columns (right) as the browser window expands.

■ How CSS Layout Works

As discussed in Chapter 1, in the early days of the Web, HTML's limitations forced designers to develop clever ways to make websites look good. The most common tool was the `<table>` tag, which was originally intended to create a spreadsheet-like display of information composed of rows and columns of data. Designers used HTML tables to build a kind of scaffolding for organizing a page's contents (see Figure 12-2). But because the `<table>` tag wasn't meant for layout, designers often had to manipulate the tag in unusual ways—like placing a table inside the cell of *another* table—just to get the effect they wanted. This method was a lot of work, added a bunch of extra HTML code, and made it very difficult to modify the design later. But before CSS, that's all web designers had.

HTML tables have one thing going for them: They provide a well-organized grid with a unified structure of individual cells. For CSS design, you use individual tags to contain content that you want to position in one area of the page. By grouping content into lots of individual containers and positioning those containers, you can create complex designs made up of columns and rows. Before HTML5, you had one tag in particular to achieve this goal: the `<div>` tag.

The `<div>` Tag

Web page layout involves putting chunks of content into different regions of the page. With CSS, one element commonly used for organizing content is the `<div>` tag. As you read on page 22, the `<div>` tag is an HTML element that has no inherent formatting properties (besides the fact that browsers treat the tag as a block with a line break before and after it). Instead, it's used to mark a logical grouping of elements or a *division* on the page.

You'll typically wrap a `<div>` tag around a chunk of HTML that belongs together. The elements comprising the logo and navigation bar in Figure 12-2 occupy the top of the page, so it makes sense to wrap a `<div>` tag around them. At the very least, you would include `<div>` tags for all the major regions of your page, such as the banner, main content area, sidebar, footer, and so on. But it's also possible to wrap a `<div>` tag around one or more additional divs. One common technique is to wrap the HTML inside the `<body>` tag in a `<div>`. Then you can set some basic page properties by applying CSS to that *wrapper* `<div>`. You can set an overall width for the page's content, set left and right margins, center all of the page's content in the middle of the screen, and add a background color or image to the main column of content.

Once you've got your `<div>` tags in place, add either a class or ID to each one, which becomes your handle for styling each `<div>` separately. The `<div>` tag for a page's banner area might look like this: `<div class="banner">`. You can also use an ID, but you can use the same ID only once per page, so when you have an element that appears multiple times, use a class. If you have several divs that position photos and their captions, for example, you can wrap those tags in a div and add a class like this: `<div class="photo">`. (For more on knowing when to use a div, read the box on page 60.) In addition, when it comes to the cascade (Chapter 5), IDs are very

powerful and easily override other styles, often forcing you to create long-winded selectors like `#home #banner #nav` a just to override previously created selectors using IDs. For this reason, many web designers avoid IDs and stick with classes.

Once you have the divs in place and have accurately identified them with IDs or class names, you can then create CSS styles to position those divs on the page using floats (Chapter 13).

WORD TO THE WISE

A Delicate Balancing Act

Although divs are critical to CSS layout, don't go crazy pelting your page with divs. A common trap is to believe you must wrap *everything* on a web page in a `<div>` tag. Say your main navigation bar is an unordered list of links (like the one described on page 304). Because it's an important element, you may be tempted to wrap a `<div>` around it: `<div class="mainNav">...</div>`.

But there's no reason to add a `<div>` when the `` tag is just as handy. As long as the `` contains the main navigation bar links, you can simply add your class to that tag: `<ul class="mainNav">`. An additional `<div>` is just unnecessary code.

Likewise, it doesn't make sense to use a `<div>` when another, more logical HTML tag is at hand. For example, say you want to add a pull quote to a long passage of text—a box aligned to the right edge of the page displaying an exciting quote pulled from the page. In this case, you can skip an extra `<div>` and

simply use the HTML `<blockquote>` tag. You can position the `blockquote` tag using the `float` property as discussed on page 220.

That said, don't be afraid of divs either. Adding a few extra divs to a page is not going to substantially change the file size or slow the page's download speed. If a div helps you get the job done, and no other HTML tag makes sense, then by all means, use a div. Also, a div is the only way to go when you want to group a bunch of different HTML tags into a cohesive unit. In fact, it's not at all uncommon to see one div surround one or more other divs.

The basic rule of thumb is you should try to keep the amount of HTML on a page down to a minimum, but use as much HTML as is needed. If adding a few divs makes sense for the design—go for it. Or, if you're digging into HTML5, try the sectioning elements described in the next section.

HTML5 Sectioning Elements

Before HTML5, divs were the main way designers organized content. HTML5 introduces many new HTML tags that are intended to group certain types of content. For example, the `<article>` tag is intended for content that makes up a single, self-contained composition—a blog post, for example. Likewise, the `<header>` tag is intended to provide headline, navigational aids, and other introductory material for a page or a section of page. Then there's the `<footer>` tag that's meant to contain concluding information like copyright notice, the name of the website's creator, the date the page was published, and so on. In a nutshell, HTML5 provides tags that take over the job of the `<div>` tag for specific types of content. (Visit www.adobe.com/devnet/dreamweaver/articles/understanding-html5-semantics.html for a quick introduction to HTML5 sectioning elements.)

NOTE

If you go the HTML5 route, then don't forget to use the HTML5 shim described in the box on page 24 to make sure that Internet Explorer 8 and earlier can format those new elements.

As you learned on page 23, the new HTML5 elements are intended to add semantics to a web page. That is, the name of the tag—`<header>`, for example—imparts identifying information about what's inside that tag. The `<figure>` tag is intended to enclose—you guessed it—a figure. In other words, if you want to enclose particular type of content inside a tag, see if an HTML5 tag fits the bill. If the content is your page's footer, then use the `<footer>` tag instead of the plain old `<div>`. In the world of HTML5, the `<div>` tag still exists and is perfectly valid to use. But these days it's generally used to group content for stylistic reasons—for example, if you'd like to add a border around a group of tags or move those tags over to the left side of the page using a float, then enclose those tags in a `<div>`. (You'll learn how to do just that in Chapter 13.)

That all said, beyond bragging rights at your next web designer meetup, there's no direct benefit to using the HTML5 right now. In the future, software might look through your HTML and identify individual articles based on the presence of the `<article>` tag, or use the HTML5 tags in some other way to better analyze your web page. Or, if you want to future-proof your web pages and be prepared the day when HTML5 rules the world, you could go ahead and use HTML5 today. However, if you've grown up using `<div>` tags and don't want to bother using some JavaScript to make HTML5 work in Internet Explorer 8 (see Note above), you may want to just stick with the `<div>` tag for now.

Techniques for CSS Layout


The vast majority of web pages use the CSS `float` property for layout (see the box on page 413 for other CSS layout options). You've already encountered this seemingly simple property in Chapter 8, where the `float` property was introduced as a way of positioning an image within a column of text by either floating the image to the left or right side. The same concept applies to other tags: By setting the width of an element and floating it to the left or right, you can create a column (the text following the element ends up wrapping around the floated element as if it were another column). By using the `float` property with multiple divs, or other tags, you're able to achieve multicolumn layouts. Taking this technique further, you can quickly create complex, multicolumn layouts by placing floated divs within floated divs.

Another CSS technique, absolute positioning, lets you place an element anywhere on the page with pixel-level accuracy. You can place an element 100 pixels from the top edge of the browser window and 15 pixels in from the left edge, for example. Page-layout programs like InDesign and Quark Xpress work this way. Unfortunately, the fluid nature of web pages and some of the weird characteristics of absolute positioning make it difficult to achieve total layout control with this technique. As you'll read in Chapter 14, it is possible to lay out a page by using absolute positioning, but, in general, this technique is better suited to smaller tasks like positioning a logo in a particular location of the page.

Don't worry if this sounds rather abstract right now—you'll see all of these techniques in action in the next three chapters.



FIGURE 12-2
 Correctly putting together the HTML necessary to convert a Photoshop mockup into HTML and CSS reality involves seeing the underlying structure and wrapping related groups of HTML within <div> tags. Sometimes, it can take a lot of divs to make a design come to life.



■ Layout Strategies

Web page layout with CSS is more of an art than a science; there's no one formula to follow for marking up your content with HTML and creating your CSS. What works for one design might not for another. Although that might not be a comforting thought—"Hey, I bought this book to learn this darn stuff"—CSS layout is something you'll learn through experience, learning how the different CSS properties work (especially floats and absolute positioning), reading about different layout techniques, following tutorials like the ones in the next two chapters, and lots of practice.

However, there are definitely some strategies you can adopt as you approach CSS layout. These are more like guidelines than hard-and-fast rules, but as you begin to see your projects through the initial visual design, start with these tips in mind.

Start with Your Content

Many designers like to jump right into the good stuff—colors, fonts, icons, and images. But beginning with the visual design is putting the cart before the horse. The most important elements of a web page are the contents: headlines, paragraphs of text, stunning photographs, navigational links, videos, and such are what people will come to your site for. They want to read, learn, and experience what your site has to offer. Content is king, so you think of what you want to say before you tackle how it should look. After all, it won't do you much good to create a fantastic, 3D-looking sidebar box if you don't have anything meaningful to put in that box.

In addition, a page's message should dictate its design. If you decide that your home page needs to sell the services of your company and highlight the excellent customer service you offer, you might decide that a large photo of your friendly staff is important, as well as a quote from a satisfied customer. Since both of these elements are important to the page's message, you can craft the visual message by making both the picture and the quote prominent and compelling.

Mobile First

Along the same lines, the rise of smartphones and tablets has driven designers to think long and hard about winnowing down their content to just the key message and facts. This *Mobile First* movement is based on the limited screen size of smartphones as well as the limited attention of people on the go. Mobile First design is about starting with your content, but it's also about getting rid of extraneous noise—including supplementary information that fits fine on a large desktop screen, but merely gets in the way on the smaller screen and detracts from the key information you're hoping to deliver.

Keep in mind that if your site will be visited by a significant number of people using smartphones or small tablets, not everyone will want to scroll through a long page of information (or pinch and zoom to see everything available on a page). Rather than trying to fill every last square inch of a 32" desktop monitor, think about simplifying your content so it's clear, direct, and easy to take in.

NOTE

The term *Mobile First* was coined by Luke Wroblewski. In fact, he wrote a fantastic short treatise on the subject that's worth reading: www.abookapart.com/products/mobile-first.

POWER USERS' CLINIC**Other CSS3 Layout Options**

Web designers initially used tables to create multicolumn layouts. Then the CSS float property came onto the scene and provided another, less code-intensive method to lay out a web page. And while most designers still use the float property to achieve their designs, that may change in the not-so-distant future.

The CSS working group at the W3C is busily finalizing plans on several other techniques for CSS layout. For example, the CSS *multicolumn* layout module provides a way to take a long column of text and display it across multiple side-by-side columns. You'll learn about it in the next chapter, on page 440.

The *flexible box* layout module provides yet another way to arrange boxes of content—vertically, horizontally, and in different directions and orders. And remarkably, this module

is pretty well supported in many browsers today. You'll read about flex in the box on page 436.

Finally, the *CSS grid* layout module is perhaps the most ambitious attempt to change how designers lay out web pages. This method lets you break up a page into a set of rows and columns, then accurately attach page elements to that grid. It's intended to make building web applications easier and more like building desktop *programs*. The CSS grid is pretty complicated and (at the time of this writing) not yet supported by any currently shipping browsers, although there is support in the beta version of IE 10. You can read more about it at <http://blogs.msdn.com/b/ie/archive/2011/04/14/ie10-platform-preview-and-css-features-for-adaptive-layouts.aspx>.

Start with a Sketch

Once you've figured out your content, you can think about organizing that content visually. Some designers start by hand coding the HTML: creating divs, adding `<header>`, `<article>`, `<footer>` tags, and so on. This is a fine approach, often called “designing in the browser” since it gives you a head start on building your site by jumping right into the HTML.

However, before jumping into the HTML, you should at least sketch out the placement of your content. You don't need anything fancy—paper and pencil work fine. Since web design is about placing content inside of boxes (divs and other HTML tags) and placing them on the page, simply sketching out a bunch of boxes, drawing columns, and so on, is a fast and easy way to try out different page layouts. You can quickly get a feel for where content should go, how big it should be, and the general color tone (light or dark).

TIP

Yahoo offers a free Stencil Kit (<http://developer.yahoo.com/yypatterns/wireframes>) that you can use in Illustrator, Visio, OmniGraffle, and other graphics programs to create web page mock-ups. The supplied user interface elements, like buttons, form fields, windows, and navigation buttons can make sketching out a page layout as simple as dragging and dropping icons.

If you're comfortable with a graphics program like Photoshop, Illustrator, or Fireworks, you can use that to create a visual design. If you're not a whiz with graphics

programs, even just drawing boxes to indicate different placement of page elements can help you refine your thinking about how the page should be laid out. It's a lot easier to change a two-column design to a four-column design by resizing boxes in Illustrator than by rewriting HTML and CSS.

However, if you do use a graphics program, don't spend too much time refining the graphic design. It's a lot of work to create the look of many CSS properties in Photoshop or Illustrator, and you'll only have to recreate that look using CSS code. In other words, try to refine a "lo-fi" look for your site on paper or in a graphics program, and then jump to your text editor to create the HTML to fit your content and use the CSS properties you've learned in this book to test out different styles.

Identify the Boxes

Once you've created a visual mockup, it's time to think of how to create the HTML markup and CSS to achieve your design goal. This process usually involves envisioning the different structural units of a page and identifying elements that look like individual boxes. For example, in Figure 12-2, there are quite a few elements that look like boxes: most obviously, the three announcement boxes near the bottom (marked as A in Figure 12-2). Each box is usually a good candidate for a separate `<div>` tag (unless there's a more appropriate HTML tag, as discussed in the box on page 409).

Often a visual clue in your mockup can help you decide if a div is needed. For example, a border line drawn around a headline and several paragraphs of text indicates you'll need to surround that group of HTML tags with a `<div>` tag that has a border applied to it.

In addition, whenever you see chunks of text sitting side by side (like the three chunks of content in the footer in Figure 12-2), you know you'll need to have each group in its own `<div>` tag—HTML tags don't usually sit side by side, so you have to use some layout mojo (like the float technique covered in the next chapter) to make that happen.

It's also common to group divs (or other tags) that sit side by side in columns within another div. For example, in the bottom half of Figure 12-2, you can see the basic set of `<div>` tags that provide the page's structure. The "news" `<div>` and the `<footer>` tag are containers for their own set of divs. While this isn't always a necessity, it can provide flexibility. For example, you can reduce the main area (the photo of the hand and the tagline) in width and move the news div to the right side to form its own column. The news items could then be stacked on top of each other rather than sitting side by side.

Go with the Flow

Tags don't normally sit side by side or layer on top of each other. Normally, HTML tags act pretty much like text in a word-processing program: filling the entire width of the page and flowing from top to bottom. Each block-level tag—headline, paragraph, bulleted list, and so on—stacks on top of the next block-level tag. Since that's the "business as usual" approach of HTML tags, you usually don't have to do any kind of positioning if you plan on stacking one div on the next.

For example, in Figure 12-2, four elements—the `<header>` tag, “main” div, the `<section>` tag, and the `<footer>` tag—span the entire width of their container (the `<body>` tag) and sit one on top of the other. Because this is the normal way block-level tags work, you don’t need to do anything special with the CSS for those four divs to stack on top of each other.

Remember Background Images

You’ve no doubt seen tiled images filling a web page’s background, or subtle gradients adding depth to a banner. But the `background-image` property provides another way to add photos to a page without resorting to the `` tag. Not only does putting an image into the background of an existing HTML tag save the few bytes of data required by the `` tag, but it also simplifies some layout challenges.

For example, in Figure 12-2, the central image of the hands holding the Chia Pet (B) is actually just a background image. This makes placing another div—the one with the tagline “Compassionate care...” (C) really easy, since it’s just sitting on top of the background of its parent div. Likewise, the picture of the doctor at the lower right of the page is just a background image placed in that div—adding some right padding pushes the text in that div out of the way of the photo.

NOTE

There are downsides to using photos in the background of divs (or any HTML tag). First, web browsers usually don’t print backgrounds—so if you’ve got a page with a map containing driving directions to your business, insert the map with the `` tag and not as a background image. Likewise, search engines don’t search CSS, so if you think the image can help attract traffic to your site, use an `` tag and include a descriptive `alt` attribute.

Pieces of a Puzzle

This tip can be filed under “creative problem solving” or “if I stare at this design long enough I’ll come up with some crazy solution.” Often, what looks like a single, unified whole is actually composed of multiple pieces.

You can see a simple example of this in Figure 12-2, even though at first glance it looks like one big white box full of content. Actually there are four stacked divs, each with a white background. So, if you’re having trouble seeing how to put together one large element on a page—a very large graphic, a rainbow that spans several columns, or just a solid background color that appears to span multiple areas of a page—think about how you could achieve the same look breaking the large unit into smaller pieces that are joined like parts in a jigsaw puzzle.

Layering Elements

If you’re a Photoshop, Illustrator, or Fireworks fan, you’re probably used to the notion of layers. Layers let you create separate canvases that float on top of each other to build one unified image. In these programs, it’s easy to make a logo float on top of a headline of text, or place a photo over another photo. If you want a web page that has this kind of effect, you have a couple of choices.

Often the easiest way to layer something on top of a photo is to put the image into the background of another tag (see the tip on page 415). Because the background image is behind the tag, anything inside that tag—text, another photo—will sit on top of the photo.

But what if you want to layer a photo on top of some text? In that case, you'll turn to the only CSS property that lets you layer elements—the `position` property. You'll learn all about that property in Chapter 15, since to position something on top of something else requires absolute positioning.

Don't Forget Margins and Padding

Finally, sometimes the simplest solution is the best. You don't always need fancy CSS to move a page element into place. Remember that padding and margins (page 195) are just empty space, and by using those properties, you can move elements around the page. For example, the tagline box (C in Figure 12-2) is positioned simply by setting the top and left padding of the parent div. As you can see in the diagram in the bottom half of Figure 12-2, the tagline is placed inside another div (`<div id="main">`). That div doesn't actually have any content besides the tagline—the photo is just a background image—so adding padding moves the tagline div down and to the right.

Building Float-Based Layouts

Float-based layouts take advantage of the `float` property to position elements side by side and create columns on a web page. As described in Chapter 7 (page 220), you can use this property to create a wrap-around effect for, say, a photograph, but when you apply it to a `<div>` tag, `float` becomes a powerful page-layout tool. The `float` property moves a page element to one side of the page (or other containing block). Any HTML that appears below the floated element moves up on the page and wraps around the float.

The `float` property accepts one of three different values—`left`, `right`, and `none`. To move an image to the right side of the page, you could create this class style and apply it to the `` tag:

```
.floatRight { float: right; }
```

The same property applied to a `<div>` tag full of content can also create a sidebar:

```
.sidebar {  
  float: left;  
  width: 170px;  
}
```

Figure 13-1 shows these two styles in action.

NOTE

The `none` value turns off any floating and positions the element like a normal, unfloat element. It's useful only for overriding a float that's already applied to an element. You may have an element with a particular class such as `.sidebar` applied to it, with that element floating to the right. But on one page you may want an element with that class to *not* float, but to be placed within the flow of the page, like this Note box. By creating a more specific CSS selector (see page 480) with `float: none`, you can prevent that element from floating.




FIGURE 13-1
 You can use the float property to lay out a web page with multiple columns. On this page, a block of content is floated to the left edge. The sidebar has a set width, but the main content doesn't, which makes this design a liquid layout. The main section of the page simply expands to fill the width of the browser window. In the upper right, the bathtub photo is floated to the right.

A simple two-column design like Figure 13-1 requires just a few steps:

1. Wrap each column in a <div> tag with an ID or class attribute.

In Figure 13-1, the news items listed in the left sidebar are wrapped in one <div>—<div class="news">—and the main content in another div—<div class="main">.

2. Float the sidebar <div> either right or left.

When you work with floats, the source order (the order in which you add HTML to a file) is important. The HTML for the floated element must appear *before* the HTML for the element that wraps around it.

Figure 13-2 shows three two-column layouts. The diagrams on the left side show the page's HTML source order: A `<div>` for the banner, followed by a `<div>` for the sidebar, and, lastly, a `<div>` for the main content. On the right side, you see the actual page layout. The sidebar comes *before* the main content in the HTML so it can float either left (top, bottom) or right (middle).

3. Set a width for the floated sidebar.

Unless you're floating an image with a predefined width, you should always give your floats a width. This way, you create a set size for the floated element, letting the browser make room for other content to wrap into position.

The width could be a fixed size like 170px or 10em. You can also use percentages for a flexible design that's based on the width of the browser window. (See page 158 for more about the pros and cons of the different measurement units.) If the sidebar is 20 percent wide, and the browser window is 700 pixels wide, then the sidebar will be 140 pixels wide. But if your visitor resizes the window to 1000 pixels, then the sidebar grows to 200 pixels. Fixed-width sidebars are easier to design for, since you don't have to consider all the different widths the sidebar might stretch to.

However, percentages let you maintain the same proportions between the two columns, which can be more visually pleasing. In addition, percentages make your designs more flexible, since the overall proportion of the page can adjust to fit the screen size, something that's important when creating responsive web designs, which you'll learn about in the next chapter.

NOTE

When the overall page design is a fixed width (as described on page 406), percentage width values for the sidebar are based on the fixed-width containing element. The width isn't based on the window size and won't change when the browser window changes size.

4. Add a left margin to the main content.

If the sidebar is shorter than the other content on the page, the text from the main column wraps underneath the sidebar, ruining the look of two side-by-side columns (see Figure 13-12 for an example). Adding a left margin that's equal to or greater than the width of the sidebar indents the main content of the page, creating the illusion of a second column:

```
.main { margin-left: 180px; }
```







By the way, it's usually a good idea to make the left margin a little bigger than the width of the sidebar: This creates some empty space—a white gutter—between the two elements. So, when you use percentages to set the width of the sidebar, use a slightly larger percentage value for the left margin.

HTML Source Order

CSS Layout

FIGURE 13-2

Creating a two-column layout is a simple matter of floating a `<div>` tag to the left (top). To make a sidebar move from the left to right side of the page (middle), just change the sidebar's CSS styling to `float: right`. You don't need to make any other changes to your CSS or HTML.



Avoid setting a width for the main content div. It's not necessary, since browsers simply expand it to fit the available space. Even if you want a fixed-width design, you don't need to set a width for the main content div, as you'll see in the next section.


■ Applying Floats to Your Layouts

Now that you've learned a basic two-column liquid layout, you can adapt it in countless ways. Converting it into a fixed-width layout is a snap. Simply wrap all the tags within the page's body inside *another* `<div>` (like `<div class="wrapper">`). Then, create a style for that new container element that has a set width, such as 960 pixels (see Figure 13-2, bottom). That width setting constrains everything inside the container box.

TIP It's also possible to create a fixed-width page without resorting to the extra wrapper div: set a width on the `<body>` tag. You already saw an example of this technique in the tutorial on page 225.

Expanding it into a three-column design isn't difficult, either (Figure 13-3). First, add another `<div>` between the two columns and float it to the right. Then add a right margin to the middle column, so that if the text in the middle column runs longer than the new right sidebar, it won't wrap underneath the sidebar.

The rest of this section explores more CSS layout techniques that use float-based layouts.



Floating All Columns

It's perfectly possible to float every column, not just the left and right sidebars. You could float the first sidebar to the left, the middle column to the left, and the right sidebar to the right, as shown in Figure 13-4, top. This approach lets you put more

than three columns in your design. You can float four or more columns, as long as there's room for all the floats to fit side by side.

When you float all columns in a design, you need to pay close attention to the widths of each column. If the total width of all the columns is more than the space available—for example, if the browser window is smaller or the columns are placed inside another `<div>` with a set width—then the last column drops down below the others. (You can read a solution to this dropping float problem on page 480.)

UP TO SPEED

You Don't Have to Reinvent the Wheel

If terms like *liquid layout* and *containing element* sound a little intimidating, don't give up. First of all, the tutorials beginning on page 440 walk you step by step through the process of laying out web pages with CSS. But there's no law saying you have to create your own CSS layouts from scratch. On the Web, you'll find plenty of pre-built and tested designs you can make your own. The LayoutGala site offers 40 different CSS designs that work in all common browsers (<http://blog.html.it/layoutgala/>). The designs are just basic skeletons consisting of `<div>` tags

and the CSS that positions them. All you need to do is fill them with your own design touches like font styling and imagery.

There are also quite a few *layout generators*—online tools that let you customize basic requirements like the number of columns you want, whether you're after a liquid or fixed layout, and so on. The Gridinator (<http://gridinator.com>) provides a simple tool for creating a complex multicolumn grid system (see the box on page 430). You can then download HTML and CSS files with the code created for you.

In addition, floating more than just the sidebars lets you change the order of your divs in the HTML. Take, for example, the left diagram in Figure 13-3, which shows the order of the `<div>` tags for that page. Because of the way floated elements work, they must appear before any content that wraps around them, so in this example, the main content area must go *after* the sidebars.

The order of the `<div>` tags in the HTML may not seem like a big deal until you try to browse the web page *without* CSS, which is the case for many alternative browsers, including screen readers that read a page's content aloud to visually impaired visitors. Without CSS, all the sidebar material (which often includes navigational elements, ads, or other information that's not relevant to the main topic of the page) appears before the content the visitor came to read in the first place. The inconvenience of having to scroll past the same sidebar content on each page will turn off some visitors. Furthermore, your page is less accessible to vision-impaired visitors, who have to listen to their screen readers read off a long list of links and ads before coming to any real information.

And if that doesn't sway you, you've got the search engines to worry about. Most search engines limit the amount of HTML they read when searching a site. On a particularly long web page, they simply stop at a certain point—possibly missing important content that *should* be indexed by the search engine. Also, most search engines give greater value to the HTML near the beginning of the file. So if you're worried about getting good placement in search engine results, it's in your best

interest to make sure the important content is as close as possible to the top of the page's HTML code.

In the top-left diagram in Figure 13-4, the main content's HTML is between the left and right sidebars, which is better than having it after both sidebars. You can even put the main content before *both* sidebars' HTML by wrapping the main content and left sidebar in one <div>, floating that <div> left, and then floating the main content right and the left sidebar left *within* that <div> (Figure 13-4, bottom). Voilà—the main column's HTML falls before the other <div> tags.

Floats Within Floats

The bottom diagram in Figure 13-4 illustrates another useful technique—floating elements *within* floats. Imagine that the main content (3) and the left sidebar (4) divs didn't exist, and only the column wrapper (2) and the right sidebar (5) were left. You'd have just a basic two-column design, with one column floated left and another floated right. In fact, it's still a two-column design even with the two divs (3 and 4) placed back inside the column-wrapper div. The difference is that the left column is itself divided into two columns.





FIGURE 13-4

There's more than one way to float a page. CSS's flexibility provides many ways to create a multicolumn layout. Using different methods of floating, you can easily change the source order of the HTML for the page, as you can see in the diagrams at left. Right-side diagrams represent final web page layout.

Although this arrangement is a bit confusing, it's also helpful in a number of instances. First, it lets you add columns within a column. The three-column layout at the top of Figure 13-5 shows a small Tips box in the middle column that also has two columns inside it. By nesting floats inside floats, you can create some very complex designs.

In addition, when you have just a couple of floated elements divided into columns with additional floated elements, it's easier to calculate the widths of page elements. That's a good thing when you need to control float drops (page 480) and other problems that occur when columns get too wide.



POWER USERS' CLINIC

Finding Order in the Grid

Graphic designers used grids to provide an underlying order to their layouts long before the Web came around. A grid is simply a series of rows and columns that help align elements within a layout. For example, in a 12-column grid, you divide the page into 12 equally sized columns, usually with a small amount of space—a *gutter*—between each.

But the grid doesn't mean that your page needs 12 skinny columns of content. Instead, you usually divide the 12 columns (often referred to as *grid units*) into groups. For example, in a three-column design, you might have one left-hand sidebar that's 3 grid units wide, a main column that's 6 grid units wide, and a right sidebar that's 3 grid units wide to fill the entire 12-unit width. This 12-unit grid has the flexibility to let you try other layouts as well, while retaining a common and consistent measurement scheme. For example, you could have three columns of equal width (4 grid units each).

In most CSS grid systems, you divide a page into rows composed of columns. There's usually some class-based nomenclature to define a row using a `<div>`, like this:

```
<div class="row">
```

And inside the row, you place additional tags, often `<div>` tags, but you can use any block-level tag like the HTML5 sectioning elements (page 409). Each of these tags includes classes indicating how many grid units wide they should be. For example, a three-column layout may have code like this:

```
<div class="span3"> </div>  
<div class="span6"> </div>  
<div class="span3"> </div>
```

The class name depends upon the grid system. Two popular grid-based frameworks—Foundation (<http://foundation.zurb.com/docs/grid.php>) and Twitter Bootstrap (<http://twitter.github.com/bootstrap/scaffolding.html#grid>)—include complete CSS-based solutions for grid systems. You use their basic CSS and their naming conventions to create columns of varying widths. For a simpler approach, read Chris Coyier's blog post at CSS-Tricks.com, where he explains how to create your own simple grid system: <http://css-tricks.com/dont-overthink-it-grids/>.

Overcoming Float Problems

As you get more adventurous with CSS, you'll probably encounter—like many web designers before you—some of the weird intricacies of working with floats. This section describes a few common problems and their solutions. (And if you ever stumble upon a problem not listed here, you can always take it to one of the online forums or discussion lists in Appendix A.)

Clearing and Containing Floats

Floats are powerful design tools because they let content flow around them. Floating a photo lets text below it move up and wrap around the image (Figure 13-1). When you're creating float-based column designs, though, sometimes you *don't* want content to move up and next to a floated element. For example, you frequently want to keep copyright notices, contact information, or other housekeeping details at the bottom of your web page, below all other content.

OVERCOMING FLOAT PROBLEMS

In the two- and three-column designs you've seen so far, if the main column is shorter than either of the floated sidebar columns, a footer can move up and around the left floated column (Figure 13-6, left). To make the footer stay down below the sidebars, you can use the `clear` property. This property prevents an element from wrapping around floats. You can make an element drop below a left-floated object (`clear: left;`) or a right floated object (`clear: right;`). For footers and other items that need to appear at the bottom of the page, you should clear *both* left and right floats, like this:

```
footer { clear: both; }
```





FIGURE 13-6
You don't always want an item to wrap around a floated element (left). Copyright notices and other material that belong at the bottom of a page usually need to clear any floats they encounter. To achieve this, use the `clear` property for the copyright notice to force it to the bottom of the page below any floated elements.

Another problem occurs when you float one or more elements inside a non-floated containing tag like a `<div>` tag. When the floated element is taller than the other content inside the div, it sticks out of the bottom of the enclosing element. This snafu is especially noticeable if that tag has a background or border. The top of the web page in Figure 13-7 shows a `<div>` tag that has an `<h1>` tag and two columns created by floating two divs. The background and border, which appear only around the `<h1>` tag, are actually applied to the entire enclosing `<div>`, including the area where the two columns are. However, since the columns are floated, they pop out of the bottom instead of expanding the borders of the box.

NOTE

For a good explanation of why floated elements can break outside of their containing blocks, read www.complexspiral.com/publications/containing-floats.

A similar problem happens in the bottom example in Figure 13-7. In this case, each image is floated left inside a containing `<div>` that has a border. Because the images are taller than their boxes, they pop out of the bottom. Unfortunately, this example is even worse than the previous one, because each image causes the image below it to wrap to the right, creating an ugly staggered effect.

**FIGURE 13-7**

A floated element can escape its containing `<div>` if it's taller than the container itself. If the containing tag includes a background or border, then the escaping elements can look like they're not even part of the container (top of page). In addition, a floated element can bump into other elements—including other floats, thereby creating a “stair-stepped” effect (bottom of page) instead of the nicely stacked boxes in Figure 13-8.

You have many ways to tackle the problem of these renegade floating elements. It's good to have more than one solution at your fingertips, so here's a list of the most popular:

- **Add a clearing element at the bottom of the containing `div`.** This solution is the most straightforward. Simply add a tag—like a line break or horizontal rule—as the last item in the `<div>` containing the floated element (that is, right before the closing `</div>` tag). Then use the `clear` property to force that extra tag below the float. This trick makes the enclosing `div` expand, revealing its background and border. You can add a line break—`
` (HTML) or `
` (XHTML)—before the closing `</div>` tag and add a class to it: `<br class="clear" />`. Then create a style for it, like this:

```
br.clear { clear: both; }
```

The problem with this technique is that it adds extra HTML.

- **Float the containing element.** An easier way is to just float the `<div>` containing the floated elements as well. A floated container `<div>` expands to fully contain any floated elements inside it. In Figure 13-8, top, the `<div>` containing the heading and two floated columns is floated to the left of the page. In the process, its entire box—background and borders—expands to fit everything inside it, including the floated elements. Strange, but true.

If you go this route, make sure you add a `clear` property to whatever element follows the floated container to make sure the following element drops below the container.

- **Use `overflow:hidden`.** Another common technique is to add the following two properties to a style for the containing block:

```
overflow: hidden;
```

The `overflow:hidden` property is just another one of those weird CSS things: It forces the containing block to expand and contain the floated elements. In general, this technique works very well. However, if you have any absolutely positioned elements (see page 410) inside the container, they may not show up. You can get into this situation if you have a drop-down menu inside another tag and the drop-downs, when they appear, are supposed to appear outside the container element. If that's the case, use one of the other methods described on these pages.

- **Use the Micro Clear Fix.** With this technique, created by Nicolas Gallagher, you add just a few styles and a class name to the tag containing the floated element. This technique is the latest in a long evolution of methods that use the `:after` pseudo-class. To use it, you add two different styles to your style sheet: One applies to all modern browsers; the other style applies to IE 7 and earlier. The whole shebang looks like this:

```
.clear:after {  
  content: " ";  
  display: table;  
  clear: both;  
}  
  
.clear {  
  zoom:1;  
}
```

The last two styles make IE 6 and 7 “have layout,” as described in the box on page 440. If you're not concerned with those browsers, then you can leave that style out of your style sheet.

Once you've added these styles to a style sheet, you simply add the class name to the div *containing* the escaping floats: `<div class="clear">`. If you're using HTML5 sectioning elements like `<article>` or `<footer>`, then add that class to them: `<article class="clear">`. See the bottom of Figure 13-8. This technique is very reliable; however, unlike the previous two techniques, you do have to add extra HTML (the class attribute) to the page.

NOTE The `zoom` property makes your page flunk the CSS validator check. To get around *that*, you can put this rule (along with any other IE-only styles) into an external style sheet and attach it to your web pages, using any of the tricks described in Chapter 17 (page 546).




FIGURE 13-8
Don't let a float escape! You have several ways to make floated elements stay inside the borders and backgrounds of their containing tag. Two methods are pictured here, though any of the four discussed would produce the same results. Floating the container works (top), as does a special combination of CSS (bottom). Both methods result in borders and backgrounds that surround the container and the floats inside.

Multiple Columns: The Easy Way

CSS3 introduces the *multicolumn layout* module: It lets you divide a single element (like a div full of text) into three, four, or more columns. It provides CSS properties to determine the number of columns, the space between columns, and to add a line (a *rule*) between the columns.

Multicolumns are intended to simulate the kind of columns you find in a newspaper or magazine, where one long story flows from the top to the bottom of one column, back to the top of the second column, down to the bottom of that column, and so on. In other words, it's not for placing columns of unrelated content next to each other (for example, a sidebar with links, and a main column containing an article). In addition, you can't set different widths for each individual column; they're all the same width.

Multiple columns work well in a magazine, where you have a set height and can see an entire page, making it easy to read to the bottom of a column and jump back to the top of the next. On a web page however, you don't know the size of your visitors' monitors, so a long column of text might force a visitor to scroll down to get to the bottom, then scroll back up to read the next column. In other words, unless you make sure you have very short columns, you might end up forcing people to scroll down and up to read one page—not very user friendly.

However, multiple columns are great for long bulleted lists with short items. Instead of one really long list of bullets, you can spread them across a page in multiple columns, saving precious vertical space. The basic syntax is pretty straightforward: you can use the `column-count` property to set the number of columns, the `column-gap` property to set the space between columns, and the `column-rule` property to draw a line

between the columns. To set the style, size, and color of the column rule, use the same syntax as for borders (page 205).

You apply these to the tag that contains the elements you wish to divide into columns. For example, say you have several paragraphs of text inside a `<div>` tag. You apply these properties to that div, and the paragraphs flow across multiple columns. If, for instance, you give that column a class called `multicol`, you can create the following style for a three-column design, with a 1em gap and a dotted rule:

```
.multicol {
  column-count: 3;
  column-gap: 1em;
  column-rule: 1px dotted black;
}
```

Mind you, Internet Explorer 9 and earlier don't understand multiple columns. In addition, you need to use vendor prefixes (page 209) for Chrome and Safari (`-webkit-column-count`, `-webkit-column-gap`, and `-webkit-column-rule`) and for Firefox (`-moz-column-count`, `-moz-column-gap`, and `-moz-column-rule`). Opera, however, understands the non-prefixed version.

There are a few other properties for multicolumns, which you can read about at the official W3C page: www.w3.org/TR/css3-multicol/. In addition, there's a simple introduction to multi-columns at <http://dev.opera.com/articles/view/css3-multi-column-layout/> and an online tool for creating and previewing multiple columns at www.aaronlumsden.com/multicol/.

Creating Full-Height Columns

HTML tables aren't great for web page layout for several reasons. They add lots of code, are difficult to update, and don't work well on alternative browsers like those used by cellphones. But tables have one thing going for them in the layout department—the ability to create columns of equal height. Equal-height columns let you add a background color or graphic to one column and have it fill the entire height

of the page. The backgrounds of the two sidebars in the top image of Figure 13-9 fill the screen height, creating solid, bold stripes on either side of the page.

CSS floats, on the other hand, fall a bit short in this regard. Table cells in a row are always the same height, which isn't true of divs. The height of a float is usually dictated by the content inside it. When there's not a lot of content, the float is not very tall. Since a background image or background color fills only the float, you can end up with solid-colored columns that stop short of the page bottom, as in the circled areas at the bottom of Figure 13-9.

NOTE

The new flexible box model fixes the problem of different height columns in a row. Unfortunately, browser support for it isn't that good yet. See the box on page 436.

As with most problems related to CSS, there are several workarounds. The most tried-and-true method is the *faux column* technique first championed by the CSS guru Dan Cederholm. The secret is to add background images to a tag that *wraps around* the stubby sidebar and the other columns on the page. Say your HTML has two `<div>` tags that contain the content for a left sidebar and the page's main content:

```
<div class="sidebar">Sidebar content here</div>
<div class="main">Main content for page, this column has a lot of text and is
much taller than the sidebar.</div>
```

The sidebar `<div>` is floated to the left edge of the page and has a width of 170 pixels. Because there's less content in the sidebar, it's shorter than the main text. Suppose you wrap that HTML in a wrapper `<div>` tag, like so:

```
<div class="wrapper">
<div class="sidebar">Sidebar content here</div>
<div class="main">Main content for page, this column has a lot of text and is
much taller than the sidebar.</div>
</div>
```

That outer div grows to be as tall as the tallest element inside it, so even if the main div is very tall, that wrapper div will be just as tall. Here's the magic: Create a style for the wrapper `<div>` with a background image the width of the sidebar, in the background color you want for the sidebar. That way, if the background image tiles vertically, it forms a solid bar the height of the wrapper `<div>` (Figure 13-9, top).

```
.wrapper { background: url(images/col_bg.gif) repeat-y left top; }
```

Web browsers display that background image directly *under the sidebar*, creating the illusion that the sidebar has a background color.



FIGURE 13-9

Full-height columns with bold background colors are a common design technique. The left and right sidebars (top) show how solid backgrounds can help visually define the different areas of a page. When a sidebar's background stops abruptly (circled at bottom), you get extra white space that's both distracting and unappealing.



NOTE You're not limited to solid colors either. Since you're using an image anyway, you can make a decorative pattern that tiles seamlessly down the left side of the page.

Reproducing this result for two columns is just a little more involved. First, add two wrapper divs:

```
<div class="wrapper1">
<div class="wrapper2">
<div class="sidebar1">Sidebar content here</div>
<div class="sidebar2">Second sidebar</div>
<div class="main">Main content for page, this column has a lot of text and is
much taller than the two sidebars.</div>
</div>
</div>
```

NOTE If the wrapper and each column are all fixed widths, you can create this faux-column look for both the left and right columns with just a single image and wrapper div. Just make the graphic as wide as the wrapper, with the left side of the graphic being the color and width of the left sidebar, the right side of the graphic the color and width of the right sidebar, and the center part of the graphic matching the background color of the center column.

If the first sidebar appears on the left side of the page and the second sidebar appears on the right side, you create two styles. Apply one style to the first wrapper `<div>` tag to add a background to the left sidebar; apply one to the second wrapper `<div>` to add a background to the right sidebar (Figure 13-10, bottom).

```
.wrapper1 { background: url(images/col1_bg.gif) repeat-y left top; }
.wrapper2 { background: url(images/col2_bg.gif) repeat-y right top; }
```

When adding a background image to the right-hand column, make sure you position the background image in the top right of the second wrapper, so that it falls underneath the second sidebar on the right side of the page.

One major problem with the faux-column technique is that it's very difficult to make it work when the columns are all percentage widths. If the widths of the sidebars are a percentage of the browser window, they can be thinner or wider depending upon a visitor's monitor. The faux-column technique requires placing a graphic in the background of the wrapper element. That graphic is a specific width and won't scale as the browser's width, and thus the column's width, changes.

One clever workaround uses CSS3 linear gradients (page 260) to add a gradient to a wrapper element. The gradient becomes the background colors for the columns inside the wrapper element. Now, you may be thinking, "I like rainbows and all, but I want the background colors to each column to be solid, not a gradient that morphs from one color to the next." Well, fear not, you can get solid colors.




FIGURE 13-10

You sometimes need to think outside the tag for creative solutions to CSS problems. To get full-height backgrounds behind floated columns, you need to resort to some extra `<div>` tags that wrap around all of the main columns of text. These divs grow to be the height of the tallest column in the group. By adding background images to these wrapper divs, you create the appearance of equal-height columns.

As described on page 262, linear gradients let you set color stops—places where a new color is defined as part of the gradient. If the first stop is white, for instance, and the second stop is white, the gradient runs from white to white. In other words, there’s no color change—it’s just one solid color. In addition, you can set a color stop at the same spot as another color stop, which lets the second color begin immediately after the other with no subtle gradient effect.

Say you have a three-column design. The first column is 25 percent wide, the middle column is 50 percent wide, and the third column is 25 percent wide. You want the first column to have a background color of red, the middle white, and the third blue.

1. Wrap all three columns in a wrapping element:

```
<div class="wrapper">
  <div class="sidebar1"> ... content here ...</div>
  <div class="main"> ... content here ...</div>
  <div class="sidebar2"> ... content here ...</div>
</div>
```

The wrapper is the element in which you'll add the gradient. In addition, if you float all three of the columns inside the wrapper, you'll need to use one of the methods described on page 425 for containing those floats.

2. Add a linear gradient, with color stops that match the width of the columns:

```
.wrapper {  
  background-image: linear-gradient(left,  
    red 0%,  
    red 25%,  
    white 25%,  
    white 75%,  
    blue 75%,  
    blue 100%);  
}
```

Red runs from 0% (far left of the wrapper) to 25%. It's the same color, so there's no gradient. Then white begins at 25%—the same point at which red ended—so again there's no gradient. White continues until the 75% mark—just a solid white stretch. Then blue begins exactly where white ends and continues to the 100% mark (the right side of the wrapper). In other words, you have three solid-color columns whose widths change with the browser width. Perfect.

Of course, you need to include the vendor-prefixed versions as well.

3. Add the vendor prefixed versions:

```
.wrapper {  
  background-image: -webkit-linear-gradient(left,  
    red 0%,  
    red 25%,  
    white 25%,  
    white 75%,  
    blue 75%,  
    blue 100%);  
  
  background-image: -moz-linear-gradient(left,  
    red 0%,  
    red 25%,  
    white 25%,  
    white 75%,  
    blue 75%,  
    blue 100%);  
  
  background-image: -o-linear-gradient(left,  
    red 0%,  
    red 25%,  
    white 25%,  
    white 75%,  
    blue 75%,  
    blue 75%);  
}
```

```
    blue 100%);  
background-image: linear-gradient(left,  
    red 0%,  
    red 25%,  
    white 25%,  
    white 75%,  
    blue 75%,  
    blue 100%);  
}
```

The downside of using a linear gradient is that it only works with solid colors (or, of course, gradients, if you'd like to do that), so you can't use a graphic in the background or borders around each column. In addition, Internet Explorer 9 and earlier don't understand gradients at all.

NOTE There are even a few other ways to make columns appear to be equal height. Check out this blog post by CSS expert Chris Coyier for an overview of the different techniques: <http://css-tricks.com/fluid-width-equal-height-columns/>. Ignore his discussion of the flexible box method, since he wrote this article before the W3C released the finalized flexbox syntax.

POWER USERS' CLINIC

Better Layout Methods Are on the Way

CSS3 includes some very promising new methods for controlling the flow of web page content. In most browsers (but not IE 9 or earlier), you can already use the multicolumn layout module to flow text over multiple columns as in newspaper and magazine design (see the box on page 430).

In addition, the new *flexible box* model provides solutions to most of the problems floats attempt to tackle, such as creating side-by-side columns of varying widths. However, *flexbox* (as it's usually called) can do a lot more, including controlling the order in which the columns are displayed independent of their order in the HTML or changing their display from left to right to right to left. Flexbox syntax is straightforward, and it provides a lot of controls for managing layout. Most browsers even support it.

Unfortunately, the CSS working group has made significant changes to flexbox syntax. They've changed the names of properties and added new ones, so the implementation in browsers as of this writing is totally out-of-date, and using

the old syntax is not recommended. Even Internet Explorer 10, which was not yet released as of this writing, is predicted to support the old, out-of-date flexbox syntax. In other words, it'll probably be some time before you can reliably use flexbox on your websites. For more on flexbox, go to the source: <http://www.w3.org/TR/css3-flexbox/>. Also, avoid any flexbox tutorials written prior to 2012. They all use the old syntax. To learn how to recognize the difference between old flexbox and new flexbox, read the article at <http://css-tricks.com/old-flexbox-and-new-flexbox/>.

Also on the horizon is the *complex grid* layout module (www.w3.org/TR/css3-grid-layout/). This module will simplify the process of defining an underlying structure of rows and columns to which you can align page elements. Although a lot of work has been put into this module, as of the end of 2012, it's not yet finalized and no browsers support it.

Finally, there are even a few preliminary ideas from Adobe for refining text layout (<http://html.adobe.com/webstandards/>).

Preventing Float Drops

Suddenly, one of your columns simply drops down below the others (Figure 13-11, top). It looks like there's plenty of room for all the columns to coexist perfectly side by side, but they don't. You've got the dreaded float drop.

A floated column drops down because there's not enough room to fit it. So be careful if you set widths for *each* column. If the available space in the browser window (or the containing block in a fixed-width design) is less than the *total* widths of the columns, then you're asking for a float drop. Also, keep the CSS box model in mind: As discussed in the box on page 196, the width of an element displayed in the browser window isn't the same as its `width` property. The displayed width of any element is a combination of its width, left and right border sizes, left and right padding, and left and right margins. For the columns to fit, the browser window (or containing block) must accommodate the combined total of all those widths.

Take, for example, the simple three-column layout in Figure 13-11. As you can see in the top example, the three columns don't fit. Here's a breakdown of the math behind the problem:

- **Wrapper div.** A fixed-width wrapper `<div>` tag encloses the entire design. Its `width` property is set to 760 pixels, so all three columns can't total more than that.
- **Sidebar 1 (left side).** Its width is 150 pixels, but it also has 10 pixels of padding, making its total onscreen width 170 pixels. (150 + 10 pixels of left padding + 10 pixels of right padding.)
- **Main content.** The main content `<div>` is 390 pixels wide, with a 1-pixel border and 15 pixels of left and right margin for a total width of 422 pixels. (You may need a calculator for this one: 390 + 1 [left border] + 1 [right border] + 15 [left margin] + 15 [right margin].)
- **Sidebar 2 (right side).** This element has a `width` property set to 150 pixels, with 10 pixels of left and 10 pixels of right padding: 170 pixels, just like Sidebar 1.

The actual widths of each element add up to a grand total of 762 pixels. That's two pixels more than the width of the wrapper `<div>`. The middle image of Figure 13-11 shows an outline around the main content `<div>` indicating its total width plus margins. Just those measly two extra pixels of width (circled) are enough to cause a column to drop down. The solution: Remove 2 pixels of space from any of the elements. Changing the main content `div`'s left and right margins from 15 to 14 pixels buys you the extra room needed for all three columns to fit side by side (bottom).

Bottom line: Float drops are always caused by not enough room to hold all of the columns.




FIGURE 13-11

It takes only a single pixel or two to ruin a design. When the width of floated elements are just a hair wider than their containing block (like a <div> with a set width, or even the browser window itself), the last floated element drops below the others (top). The actual width of an element combines many CSS properties. In the middle image, the outline around the main content area shows that it's a tad too wide to allow the right sidebar to fit (circled). Adjusting any of the elements by removing a bit of width, padding, or margins can solve the problem (bottom).

Another way to make the math easier is to never set the border or padding on column divs or elements. In this way, if you set three columns to 20%, 60%, and 20% widths, respectively, you'll know they fit side-by-side since they total 100%, and there's no padding or borders to mess that up. If you do want padding, you can simply add padding to the elements inside the column: for example, give the same left and right padding to the headlines, paragraphs, and other elements inside the div. This requires more work, but it prevents potential float drops caused by column widths totaling more than 100%.

If you want borders as well, another technique is to nest divs like this:

```
<div class="column1">
  <div class="innerColumn">
    ...content goes here ...
  </div>
</div>
```

You then set the width on the outer div—`column1` in this case—and add the padding and borders to the inner div—`innerColumn`—in the above code. Don't set a width on the inner div; it will automatically fill the width of the outer column.

Preventing Float Drops With Box-Sizing

The main culprit responsible for float drops is the wacky way browsers calculate the actual screen width for an element. You set the width to 100 pixels, for example, but the browser draws it as 122 pixels, because you've also added 10 pixels of left and right padding and a 1-pixel border around the whole thing. Fortunately, one CSS property lets you sidestep these headache-inducing calculations.

The CSS `box-sizing` property lets you tell a web browser to use a different model for calculating the actual screen width of an element. You can give it one of three values:

- The **content-box** value is how browsers normally work: The width of an element on the screen is the combined values of the left and right border thicknesses, left and right padding, and the CSS width property.

```
box-sizing: content-box;
```

- The **padding-box** value tells a browser to include the left and right padding. In other words, the display width of an element is the total of the CSS width, and the left and right padding. It doesn't include any borders around the element.

```
box-sizing: padding-box;
```

- Finally, the **border-box** property includes padding, borders, and CSS width. In general, this is the one you want to use. It keeps the math simple and helps prevent float drops, especially when you're using percentage-based widths along with pixel-based units for the border width and padding:

```
box-sizing: border-box;
```

The very good news is that almost all browsers support this scheme, including Internet Explorer 8. For Firefox, you need a vendor prefix—`-moz-box-sizing`—but all other browsers can accept the plain, non-prefixed version. It's safe to use for the vast majority of the web-surfing public. Only IE 7 and earlier won't follow these instructions; they'll resort to defining the visual width as browsers always have, so you'll end up with wider elements in IE 7 and probably float drops in float-based layouts. See the box on page 24 to help you determine whether you really care about IE 7.

Some web designers suggest setting all elements to the `border-box` setting, so that every tag will be measured in the same way. To do so, use the `*` selector, which selects every element on the page, at the top of your style sheet along with your CSS reset:

```
* {  
  -moz-box-sizing: border-box;  
  box-sizing: border-box;  
}
```

POWER USERS' CLINIC

Got Layout?

As you've probably gathered by now, Internet Explorer 6 and 7 have a long history of browser bugs. Some basic CSS that looks fine in Internet Explorer 8, Firefox, or Safari crumbles in Internet Explorer 6 or 7. Fortunately, IE 6 and 7 are dwindling in popularity (see the box on page 24), and are quickly passing into oblivion. But if you still need to support those browsers, here's a trick that will come in handy. As it turns out, you can fix many IE bugs by switching on a special IE-only property known as `layout`. This isn't a CSS concept, nor does it have anything to do with the rules of HTML. It's just a concept built into Internet Explorer (versions 7 and earlier) by the engineers who created IE. As far as IE is concerned, each page element either has `layout` or it doesn't.

In Internet Explorer, floats, list items, and absolutely positioned elements display differently depending on whether or not they have `layout`. For example, to make sure an element contains any floated elements inside them, you can add this style to your CSS:

```
.clear { zoom: 1; }
```

Then, add that class to any element that contains a floated element. The point of that style isn't really to zoom into the links. Although the IE-only `zoom` property lets you zoom into a page element (using JavaScript), it also triggers `layout` in IE 6 and 7. For reasons known only to Microsoft (and the extraterrestrials), switching on `layout` forces IE 6 and 7 to contain any floated elements inside a containing tag. The `zoom` property isn't the only one that switches on `layout` in IE. Several other (real) CSS properties also give an element `layout: position: absolute; float: left; float: right; display: inline-table; any width value; and any height value.`

The `zoom` property is a good choice because it doesn't mean anything to other browsers (unlike real CSS properties like `width` and `height`), so Safari, Firefox, and so on happily ignore it. That means you can use `zoom` anywhere you need to fix an IE bug by "adding `layout`" to an element without fear of messing up the page in other browsers. The downside of using this property is that it isn't valid CSS, so it won't pass W3C validation (see the box on page 27).

Tutorial: Multiple-Column Layouts

In this tutorial, you'll create a multicolumn, float-based layout. In the process, you'll create a three-column liquid design, as well as a fixed-width design. In addition, you'll learn a couple of different techniques for doing it.

To get started, download the tutorial files located on this book's companion website at www.sawmac.com/css3/. Click the tutorial link and download the files. All the files are in a zip archive, so you need to unzip them first, as detailed on the website. The files for this tutorial are in the `13` folder.

Structuring the HTML

The first step in creating a CSS-based layout is identifying the different layout elements on the page. You do this by wrapping chunks of HTML inside of `<div>` tags, each of which represents a different part of the page.

1. Open the *start.html* file in a text editor and click in the empty line following the HTML comment: `<!--first sidebar goes here-->`.

As you can see, some of the HTML work is already done: Currently, there's a banner and footer. Before you create any styles, you need to add the structure and content for the page. You'll next add the `<div>` tag for the left sidebar.

2. Add an opening `<aside>` for the sidebar: `<aside class="sidebar1">`. Then press Enter (Return) to create a new, empty line.

You're using the HTML5 `<aside>` tag, but you could just as easily use a `<div>` tag to create this column. (The page includes a link to a JavaScript file that lets IE 8 and earlier apply CSS to HTML5 elements; see page 24 for the full explanation.)

If you were creating a web page from scratch, at this point you'd add the HTML for the page's sidebar, perhaps a list of articles on the site, links to related websites, and so on. In this case, the HTML is already taken care of. The code for an unordered list of links is waiting for you in another file. You just need to copy and paste it into this page.

3. Open the file *sidebar1.txt*, copy all of the contents, and then return to the *start.html* file. Paste the HTML after the `<aside>` tag you created in Step 2 (or your `<div>` tag, if you went that route).

The HTML for the sidebar is nearly complete. You just need to close the `<aside>` tag.

4. Immediately after the code you just pasted, type `</aside>`.

You've just added the first layout element on the page. In a little bit, you'll style this HTML so that it looks like a column. But first, you need to add some more content.

5. Place your cursor in the empty line after this HTML comment: `<!--main content goes here-->`, and then type `<article class="main">`.

This div holds the page's main content. You'll get that HTML from another file, too.

6. Open the file *main.txt*, copy all of the contents, return to the *start.html* file, and then paste the code after the `<article>` tag you just created. Add the closing `</article>` tag exactly as in Step 4. Save the HTML file.

That's all the HTML you need to create your design for now. Next, it's time to turn your attention to building the CSS.

Creating the Layout Styles

If you preview the page now, you'll see that the banner, navigation buttons, and text are already styled. That's because this page has an external style sheet attached to it with some basic formatting. Next, you'll create styles to format the page's columns:

1. In a text editor, open the `styles.css` file.

Since the web page uses an external style sheet, you'll add all the new styles to it. You're now managing two files, the HTML file and the CSS file, so make sure you save both before previewing your work in a web browser.

2. Scroll to the bottom the CSS file. You'll see a CSS comment that reads `/* add tutorial styles below here */`. Below that, add this style:

```
.sidebar1 {  
    float: left;  
    width: 20%;  
}
```

This class style floats the sidebar div to the left of the page, and gives it a width of 20%. The width property is important in this style: Unless you're floating an image that has a set width, you should always set a width for a floated element. Otherwise, the browser sets the width based on the content inside the float, leading to inconsistent results. Here, the width is percentage-based, meaning it's determined by the width of its container. In this case, the container is the `<body>` tag, and it fills the entire browser window width. So the sidebar's onscreen width will depend on the width of the visitor's browser window.

3. Save the HTML and CSS files and preview the `start.html` file in a web browser.

The sidebar now forms a left-hand column...sort of. When the text in the main column reaches the bottom of the sidebar, it wraps around the bottom of the sidebar, as shown in Figure 13-12. While that's normally how floats work, it's not what you want in this case. To make the main body text appear like a column of its own, you have to add enough left margin to indent the main text beyond the right edge of the sidebar.

4. Create a style for the second column:

```
.main {  
    margin-left: 22%;  
}
```

Since the sidebar is 20 percent wide, a margin of 22 percent indents the main content an additional 2 percent, creating a gutter between the two columns. This additional white space not only makes the text easier to read, but also makes the page look better.

Preview the page now, and you'll see you've got yourself a two-column layout.




FIGURE 13-12

A floated element doesn't actually create a column on the page. It merely displaces any content that wraps around it, up to the point where the float ends (circled). After that, the content flows back to its normal position underneath the float.

Adding Another Column

As you can see, a two-column design isn't hard. Adding a third column so you can treat your visitors to even more information isn't any harder. In fact, the steps are quite similar to the previous part of this tutorial.

1. Open the file `sidebar2.txt`. Copy all the HTML from that file, and then return to the `start.html` file.

The HTML for this next column goes after the main text inside the `<article>` tag.

2. Locate the HTML comment `<!-- second sidebar goes here -->` near the bottom of the file. Click in the empty line below it.

It's often hard to find the right closing `</div>` when you use a lot of divs to structure a page. That's why HTML comments—like this one—can really help you identify and keep track of the HTML in your page.

- 3. Type `<aside class="sidebar2">`, press **Enter**, and then paste the HTML you copied in Step 1.** Hit Enter again, and then type `</aside>`. Save the HTML file.

When you close the `<aside>` tag, you've completed the HTML for the page's third column. Start styling it next.

- 4. In your text editor, open the `styles.css` file.** Below the `.main` style you created in Step 4 on the previous page, add a new style to the internal style sheet:

```
.sidebar2 {  
  float: right;  
  width: 20%;  
}
```

You're floating this column to the right side of the page to flank the main content with sidebars on either side.

- 5. Save all the files and preview the `start.html` file in a web browser.**

Right away, you'll notice something strange. The second sidebar appears below the main content and even runs over the footer. The problem has to do with the HTML's source order. When you float an element, only HTML that comes after that element wraps around and appears next to the floated element. In other words, since the second sidebar's HTML is after the main content, it doesn't appear *next* to the main content, only after it.

There are a couple of ways to get around this situation. You could move the second sidebar's HTML (the second `<aside>` element) before the main content's HTML (the `<article>` element). Then the first sidebar would float to the left and the second to the right; the main content would just scoot up in between them.

Alternatively, you could simply float the main column as well. If you set its width so all three columns add up to no more than 100 percent, then the three columns will sit side by side. For this example, you'll try that approach.

- 6. Edit the `.main` style so that it looks like this:**

```
.main {  
  float: left;  
  width: 60%;  
}
```

If you save the CSS file and preview the `start.html` file in a browser, you'll notice another problem—suddenly, everything's turned black! Remain calm: That's the footer trying to wrap around all the floats and causing a mess. As you read above, when you float an element and another element wraps around it, the background color and borders for that element actually extend underneath

the floated element. Strange, true...and frustrating. To fix it, you simply need to make the footer drop below—that is, *clear*—the floats.

7. Add one more style after the `.sidebar2` style:

```
footer {
  clear: both;
}
```

As described on page 425, the `clear` property forces an element to drop below floated elements. In this case, it pushes the footer down below the columns as shown in Figure 13-13.




FIGURE 13-13

Using floats you can make three elements appear as three side-by-side columns.

Adding Some Breathing Room

You've got three columns, but the text is a little jammed together. The three columns practically touch and the text on the right sidebar hugs too closely to the edge of the browser window. A little padding can help fix this.

1. Add padding to the `.sidebar1`, `.main`, and `.sidebar2` styles, so the styles look like this:

```
.sidebar1 {
  float: left;
  width: 20%;
  padding: 0 20px 0 10px;
}

.main {
  float: left;
  width: 60%;
  padding: 0 20px 0 20px;
}

.sidebar2 {
  float: right;
  width: 20%;
  padding: 0 10px 0 20px;
}
```

Here, you're using the padding shorthand property (page 231). The numbers represent the top, right, bottom, and left padding. So in the `.sidebar1` style, you're adding 0 top padding, 20 pixels of right padding, 0 bottom padding, and 10 pixels of left padding.

If you save the `styles.css` file and preview the `start.html` file in a browser, you'll notice a problem—the dreaded float drop (page 437). By adding padding, you've essentially increased the width of each column, and since the total widths of the columns (20% + 60% + 20%) already totaled 100%, that extra padding forces the third column down below the other two. It just can't fit!

There are a couple of ways to handle this problem. First, you can remove the padding from these styles, and add it to all the elements inside. In other words, add 10 pixels of left and right padding to the `<h2>`, `<h3>`, `<p>`, and `` tags. That's a lot of work.

Secondly, you could remove the padding from the styles in the CSS file and then, in the `start.html` file, add a `<div>` inside each of the columns, something like this:

```
<aside class="sidebar1">
  <div class="innerColumn">
    ... content goes here ...
  </div>
</aside>
```

Then, in the `styles.css` file, simply create a style to add the padding:

```
.innerColumn {
  padding: 0 20px 0 10px;
}
```

Because there's no width set on the `.innerColumn` style, it simply grows to fill the column, while the padding scoots everything inside of it (the headings, paragraphs, and so on) in by 10 pixels. The downside of this approach is you need to add additional HTML.

There's another way, that's a lot easier, more flexible, and widely supported by web browsers.

2. Add another style to the style sheet:

```
* {  
  -moz-box-sizing: border-box;  
  box-sizing: border-box;  
}
```

This style takes advantage of the universal selector (page 63). It applies the `box-sizing` property to every element on the page. By setting this property to `border-box`, you're instructing web browsers to use the size of the padding and border properties as part of the CSS width value. In other words, the padding doesn't add to the CSS widths you set earlier. This prevents any float drop, since the columns now only add up to 100 percent of the browser window width.

The only downside to this technique is that Internet Explorer 7 and earlier don't understand the `box-sizing` property, so you get a float drop in those browsers. See the box on page 24 to help you determine whether you're concerned about the dwindling and nearly extinct fan base of those browsers. If you do need to design for them, use the extra div technique discussed in Step 1 on page 448.

Finally, you'll add a border line to separate the columns.

3. Edit the `.main` style by adding a left and right border so that it looks like this:

```
.main {  
  float: left;  
  width: 60%;  
  padding: 0 20px;  
  border-left: dashed 1px rgb(153,153,153);  
  border-right: dashed 1px rgb(153,153,153);  
}
```

These properties add two lines, one on either side of the main content section. If you preview the page in a web browser now, it should look like Figure 13-14.




FIGURE 13-14
Adding some padding to the columns and border lines between them clearly separates the columns.

Fixing the Width

Currently, the page is a liquid design, meaning that it expands to fill the entire width of the browser window. But say you'd rather have the page stay the same width all the time—because you hate how it looks on cinema display monitors, or you don't like what happens to the design when the browser window is shrunk too small. Changing a liquid design to a fixed-width design is easy. Start by adding a little more HTML.

1. **Return to your text editor and the *start.html* file.** Directly after the opening `<body>` tag, add a new `<div>` tag:

```
<body>
<div class="pageWrapper">
```

You're wrapping the entire page inside a div, which you'll use to control the page's width. You need to make sure that tag is closed.

2. Add the closing `</div>` just before the closing `</body>` tag:

```
</div>  
</body>
```

Now that there's a div surrounding all of the content on this page, you can control the page's width by setting a width for this tag.

3. Save the HTML file, and switch to the `styles.css` file. Add another style:

```
.pageWrapper {  
  width: 960px;  
}
```

If you save the CSS and HTML files and preview the `start.html` file in a browser, you'll see that the page is indeed locked in at 960 pixels. If you make the browser window thinner than 960 pixels, you'll get scroll bars.

You don't have to set an exact width, however. If, you want the page to fit into a browser window that's thinner—say 760 pixels—you're better off avoiding an exact width. The real problem is that the page becomes hard to read when the browser is really wide. Another approach is to use the `max-width` property, which prevents the div from getting larger than a particular value, but doesn't prevent it from getting thinner to fit smaller screens. While you're at it, you'll also center the div within the browser window.

4. In the `styles.css` file, change the `.pageWrapper` style you just created so it looks like this:

```
.pageWrapper {  
  max-width: 1200px;  
  margin: 0 auto;  
}
```

The `max-width` property (which even works in Internet Explorer 7) provides a liquid layout but only up to a point. In this case, when the browser window is wider than 1200 pixels, the div won't get any wider. The margin setting here—`0 auto`—provides 0 margin for the top and bottom, and auto margins for left and right. That auto setting tells the browser to automatically figure out the margin, splitting the space evenly between left and right and centering the div in the browser window. The page should now look like Figure 13-15.




FIGURE 13-15
Using the CSS max-width property instead of width lets you provide a flexible design that fits various browser window widths, but won't get unreadably wide on an ultra-wide monitor.

Mixing Liquid and Fixed Design

The page looks pretty good, but it might look better if the black background for the nav bar at the top, the footer at the bottom, and the dark purple gradient in the banner extended all the way across the page (see Figure 13-16). Because the nav, banner, and footer are inside the pageWrapper div, those backgrounds stop when the browser window is wider than 1200 pixels. Instead, you want to keep some parts of the page—the tags with the background colors—liquid, while limiting the width of the tags containing any content.

The background color for the navigation is applied to a <nav> element in the HTML; the purple gradient is applied to a <header> element; and the black background in the footer is applied to the <footer> element. In order for their backgrounds to extend the width of the page, they can't be constrained by the pageWrapper div. So the first step is removing that style.

1. In the styles.css file, delete the .pageWrapper style you just created.

You can leave the pageWrapper div in the HTML. It won't hurt to have that little bit of extra HTML, and you may want to use it later to hang styles on.

The page is back to its fully liquid form. Now you want to constrain just the nav, banner text, footer text, and main content so they don't get any wider than 1200 pixels. To do so, you need to dig into the HTML a bit and see what elements you have to play with.

Look in the HTML for the *start.html* file and find the `<nav>` tag. Inside it, you'll see that the navigation buttons are created with a simple unordered list. Bingo. You can set the maximum width of that list to 1200 pixels and center it on the page, while leaving the `<nav>` tag (and its black background) to extend the entire browser window width. Likewise, the text inside the banner—*CSS3: The Missing Manual*—is inside a `<h1>` tag. You can set its maximum width and margin as well. In the footer, you've got a `<p>` tag you can control.

2. In the *styles.css* file, add one more style:

```
nav ul, header h1, footer p {  
    max-width: 1200px;  
    margin: 0 auto;  
}
```

This group selector targets the navigation bar, banner, and footer text, but not their containing elements. If you save the CSS file and preview *start.html* now, you'll see that the navigation, title, and footer text don't get wider than 1200 pixels. However, the main content region still fills the entire browser window. To fix that, you need to wrap the three columns in another div to create a group that you can size and center.

NOTE Another approach is to insert another `<div>` inside the `<header>` tag and wrapped around the `<nav>` and `<h1>` tags, and another `<div>` inside the `<footer>` tag. You can let the `<header>` and `<footer>` stay full width while constraining the width of those nested divs.

3. Open the *start.html* file in your text editor.

Just before the comment that introduces the first sidebar—`<!-- first sidebar goes here -->`—add `<div class="contentWrapper">`:

```
<div class="contentWrapper">  
<!-- first sidebar goes here -->  
Now, you need to close that div.
```

4. Scroll down near the bottom of the HTML file.

Between the closing `</aside>` tag and opening `<footer>` tag, add a closing `</div>` so the HTML looks like this:

```
</aside>  
</div>  
<footer>
```

Finally, you can add this new class name to the style you created in Step 2.

5. Add the new class to the group selector, like this:

```
nav ul, header h1, footer p, .contentWrapper {  
    max-width: 1200px;  
    margin: 0 auto;  
}
```

A completed version of this tutorial is in the *13_finished* folder.




FIGURE 13-16
Creating a multicolumn design is no harder than floating HTML tags: three columns, three floated elements. You can add more columns simply by adding more HTML containers (<div>, <article>, <aside>, and so on) and floating them to the left and right. Just make sure to remember to adjust their widths so there's enough room that for them to fit side by side.

Responsive Web Design

Web designers have always had to contend with designing for various screen sizes—from 760-pixel-wide laptops to gargantuan widescreen displays. However, the rise of smartphones and tablets has now made it even more imperative to design for a wide range of screen widths and heights. Some companies go so far as to create separate, mobile-only websites (see the top images in Figure 14-1). However, unless you have the time, money, and technical expertise to develop two sites and program your web server to provide the proper site to the proper device, a mobile-only website is probably out of reach.

Fortunately, there's another, simpler approach that lets you build a single site that adapts to different device widths (see bottom images in Figure 14-1). Called *responsive web design*, this technique uses several different tricks to make a page change its layout based on the width of the browser screen. On a smartphone, for example, you can lay out a page in a single, easy-to-read column to fit the narrow width of the screen (bottom-left image in Figure 14-1), while maintaining a multicolumn layout on wider monitors (bottom-right image in Figure 14-1).




FIGURE 14-1

Many large companies, like Amazon and Target, create mobile versions of their sites, optimized for display on handheld devices like the iPhone (top). Fortunately, using responsive web design techniques, you can craft one HTML file that displays differently on different-width devices (bottom). On a phone, the page may appear as one long column, while in a desktop browser, the same page takes advantage of the wider screen to include multiple columns and larger photos.

Responsive Web Design Basics

It's very hard to read a four-column web page on a phone whose screen is just 320 pixels wide. It's just as difficult to read a single column of text that's spread across the 2560 pixels of a large desktop monitor. Responsive web design, a term coined by web design pioneer Ethan Marcotte, is an attempt to solve that problem. Responsive web design, or RWD for short, lets you change the entire layout of a page

based on browser window width (among other factors), so you can create the most readable presentation for each device, without having to create multiple versions of the same website. RWD is not a single technology or technique. Instead, it brings together several CSS and HTML methods to create web pages whose layouts adapt to different screens.

NOTE Ethan Marcotte lays out his steps for RWD in his book *Responsive Web Design (A Book Apart)*. (There's nothing better than a straightforward title.) You can also read Ethan's original article about RWD at <http://www.alistapart.com/articles/responsive-web-design>.

RWD combines three main ideas: flexible grids for layout, flexible media for images and video, and CSS media queries to create different styles for different screen widths. With flexible grids, you skip fixed-width layouts. Since smartphone screens come in a wide variety of widths, it makes no sense to create a page at a fixed width; instead, you want the page to grow or shrink to fit the particular device (this is the liquid layout concept discussed on page 450). Creating flexible media lets your images and videos scale to fit the appropriate screen real estate...big photos for big monitors, smaller photos for small screens, and so on.

Finally, media queries are a CSS technology that lets you send different styles to a browser based on current conditions. For example, you can send one set of styles when the screen is less than 480 pixels wide and another set when the window is more than 760 pixels wide. You're not just limited to width either: you can craft styles that only apply to tablets in landscape view or to devices with high-pixel density (like the Retina Display on iPhone and iPads).

■ Setting Up a Web Page for RWD

If you have a smartphone, like an iPhone or Android phone, take a look at it. Open a web browser and visit www.nytimes.com. You should see (unless the *New York Times* has since made its site responsive) something like Figure 14-2. It's a large, multicolumn design smashed into the tiny screen space of the phone. Because phone manufacturers know that most websites are built for desktop screens, they've made their browsers behave a little differently than what you may be used to. Mobile browsers don't just display the page at 100 percent; if they did, then a fixed width, 960-pixel-wide page would not fit the screen and you'd see only one portion of the page at a time. You'd then have to swipe around to see all of the page. Instead, phone browsers zoom out to fit the page on screen. The exact amount they zoom out varies from phone to phone. Safari on the iPhone, for example, acts like the screen is really 980 pixels wide, so it shrinks the page down to fit within 980 pixels.



FIGURE 14-2

Websites designed for desktop browsers, like the *New York Times* site pictured here, tend to look like tiny postage stamps on phones. Visitors are forced to zoom in and drag around the screen to read everything.

In general, this behavior of mobile browsers works well for the majority of sites, but not so well with a responsive web design. Because responsive sites are intended to look good on phones, you don't want the display to zoom out, which would make the text too small to read. Fortunately, there's a simple way to override this behavior of mobile browsers. Simply add the following code to the <head> section of your web page (directly above the <title> tag is a good spot for it):

```
<meta name="viewport" content="width=device-width">
```

HTML meta tags provide extra information about the page's content and can give browsers extra instructions about how to display the page. In this case, the `viewport` refers to the browser screen, and the `content` attribute sets the width of the browser to the width of the phone's. In other words, on mobile browsers that tend to zoom out, you're telling them not to zoom out, but to just make the screen's width match the actual display of the phone.

NOTE Aside from the meta viewport tag, there's another way to make sure that a phone doesn't try to shrink your page, but instead displays it at 100 percent size. The CSS Working Group has added an `@viewport` rule to CSS. It lets you do anything the meta viewport tag does, but within your style sheet. This way, you can skip adding the `<meta>` tag to each HTML file in your site, and just add one `@viewport` rule to your main style sheet, like this:

```
@viewport { width: device-width; }
```

You should add this to the top of your style sheet, before any other styles. Unfortunately, at this time, the `@viewport` rule isn't available in all browsers, and requires vendor-prefixes for those browsers that do understand it. You can learn more about `@viewport` from <http://dev.opera.com/articles/view/an-introduction-to-meta-viewport-and-viewport/> and <http://dev.w3.org/csswg/css-device-adapt/>.

Media Queries

CSS3 includes a concept called *media queries*, which let you assign styles to a page based on the destination browser's width and height. With this method, you can create custom styles for mobile phones, tablets, and desktop browsers, and, in turn, customize your site's presentation so it looks its best on each type of device.

The whole point of responsive design is to give your site's visitors the most readable and attractive presentation possible. This usually means customizing the design to look its best at different browser widths. Many designers think of three target screens related to the three most common web browsing devices: smartphones, tablets, and desktop computers. Granted, there's a wide variety of widths for these devices...you can have small phones, large phones, 7" tablets, 10" tablets, and so on, so there's no one width for all of these devices. Just keep in mind that the goal is to make a page look good at varying widths; you can simply test out different designs and different window widths to see when a four-column design needs to become a two-column or one-column design.

Strategies for Using Media Queries

Although we recommend trial-and-error to determine what changes you need to make to a design so that it looks the best on different devices, there are a few common design changes that are routinely targeted by media queries:

- **Adjust columns.** Multiple side-by-side columns look great on a big monitor (and even on a tablet in landscape mode), but not so much on a phone. In addition, four columns is probably too many for most tablets in portrait mode, so bringing the page down to 2 or 3 columns is probably a good idea for media queries targeting tablets. Avoiding floats in mobile-targeted media query styles lets you stack a page's content containers one on top of the other. You'll try out this technique in the tutorial on page 474.
- **Flexible widths.** You can use a fixed-width design for a desktop browser—that's how designers have done it for years—but for narrower screens like those on tablets and phones, a fixed design won't fit the window. A 960-pixel-wide page

is just too much for a phone's 320 or 480 pixels. For phones and tablets, a good approach is setting the widths of your content divs to Auto or 100%. This setting converts your page from a fixed-width design to a liquid, or flexible, design. In other words, no matter how wide a phone's screen, the divs will fit 100 percent of it. If a person holds an iPhone in portrait mode (so the screen width is 320 pixels) and then suddenly turns the phone horizontally (changing the screen width to 480 pixels), divs set to Auto or 100% simply resize to fit the new space.

- **Tighten up white space.** Ample space between headlines, graphics, and other page elements adds breathing room to a design on a 23-inch monitor, but creates a scattered design and wasted space on a phone's small screen, forcing visitors to scroll excessively. Shrinking margin and padding values lets you fit more onto those small screens.
- **Adjust font sizes.** Contrast between big, bold headlines and small body type looks great on a desktop monitor, but overly large headlines waste screen space and are hard to read on a handheld device. Likewise, making body type a bit larger on phones can often make it easier to read. In other words, pay attention to font sizes as you create media query styles.
- **Changing navigation menus.** You might have a beautifully designed horizontal navigation bar that spans the top of your web page, with a dozen buttons to take visitors to different sections of your site. Unfortunately, as the browser window becomes thinner, those buttons may no longer fit across the screen. Instead, they'll break into two, three, or more lines on the screen. You'll see an example of this in the tutorial on page 474. It may be all right if the navigation bar becomes a few lines instead of just one, or it might take up too much of the top of the screen, forcing viewers to scroll down just to get to the first bit of actual content.

Unfortunately, there's no straightforward CSS solution. Many sites use JavaScript to dynamically change the navigation menu into a HTML drop-down menu, so it only takes up a small bit of space (to learn how to do so, visit <http://css-tricks.com/convert-menu-to-dropdown/>). There are other solutions as well. For an overview of different approaches some sites take to this problem, read <http://bradfrostweb.com/blog/web/responsive-nav-patterns/> and <http://bradfrostweb.com/blog/web/complex-navigation-patterns-for-responsive-design/>.

- **Hide content on handheld devices.** Many designers strip away content from mobile versions of sites. While it's easy to scan several columns and hundreds of lines of text on a desktop monitor, too much information on a phone can be overwhelming. You can use CSS to simply hide content that you think is superfluous for mobile users by setting the CSS `display` property to none.

However, keep in mind that whenever you hide content, you're keeping a visitor away from information your site provides. This can be particularly shocking if someone visits your site using their desktop computer, then later visits the site on her phone only to find that important information she was looking for is

now gone. In addition, even though you hide that content with CSS, the HTML is still there, forcing the mobile phone to waste time and bandwidth downloading HTML that it doesn't use.

- **Use background images.** If you put a 960-pixel banner on a page, no phone will display it without zooming out. One approach is to make sure your images are small enough to fit inside a phone's screen, or to use CSS background images instead. For example, you can create a div and add a class to it like this: `<div class="logo">`. Then, in the style sheet for the desktop browser, set the div's width and height to match the size of the large logo, using the `background-image` property to insert the image into the background. For example:

```
.logo {
  width: 960px;
  height: 120px;
  background-image: url(images/large_logo.png)
}
```

You could then put another style inside the style sheet used for mobile phones that resizes that div and uses a different background image:

```
.logo {
  width: 320px;
  height: 60px;
  background-image: url(images/small_logo.png)
}
```

On page 472, you'll learn how to scale images that you've inserted into the HTML using the `` tag, so they fit different browser widths.

NOTE You can find an overview of different strategies you can use to alter the layout of a page for different devices at www.lukew.com/ff/entry.asp?1514.

Creating Breakpoints

Media queries let you send different styles to browsers based on their screen widths. For example, you can tell a browser “If your screen is no larger than 480 pixels, apply these styles,” or, “If your screen is more than 480 pixels but less than 769 pixels, then use these styles.” The different width values you specify—480, 769, and so on—are often called *breakpoints* in responsive design. Basically, at which value does the design start to break down?

An easy way to determine this is to take a completed desktop design and open it in a web browser. Grab the browser window's sizing handle and slowly make the window narrower. At a certain point, the design will probably start to look terrible. Those four columns, for example, will get mighty cramped. The point at which the design starts to look bad is a good candidate for a breakpoint; in other words, it's

a good size at which to define a new media query and load some new styles to remove a column or two.

It's common to create three sets of media queries for three different breakpoints—one for smartphones, one for tablets, and one for desktop monitors. The exact breakpoint you use will vary from design to design (as well as from device to device), but a common starting point is a screen less than 480 pixels gets one set of styles, a screen between 481 and 768 gets another set of styles, and anything over 768 gets the desktop design. However, it's up to you. Some designers make the tablet design go up to 1024 pixels, and send desktop styles to browsers wider than 1024.

Some designers even go so far as designing four or five different breakpoints so their designs look best in a wide range of screen widths. The exact details on how you create these breakpoints using media queries is coming up on page 461.

Desktop First or Mobile First?

Another thing to consider is which device are you designing for first? You don't need to create three separate sets of styles, one for each width device you're targeting. You can, and should, start with a *default* design; that is, a design that works without media queries. You can then create media query styles to override the default styles and reformat the page for the particular screen width. There are two main approaches:

- **Desktop first.** You can design your site with the desktop in mind. Throw in all the columns you want. Polish and finalize the design so it looks great on a large monitor. This becomes your base design, and you can put all of these styles into an external style sheet and link it to the pages of your site as you normally would.

Then, you add media queries for tablets and phones. Those media query styles will tweak the base desktop design—remove columns, make headline text smaller, and so on. A benefit of this approach is that browsers that don't understand media queries will get the basic desktop styles. Most phones do understand media queries, but older desktop browsers like Internet Explorer 8 and earlier don't. So the desktop first approach means IE 8 will get the styles it needs to create a great desktop presentation.

- **Mobile first.** You can flip that approach on its head by designing first for mobile browsers. This time, you put the basic small-screen styles in a regular external style sheet, and then refine the design for tablets and desktops by adding columns and other adjustments for larger screens in media queries.

Whichever method you choose, you should use a regular external style sheet linked to the web page as you normally would. In that style sheet, include all the styles that are common *across* the different devices. For example, you'll still want the same color palette and same fonts across all versions of the site. You may also keep the same styling for links, images, and other HTML elements consistent. In other words, you don't need to create three entirely separate sets of styles for each device; start with one set that applies across phones, tablets, and desktop browsers, then refine the design for the media query-targeted devices.

Creating Media Queries

A *query* is just a question asked of a web browser: “Is your screen 480 pixels wide?” If the answer is Yes, the browser launches a style sheet for just that size device (a style sheet that you supply, as explained on the previous page). The code that makes this happen looks pretty much the same as that for any external style sheet:

```
<link href="css/small.css" rel="stylesheet" media="(width: 480px)">
```

The one addition to this standard style sheet link is the `media` attribute, which sets up the conditions under which a browser uses a particular sheet. In the example above, a browser loads the *small.css* external style sheet when someone views your site with a browser whose width measures 480 pixels. The parentheses around the query—`(width: 480px)`—are required. If you leave them out, the browser will ignore the query.

NOTE

While mobile browsers and most desktop browsers understand media queries, Internet Explorer 8 and earlier don’t. You can make older versions of IE understand your media queries by adding a bit of JavaScript to the `<head>` of your document. You’ll need to download the *respond.js* file from <http://tinyurl.com/7w49a6z>. Put the file in your site, and then link it to your page using the `<script>` tag. For example:

```
<!--[if lte IE 8]>
<script src="respond.min.js"></script>
<![endif]-->
```

This little maneuver forces IE 8, 7, and 6 to understand media queries.

Because 480 pixels is very precise—what if someone’s using a phone with a smaller screen, say one that’s just 300 pixels wide?—it’s best to use a range of values in your media query. For example, you might want to apply a particular style for screens that are *less than or equal to* 480 pixels wide. You do that like this:

```
<link href="css/small.css" rel="stylesheet" media="(max-width:480px)">
```

The notation `"(max-width:480px)"` is the same as saying “for screens that are at most 480 pixels wide.” So the styles inside the *small.css* file apply to screens that are 480px wide, 320 pixels wide, and 200 pixels wide, for example.

Likewise, there’s a `min-width` option that determines whether a browser is *at least* a certain width. This is useful when you target a device that’s bigger than a mobile phone or tablet. For example, you can write this link to apply styles to screens wider than the 768 pixels of many tablets:

```
<link href="css/large.css" rel="stylesheet" media="(min-width:769px)">
```

To use this style sheet, a browser window must be at least 769 pixels wide—that’s 1 pixel wider than 768, the width of some tablets.

And finally, you can set *both* max widths and min widths to target devices that *fall between* phones and desktop browsers. For example, to create a set of styles for a tablet that's 768 pixels wide, you could use this CSS code:

```
<link href="css/medium.css" rel="stylesheet" media="(min-width:481px) and (max-width:768px)">
```

In other words, the browser's screen must be at least 481 pixels wide, but not more than 768 pixels wide. This *medium.css* file wouldn't apply to a 320-pixel-wide smartphone, nor would it apply to a desktop browser with a screen width of 1024 pixels.

NOTE

CSS3 media queries can do more than just check the width of a browser. The current media query standard states that you can check for height, orientation (whether a visitor holds a mobile phone in portrait or landscape mode), and even whether a device uses a color or monochrome screen. There are a few other browser characteristics you can check with media queries, but not all browsers support the queries. You can learn more about media queries at the W3C website: www.w3.org/TR/css3-mediaqueries.

Including Queries Inside a Stylesheet

The technique demonstrated above provides one way to use media queries by using the `<link>` tag to load different style sheets for different screen sizes. However, you can also add media queries within a single style sheet. You may want to do this so you don't have to add multiple `<link>` tags to an HTML file, for example, or you may want to keep your media query styles together with your main style sheet.

There are a couple of ways to add media queries to a style sheet:

- **Use the `@import` directive.** You read about this technique on page 42. The `@import` directive lets you load additional external style sheets within either an internal or external style sheet. You can also use `@import` with a media query. For example, say you want to load an external style sheet named *small.css* containing styles for displays that are 320 pixels or smaller. To do that, add the `@import` directive directly to a style sheet:

```
@import url(css/small.css) (max-width:320px);
```

Unfortunately, as the note on page 461 points out, Internet Explorer 8 and earlier only understand media queries if you use a JavaScript program called *respond.js*. That program doesn't work with media queries that use the `@import` technique, so if you use `@import` and a media query to load a style sheet for desktop browsers, IE 8 and earlier won't load those styles. That's not a huge concern, since you don't necessarily need to use media queries with desktop browsers (see page 460).

NOTE

As noted on page 42, you must place `@import` directives at the beginning of a style sheet. They can't come after any styles. As a result, you may run into problems with the cascade, where styles you defined in an external style sheet and loaded using `@import` can be overridden by later styles in the style sheet. (See Chapter 5 for more on this issue.) You can get around it by simply having one external style sheet that only contains `@import` directives. The first loads a basic style sheet for all devices, and the second and third load style sheets using media queries, like this:

```
@import url(css/base.css); /* no media query, applies to all */
@import url(css/medium.css) (min-width:481px) and (max-width:768);
@import url(css/small.css) (max-width: 480px);
```

- **Embed the media query in the style sheet.** You can also embed a media query directly inside a style sheet, like this:

```
@media (max-width: 480px) {
    body {
        /*style properties go here*/
    }
    .style1 {
        /*style properties go here*/
    }
}
```

The `@media` directive acts as a kind of container for all of the styles that match the query. So in this example, the `body` and `.style1` styles only apply to devices whose screen is no wider than 480 pixels. By using embedded `@media` directives like this, you can keep all of your styles organized into one style sheet. A good approach is to start your external style sheets with styles that aren't contained in a media query using either the desktop first or mobile first approach, and then add media queries for the remaining devices.

A Basic Stylesheet Structure

As you can tell, there are many different ways to use media queries to target different devices: desktop first, mobile first, separate style sheets, a single style sheet, and so on. As you gain more experience, you'll figure out which approach is best for which project. But as a starting point, you can always create a single external style sheet that includes styles for desktop displays, and then add media queries to modify that base-level design for tablets and phones. Here's a skeletal structure for just such a file:

```

/* Put your reset styles here */
/* Put styles for desktop and basic styles for all devices here */
body {
  /* properties for body here */
}

/* medium display only */
@media (min-width: 481px) and (max-width:768px) {
  body {
    /* properties that only apply to tablets */
  }
}

/* small display only */
@media (max-width:480px) {
  body {
    /* properties that only apply to phones */
  }
}

```

You'll see this structure in action in the tutorial starting on page 474, and you'll find a basic starter style sheet called *desktop_first.css* in the *14* folder in this chapter's tutorial folder (www.sawmac.com/css3). Remember that even though this file includes media queries, it's still just a regular style sheet and is linked to a web page the usual way. For example, if you save the this file as, you'd add this HTML to the <head> of a web page:

```
<link href="styles.css" rel="stylesheet">
```

Mobile First

If you decide to go the mobile-first route, you first create a set of styles aimed at mobile browsers, and then add media queries to alter the design for tablets and then desktop browsers. Here's a basic style sheet structure for that approach:

```

/* Put your reset styles here */
/* Put styles for mobile and basic styles for all devices here*/
body {
  /* properties for body here */
}

/* medium display only */
@media (min-width: 481px) and (max-width:768px) {
  body {
    /* properties that only apply to tablets */
  }
}

```

```
/* large display only */
@media (min-width:769px) {
  body {
    /* properties that only apply to phones */
  }
}
```

If you go this route, remember that Internet Explorer 8 and earlier don't understand media queries and require some JavaScript to apply the large display styles. Otherwise, they'll display only the mobile styles for the site (see the tip on page 461).

Flexible Grids

You may be tempted to design fixed-width layouts that are 320 pixels wide, which is typical for the iPhone and some Android phones; 720 pixels wide, for iPads in portrait (tall) mode; and 1000 for desktop monitors. Don't do it. While the iPhone is very popular, it's far from the only phone out there. Android phones come in all sorts of shapes and sizes, and therefore, widths. You'll undoubtedly see many other unusually sized devices, and tablets come in a wide array of widths. In other words, there is no universal width for smartphones and tablets, so the best approach is to create flexible-width pages.

Flexible grids are a core component of responsive web design. They're nothing much more than the liquid layout discussed on page 406, in which the page's overall width resizes to fit different width screens. In most cases, that means you set the width to 100%. However, for desktop displays, you may want to use the `max-width` property (page 219) to make sure the page isn't absurdly wide on large desktop monitors.

In addition, the individual columns within a design should be percentage based, instead of set with a fixed pixel- or em-based measurement. Individual columns also need to grow wider or narrower to fit the changing page width.

TIP As discussed in the box on page 425, there are many freely available prepackaged grid systems—HTML and CSS code that make building multicolumn layouts easier. However, you already learned the basics of creating liquid layouts in the previous chapter.

For example, say you want to create a two-column design where the first column is one-third the width of the page and the second is two-thirds. You may start with some simple HTML, like this:

```
<div class="columns">
  <div class="one-third">
    ...content goes here...
  </div>
  <div class="two-thirds">
    ...content goes here...
```

```
</div>  
</div>
```

You can then create several CSS styles to create the fluid layout:

```
.columns {  
  width: auto; /* same as 100% */  
  max-width: 1200px;  
}  
  
.columns:after {  
  content: "";  
  display: table;  
  clear: both;  
}  
  
.one-third {  
  float: left;  
  width: 33%;  
}  
  
.two-thirds {  
  float: left;  
  width: 67%;  
}
```

The first style—.columns—sets the width of the div containing the columns. Setting the width property to a value of auto is the same as setting it to 100%, while the max-width property will keep the box from getting too wide. The second style—.columns:after—helps contain the two floated columns (for more detail on how that works, see page 425). Finally, the last two styles just set the widths of the two divs to 33% (one-third the width of its container) and 67% (two-thirds) and floats them left so they appear side-by-side.

The Importance of HTML Source Order

When you're holding a phone upright in your hand, there's simply not enough room to have two, let alone three, columns in a row and still have a readable page. So many designers simply lay out a page in one long column for display on a mobile phone. To do so, just remove any floats from the columns you've created. For example, if you create a three-column design for desktop display using floats to position the columns side-by-side, simply set the float property to none on those elements. They then display as HTML normally does—one block-level tag on top of the other.

This makes the HTML source order very important. For example, a page may have two sidebars, one with a list of links to related sites, the other with ads for products your company sells. A middle column contains the main content—the stuff your audience is really after when they visit the page. One way to lay this out in columns is to float the first sidebar left and the second sidebar right, and let the main column simply wrap around the two and sit in the middle.

In terms of HTML, this would mean the two sidebar divs appear first, followed by the tag containing the main content. If you made this page mobile-friendly by removing the floats on these sidebars, you'd end up with the two sidebars appearing *above* the main content. Your audience would be faced with scrolling down past the ads and links just to get to the content they're after.

A more user-friendly approach is to place the main content container above the sidebars. As discussed on page 421, this method can require adding some additional containers and floating all the elements including the main content div.

In short, be aware of how you order your HTML before you try to lay out a multicolumn design for the desktop. The easiest way to see what's going on is to view the web page without any CSS applied. You can then see all the divs and other block-level elements stacked on top of each other and get a good idea of what the page will look like as a single column on a phone.

NOTE

The tutorial on page 421 demonstrates how you can create a three-column desktop design while keeping the most important content near the top of the page.

Reset the Box Model

As explained on page 437, when you use percentage-based widths, you run into the danger of float drops, where the total width of columns in a row exceeds 100 percent, so the last column drops down below the others. Because of the way browsers calculate the widths of elements, adding a border around a div, or padding inside it, will make the div's onscreen width greater than the width you set in the CSS.

For example, if you make one column 33 percent wide and another 67 percent wide (as in the example on the previous page), they'd fit perfectly next to each other, since their combined widths are 100%. However, if you add a 1 pixel border to the column, their combined width would be 100% + 2 pixels (the left and right borders). They'd now be too large to fit in the window, and the second column would drop down below the first.

There are a couple of ways to deal with this predicament, and they're detailed on page 437. But the most straightforward solution is to tell the web browser to *include* the border and padding widths and heights as part of its box model calculation. In other words, you can make the browser include the border and padding as part of the CSS width property, so adding more padding or a border doesn't increase an element's width (or height). Since that's a good thing for all elements, it's best to use a universal selector so you can reset the box model on every element on a page:

```
* {  
  -moz-box-sizing: border-box;  
  box-sizing: border-box;  
}
```

Firefox still uses a vendor prefix for this property, so you need to use the `-moz-box-sizing` version. Fortunately all other browsers, including Internet Explorer 8 and up, understand the non-prefixed version. A good place to put this style is in the page's CSS reset (page 115).

NOTE

Internet Explorer 7 doesn't understand the `box-sizing` property, so this approach won't work for it. IE 7 is quickly disappearing (see the box on page 24), but if you still need to support it, there are a couple of other ways to prevent float drops on percentage-based layouts (see page 437).

Converting Fixed Width to Flexible Grids

If you're starting with a brand new design, thinking in terms of percentages shouldn't be too hard. After all, if you wanted four equal-width columns, you'd set each to 25%:

```
width: 25%;
```

However, if you've already got a fixed-width website design and you want to convert it to a fluid design, things get a little trickier. To start with, say you design a page with a fixed width of 960 pixels. You either wrap the page in a `<div>` tag and give that div a width of 960 pixels, or simply set the `<body>` tag to that width. In either case, you now want that container to be completely fluid. That's easy, just change

```
width: 960px;
```

to

```
width: auto;
```

Setting an element's width to `auto` is much the same as setting it to `100%`; its width will be as wide as its container.

Next, you need to convert any column widths from pixel values to percentages. Ethan Marcotte, the champion of responsive web design, has come up with a nifty formula to make this relatively easy to figure out: *target / context = result*. In English, it means, "take the width (in pixels) of the element you wish to convert and divide it by the width of its container (in pixels)." The result is a fractional value that you convert to percentages.

Here's an example. Suppose that inside that 960-pixel-wide page, you have two columns: a sidebar that's 180 pixels wide and a main column that's 780 pixels wide. In your CSS file, you have some code like this:

```
.sidebar {  
  float: left;  
  width: 180px;  
}  
  
.main {  
  float: left;  
  width: 780px;  
}
```


Of course, you'd have a lot of other CSS in there like borders, background colors, and so on, but for this exercise, you're just concerned about the widths. Starting with the sidebar, you'd take its width—180 pixels—and divide it by its container's width—960 pixels. The result—.1875—multiplied by 100 gives you the percentage value: 18.75%. Likewise, for the main column, you'd divide 780 by 960 to get .8125. Multiply that by 100 to get 81.25%. In other words, you end up changing the widths of those styles like this:

```
.sidebar {  
  float: left;  
  width: 18.75%;  
}  
  
.main {  
  float: left;  
  width: 81.25%;  
}
```

Don't round up the new values. In other words, don't turn 18.75% into 19%; doing so will most likely cause the columns to no longer sit side-by-side, resulting in a float drop. Browsers can handle decimal values just fine. In fact, feel free to use all the numbers that your calculator returns. A width of 25.48488% is perfectly acceptable.

The same applies to a column inside another column. For example, say in the main column above, you have one section of two floated divs that create two additional columns within the main column. Both divs shared the same width—390 pixels—so to calculate their width in percentages you take their current width in pixels—390—and divide it by their container's width—in this example, the main column is 780 pixels. The result is .5. Multiply that by 100 to get 50%. (But you don't really need to do the math. After all, if you have two equally sized columns sitting side-by-side, you know that each takes up half the available space, or 50%.)

As you recreate your design and figure out percentage values, keep in mind that the total width of all columns in a single row can't exceed 100%.

TIP

You can use the same formula to convert pixel-sized type to ems. Say you have paragraph text that's 18 pixels (the target). The default size of regular text (the context) is 16 pixels. Just divide 18 by 16 to get the new size in ems: 1.125em.

UP TO SPEED

Testing Responsive Designs

Since responsive designs are intended to adapt to the screens of different browsing devices, you'll need to find a way to view your pages at different screen widths. The easiest way to test your media queries is to view the page on a desktop browser and resize the browser window. Drag it in to make it thinner, and view what happens at each breakpoint or media query that you set. This technique works pretty well, but not all browsers let you scale the window down to the 320-pixel width of some phones.

There are also several web-based tools that let you preview your pages inside windows of different dimension. The responsivepx site (<http://responsivepx.com>) lets you enter a URL for a page on the Web, then input different screen heights and widths. The site opens the page in an `<iframe>` of the set width. The browser applies any media queries that pertain to that width screen, so you can preview the effect of your media queries.

The Responsinator (www.responsinator.com) comes with several preset window widths that match popular devices like iPhone, Samsung Galaxy, iPad, Kindle, and others. Just enter your site's URL, and its page will appear inside simulated screens. The Responsinator only works with files that you've uploaded to a web server on the Internet.

If you have a smartphone or tablet, you can preview a page directly from your computer on those devices, using Adobe's Edge Inspect tool (<http://html.adobe.com/edge/inspect/>). This sophisticated tool is a great way to preview your working design in progress. Alternatively, you can just put your design up on a web server, whip out your phone, and visit that page to see what it looks like. Of course, unless you have dozens of smartphones, you won't know exactly what all people using mobile browsers will experience.

Fluid Images

While a flexible layout creates a design that works in a wide range of browser window widths, you'll encounter a problem if you've inserted images in your pages. Although columns in a flexible design shrink as the window gets smaller, images usually don't. This can lead to graphics overflowing their bounds and no longer fitting within the width of a column (see Figure 14-3).

Fortunately, there's a way to make images flexible as well. It requires two steps: a new CSS style and some changes to your HTML:

1. First, in your style sheet, add the following style:

```
img { max-width: 100%; }
```

This sets the maximum width of any image to 100 percent of the width of its container. In other words, an image can never be bigger than a column, div, or any HTML element that it sits inside of.

This alone isn't enough to make an image flexible. Usually, when you insert an `` tag, you also add the height and width for that image. That's the size the

browser uses when displaying the image. With the `max-width` property in place, the image still won't get wider than the column, but its height is still locked to the value set in the HTML. In other words, the image will conform to the width of the column, but its height won't change, resulting in a distorted image. The solution is straightforward: just remove the `width` and `height` attributes from the HTML.

2. Locate every `` tag in the page and remove the height and width attributes.

In other words, turn this HTML:

```

```

into this:

```

```

Many text editors have search and replace features that can speed up the process of finding and removing these attributes.




FIGURE 14-3

When a column gets thinner than an image inside it, that image overflows the bounds of the column, usually overlapping other columns and content.

This approach assumes, of course, that you want all your images to fill the column they're in. In many cases, you'll want images to be smaller than that; for example, a photo that's floated to the right of the main column, with text wrapping around it. To deal with differently sized images, you can create different classes, with different `max-width` settings, and apply those classes to particular `` tags within the HTML.

For example, say you want to float an image to the left of a column and size it to 40 percent of the column. First create a class style:

```
.imgSmallLeft {  
  float: left;  
  max-width: 40%;  
}
```

Then apply that class to the `` tag:

```

```

A more flexible approach is to break the size and the float into separate classes:

```
.imgSmall {  
  max-width: 40%;  
}  
  
.imgLeft {  
  float: left;  
}
```

Then apply both classes to the image:

```

```

By using two classes, you can apply the `imgSmall` class to any image, even ones you decide to float right or not float at all.

NOTE

You can resize background images by using the `background-size` property discussed on page 253. It doesn't work in Internet Explorer 8 or earlier.

The Downsides of Fluid Images

Fluid images have a couple of problems. First, since the image will grow to fit 100% (or whatever percentage you specified) of the column width, it's possible for that image to be stretched beyond its natural width. For example, say you insert a 200-pixel-wide image into a sidebar. When the page that image is on is displayed on a really wide monitor, the browser might make that sidebar 300 pixels wide. The image will fit that column and also stretch to 300 pixels. Since that's wider than the image file, the image will appear distorted and pixelated. In other words, make sure the image file itself is sized to fit at the widest width the column can scale to.

Secondly, when the page is viewed on a phone, the column widths and images can shrink to a width that's much smaller than on a desktop browser. This means the images are actually shrunk on screen. While the image quality won't suffer, you're forcing users of mobile phones to download image files that are much larger than really necessary. They're wasting their bandwidth on unnecessarily large image files. Unfortunately, there's no great solution to this problem yet; in fact, champions of responsive web design recognize this as one of the biggest problems with RWD.

Among other people working on the problem of fluid images, a W3C community group has formed to try to answer this problem via HTML. You can read about their progress at <http://picture.responsiveimages.org> and <http://www.w3.org/community/respimg/>. In the meantime, you may choose not to worry about the larger image files for mobile and wait for a solution to arrive—perhaps one already has by the time you’re reading this. Or try a very good but somewhat complicated solution called *adaptive images*. It uses JavaScript and PHP to send images of the appropriate size to each device. In other words, a small, handheld browser receives smaller image files for its smaller screen, while desktop browsers download larger images. To learn more about it, visit <http://adaptive-images.com>.

Videos and Flash

If you use the HTML5 video tag or embed Flash content, you can also use the max-width trick to make those elements scale with their containers as well. Simply add this style to your style sheet:

```
img, video, embed, object {
  max-width: 100%;
}
```

Unfortunately, this style doesn’t do anything to help with videos that are embedded using iframes (the most common way to add a YouTube or Vimeo video to a page). For embedded YouTube videos, use Dave Rupert’s and Chris Coyier’s FitVids JavaScript program: <http://fitvidsjs.com>. This small bit of JavaScript code makes sure most embedded videos scale up or down to fit their container.

UP TO SPEED

When Is a Pixel Not a Pixel?

Most people think of a pixel as a single dot on a screen or monitor. And it is. But thanks to new high-density pixel displays like Apple’s Retina displays, you now have to think of pixels in two different ways. A device like an iPhone 5 has a resolution of 1136 pixels by 640 pixels. That’s a lot of pixels, and the iPhone squishes those pixels into a smaller area than most other screens. It crams 326 pixels into every inch of the screen. Desktop monitors usually have around 100 pixels per inch. In other words, the iPhone puts three times as many pixels into one inch of its screen than many desktop monitors. The result is very clear, sharp images.

This poses a problem for web designers, however. If you give your text a size of 16 pixels, that would look fine on a desktop monitor (about .16 inches tall), but would be unreadable in a phone with a high-density screen—.04 inches tall.

Fortunately, that’s not what browsers with high-density displays do. They actually make a single CSS pixel fill *multiple* pixels on its screen, so text that’s 16 pixels tall is actually displayed using *more* than 16 pixels. Phones and other devices with high-density pixel displays make a distinction between a *device pixel*—an actual dot on a screen—and a *CSS pixel*.

A CSS pixel is a calculation based on the screen’s pixel density and its distance from the viewer. Since a phone is held closer to your face than a monitor, items on its screen appear bigger than similarly sized items on a monitor that’s 28 inches away.

On an iPhone, 1 CSS pixel is actually represented by 4 device pixels. So 16-pixel-tall type is actually 32 device pixels tall. Different devices like Android phones have different pixel densities and so use different calculations to determine how many screen pixels to use to display a single CSS pixel.

■ Responsive Web Design Tutorial

In this tutorial, you'll take the layout you created in the last chapter (with the addition of a few images) and turn it into a responsive web design. You'll use a desktop-first approach—so the basic CSS styles work best in a desktop browser—and then you'll add media queries to change the look for medium-size screens (like tablets) and small screens (like phones).

To get started, download the tutorial files located on this book's companion website at www.sawmac.com/css3/. Click the tutorial link and download the files. All the files are in a zip archive, so you need to unzip them first. The files for this tutorial are in the **14** folder.

Changing the HTML Source Order

In creating a layout for a small screen, you'll turn your three-column design into single-column layout with each block of content stacked one on top of the other. One problem with the HTML from the page you worked on in the previous tutorial is that the left sidebar appears first in the source order, so if you turn this into a single-column design, that sidebar will appear before the main content.

It would be better for the site's visitors if they can get directly to the main content first, then scroll down to see the supplemental information from the sidebars. To achieve that, you have to add a little HTML and move some already-existing HTML. You'll use the technique described on page 438 in the last chapter (see Figure 13-11): move the main content container up above the first sidebar, and then wrap the main content and the sidebar in a new `<div>` tag. You'll float that new div left, the main content right, and the sidebar left. This arrangement will maintain the same visual layout for desktop displays—first sidebar on the left, main content in the middle, and second sidebar on the right—but then stack the main content above the two sidebars for the mobile design.

- 1. Open the file `rwd.html` in the **14** folder.**

This page is the same as the completed page from last chapter's tutorial. First, you'll move the main content up.

- 2. Locate the HTML comment `<!-- main content goes here -->`, and select it and all the HTML down to and including the closing `</article>` tag.**

In other words, select that comment and everything down to the `<!-- second sidebar goes here -->` comment.

- 3. Cut that text to the clipboard, using Edit→Cut (or using whatever method your text editor provides).**

Next, you'll paste that code above the first sidebar.

- 4. Locate the `<div class="contentWrapper">` tag toward the top of the file.**

Add an empty line after it, but before the `<!-- first sidebar goes here -->` comment, and choose Edit→Paste to paste the main content above the sidebar.

Now you need to add a `<div>` tag to enclose the main content and the first sidebar.

5. **After the `<div class="contentWrapper">` tag, add `<div class="columnWrapper">`.**
The HTML should look like this:

```
<div class="contentWrapper">
<div class="columnWrapper">
<!-- main content goes here -->
```

Next, you'll close that div.

6. **Locate the closing `</aside>` for the first sidebar.** It's just before the `<!-- second sidebar goes here -->` comment. Add `</div>` after the `</aside>` so that the HTML looks like this:

```
</aside>
</div>
<!-- second sidebar goes here -->
```

That's it for the HTML changes for now. You can find a file called *new-source-order.html* in the 14 folder with all of these HTML changes, if you got lost or want to check your work.

If you preview this page in a web browser, you'll see there's a three-column layout, but the main content's on the left side, and the first sidebar is in the middle (Figure 14-4). You can fix that with some CSS.

7. **Open the file *styles.css* in the 14 folder.**

This file contains the CSS you created in the last chapter. You'll first need to add a new style for the column wrapper and float it left so it sits next to the right sidebar.




FIGURE 14-4

The page is still a three-column design, but now the main content is on the left and the left sidebar is in the middle. A couple of simple styles can get those columns back into their original positions.

8. Near the bottom of the file, before the `.sidebar1` style, add the following style:

```
.columnWrapper {  
    float: left;  
    width: 80%;  
}
```

The width setting here is the combined widths of the left sidebar (20%) and the main column (60%). What you're actually doing is creating a two-column layout: the first column is this new `<div>` tag, and the second column is the right sidebar. The main content container and the left sidebar are actually two columns inside this column wrapper div—in other words, columns within a column, as described on page 438 and pictured in Figure 13-11.

Next, you'll adjust the floats and widths of the main column and first sidebar.

9. Change the width value of the `.sidebar1` style to 25%. The style should look like this:

```
.sidebar1 {  
    float: left;  
    width: 25%;  
    padding: 0 20px 0 10px;  
}
```

Originally, this sidebar took up 20% of the entire page width, but now that it's inside the column wrapper div, you need to adjust the sidebar and main content columns' widths to fit within the 80% width of the column wrapper. In other words, the percentage width you're specifying isn't a percentage of the entire page, it's a percentage of the column wrapper, which only takes up 80% of the page.


To figure out the new percentage, take the older percentage—20%—and divide it by the width of its container—80%—and then multiply by 100. So 20 divided by 80 is .25. Multiply that by 100 and you get 25%. You'll use the same technique to change the width of the main content.

10. Locate the `.main` style, and change the float to right, and the width to 75%, so the style looks like this:

```
.main {  
    float: right;  
    width: 75%;  
    padding: 0 20px;  
    border-left: dashed 1px rgb(153,153,153);  
    border-right: dashed 1px rgb(153,153,153);  
}
```

You're floating this element to the right, so it appears to the right of the first sidebar, which places the main content in the middle again. You calculate the width by taking the old width and dividing it by the width of its container: $60/80 = .75$, or 75%. If you save the files and preview the `rwv.html` file in a web browser, it should look like Figure 14-5.

NOTE This particular design won't get wider than 1200 pixels thanks to the `max-width` set in the group selector `nav ul`, `header h1`, `footer p`, `.contentWrapper`. If you want this design to fill the browser window, no matter how wide it is, just remove the `max-width: 1200px;` declaration from that group selector.



Fluid Images

You've successfully created a fluid layout. If you preview the page now and resize the browser window, you'll notice that as you make the window narrower, the columns get smaller. Unfortunately, some of the images are wider than the columns and the pop out of the design. As you read on page 454, part of responsive web design is making your images respond to changes in the width of the browser window as well. To make that work, you need to add some CSS and remove some HTML.

1. **Open the *styles.css* file in your text editor.** At the bottom of the style sheet, add a style for the `img` tag:

```
img {  
    max-width: 100%;  
}
```

This style makes the maximum width of an image equal to 100 percent of its container's width. So for a column that's 200 pixels wide on screen, the image will be 200 pixels wide. If a visitor resizes the browser window, and the column shrinks in size, the image will shrink to fit the column.

This only works, however, if you remove the image's width and height properties in the HTML.

2. **Delete the height and width attribute for each of the four `` tags in the *rwd.html* file.**

There are four graphics—*clouds.jpg*, *jellyfishy.jpg*, *gator.jpg*, and *mule.jpg*. Remove the width and height attribute—for example:

```

```

should become

```

```

If you save the CSS and HTML files and preview the page in a web browser, you'll see that the images do change size as you make the page thinner. However, the two images in the main column are *really* big. Using `max-width: 100%` for the `` tag does create flexible images, but in many cases, you won't want all images to be as wide as their column. In the case of the two images in the main column, they'd look a whole lot better if they were only half the size of the main column. You can do that by applying some classes to those tags and adding some styles.

3. **In the *styles.css* file, add the following styles to the bottom of the style sheet:**

```
img.half {  
    max-width: 50%;  
}  
  
img.left {  
    float: left;  
    margin: 0 10px 10px 0;  
}  
  
img.right {  
    float: right;  
    margin: 0 0 10px 10px;  
}
```

The first style sets the max-width to just 50%—half the column width. The other two styles let you float an image to the left or the right of the column, to let text wrap around them. To make use of these class styles, you need to add a bit of HTML to the images

4. In the `rwd.html` file, locate the `` tag for the `clouds.jpg` image—``—and add `class="half right"` so it looks like this:

```

```


It's common and often useful to apply more than one class to an element. In this way, you can combine simpler, modular styles to create more complex designs. In this case, the `half` class resizes the images, while the `right` class floats the image to the right. Simply by changing `right` to `left` you can move the image to the left of the column, while still maintaining the sizing property of the `half` style.

5. For the `jellyfish.jpg` image, add `class="half left"` so its HTML code looks like this:

```

```

Now the images are all sized. The page should look like Figure 14-6. If you want, you can create additional styles for other sizes, and even specify pixel sizes to allow particular images to resize to their full widths, but no more (see page 219).



Adding Styles for Tablet Screens

The design at this point works the same in every device: desktop, tablets, and mobile phones. It's a flexible design that shrinks or grows to fit the browser window. But at a certain point, the sidebar columns are just too thin to be readable. The first media query you'll add will target screens that are between 480 and 768 pixels and will move the right sidebar to the bottom of the page, converting the three-column design into a more readable two-column design.

1. **Open the `styles.css` file in your text editor.** Scroll to the bottom of the file and add:

```
@media (min-width: 481px) and (max-width:768px) {  
  
}
```

Here's the first media query. It targets screens that are at least 481 pixels, but no more than 768 pixels. In the next part of this tutorial, you'll craft a media query for devices that are no more than 480 pixels wide. So this media query excludes those devices, but also excludes devices that are more than 768 pixels. In other words, any styles you place in this section of the style sheet won't apply to desktop browsers (unless you resize the window so that it's very thin); nor will they apply to most phones.

The first thing you'll do is remove the float from the right sidebar.

2. **Inside the media query you added in the last step, add the following style (in bold):**

```
@media (min-width: 481px) and (max-width:768px) {  
  .sidebar2 {  
    float: none;  
    width: auto;  
  }  
}
```

This removes the float from that sidebar, and sets its width to auto (overriding the 20% width from the `.sidebar2` style earlier in the style sheet). However, this doesn't make the sidebar drop down below the other two columns. Because the column wrapper div is also floated left, the second sidebar wraps around it (see page 421 for more on how floats work). You'll need to make the sidebar clear those floats.

3. **Edit the style you added in the last step by adding the code in bold:**

```
.sidebar2 {  
  float: none;  
  width: auto;
```

```

clear: both;
border-top: 2px solid black;
padding-top: 10px;
}

```

The `clear` property (discussed on page 425) makes this sidebar drop down below the other two columns. You've also added a distinctive top border to further visually separate this container from the above columns.

If you preview the page now, you'll see that the two columns don't span the entire width of the page. That's because earlier in Step 8 on page 476, you set that column wrapper to 80% of the page width. You need to reset that style inside the tablet media query.

4. After the `.sidebar2` style, add the following:

```

.columnWrapper {
width: auto;
float: none;
}

```

Make sure that style goes inside the media query. It resets the column wrapper's width to `auto` (the same as 100%) so it spans the entire width of the page. We don't need the `float` on this element any more either, since the `sidebar2` column has dropped below. Because there are now only two columns, you can remove the right border that's applied to the main content column.

5. Add one last style after the `.columnWrapper` style. The complete media query should now look like this (changes in bold):

```

@media (min-width: 481px) and (max-width:768px) {
.sidebar2 {
float: none;
width: auto;
clear: both;
border-top: 2px solid black;
padding-top: 10px;
}

.columnWrapper {
width: auto;
}

.main {
border-right: none;
}
}

```

6. Save the `styles.css` file and preview the `rwd.html` file in a web browser. Resize the browser window until only two columns appear.

The page should look like Figure 14-7.




FIGURE 14-7

From three columns to two columns, with one media query and just three simple styles.

Adding Phone Styles

Finally, it's time to add styles for devices that are no wider than 480 pixels.

1. **Open the *styles.css* file in your text editor.** Scroll to the bottom of the file and add another media query:

```
@media (max-width:480px) {  
  
}
```

Make sure this goes after the other media query, not inside it. Here we'll target devices that are no wider than 480 pixels. The first step is to *linearize* the layout; that is, remove all of the floats so the content is stacked in a single column for easy reading on a small screen.

2. **Inside that media query, add the following style:**

```
.columnWrapper, .main, .sidebar1, .sidebar2 {  
    float: none;  
    width: auto;  
}
```

This removes the float from the column wrapper and all the columns. Setting the width to auto makes them fill their container completely. So now the three columns are simply block-level elements stacked one on top of the other, with the main content on top and the two sidebars underneath.

The main content area still has borders from the styles earlier in the style sheet. These left and right borders provide visual separation from the left and right sidebars in the three-column layouts, but you don't need them in this stacked layout, so you can remove them. On the other hand, adding visual separation between the now-stacked content blocks would be nice to have.

3. **After the style you just added (and still inside the 480-pixel media query), add these two styles:**

```
.main {  
    border: none;  
}  
  
.sidebar1, .sidebar2 {  
    border-top: 2px solid black;  
    margin-top: 25px;  
    padding-top: 10px;  
}
```

The second group selector here adds a border above each sidebar as well as some top margin and padding to clearly mark off the different content regions on the page.

Save the CSS file and preview the *rwd.html* page in a web browser. Drag the browser window so it's less than 480 pixels wide. You'll now see the one-column

design. If you view this page on a phone, you'll notice that the headline looks really big (Figure 14-8). In addition, the navigation buttons look a little out of control. You'll fix those two problems next.



FIGURE 14-8

Even when you get the width of a page correctly sized for a mobile phone, there's still work to do. Here, a headline, which is the perfect size for a desktop browser, is an oversized monster on the phone taking up way too much valuable screen space.

4. Add a style for the `<h1>` tag inside the 480-pixel media query:

```
header h1 {  
    font-size: 1.5em;  
}
```

This style reduces the text size in the `<h1>` tag so it now fits on a single line. It's often a good idea to reduce the size of headlines when converting a desktop design to one viewed on a little phone screen. You may also find that you should *increase* the font size for body text to make it easier to read. There are a lot of

ways you can tweak the phone design of your page, and it's up to you to figure out what looks best.

Now, you'll tackle the navigation bar. The dashed borders separating the buttons look bad and jumbled. In addition, the buttons are aligned to the left, creating an out-of-balance asymmetry. They'll look better centered and without those borders.

5. Add another style after the header h1 style you added in the previous step:

```
nav {  
  text-align: center;  
}
```

The nav buttons are contained inside an HTML5 `<nav>` element. By setting the `text-align` value to `center`, all text inside that nav should be centered. However, the buttons are actually floated to the left, so this is only the first step. (You can turn to page 304 for more information on using floats to create a horizontal navigation bar.)

6. Add two more styles after the nav style:

```
nav li {  
  float: none;  
  display: inline-block;  
}  
  
nav a {  
  float: none;  
  display: inline-block;  
  border: none;  
}
```

You're removing the floats from both the list items and the links. In addition, you turn these elements into inline blocks. As described on page 308, using `inline-block` on navigation elements lets you place links side-by-side, while still preserving padding and margins. In addition, the `inline-block` method is the only way to center these buttons.

7. The final 480-pixel media query should look like this:

```
@media (max-width:480px) {  
  .columnWrapper, .main, .sidebar1, .sidebar2 {  
    float: none;  
    width: auto;  
  }  
  
  .main {  
    border: none;  
  }  
}
```

```
.sidebar1, .sidebar2 {
    border-top: 2px solid black;
    margin-top: 25px;
    padding-top: 10px;
}

header h1 {
    font-size: 1.5em;
}

nav {
    text-align: center;
}

nav li {
    float: none;
    display: inline-block;
}

nav a {
    float: none;
    display: inline-block;
    border: none;
}
}
```

Save all of your files and preview the `rwd.html` file in a web browser. Resize the browser window so it's less than 480 pixels to see the phone design; resize the window until the two-column design pops into view; and then again until you see the three-column, desktop version. You should see designs like those pictured in Figure 14-9. You'll find a completed version of this tutorial in the `14_finished` folder.




FIGURE 14-9
One, two, and three columns, all in a single web page. Thanks to responsive web design techniques, you can transform a single web page to best fit any wide device.

Positioning Elements on a Web Page

When the World Wide Web Consortium introduced *CSS Positioning*, some designers understandably thought they could make web pages look just like print documents created in programs like InDesign or Quark XPress. With just a couple of CSS properties, CSS Positioning lets you position an element in a precise location on a page—say 100 pixels from the top of the page and 200 pixels from the left edge. Pixel-accurate placement seemed to promise that, at last, you could design a page simply by putting a photo here, a headline there, and so on.

Unfortunately, the level of control designers expected from CSS Positioning never materialized. There have always been differences in how various browsers display CSS positioned elements. But, even more fundamentally, the Web doesn't work like a printed brochure, magazine, or book. Web pages are much more fluid than printed pages. Once a magazine rolls off the press, readers can't change the page size or font size. About the only way they can change the look of the magazine is to spill coffee on it.

Web visitors, on the other hand, can tinker with your handcrafted presentation. They can increase their browser's font size, potentially making text spill out of your precisely placed and sized layout elements. But the news isn't all bad: As long as you don't try to dictate the exact width, height, and position of *every* design element, you'll find CSS's positioning properties powerful and helpful. You can use these properties to make a text caption appear on top of a photo, place a logo anywhere on the page, and much more.

■ How Positioning Properties Work

The CSS `position` property lets you control how and where a web browser displays particular elements. Using `position`, you can, for example, place a sidebar anywhere you wish on a page or make sure a navigation bar at the top of the page stays in place even when visitors scroll down the page. CSS offers four types of positioning:

- **Absolute.** Absolute positioning lets you determine an element's location by specifying a `left`, `right`, `top`, or `bottom` position in pixels, ems, or percentages. (See Chapter 6 for more on picking between the different units of measurement.) You can place a box 20 pixels from the top and 200 pixels from the left edge of the page, as shown in Figure 15-1, middle. (More in a moment on how you actually code these instructions.)

In addition, absolutely positioned elements are completely detached from the flow of the page as determined by the HTML code. In other words, other things on the page don't even know the absolutely positioned element exists. They can even disappear completely underneath absolutely positioned items, if you're not careful.

NOTE

Don't try to apply both the `float` property and any type of positioning other than `static` (explained below) or `relative` to the same style. The `float` property and `absolute` or `fixed` positioning can't work together on the same element.

- **Relative.** A relatively positioned element is placed relative to its current position in the HTML flow. So, for example, setting a `top` value of 20 pixels and `left` value of 200 pixels on a relatively positioned headline moves that headline 20 pixels down and 200 pixels from the left *from wherever it would normally appear*.

Unlike with absolute positioning, other page elements accommodate the old HTML placement of a relatively positioned element. Accordingly, moving an element with relative positioning leaves a "hole" where the element would have been. Look at the dark strip in the bottom image of Figure 15-1. That strip is where the relatively positioned box *would have* appeared, before it was given orders to move. The main benefit of relative positioning isn't to move an element, but to set a new point of reference for absolutely positioned elements that are nested inside it. (More on that brain-bending concept on page 493.)

- **Fixed.** A fixed element is locked into place on the screen. It does the same thing as the `fixed` value for the `background-attachment` property (page 579). When a visitor scrolls the page, fixed elements remain onscreen as paragraphs and headlines, while photos disappear off the top of the browser window.

Fixed elements are a great way to create a fixed sidebar or replicate the effect of HTML frames, where only a certain portion (frame) of the page scrolls. You can read about how to create this effect on page 506.




FIGURE 15-1

CSS offers several ways to affect an element's placement on a web page. The static option, top, is the way browsers have presented content since the beginning of the Web. They simply display the HTML in top-to-bottom order. Absolute positioning (middle) removes an element from the page flow, placing it on top of the page, sometimes overlapping other content. Relative positioning (bottom) places an element relative to where it would normally appear on the page and leaves a hole (the dark background here) where that element would've been without relative positioning.

- **Static** positioning simply means the content follows the normal top-down flow of HTML (see Figure 15-1, top). Why would you want to assign an element static positioning? The short answer: You probably never will.

To change the positioning of any element, simply use the `position` property followed by one of the four keywords: `absolute`, `relative`, `fixed`, `static`. To create an absolutely positioned element, add this property to a style:

```
position: absolute;
```

Static is the normal positioning method, so unless you're overriding a previously created style that already has a position of `absolute`, `relative`, or `fixed`, you won't need to specify that. In addition, static elements don't obey any of the positioning values discussed next.

Setting a positioning value is usually just part of the battle. To actually place an element somewhere on a page, you need to master the various positioning properties.

Setting Positioning Values

The display area of a web browser window—also called the `viewport`—has top, bottom, left, and right edges. Each of the four edges has a corresponding CSS property: `top`, `bottom`, `left`, and `right`. But you don't need to specify values for all four edges. Two are usually enough to place an item on the page. You can, if you want, place an element 10 ems from the left edge of the page and 20 ems from the top.

To specify the distance from an edge of a page to the corresponding edge of the element, use any of the valid CSS measurements—pixels, ems, percentages, and so on. You can also use negative values for positioning like `left: -10px`; to move an element partly off the page (or off another element) for visual effect, as you'll see later in this chapter (page 503).

After the `position` property, you list one or more properties (`top`, `bottom`, `left`, or `right`). If you want the element to take up less than the available width (to make a thin sidebar, for example), then you can set the `width` property. To place a page's banner in an exact position from the top and left edges of the browser window, create a style like this:

```
.banner {  
  position: absolute;  
  left: 100px;  
  top: 50px;  
  width: 760px;  
}
```

This style places the banner as pictured in Figure 15-2, top.

NOTE If you don't specify a vertical positioning value (for left or right), the browser places the element in the same place on the page vertically as it would if there were no positioning. The same is true for horizontal settings (top or bottom). In other words, if you simply set an element to a position of `absolute` but don't provide any placement values for top, right, bottom, or left, the browser simply keeps the element in the same place on the page, but stacked above other content.




FIGURE 15-2

One useful aspect of absolute positioning is the ability to place an item relative to the right edge of the browser window (middle). Even when the width of the browser changes, the distance from the right edge of the window to the right edge of the positioned element stays the same (bottom).

Here's another example: placing an element so it always remains a fixed distance from the right side of the browser. When you use the `right` property, the browser measures the distance from the right edge of the browser window to the right edge of the element (Figure 15-2, middle). To position the banner 100 pixels from the right edge of the window, you'd create the same style as above, but simply replace `left` with `right`:

```
.banner {  
  position: absolute;  
  right: 100px;  
  top: 50px;  
  width: 760px;  
}
```

Since the position is calculated based on the right edge of the browser window, adjusting the size of the window automatically repositions the banner, as you can see in Figure 15-2, bottom. Although the banner moves, the distance from the right edge of the element to the right edge of the browser window remains the same.

You can even specify *both* left and right position properties as well as both top and bottom and let the browser determine the width and height of the element. Say you want a central block of text positioned 10 percent from the top of the window and 10 pixels from both the left and right edges of the window. To position the block, you can use an absolutely positioned style that sets the `top`, `left`, and `right` properties to 10%. In a browser window, the left edge of the box starts from the left edge of the window to 10 percent of the window's width, and the right edge extends to 10 percent from the right edge (Figure 15-3). The exact width of the box, then, depends on how wide the browser window is. A wider window makes a wider box; a thinner window, a thinner box. The left and right positions, however, are always 10 percent of the browser window's width.

The width and height properties, which you learned about in Chapter 7, work exactly the same way for positioned elements. To place a 50 x 50 pixel gray box in the top-right corner of the browser window, create this style:

```
.box {  
  position: absolute;  
  right: 0;  
  top: 0;  
  width: 50px;  
  height: 50px;  
  background-color: #333;  
}
```

The same caveat mentioned on page 214 applies here as well: Be careful with setting heights on elements. Unless you're styling a graphic with a set height, you can't be sure how tall any given element will be on a page. You might define a sidebar to be 200 pixels tall, but if you end up adding enough words and pictures to make the sidebar taller than 200 pixels, then you end up with content spilling out of the sidebar. Even if you're sure the content fits, a visitor can always pump up the size of her

browser's font, creating text that's large enough to spill out of the box. Furthermore, when you specify a width and height in a style and the contents inside the styled element are wider or taller, strange things can happen.

When Absolute Positioning Is Relative

So far, this chapter has talked about positioning an element in an exact location in the browser window. However, absolute positioning doesn't always work that way. In fact, an absolutely positioned element is actually placed *relative* to the boundaries of its closest positioned ancestor. Simply put, if you've already created an element with absolute positioning (say a <div> tag that appears 100 pixels down from the top of the browser window), then any absolutely positioned elements with HTML *inside* that <div> tag are positioned relative to the div's top, bottom, left, and right edges.




FIGURE 15-3

You can let a browser figure out an element's width simply by setting both the left and right values of an absolutely positioned element.

NOTE

If all this talk of parents and ancestors doesn't ring a bell, then turn to page 104 for a refresher.

In the top image of Figure 15-4, the light gray box is absolutely positioned 5 ems from the top and left edges of the browser window.




FIGURE 15-4

You can place an element relative to the browser window (top) or relative to a positioned ancestor (bottom).

There's also a `<div>` tag nested inside that box. Applying absolute positioning to that `<div>` positions it *relative to its absolutely positioned parent*. Setting a bottom position of 0 doesn't put the box at the bottom of the screen; it places the box at the bottom of its parent. Likewise, a right position for that nested `<div>` refers to the right of the edge of its parent (Figure 15-4, bottom).

Whenever you use absolute positioning to place an element on the page, the exact position depends upon the positioning of any other tags the styled element is nested in. Here are the rules in a nutshell:

- **A tag is positioned relative to the browser window** if it has an absolute position *and* it's not inside any other tag that has either absolute, relative, or fixed positioning applied to it.
- **A tag is positioned relative to the edges of another element** if it's inside another tag with absolute, relative, or fixed positioning.

When (and Where) to Use Relative Positioning

You get one big benefit from placing an element relative to another tag: If that tag moves, the positioned element moves along with it. Say you place an image inside an `<h1>` tag, and you want the image to appear on the right edge of that `<h1>` tag. If you simply position the image in an exact spot in the browser window on the left edge of the `<h1>` tag, you're taking your chances. If the `<h1>` moves, the absolutely positioned image stays glued to its assigned spot. Instead, what you want to do is position the image relative to the `<h1>` tag, so that when the headline moves, the image moves with it (bottom two images in Figure 15-5).

NOTE You can use the `background-image` property to place an image into the background of an `<h1>` tag. But if the graphic is taller than the `<h1>` tag, or you want the graphic to appear *outside* the boundaries of the headline (see the example third from the top in Figure 15-5), then embed the image with the `` tag and use the relative positioning technique described in this section.

You could use the `position` property's relative value to place the image, but that has drawbacks, too. When you set an element's position to `relative` and then place it—maybe using the `left` and `top` properties—the element moves the set amount from where it would normally appear in the flow of the HTML. In other words, it moves relative to its current position. In the process, it leaves a big hole where it would've been if you hadn't positioned it at all (Figure 15-1, bottom). Usually, that's not what you want.

A better way to use relative positioning is to create a new positioning context for nested tags. For instance, the `<h1>` tag in the example at the beginning of this section is an ancestor of the `` tag inside it. By setting the position of the `<h1>` tag to `relative`, any absolute positioning you apply to the `` tag is relative to the four edges of the `<h1>` tag, not the browser window. Here's what the CSS looks like:

```
h1 { position: relative; }
h1 img {
  position: absolute;
  top: 0;
  right: 0;
}
```




FIGURE 15-5
Top: A graphical button (circled) is placed inside an `<h1>` tag.

Second from top: Adding absolute positioning to the button—`right: -35px; top: -35px;`—moves it outside of the `<h1>` tag area and places it in the top-right corner of the browser window (circled). (In fact, it's placed a little outside of the browser window thanks to the negative positioning values.)

Third from top: Adding `position: relative;` to the `` tag. The same top and right values move the `` tag to the `<h1>` tag's top-right corner.

Bottom: When you move the heading down the page, the graphic goes along for the ride.

Setting the image's top and right properties to 0 places the image in the upper-right corner of the headline—not the browser window.

In CSS, the term *relative* doesn't exactly mean the same thing it does in the real world. After all, if you want to place the `` tag relative to the `<h1>` tag, your first

instinct may be to set the image's position to relative. In fact, the item that you want to position—the image—gets an absolute position, while the element you want to position the element *relative to*—the headline—gets a setting of relative. Think of the relative value as meaning “relative to me.” When you apply relative positioning to a tag, it means “all positioned elements inside of me should be positioned relative to my location.”

NOTE Because you'll often use relative positioning merely to set up a new positioning context for nested tags, you don't even need to use the left, top, bottom, or right settings with it. The `<h1>` tag has `position: relative`, but no left, top, right, or bottom values.

Stacking Elements

As you can see in Figure 15-6, absolutely positioned elements sit “above” your web page and can even reside on top of (or underneath) other positioned elements. This stacking of elements takes place on what's called the z-index. If you're familiar with the concept of layers in Photoshop, Fireworks, or Adobe InDesign, then you know how the z-index works: It represents the order in which positioned elements are stacked on top of the page.




FIGURE 15-6

When you use z-index to control how positioned elements are stacked, parent elements define the stacking order for their children. In the top two examples, the text box isn't positioned, so it shares the z-index of the page itself, which has a z-index value of 0. So the buttons in those two text boxes are stacked relative to and above the page. But the text box in the bottom image has an absolute position and a z-index of 1000. This containing `<div>` becomes the starting point for stacking the images inside it. So even though the div's z-index is 1000, its nested children (with lower z-index values) appear on top of it, while the text box itself sits above the page.

To put it another way, think of a web page as a piece of paper and an absolutely positioned element as a sticky note. Whenever you add an absolutely positioned element to a page, it's like slapping a sticky note on it. Of course, when you add a sticky note, you run the risk of covering up anything written on the page below.

Normally, the stacking order of positioned elements follows their order in the page's HTML code. On a page with two absolutely positioned `<div>` tags, the `<div>` tag that comes second in the HTML appears *above* the other `<div>`. But you can control the order in which positioned elements stack up by using the CSS `z-index` property. The property gets a numeric value, like this:

```
z-index: 3;
```

The larger the value, the closer to the top of the stack an element appears. Say you have three absolutely positioned images, and parts of each image overlap. The one with the larger `z-index` appears on top of the others (see Figure 15-6, top). When you change the `z-index` of one or more images, you change their stacking order (Figure 15-6, middle).

You can even use negative `z-index` numbers, which can come in handy when you want to position an element underneath its parent or any of its ancestors. For example, in the top image in Figure 15-6, the `<div>` tag is relatively positioned. If you wanted to place one of the images behind the `<div>`, you could use a negative `z-index` value:

```
z-index: -1;
```

While most browsers support negative `z-index` values, Internet Explorer 7 and earlier don't, so if you need to support Internet Explorer 7, then it's best to skip negative `z-indexes` completely.

NOTE

It's perfectly OK to have gaps in `z-index` values. In other words, 10, 20, 30 does the exact same thing as 1, 2, 3. In fact, spreading out the numerical values gives you room to insert more items into the stack later. And, when you want to make sure nothing ever appears on top of a positioned element, give it a really large `z-index`, like this: `z-index: 10000;`. But don't get too carried away: some browsers can only handle a maximum `z-index` of 2147483647.

Hiding Parts of a Page

Another CSS property often used with absolutely positioned elements is `visibility`, which lets you hide part of a page (or show a hidden part). Say you want a label to pop into view over an image when a visitor mouses over it. You make the caption invisible when the page first loads (`visibility: hidden`), and switch to visible (`visibility: visible`) when the mouse moves over it.

The `visibility` property's `hidden` value is similar to the `display` property's `none` value, but there's a fundamental difference. When you set an element's `display` property to `none`, it literally disappears from the page without a trace. However, setting the `visibility` property to `hidden` prevents the browser from displaying the element's

contents, but leaves an empty hole where the element would have been. When applied to absolutely positioned elements that are already removed from the flow of the page, `visibility: hidden` and `display: none` behave identically. Most developers simply use the `display: none` method and skip the visibility property entirely.

There's yet another way to hide an element—set its opacity to 0 like this:

```
opacity: 0;
```

To make it reappear, you can set its opacity back to 1:

```
opacity: 1;
```

The benefit of using opacity is that it's one of the CSS properties that a browser can animate. This means you can use the CSS transitions you learned about in Chapter 10 to animate changes in opacity. For example, you can make an element appear to fade into view by changing its opacity from 0 to 1 and adding a transition.

The most common way to switch an element from hidden to displayed and back again is with JavaScript. But you don't have to learn JavaScript programming to use the visibility property (or, for that matter, the display property). You can use the `:hover` pseudo-class (see page 294) to make an invisible element visible. For example, say you wanted to place a caption over an image, but you only want that caption to show up when a visitor mouses over the image (see Figure 15-7). You could do that following these steps:

1. Create the HTML for the image and caption.

One way to do this would be to use the HTML5 `<figure>` and `<figcaption>` tags, like this:

```
<figure class="hat">  
  
<figcaption>A picture of a hat</figcaption>  
</figure>
```

Here you're applying a class—`hat`—to the `<figure>` tag so you can style just that one figure.

NOTE As mentioned in the box on page 24, IE 8 and earlier don't apply CSS to HTML5 elements without a little help from some simple JavaScript. If you don't want to bother with that, you could simply use `<div>` tags instead of the `<figure>` and `<figcaption>` tags.

2. Position the caption.

To place the caption on top of the image, you use absolute positioning. To place the caption in relation to the `img`, you should set its parent (the `<figure>` tag) to relative and also give the parent a set width that matches the dimensions of the photo.

```
.hat {
  position: relative;
  width: 100px;
  height: 100px;
}

.hat figcaption {
  position: absolute;
  bottom: 0;
  left: 0;
  right: 0;
  background-color: white;
}
```

The caption is placed at the bottom of the figure (`bottom: 0`). By setting its left and right values to 0, it will span the entire width of the figure.

3. Hide the caption.

With the current code, a browser would display the caption on top of the image, but you want that to happen only when someone’s mouse hovers over the image. To hide it, add either `visibility: hidden;` or `display: none;` to the `.hat figcaption` style.

```
.hat figcaption {
  display: none;
  position: absolute;
  bottom: 0;
  left: 0;
  right: 0;
  background-color: white;
}
```

4. Make the caption appear when a visitor mouses over the image.

To do this, you’ll employ a little trick with the `:hover` pseudo-class (page 294). You want to make the caption visible when the visitor mouses over the image. Unfortunately, there’s no way to create a style that affects the caption when the mouse moves over the image. However, since the caption is inside the `<figure>` tag, you can craft a descendent selector that affects the caption when the mouse moves over the figure:

```
.hat:hover figcaption {
  display: block;
}
```

This descendent selector basically says “target any `<figcaption>` tag that’s inside an element with the class of `hat`, but only when the mouse is over that element.” This selector only works because the `figcaption` tag is a descendent of the element being hovered over.


You can elaborate on this idea to create CSS-based pop-up tooltips. For a basic CSS method of adding pop-up tooltips—additional information that appears when someone mouses over a link—check out www.menucool.com/tooltip/css-tooltip. You also have many JavaScript options to choose from: the jQuery aTip2 plug-in is a full-featured and easy-to-use JavaScript tooltip based on the jQuery framework: <http://craigsworks.com/projects/qtip2/>.

As mentioned earlier, you can also use the `opacity` setting to hide and show an element, as well as use a transition to animate this effect. To do that, you can change the previous styles to look like this:

```
.hat figcaption {
  opacity: 0;
  -webkit-transition: opacity .5s ease-in;
  -moz-transition: opacity .5s ease-in;
  -o-transition: opacity .5s ease-in;
  transition: opacity .5s ease-in;
  position: absolute;
  bottom: 0;
  left: 0;
  right: 0;
  background-color: white;
}

.hat:hover figcaption {
  opacity: 1;
}
```

You'll see this in action in the tutorial on page 507. Remember, however, that transitions don't work in Internet Explorer 9 or earlier. That's OK in this case; your visitors will still see the caption appear, it just won't fade in and out of view smoothly.



■ Powerful Positioning Strategies

As explained at the beginning of this chapter, you can run into trouble when you try to use CSS positioning to place *every* element on a page. Because it's impossible to predict all possible combinations of browsers and settings your visitors will use, CSS-controlled positioning works best as a tactical weapon. Use it sparingly to provide exact placement for specific elements.

In this section, you'll learn how to use absolute positioning to add small but visually important details to your page design, how to absolutely position certain layout elements, and how to cement important page elements in place while the rest of the content scrolls.

Positioning Within an Element

One of the most effective ways to use positioning is to place small items relative to other elements on a page. Absolute positioning can simulate the kind of right alignment you get with floats. In the first example in Figure 15-8, the date on the top headline is a bit overbearing, but with CSS you can reformat it and move it to the right edge of the bottom headline.

In order to style the date separately from the rest of the headline, you need to enclose the date in an HTML tag. The `` tag is a popular choice for applying a class to a chunk of inline text to style it independently from the rest of a paragraph.

```
<h1><span class="date">Nov. 10, 2006</span> CosmoFarmer Bought By Google</h1>
```

Now it's a matter of creating the styles. First, you need to give the containing element—in this example, the `<h1>` tag—a relative position value. Then, apply an absolute position to the item you wish to place—the date. Here's the CSS for the bottom image in #1 of Figure 15-8:

```
h1 {  
  position: relative;  
  border-bottom: 1px dashed #999999;  
}  
  
h1 .date {  
  position: absolute;  
  bottom: 0;  
  right: 0;  
  font-size: .5em;  
  background-color: #E9E9E9;  
  color: black;  
  padding: 2px 7px 0 7px;  
}
```

Some of the properties listed above, like `border-bottom`, are just for looks. The crucial properties are bolded: `position`, `bottom`, and `right`. Once you give the headline a relative position, you can position the `` containing the date in the lower-right corner of the headline by setting both the `bottom` and `right` properties to 0.




FIGURE 15-8

Absolute positioning is perfect for simple design details like placing a date in the lower-right corner of a headline (top), punching an image out of its containing block (middle), or placing a caption directly on top of a photo (bottom). (You'll learn the caption trick in the tutorial on page 507.)

Breaking an Element Out of the Box

You can also use positioning to make an item appear to poke out of another element. In the second example in Figure 15-8, the top image shows a headline with a graphic. That is, the `` tag is placed inside the `<h1>` tag as part of the headline. Using absolute positioning and negative `top` and `left` property values moves the image to the headline's left and pushes it out beyond the top and left edges. Here's the CSS that produces that example:


```
h1 {  
  position: relative;  
  margin-top: 35px;  
  padding-left: 55px;  
  border-bottom: 1px dashed #999999;  
}  
  
h1 img {  
  position: absolute;  
  top: -30px;  
  left: -30px;  
}
```

The basic concept is the same as the previous example, but with a few additions. First, the image's `top` and `left` values are negative, so the graphic actually appears 30 pixels above the top of the headline and 30 pixels to the left of the headline's left edge. Be careful when you use negative values. They can position an element partially (or entirely) off a page or make the element cover other content on the page. To prevent a negatively positioned element from sticking out of the browser window, add enough margin or padding to either the body element or the enclosing, relatively positioned tag—the `<h1>` tag in this example. The extra margin provides enough space for the protruding image. In this case, to prevent the image from overlapping any content above the headline, add a significant top margin. The left padding of 55 pixels also moves the text of the headline out from under the absolutely positioned image.

Creating CSS-Style Frames Using Fixed Positioning

Since most web pages are longer than one screen, you may want to keep some page elements constantly visible—like a navigation panel, search box, or your site logo. HTML frames were once the only way to keep important fixtures handy as other content scrolled out of sight. But HTML frames have major drawbacks. Since each frame contains a separate web page file, you have to create several HTML files to make one complete web page (called a *frameset*). Not only are framesets time consuming for the designer, they also make your site hard for search engines to search. And HTML framesets can also wreak havoc for visitors who use screen readers due to vision problems or those who want to print pages from your site.

Nevertheless, the idea behind frames is still useful, so CSS offers a positioning value that lets you achieve the visual appearance of frames with less work. You can see a page created using the *fixed* value in Figure 15-9.

**FIGURE 15-9**


Revisit the Web of yesteryear, but with a lot less code. Using the position property's fixed value, you can emulate the look of HTML frames by fixing some elements in place but still letting visitors scroll through the content of a very long web page. The scrollbar (circled) moves only the large text area; the top and bottom banners and the sidebar stay fixed.

Fixed positioning works much like absolute positioning in that you use the left, top, right, or bottom properties to place the element. Also like absolutely positioned elements, fixed positioning removes an element from the flow of the HTML. It floats above other parts of the page, which simply ignore it.

Here's how you can build the kind of page pictured in Figure 15-9, which has a fixed banner, sidebar, and footer, and a scrollable main content area:

1. Add <div> tags with class (or ID) attributes for each section of the page.

You can have four main <div> tags with classes (or IDs) like banner, sidebar, main, and footer (Figure 15-10). The order in which you place these tags in the HTML doesn't matter. Like absolute positioning, fixed positioning lets you place elements on a page regardless of their HTML order.

**FIGURE 15-10**

With fixed positioning, you can lock any number of page elements in place, so they're always in view when your visitor scrolls. In this example, the header (1), sidebar (3), and footer (4) are fixed while the content in the main area of the page (2) is free to scroll.

2. Add your material to each <div>.

In general, use the fixed divs for stuff a visitor should always have access to in the areas you wish to be locked in place. In this example, the banner, sidebar, and footer contain the site logo, global site navigation, and copyright notices.

The main content goes into the remaining <div> tag. Don't add too much information to a fixed <div>, however. If a fixed sidebar is taller than the visitor's browser window, he won't be able to see the entire sidebar. And since fixed elements don't scroll, there'll be no way (short of buying a bigger monitor) for that visitor to see the sidebar content that doesn't fit in his browser window.

3. Create styles for all fixed elements.

The left, right, top, and bottom values are relative to the browser window, so just determine where on the screen you'd like them to go and plug in the values. Specify a width for the elements as well.

NOTE Unlike absolute positioning, fixed positioning is *always* relative to the browser window, even when an element with fixed positioning is placed inside another tag with relative or absolute positioning.

The styles to position the elements numbered 1, 3, and 4 in Figure 15-10 look like this:

```
.banner {
  position: fixed;
  left: 0;
  right: 0;
  top: 0;
}

.sidebar {
  position: fixed;
  left: 0;
  top: 110px;
  width: 175px;
}

.footer {
  position: fixed;
  bottom: 0;
  left: 0;
  right: 0;
}
```

4. Create the style for the scrollable content area.

Since fixed-position elements are removed from the flow of the HTML, other tags on the page have no idea the fixed-position elements are there. So, the `<div>` tag with the page's main content, for example, appears underneath the fixed items. The main task for this style is to use margins to move the contents clear of those areas. (The concept is the same as for absolutely positioned layouts, as discussed on page 493.)

```
.main {  
  margin-left: 190px;  
  margin-top: 110px;  
}
```

Fixed positioning is well supported in browsers: Internet Explorer 8 and up, as well as all other major browsers (including the latest iOS and Android mobile browsers) support fixed positioning.

■ Tutorial: Positioning Page Elements

This tutorial lets you explore a few different ways to use absolute positioning, like creating a three-column layout, positioning items within a banner, and adding captions on top of photos. Unlike the previous chapter, where you wrapped chunks of HTML in `<div>` tags and added class names to them, in these exercises, most of the HTML work has already been done for you. You can focus on honing your new CSS skills.

To get started, download the tutorial files located on this book's companion website at www.sawmac.com/css3/.

Enhancing a Page Banner

First, you'll make some small but visually important changes to a page banner. You'll create styles that refer to HTML tags with classes applied to them. (Again, that part has been taken care of for you.)

1. Launch a web browser and open the file **15→hats.html**.

On this web page (Figure 15-11), start by repositioning several parts of the banner.




FIGURE 15-11

This page has a lot of stuff—logo graphic, banner, nav bar, and a gallery of images and captions. But there's not much visual structure. Just normal, static HTML with everything running from top to bottom of the page. You can make it more readable and interesting with some absolute positioning.

2. **Open the `hats.html` file in a text editor.** Place your cursor between the opening and closing `<style>` tags.

Along with the `<style>` tags for an internal style sheet, the page already has an attached external style sheet with some basic formatting. Start by moving the small hat image to the left side of the banner. To help break up the boxy look that's typical of CSS designs, break this graphic out of the banner's borders, so it looks like a slapped-on sticker.

3. **In the internal style sheet, add this new style:**

```
header .badge {
    position: absolute;
    top: -20px;
    left: -90px;
}
```

The graphic is inside of an HTML5 `<header>` tag, and the graphic itself has a class of `badge`. This style positions the top-left corner of the graphic 90 pixels to the left and 20 pixels above the top of the page.

Preview the page now, and you'll see a couple of problems. First, the graphic hangs off the edge of the page, but you really want it to hang off the edge of the banner area. You'll tackle that problem now.

4. Add this style above the one you just created:

```
header {  
  position: relative;  
}
```

It's good practice to place the CSS code for styles that control a general section of a page (like this header style) above the code for styles that format just parts of that section (like the style you created in Step 3). Also, grouping styles for related sections makes it easier to find styles when you need to analyze or edit a page's CSS. In this case, the header style goes first in the internal style sheet because it applies to a large chunk of HTML. But you should keep the header `.badge` style near it as you add more styles to the page. (You can read more about techniques for organizing your CSS on page 541.)

The header style creates a new positioning context for any nested tags. In other words, the `relative` setting makes any other positioned elements inside this tag place themselves relative to the edges of the banner. This change in positioning shifts the placement of the style you created in Step 3. Now it's 20 pixels above and 90 pixels to the left of the banner box. The badge still hangs off the page just a little bit, so you'll add some margin to the header to move it down a bit.

5. Edit the header style by adding the two bolded lines below:

```
header {  
  position: relative;  
  margin-top: 20px;  
  padding: 20px 0 0 10px;  
}
```

This margin adds enough space above the header to move it and the graphic down. In addition, the padding adds space inside the header so the headline (and the soon to be repositioned nav bar) don't feel so cramped. But now you have another problem—"The Hat Gallery" headline is partially hidden underneath the badge. Overlapping elements is one of the hazards of absolute positioning. In this case, you can fix the problem by changing the badge's `z-index` and moving it behind the text.

6. Add `z-index: -1` to the header `.badge` style:

```
header .badge {  
  position: absolute;  
  top: -20px;  
  left: -90px;  
  z-index: -1;  
}
```

The -1 value places the absolutely positioned element behind its parent—in this case behind the text (see Figure 15-12). Next, you'll use absolute positioning to move the navigation bar to the right side of the header.

7. Add another style after the header .badge style.

```
header nav {
  position: absolute;
  right: 0;
  top: 45px;
}
```

Although you could position the navigation bar by floating the `<h1>` tag, in this case, it's a lot easier to use absolute positioning. Here, you've created a tag style for the HTML5 `<nav>` tag, when it's also inside a `<header>` tag. Remember, in Step 4, you gave the header a relative position, which means any tags inside it—like the `<nav>` tag—are positioned in relation to it, so the `right` value of 0 in this style places the right edge of the navigation bar on the right edge of the banner (see Figure 15-12).




FIGURE 15-12

Absolute positioning is a big help in placing small elements like the hat graphic and the navigation bar. Unlike floats, the exact position of the image and the navigation bar in the HTML code isn't important, giving you a lot of layout flexibility. You can achieve the same effect without absolute positioning, but it would be harder.

Placing Captions on the Photos

In Chapter 8, you learned one way to add a caption to a photo (page 275). In the examples from that chapter, the captions sat underneath the photos, which is what you want most of the time. But someday, you may want to add a caption directly on a photo, like the subtitles TV news shows love to display across the lower third of the screen.

1. Open *hats.html* in your text editor.

There is a gallery of photos on this page. The HTML for one image looks like this:

```
<figure>
  
  <figcaption><strong>Nam libero tempore.</strong> Soluta nobis est eligendi
  optio cumque nihil impedit quo minus id quod maxime placeat facere possimus,
  omnis voluptas assumenda est, omnis dolor repellendus
  </figcaption>
</figure>
```

This example uses the HTML5 `<figure>` and `<figcaption>` tags. The `<figure>` tag is normally a block-level tag, but since you want the images to sit side-by-side, start by changing them to inline elements.

NOTE

Because Internet Explorer 8 and earlier can't style HTML5 tags, you're adding a bit of JavaScript to tell those browsers to get with the program. See the box on page 24 for how this scheme works.

2. Add another style below the header `nav` style you added earlier.

```
.gallery figure {
  display: inline-block;
  width: 300px;
  height: 210px;
  margin: 15px;
  position: relative;
}
```

This HTML creates a descendent selector. The `<figure>` tags are all grouped inside a `<div>` tag with the class of `gallery` applied to it. You're using a descendent selector since you may add other figures to this page that aren't part of the gallery and should be formatted differently. This descendent selector targets just the `<figure>` tags you're after at the moment.

By making the `figure` tag an `inline-block` element, the figures can all sit side-by-side. The width and height values match the width and height of the images. In other words, you want the `<figure>` tag to only be large enough to hold the images. The margin value adds a little space around the figures so they don't bump into each. Finally, the `position: relative` declaration sets a new positioning context, so you can position each caption in relation to its figure.

Now it's time to position the captions.

3. Add one more style below the one you just added:

```
.gallery figcaption {  
    position: absolute;  
    top: 15%;  
    bottom: 15%;  
    left: 0;  
    right: 0;  
    background-color: rgb(153,153,153);  
  
    background-color: rgba(153,153,153,.9);  
}
```

The `<figcaption>` tags are absolutely positioned using all four positioning quadrants: top, bottom, left, and right. Basically, the captions will span the entire figure, but be placed a bit below the top and above the bottom (in fact, 15 percent below and above). Using all four settings means that you don't need to worry about setting a width or a height for the captions; instead, you leave it up to the browser.

Finally, two `background-color` declarations are set. The first is for Internet Explorer 8 and earlier (which doesn't understand the transparency settings of RGBA colors). The second is for modern browsers, and places a semi-transparent background atop each figure, which means you can see the image through the caption's background.

Now for some simple text enhancements.

4. Edit the style you just created by adding the bolded code below:

```
.gallery figcaption {  
    position: absolute;  
    top: 15%;  
    bottom: 15%;  
    left: 0;  
    right: 0;  
    background-color: rgb(153,153,153);  
    background-color: rgba(153,153,153,.9);  
    padding: 20px;  
    font-family: Titillium, Arial, sans-serif;  
    font-weight: 400;  
    font-size: .9em;  
    color: white;  
}
```

The padding just provides a little breathing room for the text, while the other properties set a font, size, and color.

If you preview the page now, you'll see that the captions appear on top of all of the images. Next, you'll change the style so the captions appear only when a visitor mouses over an image. Start by hiding the captions.

5. Add opacity: 0; to the style:

```
.gallery figcaption {  
    position: absolute;  
    top: 15%;  
    bottom: 15%;  
    left: 0;  
    right: 0;  
    background-color: rgb(153,153,153);  
    background-color: rgba(153,153,153,.9);  
    padding: 20px;  
    font-family: Titillium, Arial, sans-serif;  
    font-size: .9em;  
    font-weight: 400;  
    color: white;  
    opacity: 0;  
}
```

Setting the opacity to 0 makes the caption invisible. You may also use `display: none;` or `visibility: hidden;` to hide the captions, but this way you can animate the opacity value by using a CSS transition—in fact, you'll add that effect in a moment. But first, you need to add a `:hover` state so when a visitor hovers over the image, its caption appears.

6. Add the following to the style sheet:

```
figure:hover figcaption {  
    opacity: 1;  
}
```

This tricky bit of CSS can be translated to “when the mouse moves over the figure element (`figure:hover`), set the opacity of the caption to 1.” In other words, moving the mouse over the `<figure>` tag makes the descendent `<figcaption>` tag visible. Save the page and try it out. When you mouse over the figure, the caption should appear. We can animate this effect by adding a transition to the `.gallery figcaption` style.

7. Edit the `.gallery figcaption` style so that it looks like this (additions are in bold):

```
figcaption {  
    position: absolute;  
    top: 15%;  
    bottom: 15%;  
    left: 0;  
    right: 0;
```

```
background-color: rgb(153,153,153);
background-color: rgba(153,153,153,.9);
padding: 20px;
font-family: Titillium, Arial, sans-serif;
font-size: .9em;
font-weight: 400;
color: white;
opacity: 0;
-webkit-transition: opacity .75s ease-out;
-moz-transition: opacity .75s ease-out;
-o-transition: opacity .75s ease-out;
transition: opacity .75s ease-out;
}
```

You’ve added the `transition` property. Of course, to get it to work in the most browsers possible, you must add the appropriate vendor prefixes (`-webkit-`, and so on). While Internet Explorer 9 and earlier don’t understand transitions, that’s OK; the captions will still appear in those browsers. They’ll just appear and disappear instantly instead of fading in and out smoothly.

Finally, you’ll make the copyright notice stick to the bottom of the browser window, using fixed positioning.

8. Add one last style to the style sheet:

```
footer {
    position: fixed;
    bottom: 0;
    left: 0;
    right: 0;
    padding: 10px;
    background-color: black;
    color: white;
}
```

As you read on page 504, fixed positioning lets you “stick” an element to a specific spot in the browser window. In this case, it’s fixed to the bottom of the page (`bottom: 0`) and extends the entire width of the page (thanks to the `left: 0` and `right: 0` declarations). The last three declarations simply add a bit of space around the footer, giving it a black background and white text.

The final page should look like Figure 15-13. You’ll find a completed version of this tutorial in the [15_finished](#) folder.




FIGURE 15-13
With some clever CSS, you can easily make captions fade into view when mousing over an image (circled).

Advanced CSS

CHAPTER 16:
CSS for the Printed Page

CHAPTER 17:
Improving Your CSS Habits



CSS for the Printed Page

Believe it or not, sometimes people will want to see your web pages on paper. People who make a purchase on your site may want to print out a receipt, for example. If you have a cooking site, you'll certainly want to let your guests print their favorite recipes on paper or index cards for use in the kitchen. Even if your website consists of mostly text articles intended to be read online, some visitors will want to print a hard copy for a class project or archiving. So what becomes of your carefully crafted designs when the ink hits the paper? White text on a black background can waste gallons of toner, and some browsers may not even print the background. Do visitors really need to see your site's navigation bar on the printed page? Probably not.

Web designers used to solve this dilemma by creating separate *printer-friendly* versions of their sites—essentially creating a duplicate site formatted just for printing. Not only is that a lot more work than building one version of the site, it also means changing multiple files each time a page needs editing. Fortunately, CSS offers a better way—the ability to make a page look one way when displayed on a screen and a different way when printed (see Figure 16-1). The secret? Media style sheets.

■ How Media Style Sheets Work

The creators of CSS were pretty thorough when they envisioned all the different ways people might view websites. They knew while most people view the Web using a computer and monitor, sometimes people want to print out a page. In addition, new web surfing devices like mobile phones, handhelds, and televisions have their own unique requirements when it comes to web design.

To accommodate these different methods of surfing, CSS lets you create styles and style sheets that specifically target a particular media type. CSS recognizes 10 different media types: `all`, `braille`, `embossed`, `handheld`, `print`, `projection`, `screen`, `speech`, `tty`, and `tv`. The browser applies the style sheet only when that media type is active. In other words, the browser can apply one style sheet for the screen and a different one when printing. Many of these media types are for very specialized applications like a Braille reader for the blind, a speech reader (for those who want or need to hear a page in spoken form), or a teletype machine. These types may not work in the real world, as they depend on devices programmed to understand them. You should be aware, however, of three types: `all`, `screen`, and `print`.

- **All** applies to every type of device. When a style or style sheet applies to `all` media types, every device accessing the page uses those same styles. Printers and monitors alike attempt to format the page the same way. (Styles actually work this way already when you embed them in the page or link them from an external style sheet, so you don't need to specify "all media types" when adding a style sheet to a page.)
- **Screen** styles display only on a monitor. When you specify the `screen` media type, the browser ignores those styles when it prints the page. This media type lets you isolate styles that look good on screen but awful on paper, like white text on a black background.
- **Print** styles apply only when the page is printed. Print styles let you create styles that use printer-friendly font sizes, colors, graphics, and so on.

One approach is to build styles with your monitor in mind first, and then attach them using one of the methods described below (methods like `internal` or `external`, `linked` or `imported`). At the outset, these styles work for both the monitor and the printer. Then, you create a style sheet that applies only when printing. It overrides any of the main styles that negatively affect the look of the page when printed. You'll learn this technique starting on page 523. Alternatively, you can create two different media style sheets—one for `screen` and the other for `print`—and attach them to your web pages, as described in the next section.

TIP Another popular technique is to create three style sheets: one for the printer, one for the screen, and a third with styles that should appear both on a monitor and when printed. You specify the media types for the printer and screen style sheets and attach the third, shared set of styles as you would normally.





FIGURE 16-1

Using a printer style sheet can save paper, ink, and frustration by letting visitors print just the information they're after and leave unneeded extras on the monitor. In this example, a page from the great web development site, A List Apart, looks nice onscreen (top) and simple, clean, and informative when printed (bottom). Notice how the printed version expands to fill the entire width of the page and leaves off logo, navigation, and ads.



■ How to Add Media Style Sheets

Media style sheets are simply CSS style sheets: They can be either internal or external. However, when you want a web browser to apply the styles for only a particular device such as a screen or printer, you need to add the style sheet to your web page in a slightly different way than usual.

Specifying the Media Type for an External Style Sheet

To attach an external style sheet while specifying a particular media type, use the `<link>` tag with a *media* attribute. To link a style sheet that should be used only for printing, add this HTML to your web page:

```
<link rel="stylesheet" media="print" href="print.css"/>
```

NOTE

Technically, the rules of CSS also let you define a media type when using the `@import` method of attaching an external style sheet (see page 42), like so: `@import url(print.css) print;`. But since Internet Explorer 8 and earlier refuses to understand this code, you should avoid using it.

If you don't specify any media, a web browser assumes you're targeting all media, so it uses the style sheet for screen display, printing, and so on. In addition, you can specify *multiple* media types by separating them with commas. A linked external style sheet targeting multiple media might look like:

```
<link rel="stylesheet" media="screen, projection, handheld" href="screen.css"/>
```

You probably won't need to specify more than one until browsers start recognizing multiple media types.

TIP

When you build and test printer style sheets, leave off the `media="print"` attribute and turn off any screen-only style sheets. For example, change `media="screen"` to `media="speech"`. This technique lets you view the page in a web browser but have it display as if it were formatted for a printer. Once the printer style sheet looks good, make sure to set its media type to `print` and turn on any screen-only style sheets.

Specifying the Media Type Within a Style Sheet

You can also include media-specific styles directly inside a style sheet using the `@media` directive. You've already seen the `@media` directive in Chapter 14, for creating media queries to target different features and settings of a web browser (such as screen width). You can use the `@media` directive to target different screens as well as printing. Maybe you want to add a couple of print-specific styles to an internal style sheet. Or perhaps you'd like to keep all your styles in a single external style sheet and just add a few printer-only styles. You can do so using the `@media` directive, like so:

```
@media print {  
    /* put your styles for the printer in here */  
}
```

Be careful to include that closing brace (on the last line), otherwise the directive won't work. Here's an example of using `@media` to include two printer-only styles:

```
@media print {
  h1 {
    font-size: 24pt;
  }

  p {
    font-size: 12pt;
  }
}
```

Technically, it doesn't really matter whether you put all styles in a single file and use the `@media` method or put media-specific styles in their own external style sheets (like `screen.css`, and `printer.css`). Putting all your printer-only styles in their own external style sheet named something like `printer.css` makes it a lot easier to find and edit styles for print only.

■ Creating Print Style Sheets

First, see how pages on your site print before embarking on a print-specific redesign. Often, all the information on a web page prints without problems, so you may not have to add a printer style sheet to your site. But in some cases, especially when using heavy doses of CSS, pages look awful printed. For example, since web browsers don't print background images unless instructed to, you might end up with large blank spaces where those background images were. But even if a page looks the same in print as it does on the screen, you have many ways to improve the quality of the printed version by adding custom printer-only styles (see Figure 16-2).




FIGURE 16-2
When printing a web page, you really don't need navigation links or information that's not related to the topic at hand. With a printer style sheet, you can eliminate sidebars, navigation bars, and other content designed for web browsing (left). The result is a simply formatted document—perfect for printing (right).

TIP

A quick way to see how a page will print without wasting a lot of paper and toner is to use your browser's Print Preview command. On Windows, this command is usually available from the browser's File→Print Preview menu. On a Mac, you usually first choose File→Print, and then click Preview in the window that appears. Using Print Preview, you can check to see whether a page is too wide to fit on one page and see where page breaks occur.

Using !important to Override Onscreen Styling

As mentioned earlier, it's often useful to create a style sheet without specifying a media type (or by using `media="all"`). When you're ready to define some print-specific rules, you can just create a separate style sheet to override any styles that don't look good in print.

Say you've got an `<h1>` tag that's styled to appear blue onscreen, and you've also chosen rules controlling letter spacing, font weight, and text alignment. If the only thing you want to change for your printed pages is to use black rather than blue, then you don't need to create a new style with a whole new set of properties. Just create a main style sheet that applies in both cases and a print style sheet that overrides the blue color for the `<h1>` tag.

One problem with this approach is that you need to make sure the printer styles actually *do* override the main style sheet. To do this successfully, you have to carefully manage the *cascade*. As discussed in Chapter 5, styles can interact in complex ways: Several styles may apply to the same element, and those styles' CSS properties can merge and override each other. There's a surefire way to make sure one property trumps all others—the `!important` declaration.

When you add `!important` after the value in a CSS declaration, that particular property overrides any conflicts with other styles. Add this rule to a print style sheet to ensure that all `<h1>` tags print in black:

```
h1 {  
    color: #000 !important ;  
}
```

This `h1` style overrides even more specific styles, including `#main h1`, `h1.title`, or `#wrapper #main h1` from the main style sheet.

Reworking Text Styles

You may not necessarily want to have text look the same onscreen as it does in print. A good place to start when creating a printer style sheet is by modifying the `font-size` and `color` properties. Using pixel sizes for text doesn't mean much to a printer. And while bright green text may look good onscreen, it may come out a difficult-to-read pale gray when printed.

Pixels and ems (page 158) make sense for onscreen text, but the measurement of choice for printing is *points*. Points are how Word and other programs measure font sizes, and they're what printers expect. In practice, most web browsers translate pixel and ems to something more printer friendly anyway. The base onscreen font

size for most browsers—16 pixels—prints out as 12 points. But there’s no consistent way to predict how every browser will resize text, so for maximum printing control, set the font size specifically to points in your print style sheets.

To make all paragraphs print in 12-point type (a common size for printing), use the following rule:

```
p {  
  font-size: 12pt;  
}
```

NOTE As with ems, you don’t add an “s” when setting the font to a point size: 12pt not 12pts.

Likewise, screen colors don’t often translate well when printed in black-and-white on a laser or inkjet printer. Crisp black text on white paper is much easier to read, for instance, than light gray letters. What’s more, as you’ll see in the next section, white text on a black background, although very legible onscreen, often doesn’t print well. To make text most readable on paper, it’s a good idea to make all text print black. To make all paragraph text black, add this style to your print style sheet:

```
p {  
  color: #000;  
}
```

As mentioned on the previous page, if your print style sheet competes with styles from another attached style sheet, then use `!important` to make sure your printer styles win:

```
p {  
  font-size: 12pt !important;  
  color: #000 !important;  
}
```

To make sure *all* text on a page prints black, use the universal selector (page 63) and `!important` to create a single style that formats every tag with black text:

```
* { color: #000 !important; }
```

Of course, this advice applies only if your site is printed out in black and white. If you think most visitors to your site use color printers, then you may want to leave all the text color in or change the colors to be even more vibrant when printed.

Styling Backgrounds for Print

Adding background images and colors to navigation buttons, sidebars, and other page elements adds contrast and visual appeal to your web pages. But you can’t be sure if the background will come through when those pages are printed. Because colored backgrounds eat up printer ink and toner, most web browsers don’t normally print them, and most web surfers don’t turn on backgrounds for printing even if their browser has this feature.

In addition, even if the background does print, it may compete with any text that overlaps it. This is especially true if the text contrasts strongly with a colorful background on a monitor but blends into the background when printed on a black-and-white printer.

NOTE

White text on a black background used to pose the biggest problem—your visitor would end up with a blank white page. Fortunately, most current web browsers have the smarts to change white text to black (or gray) when printing without backgrounds.

REMOVING BACKGROUND ELEMENTS

The easiest way to take care of backgrounds is to simply remove them in your print style sheet. Say you reverse out a headline so that the text is white and the background is a dark color. If the style that creates that effect is named `.headHighlight`, then duplicate the style name in your print-only style sheet, like this:

```
.headHighlight {  
  color: #000;  
  background: #FFF;  
}
```

This style sets the background to white—the color of the paper. In addition, to get crisp printed text, this style sets the font color to black.

GEM IN THE ROUGH**Two Birds with One Stone**

You can use the `background-color` property to set a background color to white like this: `background-color: white`. You get the same effect using the background shorthand method: `background: white`. Remember that the `background` property (page 255) can also specify a background image, how the image repeats, and its position.

But when you leave out any values using the shorthand method, the web browser resets to its normal value.

In other words, by omitting a background image value, the browser sets that value to its normal setting—none. So a declaration like `background: white`; not only sets the background color to white but also removes any background images. By using the background shorthand property, you kill two birds—setting a white background and removing images—with very little code.

■ LEAVING BACKGROUND ELEMENTS IN

If you don't want to get rid of the background, you can leave it in and hope that visitors set their browsers to print them. If you leave background elements in your print style sheet and text appears on top of them, then make sure the text is legible with the backgrounds on *and* off.

Another thing to consider when using background images: Do you *need* the image to print out? Say you place a company's logo as a background image of a `<div>` tag used for the banner of a page. Because the logo is in the background, it may not print. Your company or client may not be happy when every page printed from their site lacks a logo. In this case, you've got a few options. You can insert the logo as a regular `` tag instead of a background image. This technique works, but what if the logo looks great on a full-color monitor but no good at all when printed on a black-and-white printer? Another technique is to leave the logo in as a background image and add another, more printer-friendly logo using the `` tag. You then hide that `` tag onscreen but show the printer-friendly logo when printed. Here's how:

1. **Add the `` tag to your HTML in the spot where you want it to appear when printed:**

```

```

2. **Then, in the main style sheet (the one that applies when the page is displayed on screen), add a style that hides that image:**

```
.logo { display: none; }
```

3. **In the print style sheet, add one last style to display the image:**

```
.logo { display: inline; }
```

Now that logo won't appear on screen, but will when printed.

Hiding Unwanted Page Areas

Web pages are often loaded with informational and navigational aids like navigation bars, sidebars full of helpful links, search boxes, and so on. These elements are great for surfing the Web, but don't do much good on a piece of paper. Your web pages may also contain ads, movies, and other doodads that people don't like to waste expensive ink and toner on. You can do your visitors a favor by stripping these onscreen frills out of the content they really want to print.

POWER USERS' CLINIC

Revealing Links in Print

Imagine a coworker hands you a printout of a fascinating article she found on the Web. You're reading along and come to this passage: "And that's when I found the secret to eternal life *here*." The underline tells you there's a clickable link that reveals the secret. But on a piece of paper, of course, you have no way to follow where the link leads.

To prevent this conundrum on your own pages, you can make linked URLs print along with the rest of the text: "secret to eternal life here (http://www.pyramind_scam.com)." Using an advanced selector—`:after`—and an advanced CSS property called `content`, you can print text that doesn't appear onscreen at the end of a styled element. Unfortunately, the `:after` selector and `content` property trick doesn't work in Internet Explorer 7 or earlier. But it does work in Internet Explorer 8 (and later), Firefox, Safari, and Opera, so you can at least spell out URLs for the benefit of visitors using those browsers.

To do so, add a style to the print style sheet that prints the URL after each link.

You can even add other text items like parentheses to make it look better:

```
a:after {
  content: " (" attr(href) ") ";
}
```

However, this CSS doesn't distinguish between external or internal links, so it also prints unhelpful document-relative links to other pages on the same site: "Visit the home page (../index.html)." Using an advanced attribute selector (page 321), you can force the style to print only absolute URLs (the ones that begin with `http://`), like so:

```
a[href^="http://"]:after {
  content: " (" attr(href) ") ";
}
```

Fortunately, all browsers that understand the `:after` selector and `content` property understand this advanced attribute selector.

If you use root-relative links on your site, you can use another technique to print the correct, full URLs. See this article for more information: www.alistapart.com/articles/goingtoprint.

In addition, because some links can be really long, they may not fit on the printed page and be clipped at the paper's edge. To overcome this, you can use the `word-wrap` property to tell the browser to break links over multiple lines:

```
a {
  word-wrap: break-word;
}
```

Add the above style to your printer style sheet.

As you learned in the third part of this book, one way to lay out a page is to wrap `<div>` tags around different layout elements—banner, main navigation, content, copyright notice, and so on. By styling each `<div>` using floats or absolute positioning, you can place various page elements right where you want them. You can use that same structure to create a print-only style sheet that hides unwanted elements using the `display` property.

By setting the `display` value to `none`, you can make a web browser remove a styled element from a page. So to prevent a sidebar from printing, simply redefine that style in a print style sheet and set its `display` property to `none`:

```
.sidebar {
  display: none;
}
```

For most pages, you want the print style sheet to display only the most basic informational elements—like the logo, the main content, and a copyright notice—and hide everything else. You can easily hide multiple elements with a group selector, like so:

```
.banner, .mainNav, .sidebar, .ads, .newsLinks {  
    display: none;  
}
```

Remember, these styles go into your print style sheet, not the main style sheet. Otherwise, you'd never see the navigation, banner, or other important areas of your page onscreen. However, at times you might want to hide something from your main style sheet and reveal it only when printed.

Say you place your site's logo as a background image inside the banner area of a page. You may want to do this to have text or links appear on top of an empty area of the logo graphic. You (or your boss or client) certainly want the logo to appear on any printed pages, but since not all browsers print background images, you can't be sure the logo will appear when printed. One solution is to insert an `` tag containing a modified, printer-friendly version of the logo graphic; add a class to the image; create a class style in the main style sheet with the `display` property set to `none`; and then set the `display` property for the same class style in the print style sheet to `block`. Voilà! The logo appears only when the page is printed.

Adding Page Breaks for Printing

Version 2.1 of the Cascading Style Sheet standard includes many CSS properties aimed at better formatting a printed web page: from setting the orientation of the page to defining margins and paper size. (You can see the full list at www.w3.org/TR/CSS21/page.html.) Unfortunately, today's web browsers recognize very few of these print styles.

Two widely recognized properties are `page-break-before` and `page-break-after`. `Page-break before` tells a browser to insert a page break before a given style. Say you want certain headings to always appear at the top of a page, like titles for different sections of a long document (see Figure 16-3). You can add `page-break-before: always` to the style used to format those headings. Likewise, to make an element appear as the last item on a printed page, add `page-break-after: always` to that element's style.

The `page-break-before` property is also useful for large graphics, since some browsers let images print across two pages, making it a little tough to see the whole image at once. If you have one page with three paragraphs of text followed by the image, then the browser prints part of the image on one page and the other part on a second page. You don't want your visitors to need cellophane tape to piece your image back together, so use the `page-break-before` property to make the image print on a new page, where it all fits.

Here's a quick way to take advantage of these properties. Create two class styles named something like `.break_after` and `.break_before`, like so:

```
.break_before { page-break-before: always; }  
.break_after { page-break-after: always; }
```

You can then selectively apply these styles to the elements that should print at the top—or bottom—of a page. If you want a particular heading to print at the top of a page, then use a style like this: `<h1 class="break_before">`. Even if the element already has a class applied to it, you can add an additional class like this: `<h1 class="sectionTitle break_before">`.




FIGURE 16-3
Normally when printing a web page, a browser breaks the content into multiple pages to fit as much content on each page as possible (left). But if you want to put page breaks in more attractive and logical places, then use the page-break-before property (right).

Tutorial: Building a Print Style Sheet

In this tutorial, you'll create a print style sheet. To make the printed version of a web page look better, you'll add styles that remove unwanted page elements and backgrounds, change text formatting, and print the URLs attached to any links on the page.

To get started, download the tutorial files from this book's companion website at <http://www.sawmac.com/css3/>. Click the tutorial link, and then download the files. All of the files are in a zip archive, so you need to unzip them first. (You'll find detailed instructions on the website.) The files for this tutorial are in the `16` folder.

Remove Unneeded Page Elements

To get started, you first need to understand how the page is laid out so you can decide which elements you want printed.

1. Launch a web browser and open 16→print.html.

This web page is a float-based layout consisting of several `<div>` tags (see Figure 16-4). In all likelihood, anyone printing this page is most interested in the main content—the large central body of text. Printing the navigation bar and sidebar is just a waste of toner, so your print style sheet should hide these parts of the page.

2. In a text editor, create a new file named *print.css* and save it along with the main style sheet in the *css* folder inside the 16 folder.

In your new print style sheet, the first order of business is to hide the navigation bar and other parts of the page that you don't want to print.

3. Using the *display* property, create a new group selector that hides the navigation elements and sidebar, like so:

```
.sidebar, .navWrapper, .footerNav {  
  display: none;  
}
```

With the *display* property set to *none*, web browsers hide those elements so they won't print. But first you need to attach this external style sheet to your web page so browsers can find it.

4. In your text editor, open 16→print.html.

This page already has an attached style sheet—*main.css*. This external style sheet provides all of the formatting for the page when it's displayed in a browser. Also, since the style sheet is attached using the `<link>` tag with no media attribute specified, it applies when the page is printed as well. Your print style sheet, then, needs to override any styles from the *main.css* file that won't look good in print. The first step in that process is attaching the print style sheet after the *main.css* file in the html of this page.

5. Locate the `<link>` tag in the head of the page used to attach the *main.css* file. Insert a blank line after that tag, and then add the following:

```
<link href="css/print.css" rel="stylesheet" media="print">
```

If properties from two styles with the same name conflict, the properties from the style sheet last linked on the page wins, so this `<link>` must go *after* the other `<link>`. That way, if the *main.css* file has a class named `.copyright` that creates white, 10-pixel type on a black background, you can create another style named `.copyright` in the print style sheet with black, 12-point type on a white background. Even though the two styles share the same name, the properties from the print style sheet win because it's the last one linked. (See page 115 for more detail on this cascading rule.)




FIGURE 16-4
CSS layout lets you control the placement of elements on a page. When printing a page, some elements are better off not appearing at all. The banner, sidebar, and navigation elements don't add useful information to a printed document.

6. Save the *print.css* and *print.html* files, and then preview *print.html* in a web browser.

The page should look no different than it did in Step 1. That's because you haven't printed it yet. You can see the effect of the print style sheet by using your browser's Print Preview command.

7. If you're using Windows, choose File→Print Preview. Mac fans should choose File→Print, and then, in the Print window that appears, click the Preview button.

In the Print Preview window, you'll see that the right sidebar and navigation have disappeared. But the design still doesn't look that great. The main content doesn't fill the page as it should. You'll fix that—and a few other things—next.

Adjusting the Layout

Currently, the main content and the footer copyright notice don't fit the printed page correctly: The main content stops short of the right edge of the page, while the copyright is indented from the left edge. Both would look better if they filled the entire printable area.

Two styles are currently controlling the layout. In Figure 16-4, you can see that the page is divided into several areas, each created with a separate `<div>` tag. The `.mainWrapper` and `.footer` are both used to center and set a width of 900 pixels for the main content area and the footer area. In addition, the `.main` style has a set width, while the `.footerMain` style has a left margin. Since you don't know what size paper this page might be printed on, you should get rid of all widths and remove any margins.

1. **Return to your text editor and the `print.css` file.** Add one new group style to remove widths and margins of the areas of the page that will be printed:

```
.banner, .mainWrapper, .footer, .main {  
  width: auto;  
  margin: 0;  
  padding: 0;  
}
```

The first declaration—`width: auto`—affects several areas of the page. It overrides the 900-pixel width setting for the main text and footer in the `main.css` file and leaves the exact width up to the web browser. Auto simply lets the `<div>` fill the entire available width, so no matter the paper size—letter, A4, or whatever—the content fills the width of the printed page. The two other declarations, `margin` and `padding`, remove any space around these divs.

The copyright content, contained inside a `<div>` with the class `footerMain`, doesn't have a set width, but it does have a left margin—that indent will look strange when printed, so you should get rid of it.

2. **Add another style to the `print.css` style sheet:**

```
.footerMain {  
  margin: 0;  
}
```

While you've hidden the right sidebar, which is positioned using a float, the main content is still floated—it doesn't have to be for the printed page.

3. **Add another style to the `print.css` style sheet:**

```
.main {  
  float: none;  
}
```

Other problems can arise when printing a float-based layout. As described on page 428, floated elements can pop out of the bottom of their containers, preventing backgrounds and borders from showing properly. One solution: Add the declaration `overflow: hidden;` to the containing block's style. However, hiding overflowing content can sometimes cause printed material to not show up. So, you need to turn that off for two styles.

4. Add another style to the *print.css* style sheet:

```
.mainWrapper, .footer {  
    overflow: visible;  
}
```

This style ensures that content inside those two divs is fully displayed.

There are also a few background colors and images sprinkled throughout the page. Sometimes background images and colors print out, but often they don't. It all depends on the browser and the visitor's settings. Some browsers don't print background elements at all; others can print them but give folks the option of turning them on or off. Printing backgrounds is useful when it's important for the printed page to look just like the screen version. But when you have backgrounds that would only be a distraction and a waste of ink, do your visitors a favor and disable them.

5. Add another style to the *print.css* style sheet:

```
html, body, .banner, .footerWrapper {  
    background: #FFF;  
}
```

When viewed onscreen, this page has various background colors and images. The banner, for example, has a background image for the "About Us" tag and the footer area has a purple background color. This style sets the background color of the page and banner to white *and* removes the graphic. (See page 526 for the story on why the background image disappears as well.)

The banner area containing the site logo also doesn't look very good in print. That area is too tall, since it was expanded to hold a background image that won't appear in print. So you'll adjust the height—and while you're at it, you'll improve the overall look of this top section by centering the logo and adding lines above and below it.

6. Add a new style to the *print.css* file:

```
.banner {  
    height: auto;  
    text-align: center;  
    border-bottom: 2pt solid #000;  
    border-top: 2pt solid #000;  
    padding: 10pt 0;  
    margin-bottom: 15pt;  
}
```

The first property eliminates the height of the banner, letting it size itself based on the content of the `<div>`. In other words, it will just be as tall as the logo graphic inside it. The `text-align` property centers the logo for a refined, classic look. The border settings add lines above and below the logo, while the padding adds space between the logo and the borders. Note these styles use `pt` (points), since that's a more normal way of measuring items for print.

Feel free to save this file, preview the `print.html` file in a web browser, and use the Print Preview function to see how the printed version's coming along.

Reformatting the Text

While colored text and pixel-sized fonts may work on the screen, laser printers understand point sizes better. Also, solid black text looks better on white paper. In this section, you'll adjust the text accordingly to look better in print.

1. In the `print.css` file, add the following CSS rule:

```
* {  
  color: #000000 !important;  
}
```

This style is the CSS equivalent of a sledgehammer. It essentially tells every tag to use black text no matter what. The `*` (universal selector) is a quick way of specifying a style for every single element on a page, while the `!important` declaration cancels out any conflicts caused by the cascade. So even though `*` isn't a very specific style, the color property here trumps the same property in much more specific styles like `.main h1` or `.nav .mainNav a`.

Next you'll set new font sizes for the text.

2. Add the following three styles:

```
h1 {  
  font-size: 30pt !important;  
}  
  
h2 {  
  font-size: 16pt !important;  
}  
  
p, li {  
  font-size: 11pt !important;  
}
```

These styles make each of these tags use a more printer-friendly font size. The addition of `!important` makes these sizes always apply to those tags regardless of any style conflicts with the `main.css` style sheet.

NOTE In this case, `h1`, `h2`, `p`, and `li` are the only tags that print from the `print.html` page. Your pages may require you to redefine text sizes for other tags like `blockquote`, other headlines and so on.

Just for fun, add a couple of styles to change the font size of the copyright notice and add a borderline above it.

3. Add the following two styles:

```
.footerMain {
    margin-top: 15pt;
    border-top: 1pt solid #000;
    padding-top: 5pt;
}

.footerMain p {
    font-size: 9pt !important;
}
```

The CSS properties in these styles should all be old hat by now. They adjust space above the footer, add a borderline, add some space between the border and the copyright, and make the copyright notice text smaller. Notice the `!important` declaration in the `.footerMain p` style. You need to add this because the `p` style from Step 2 has `!important` as well. Because `.footerMain p` has greater specificity (see page 114 for more on this concept) than `p`, its `!important` declaration wins out.

Displaying URLs

For a final flourish, you'll add one more style that prints the URL next to the text of each link on the page. That way, the onscreen text "Click here to find out more" will print as "Click here to find out more (www.outmore.com)" so anyone reading the printed version can visit the site referenced by the link. This technique uses some advanced CSS that Internet Explorer 6 and 7 doesn't understand, but it doesn't do any harm in those browsers, either. And it *is* a great enhancement for visitors who print from your site with IE 8, 9, and 10, as well as Chrome, Firefox, and Safari.

1. Add one last style to the `print.css` style sheet:

```
a:after {
    content: " (" attr(href) ") ";
}
```

In the `content:` line, this style adds the URL (the `attr(href)` part) at the end of each link (the `a:after` part).

2. Save the `print.css` file.

In your browser, open `print.html` and print it.

The printed page should look something like Figure 16-5—a simple, barebones, just-the-facts page.

You'll find a completed version of the page in the `16_finished` folder.

The Design List

About The Design List

Ut labore et dolore magna aliqua. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Velit esse cillum dolore ullamco laboris nisi ut enim ad minim veniam.

Ut aliquip ex ea commodo consequat. Cupidatat non proident, sunt in culpa sed do eiusmod tempor incididunt. Excepteur sint occaecat mollit anim id est laborum. Ut labore et dolore magna aliqua. Quis nostrud exercitation velit esse cillum dolore ut enim ad minim veniam.

Related Sites

- **Print Magazine** (<http://www.printmag.com/>)
- **Communication Arts** (<http://www.commarks.com/>)
- **ATGA** (<http://www.aga.org/>)
- **Sawyer McFarland Media** (<http://www.sawmac.com/>)

Not Just Another Discussion

Ut labore et dolore magna aliqua. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Velit esse cillum dolore ullamco laboris nisi ut enim ad minim veniam.

Ut aliquip ex ea commodo consequat. Cupidatat non proident, sunt in culpa sed do eiusmod tempor incididunt. Excepteur sint occaecat mollit anim id est laborum. Ut labore et dolore magna aliqua. Quis nostrud exercitation velit esse cillum dolore ut enim ad minim veniam.

Could it Actually Be From Another Planet?

Ut labore et dolore magna aliqua. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Velit esse cillum dolore ullamco laboris nisi ut enim ad minim veniam.

Copyright 2010, The Design List

All rights, including photographic, polygraphic, and mineral are reserved. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Duis aute irure dolor mollit anim id est laborum. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Duis aute irure dolor mollit anim id est laborum. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Duis aute irure dolor mollit anim id est laborum. Sed do eiusmod tempor incididunt eu fugiat nulla pariatur. Duis aute irure dolor mollit anim id est laborum.

FIGURE 16-5

Its looks aren't much to write home about, but this page's simplicity makes it perfect for printing. It'll earn you the appreciation of visitors who are looking for a clean presentation of the facts, free from navigation buttons, ads, and ink-wasting background images.

Improving Your CSS Habits

At this point, this book has covered most aspects of Cascading Style Sheets. With the addition of CSS-based layout, which you learned about in Part Three, you're now an unstoppable web-designing machine. But even after you've mastered all the properties CSS offers, nailed those annoying browser bugs, and learned great tricks for producing beautiful web pages, you can still stand to learn a few techniques that'll make your CSS easier to create, use, and maintain.

This chapter covers some recommendations for creating and using CSS. None of them count as “must know” CSS essentials, but they can make your CSS work go faster, leading to less frustration and greater productivity.

■ Adding Comments

When it's time to edit a style sheet weeks, months, or even years after creating it, you may find yourself wondering, “Why did I create that style? What does it do?” As with any project, when you're building a website, you should keep notes of what you did and why. Fortunately, you don't need a pad of paper to do this. You can embed your notes right into your style sheets using CSS comments.

A CSS comment is simply a note contained within two sets of characters, `/*` and `*/`. As with HTML comments, CSS comments aren't read or acted on by a web browser, but they do let you add helpful reminders to your style sheets. You don't need to comment *everything* in your style sheets—after all, most properties like `color`, `font-family`, `border-color`, and so on are self-explanatory. But it's a good idea to add a comment for a style when it isn't immediately obvious what the style or property

does. For example, you might reset the CSS box model so that the width and height of an element is calculated with the border and padding taken into account:

```
* {
  -moz-box-sizing: border-box;
  box-sizing: border-box;
}
```

At the time you wrote the style, you knew what you were doing, but will you still remember three months later? Or, what if someone who's not familiar with this trick needs to edit your CSS at some point? Add a comment and it'll be easy for you or someone else who needs to work on the site to figure out what the style does and why it was created:

```
/* Reset box model sizing on all elements */
* {
  -moz-box-sizing: border-box;
  box-sizing: border-box;
}
```

If you have a lot to say, comments can span multiple lines as well. Just begin with `/*`, type all the comments you'd like, then end with `*/`. This is handy when adding background information at the beginning of a style sheet, as pictured in Figure 17-1.




FIGURE 17-1

CSS comments can help you identify your styles for later editing. You can also use them to provide helpful introductory information that lets you keep track of the version of the site or style sheets, add copyright information, and identify yourself as the CSS master behind it all.

■ Organizing Styles and Style Sheets

You've learned a lot in this book about creating styles and style sheets. But when you're designing a site that's meant to last, you can incorporate a few other steps to help you out in the future. The day will come when you need to change the look of the site, tweak a particular style, or hand off your hard work to someone else who'll be in charge. In addition to leaving notes for yourself and others, a little planning and organization within your CSS will make things go more smoothly down the road.

Name Styles Clearly

You've already learned the technical aspects of naming different types of selectors—class selectors begin with a `.` (period) to identify the styles as a class, and ID styles begin with the `#` symbol. In addition, the names you give IDs and classes must begin with a letter and can't contain symbols like `&`, `*`, or `!`. But beyond those requirements, following some rules of thumb can help you keep track of your styles and work more efficiently.

■ NAME STYLES BY PURPOSE NOT APPEARANCE

It's tempting to use a name like `.redhighlight` when creating a style to format eye-catching, fire-engine-red text. But what if you (or your boss or your client) decide that orange, blue, or chartreuse look better? Let's face it: a style named `.redhighlight` that's actually chartreuse is confusing. It's better to use a name that describes the *purpose* of the style. For example if that "red" highlight is intended to indicate an error that a visitor made while filling out a form, then use the name `.error`. When the style needs to alert the visitor of some important information, a name like `.alert` would work. Either way, changing the color or other formatting options of the style won't cause confusion because the style's still intended to point out an error or alert the visitor—regardless of its color.

Likewise, avoid names that provide exact sizes, like `.font20px`. While that font may be 20 pixels today, maybe you'll make it 24 pixels tomorrow, or switch from pixels to ems or percentages. Using a tag selector may be a better route: Apply the font size to an `h2` or `p` tag or even a descendent selector like `.sidebar1 p`.

■ DON'T USE NAMES BASED ON POSITION

For the same reason you avoid naming styles by appearance, you should avoid naming them by position. Sometimes a name like `.leftSidebar` seems like an obvious choice—"I want all this stuff in a box placed at the left edge of the page!" But it's possible that you (or someone else) will want the left sidebar moved to the right, top, or even bottom of the page. All of a sudden, the name `.leftSidebar` makes no sense at all. A name more appropriate to the purpose of that sidebar—like `.news`, `.events`, `.secondaryContent`, `.mainNav`—serves to identify the sidebar no matter where it gets moved. The names you've seen so far in this book—`.gallery`, `.figure`, `.banner`, `.wrapper`, and so on—follow this convention.

The temptation is to use names like `.header` and `.footer` (for elements that always appear at the top or bottom of the page, for example) since they're so easily understood, but you can often find names that are better at identifying the content of an element—for example, `.branding` instead of `.header`. On the other hand, sometimes using a name with position information does make sense. For example, say you wanted to create two styles, one for floating an image to the left side of a page and another for floating an image to the right side. Since these styles exist solely to place an image to the left or right, using that information in the style names makes sense. So `.floatLeft` and `.floatRight` are perfectly legitimate names.

■ AVOID CRYPTIC NAMES

Names like `.s`, `.s1`, and `.s2` may save you a few keystrokes and make your files a bit smaller, but they can cause trouble when you need to update your site. You could end up scratching your head, wondering what all those weird styles are for. Be succinct, but clear: `.sidebar`, `.copyright`, and `.banner` don't take all that much typing, and their purpose is immediately obvious.

NOTE

You can also learn a lot from checking out the naming conventions used on other sites. The web inspector built into most browsers gives you a quick way to reveal style names.

Use Multiple Classes to Save Time

Often, two or more items on a web page share many similar formatting properties. You may want to use the same border styles to create a frame around a bunch of images on a page, but there may be some formatting differences between those items as well. Maybe you want some images to float to the left and have a right margin, while some photos float to the right and have a left margin (Figure 17-2).

The most obvious solution is to create two class styles, each having the same border properties but different float and margin properties. You then apply one class to the images that should float left and another to the images that should float right. But what if you need to update the border style for all of these images? You'll need to edit *two* styles, and if you forget one, the images on one side of the page will all have the wrong frames!

POWER USERS' CLINIC

CSS Preprocessors

If getting things done efficiently and quickly is your thing, then take a look at CSS preprocessors. A *preprocessor* is a tool that takes some code and processes it into a final product. In the case of CSS, a preprocessor lets you write CSS in a kind of shorthand version and then process it into a finalized CSS file that you put on your web server.

CSS preprocessors have quite a few benefits.

- **CSS variables.** Preprocessors let you define a variable—a kind of placeholder for information—and use it as a value in your CSS. For example, say you have a blue color that you want to use throughout your site. Normally, you'd add the color in your CSS as a hex or RGB value. When you want to change that color, you have to find every instance of the hex value and change it. With a preprocessor, you can define that color once, at the beginning of the style sheet. If you want to change the color, just change the variable, and the color is updated throughout the style sheet.
- **CSS3 the easy way.** As you read earlier, you often need to use vendor prefixes when adding newer CSS properties. This often involves writing four or more lines of code for a single property like a `linear-gradient`. Most CSS preprocessors can write the code for you. You usually just need to write the normal CSS property—`background-image: linear-gradient(red, blue);`. The preprocessor then adds all the additional code to work different browsers.
- **Combining style sheets and minifying files.** As you'll read on page 546, it's often convenient to break your CSS up

into multiple style sheets. This keeps your CSS in separate, manageable files of related styles. However, from a web server performance perspective, it's best to send as few files as possible. CSS preprocessors let you keep your CSS in different files, but then can combine them into a single external style sheet that your web pages can use. What's more, you can strip out extraneous space, CSS comments, and other characters that aren't needed to make your CSS work and add unwanted size to your CSS files.

The two most common CSS preprocessors are LESS (<http://lesscss.org>) and SASS (<http://sass-lang.com>). There are two drawbacks to using these. First, they assume that you already have a really good understanding of CSS. If you're not perfectly comfortable with selectors and CSS properties, learning the sometimes strange syntax of LESS and SASS will probably only confuse you.

Second, both require some elaborate setup on your computer. They're basically small computer programs that run in the background performing their processing tasks. However, you can overcome this limitation by using a standalone program like the free Scout (<http://mhs.github.com/scout-app/>) or the commercial Compass.app (<http://compass.handlino.com>). They both run on Windows and Mac and can convert LESS and SASS files to regular old external style sheets.



FIGURE 17-2
The two photos pictured here have the same class style applied to them. This style provides the border around the image. In addition, the left image has a class style that merely floats the image left, whereas the right image has a different class that floats it to the right. In other words, each image has two classes applied to it.

There's a trick that works in all browsers that not all designers take advantage of—*multiple classes* applied to the same tag. This just means that when you use the class attribute for a tag, you add two (or more) class names like this: `<div class="note alert">`. In this example, the `<div>` tag receives formatting instructions from both the `.note` style and the `.alert` style.

Say you want to use the same border style for a group of images, but some of the images you want floating left and others you want floating right. You'd approach the problem like this:

- 1. Create a class style that includes the formatting properties shared by all the images.**

This style could be called `.imgFrame` and have a 2-pixel, solid black border around all four edges.

- 2. Create two additional class styles, one for the left floated images and another for the right floated images.**

For example, `.floatLeft` and `.floatRight`. One style would include properties unique to one set of images (floated left with a small right margin), while the other style includes properties specific to the second group of images.

3. Apply both classes to each tag, like so:

```

```

or

```

```

At this point, two classes apply to each tag, and the web browser combines the style information for each class to format the tag. Now if you want to change the border style, then simply edit one style—.imgFrame—to update the borders around both the left and right floated images.

NOTE

You can list more than two classes with this method; just make sure to add a space between each class name.

This technique is useful when you need to tweak only a couple of properties of one element, while leaving other similarly formatted items unchanged. You may want a generic sidebar design that floats a sidebar to the right, adds creative background images, and includes carefully styled typography. You can use this style throughout your site, but the width of that sidebar varies in several instances. Perhaps it's 33 percent wide on some pages and 25 percent wide on others. In this case, create a single class style (like `.sidebar`) with the basic sidebar formatting and separate classes for defining just the width of the sidebar—for example, `.w33per` and `.w25per`. Then apply two classes to each sidebar: `<div class="sidebar w33per">`.

Organize Styles by Grouping

Adding one style after another is a common way to build a style sheet. But after a while, what was once a simple collection of five styles has ballooned into a massive 500-style CSS file. At that point, quickly finding the one style you need to change is like looking for a needle in a haystack. (Of course, haystacks don't have a Find command, but you get the point.) If you organize your styles from the get-go, you'll make your life a lot easier in the long run. There are no hard and fast rules for *how* to group styles together, but here are two common methods:

- **Group styles that apply to related parts of a page.** Group all the rules that apply to text, graphics, and links in the banner of a page in one place. Then group the rules that style the main navigation in another, and the styles for the main content in yet another.
- **Group styles with a related purpose.** Put all the styles for layout in one group, the styles for typography in another, the styles for links in yet another group, and so on.

■ USING COMMENTS TO SEPARATE STYLE GROUPS

Whichever approach you take, make sure to use CSS comments to introduce each grouping of styles. Say you collected all the styles that control the layout of your pages into one place in a style sheet. Introduce that collection with a comment like this:

```
/* *** Layout *** */
```

or

```
/* -----  
                Layout  
----- */
```

As long as you begin with `/*` and end with `*/`, you can use whatever frilly combination of asterisks, dashes, or symbols you'd like to help make those comments easy to spot. You'll find as many variations on this as there are web designers. If you're looking for inspiration, then check out how these sites comment their style sheets: www.wired.com, www.mezzoblue.com, and <http://keikibulls.com>.

TIP For a method of naming comments that makes it easy to find a particular section of a style sheet you're editing, check out www.stopdesign.com/log/2005/05/03/css-tip-flags.html.

Using Multiple Style Sheets

As you read in Chapter 16, you can create different style sheets for different types of displays—maybe one for a screen and another for a printer. But you may also want to have multiple onscreen style sheets, purely for organizational purposes. This takes the basic concept from the previous section—grouping related styles—one step further. When a style sheet becomes so big that it's difficult to find and edit styles, it may be time to create separate style sheets that each serve an individual function. You can put styles used to format forms in one style sheet, styles used for layout in another, styles that determine the color of things in a third, another style sheet for keeping your Internet Explorer hacks, and so on. Keep the number of separate files reasonable since having, say, 30 external CSS files to weed through may not save time at all. In addition, the more external CSS files, the more requests your web server has to answer. That's one source for slower website performance.


At first glance, it may seem like you'll end up with more code in each web page, since you'll have that many more external style sheets to link to or import—one line of code for each file. Ah, but there's a better approach: Create a single external style sheet that uses the `@import` directive to include multiple style sheets. Figure 17-3 illustrates the concept.

Here's how to set up this type of arrangement:

- 1. Create external style sheets to format the different types of elements of your site.**

For example, a *color.css* file with styles that control the color of the site, a *forms.css* file that controls form formatting, a *layout.css* file for layout control, and a *main.css* file that covers everything else (see the right side of Figure 17-3).

NOTE These suggestions are just a few possibilities. Organize your styles and style sheets in whatever way seems most logical and works best for you. For more suggestions, check out this article on modular CSS design: www.contentwithstyle.co.uk/content/modular-css.



2. Create an external style sheet and import each of the style sheets you created in Step 1.

You can name this file *base.css*, *global.css*, *site.css*, or something generic like that. This CSS file won't contain any rules. Instead use the `@import` directive to attach the other style sheets like this:

```
@import url(main.css);  
@import url(layout.css);  
@import url(color.css);  
@import url(forms.css);
```

That's the only code that needs to be in the file, though you may add some comments with a version number, site name, and so on to help identify this file.

NOTE For a better way to attach an "IE-only" style sheet, see page 559.

3. Finally, attach the style sheet from Step 2 to the HTML pages of your site using either the `<link>` tag or the `@import` method. (See page 42 for more on using these methods.) For example:

```
<link rel="stylesheet" href="base.css">
```

Now, when a web page loads, the browser loads *base.css*, which in turn tells the browser to load the four other style sheets.

It may feel like there's a whole lot of loading going on here, but once the browser has downloaded those files and stored them in its cache, it won't have to retrieve them over the Internet again. (See the box on the next page.)

There's another benefit to using a single external style sheet to load several other style sheets: If you decide later to further divide your styles into additional styles sheets, then you won't have to muck around with the HTML of your site. Instead, just add one more `@import` directive to that gatekeeper style sheet (see Step 2). If you decide to take all the styles related to type out of the `main.css` file and put them in their own `type.css` file, then you won't need to touch the web pages on your site. Simply open the style sheet with all of the `@import` directives in it and add one more: `@import url(type.css)`.

This arrangement also lets you have some fun with your site by swapping in different style sheets for temporary design changes. Say you decide to change the color of your site for the day, month, or season. If you've already put the main color-defining styles into a separate `color.css` file, then you can create another file (like `summer_fun.css`) with a different set of colors. Then, in the gatekeeper file, change the `@import` directive for the `color.css` file to load the new color style file (for example, `@import url(summer_fun.css)`).


■ Eliminating Browser Style Interference

When you view a web page that hasn't been "CSS-ified" in a web browser, you can see that HTML tags already have some minimal formatting: headings are bold, the `<h1>` tag is bigger than other text, links are underlined and blue, and so on. In some cases, different web browsers apply slightly different formatting to each of these elements. You may experience some frustrating "it *almost* looks the same in Internet Explorer and Firefox and Safari" moments.

As discussed on page 115, to deal with these browser differences, it's a good idea to "zero out" the formatting for commonly used tags so your audience can see the beautiful styling you worked so hard to create (see Figure 17-4). All you have to do is set up some basic styles at the beginning of your style sheet that remove the offensive formatting.

Here are some things you may want to do to make browsers stop meddling with your designs:

- **Remove padding and margins.** Browsers add top and bottom margins to most block-level elements—the familiar space that appears between `<p>` tags, for example. This can cause some weird display issues like when the exact margin amount is inconsistently applied across browsers. A better approach is to remove padding and margins from the block-level tags you use, and then purposely add the amount you want by creating new styles.



- **Apply consistent font sizes.** While text inside a `<p>` tag is displayed as 1 em, web browsers apply different sizes to other tags. You can force all tags to be 1 em to begin with, and then create additional styles with specific font sizes for the different tags. That way, you stand a much better chance of getting consistent font sizes across browsers.
- **Make sure HTML5 elements are displayed as blocks.** New HTML5 elements like `article`, `aside`, and `section` are block-level elements like headlines and `div`s. However, browsers that don't understand these elements won't necessarily display them as blocks. It's a good idea to add `display: block` for those elements. In addition, use the HTML5 shiv (<http://code.google.com/p/html5shiv/>) as described in the box on page 24, to get IE 8 and earlier to understand any CSS applied to HTML5 tags.

POWER USERS' CLINIC

A Pain in the Cache

The web browser's cache is usually every website owner's friend. As discussed on page 39, the cache makes sure frequent visitors to your site don't have to download the same file over and over again, which would slow down their experience and increase your web hosting bills. However, the cache can be a pain when it's time to update your site's appearance. For example, if all of the pages in your site reference an external style sheet named *main.css*, then visitors to your site will cache that file. However, when you update that file with all new styles and a completely new look and feel for your site, previous visitors to your site may continue to access the old style sheet from their hard drive instead of the new *main.css* file you've updated.

Eventually, a visitor's cache will clear and they'll get the new CSS file, but you have one simple way to defeat the cache—by updating the `<link>` tag on each HTML page. Normally a `<link>` tag to an external style sheet looks like this:

```
<link rel="stylesheet" href="main.css">
```

However, if you add a query string after the name of the *.css* file (for example, *main.css?v=1*), then a web browser will see the file as *main.css?v=1* and not just *main.css*. If you change the number after the *v=* whenever you change the external style sheet, then browsers consider that a new file

and will download the external style sheet from the web server instead of using the cached site.

For example, suppose when you launch your site, the *main.css* file is the first version of the site's CSS. You can then use this link:

```
<link rel="stylesheet" href="main.  
css?v=1">
```

Then when you update the *main.css* file, you change the `<link>` to this:

```
<link rel="stylesheet" type="text/css"  
href="main.css?v=2">
```

The web browser considers this different from the cached version of the *main.css* file and downloads the file from the web server. In reality, the *?v=1* doesn't do anything—it doesn't affect how your web server works, for example. It's a way of telling a web browser to redownload the file.

The downside of this technique is that you must update the `<link>` tag for every HTML file on your site. If you're comfortable with PHP, there's a more automated way to handle this problem: <http://ikeif.net/2009/03/27/stop-caching-files-php-function>.

- **Set a consistent line height.** Browsers can have subtle differences in the line height (page 167) values they use by default. By setting a multiplier on the `<body>` tag—`body { line-height: 1.2; }`—you make sure that browsers apply the same line height. The 1.2 value is equivalent to 120 percent of the tag's text size. You can, of course, change this value to match your design sense.
- **Improve table borders and create consistent table cells.** As you read on page 380, applying a border to a table cell usually creates an unpleasant gap between cell borders and doubles up the borders between cells. You should get rid of both the space and the extra borders. In addition, the `<th>` and `<td>` tag are given different alignments and font weights.

- **Remove borders from linked images.** Some browsers add a colored border around any image inside of a link. If you're like most people, you find this border both unattractive and unnecessary. Remove it and start fresh.
- **Set consistent list indents and bullet types.** Different browsers indent bulleted and numbered lists in different ways, and you'll even find the type of bullet used can vary between browsers. It's good to set a consistent indent and bullet type.
- **Remove quote marks from quoted material.** If you ever use the <q> tag to identify a quote (<q>To err is human</q> for example), then you may have noticed that some browsers (Firefox, Safari) automatically add quote marks (' ') around the quote and some (Internet Explorer 6 and 7) don't. And even within the browsers that do add quote marks, the type of mark added varies; for example, IE 8 inserts single quotes (' '), while Firefox adds double quotes (" "). For a consistent presentation, it's best to remove these quote marks.

To put these ideas into action, here are a few basic styles you can add at the beginning of your style sheet:

```
/* reset browser styles */

html, body, div, span, object, iframe, h1, h2, h3, h4, h5, h6, p, blockquote,
pre, a, abbr, acronym, address, big, cite, code, del, dfn, em, img, ins, kbd,
q, s, samp, small, strike, strong, sub, sup, tt, var, b, u, i, center, dl, dt,
dd, ol, ul, li, fieldset, form, label, legend,

table, caption, tbody, tfoot, thead, tr, th, td, article, aside, canvas, de-
tails, embed,

figure, figcaption, footer, header, hgroup, menu, nav, output, ruby, section,
summary,

time, mark, audio, video {
    margin: 0;
    padding: 0;
    border: 0;
    font-size: 100%;
    vertical-align: baseline;
}

article, aside, details, figcaption, figure, footer, header, hgroup, menu,
nav, section {
    display: block;
}

body {
    line-height: 1.2;
}

table {
    border-collapse: collapse;
```

```
        border-spacing: 0;
    }

    ol {
        padding-left: 1.4em;
        list-style: decimal;
    }

    ul {
        padding-left: 1.4em;
        list-style: square;
    }

    blockquote, q {
        quotes: none;
    }

    blockquote:before, blockquote:after,
    q:before, q:after {
        content: '';
        content: none;
    }

    /* end reset browser styles */
```

The first two styles here are group selectors that apply the same formatting to every one of the tags listed. Add these styles to the beginning of your style sheet, and then, further down the style sheet, override them on a case-by-case basis. After zeroing out the margins and font size for the `<h1>` tag, you may want to give the `<h1>` tag a specific top margin value and font size. Just add another style, like so:

```
h1 {
    margin-top: 5px;
    font-size: 2.5em;
}
```

Thanks to the cascade (see Chapter 5), as long as this `h1` style appears in the style sheet *after* the group selector (the reset style that removes the margins and changes the font size), the new values take precedence.

You'll find the file `reset.css` in the `17` folder inside the `tutorials` folder. Just copy the code from that file into your own style sheets.

NOTE

Some designers take a different approach to the problem of inconsistent browser styles. The Normalize.css project (<http://nicolasgallagher.com/about-normalize-css/>) aims to provide consistent baseline styles while still retaining the basic differences in HTML tags. For example, instead of making headlines and paragraphs the same size, Normalize.css keeps headlines at varying sizes. It also includes many other styles aimed at fixing bugs present in some browsers.

Using Descendent Selectors

Classes and IDs are great for marking specific tags for styling. For example, you can add a class to a paragraph—`<p class="intro">`—and pinpoint just that one paragraph with its own look as determined by the `.intro` class style. Trouble is, it's so easy to add a class or ID to a tag, lots of designers tend to add classes and IDs to *everything* (well, almost everything). The pros even have a diagnosis for this disease—*classitis*. Adding a class to every tag is not only a waste of your time, it also makes your HTML slower to download. Most important, there's a better way to exert pinpoint control over your tags without resorting to too many classes or IDs—descendent selectors.

Descendent selectors are a powerful tool for efficient website building. As discussed in Chapter 3, they let you pinpoint the tags you want to style with greater accuracy than tag styles, with less work than class styles. Most of the time you want to format *all* the links in a navigation bar the same way, but that doesn't mean you want to format all of the links in the entire *page* the same way. What you need is a way to say (in CSS), "Format *only* the links in the nav bar this way"—without having to apply a class style to each of those links. In other words, you need the ability to format the same HTML in different ways depending on where it's located—and that's exactly what descendent selectors offer (see Figure 17-5).




FIGURE 17-5

The same HTML was pasted into both the left sidebar and the larger right area of this web page. By using descendent selectors, identical HTML tags (<h1>, <p>, , and) are formatted differently based solely on where they're located on the page.

Compartmentalize Your Pages

One of your biggest allies in using descendent selectors effectively is the `<div>` tag. Since this HTML tag lets you create logical *divisions* in a page, you can use it to identify different layout elements like a banner, a sidebar, a column of text, and so on. As discussed on page 408, you can organize the content of your page into different areas by wrapping HTML in a `<div>` tag.

Group the title of a story and a list of links used to navigate the story's pages like this:

```
<div>
  <h2>The CosmoFarmer Revolution</h2>
  <ul>
    <li><a href="page1.html">Page 1</a></li>
    <li><a href="page2.html">Page 2</a></li>
    <li><a href="page3.html">Page 3</a></li>
  </ul></div>
```

After adding the `<div>`, identify it for CSS purposes with a `class` attribute: `<div class="pullQuote">`. When you want to include the same type of layout element more than once on a page—multiple pull quotes in a single story perhaps—use a class.

Suppose the list of links in the HTML above appears twice on a page—at the beginning of the text and at the end. You'd apply a class to it like this:

```
<div class="storyNav">
  <h2>The CosmoFarmer Revolution</h2>
  <ul>
    <li><a href="page1.html">Page 1</a></li>
    <li><a href="page2.html">Page 2</a></li>
    <li><a href="page3.html">Page 3</a></li>
  </ul>
</div>
```

NOTE You don't always need to add a `<div>` tag to style a group of elements. If the preceding HTML had only an unordered list of links and didn't include the `<h2>` tag, then you could just as easily skip the `<div>` tag and simply add a class to the unordered list: `<ul class="storyNav">`. You could also wrap the `` tag in the HTML5 `<nav>` tag and apply the class to it.

Once you identify each `<div>` on a page, it becomes very easy to use a descendent selector to target tags inside a particular `<div>`. Say you want to create a unique look for each of the links in the above HTML. You'd create a descendent selector like this:

```
.storyNav a {
  color: red;
  background-color: #ccc;
}
```

Now links will appear as red text on a light gray background, but *only* when they appear *inside* another tag with the `storyNav` class applied to it. Best of all, if you want to add another link (like `page4.html`) to this list, then you don't have to lift a finger to format it like the other links. The browser handles all of that automatically when it applies the descendent selector.

Formatting other tags inside that `<div>` is a simple matter of creating a descendent selector that begins with the class name—`.storyNav`, for instance—followed by a space and the tag you want to style. To format the `<h2>` that appears inside the `<div>`, create the descendent selector `.storyNav h2`.

Identify the Body

Because descendent selectors provide such specific targeting of styles, you can easily create styles that not only apply to one particular area of a page, but also apply only to particular *types* of pages on your site. Say you want to style the `<h1>` tag differently on the home page than on other pages of the site. An easy way to distinguish `<h1>` tags on the home page is to add a class to the `<body>` tag of the home page:

```
<body class="home">
```

You can style the `<h1>` tag on the home page using a descendent selector: `.home h1`. With this technique, you can create entirely different looks for any tag on any particular page of your site (see Figure 17-6). One approach is to identify the section of the site each page is in. Say your site is divided into four sections—news, events, articles, and links. On each page within a section, add either a class or ID to the `<body>` tag. So each page in the news section might have the following HTML: `<body class="news">`, while pages in the events section would have `<body class="events">`.

NOTE Another common CSS technique is to use a class to identify the type of layout you want for a particular page (like a one-, two-, or three-column design).

One great use for identifying a page's section in the site is to highlight that section's button in a navigation bar. The highlighted button acts as a kind of "you are here" marker, as shown in Figure 17-6. If a page is in the news section of your site, you can highlight the "news" button so visitors can tell immediately which section they're in.

Here's how to format a navigation button differently depending on which section of your site it's in:

- 1. Add a class to the `<body>` tag indicating the section the page is in.**

For example, `<body class="home">`. Do the same thing for each section, so pages in the news section of the site would have code like this: `<body class="news">`.

- 2. Add a navigation bar to the page.**

Step-by-step instructions are on page 303.

3. Identify each link within the navigation bar.

For a link to the home page, you might have this code: `Home`. The class lets you identify that particular link as the one going to the home page. Repeat for the other links: `News` and so on.

At this point, you have enough information in your HTML to uniquely format each section's link using CSS. In this example, you know that the Home page link is nested inside a `<body>` tag with the class of *home* only on the Home page.

4. Create a descendent selector to format each section's link differently when the link is inside a page for that section.

For the home page in this example, the descendent selector would look like this:

```
.home .homeLink
```



This selector formats the `.homeLink` only when it's inside another tag with the ID `#home`. In most cases, you'll want the look of the “you are here” button to be the same for each section of the site, so you can use a group selector (page 62) to group all the descendent selectors for each section's button. That way, you can apply the same formatting to each button without creating separate rules for each button. A group selector to highlight the current section's navigation button with a light yellow background may look like this:

```
.home .homeLink,  
.news .newsLink,  
.articles .articlesLink,  
.links .linksLink {  
  background-color: #FBF9F9;  
}
```

TIP When creating a group selector that includes several descendent selectors, keep each selector on its own line as in this example. This way, it's easier to identify each selector in the group when you need to go back and edit your style sheet.

Using the same technique, make additional styles to apply different looks for the links when you hover over them, click them, or when they've been visited. See page 68 for the details.

These few examples are just some of the ways you can take advantage of descendent selectors. They can make your style sheets a little more complex. You'll have styles like `.home .navbar a`, for example, instead of a simple class like `.navLink`. But once the styles are set up, you'll need to do very little further formatting. HTML pasted into different areas of the page automatically gets formatted in strikingly different ways. Almost like magic.

POWER USERS' CLINIC

Object Oriented CSS

Object Oriented CSS is another approach to organizing and using CSS. The term was coined by CSS expert Nicole Sullivan and the approach was developed to respond to the complexity of very large sites with a wide variety of HTML structures. On large sites, you might end up having really different HTML containing similar types of information.

For example, in one case you might use a bulleted list to display a name, info, and photo for a list of contacts. But on another page you might use the `<article>` tag for each contact. Say you wanted to format those elements similarly because they really are the same type of information. If you use CSS styles that depend on that HTML, you could end up with either duplicate styles or group selectors like this:

```
article img, li img {
    /* formatting info here */
}
```

Object Oriented CSS recommends abandoning any CSS that's tied to actual HTML elements and instead use classes. In other words, you'd apply class names throughout your HTML and then use CSS class styles to format them. In this way it doesn't

matter what HTML tags you use. As long as they use the same classes, they'll look the same.

This may sound a lot like the “classitis” problem described on page 111, and in a sense, it is. Object Oriented CSS does require adding lots of class attributes to your HTML. If you're using a content management system like WordPress, then this might not be much work—you can add the class names into the template files. But if you're building every page by hand, this approach could add a lot of work.

For a quick introduction to Object Oriented CSS, read <http://coding.smashingmagazine.com/2011/12/12/an-introduction-to-object-oriented-css-ooCSS/>. You can find the OOCSS project at <https://github.com/stubbornella/ooCSS>.

Another related approach from Jonathon Snook, called Scalable and Modular Architecture for CSS (or SMACSS), is a simpler style guide for creating reusable CSS components. You can read more about it at <http://smacss.com>. You can also find a bunch of videos discussing SMACSS at <http://tv.adobe.com/watch/adc-presents/smacss-introduction-to-a-scalable-and-modular-architecture-for-css/>.


■ Trying Different CSS for Internet Explorer

Browsers don't always behave the way you, or the rules of CSS, expect. Browsers like Safari, Firefox, and Internet Explorer 10 handle CSS quite well and display CSS-based web pages consistently and predictably. Getting your designs to work in Internet Explorer 7, 8, and even 9 for Windows can be more of a challenge. Although these browsers are old by today's standards, they still make up the majority of web browsers in use.

It's not uncommon to create styles that aim to fix just particular versions of Internet Explorer. The `zoom` property discussed on page 428, for example, solves some problems that plague IE 7 and earlier. Internet Explorer 8 and earlier don't understand how to properly format HTML5 tags. One solution is to send certain content like style sheets, JavaScript and even HTML to just Internet Explorer. In fact, you can target specific versions of Internet Explorer to send different code to each version.

You can collect IE-only styles in a single place by using Internet Explorer's *conditional comments* feature (Figure 17-7). This Microsoft invention provides a way of inserting HTML that only Internet Explorer understands. Other browsers simply see the code as an HTML comment and ignore it.

Conditional comments can even target different versions of IE. You can put all of your IE 7-only styles in a single external style sheet (like *IE7_styles.css*) and use a conditional comment to link it to IE 7 browsers only. This approach also makes it a snap to eliminate those styles when IE 7 finally goes the way of the dinosaurs. Just remove the external style sheet. Your non-IE visitors will benefit, too. When you use conditional comments, other browsers don't download those external style sheets at all. As a result, your site opens and runs faster for these lucky folks.



Here's the basic structure of a conditional comment:

```
<!--[if IE]>
Some HTML code that only applies to IE goes here.
<![endif]-->
```

The `<!--[if IE]>` is the *condition* itself. It translates to: “If this browser is Internet Explorer, then process the following HTML.” So any Internet Explorer browser acts on the HTML that comes after this line of code and stops when it gets to the `<![endif]-->` statement. In this way, you can add any HTML—text, images, styles, and even links to external style sheets—to Internet Explorer only.

NOTE Non-IE browsers simply view conditional statements as HTML comments and ignore them.

Targeting Different Versions of IE

Conditional comments also let you specify which *version* of Internet Explorer the style sheet applies to. Say you want to have a particular style sheet load only for Internet Explorer 7. Add the following conditional comment to your web page’s head:

```
<!--[if IE 7]>  
<link href="IE7_styles.css" rel="stylesheet" >  
<![endif]-->
```

Or, using the @import method:

```
<!--[if IE 7]>  
<style>  
@import url(IE7_styles.css)  
</style>  
<![endif]-->
```

This targets IE 7 in particular and won’t apply to any earlier version. However, you sometimes want to include other versions. For example, you might create a style sheet that applies to Internet Explorer 6, 7, and 8. In this case, you can use `lte`, which stands for “less than or equal to,” so `lte IE 8` means “if this browser is version 8 or earlier of Internet Explorer”:

```
<!--[if lte IE 8]>  
<link href="IE_styles.css" rel="stylesheet">  
<![endif]-->
```

Add any conditional comments *after* any other linked style sheets. Most IE hacks tend to redefine styles already present in the style sheet—styles that work for other browsers. And due to the nature of the cascade, rules defined later in a page can override earlier defined styles. To make sure your redefined IE-only styles successfully take hold in Internet Explorer, they should appear after any other style sheets attached to the page.

Here’s the code you might use to link: a style sheet for all browsers, a style sheet just for IE 8, and a style sheet for IE 7 and earlier:

```
<link href="global_styles.css" rel="stylesheet" type="text/css" />  
<!--[if IE 8]>  
<link href="IE8_styles.css" rel="stylesheet" type="text/css" />  
<![endif]-->  
<!--[if lte IE 7]>  
<link href="IE_old_styles.css" rel="stylesheet" type="text/css" />  
<![endif]-->
```

NOTE

For more information on Internet Explorer’s conditional comments, visit the source: [http://msdn.microsoft.com/en-us/library/ms537512\(VS.85\).aspx](http://msdn.microsoft.com/en-us/library/ms537512(VS.85).aspx).

Appendixes

APPENDIX A:
CSS Property Reference

APPENDIX B:
CSS Resources



CSS Property Reference

Mastering Cascading Style Sheets involves knowing how to use a large number of CSS properties that control the appearance of text, images, tables, and forms. To help you in your quest, this appendix gives you a summary of common properties and values you'll use to create your own styles. This list covers nearly all of the CSS 2.1 standard properties—the ones that most web browsers support—as well as a handful of the most useful and commonly supported CSS3 properties.

NOTE The latest CSS specification is really quite large. In fact, to better manage the growth of CSS, the W3C split CSS into many modules—each module describes a particular property or set of related properties. For full details straight from the horse's mouth, visit the latest CSS specifications from the World Wide Web Consortium at www.w3.org/Style/CSS/current-work.

■ CSS Values

Every CSS property has a corresponding value. The `color` property, which formats font color, requires a color value to specify which color you want to use. The property `color: #FFFFFF`; creates white text. Different properties require different types of values, but they come in four basic categories: colors, lengths and sizes, keywords, and URLs.

Colors

You can assign colors to many different properties, including those for font, background, and borders. CSS provides several different ways to specify color.

■ KEYWORDS

A web color keyword is simply the name of the color, like white or black. There are currently 17 recognized web color keywords: aqua, black, blue, fuchsia, gray, green, lime, maroon, navy, olive, orange, purple, red, silver, teal, white, and yellow. Some browsers accept more keywords, and CSS3 promises to offer many more in the future: for one example, RGBA color, see page 155. You can read a lot more about CSS3 at www.w3.org/TR/css3-color.

■ RGB VALUES

Computer monitors create colors using a mixture of red, green, and blue light. These RGB values can create (nearly) the full spectrum of color. Almost every design, illustration, and graphics program lets you specify colors, using RGB, so it's easy to transfer a color from one of those programs to a CSS property. CSS represents RGB values in several ways:

- **Hex values.** The method most commonly used on the Web for identifying color, hex color values consist of three two-character numbers in the hexadecimal (that is, base 16) system. #FF0033 represents an RGB value composed of red (FF, which equals 255 in normal, base 10 numbers), green (00), and blue (33). The # tells CSS to expect hex numbers ahead, and it's required. If you leave off the #, a web browser won't display the correct color.

TIP

If all three two-digit values are repeated pairs of digits, you can shorten the hex value by using just the first number of each pair. For example, #361 means the same thing as #336611.

- **RGB percentages.** You can also specify a color using percentage values, like this: `rgb(100%, 0%, 33%)`. You can get these numbers from image-editing and design programs that can define colors by using percentages (which is most of them).
- **Integer values.** Finally, you can use integer RGB values to specify a color. The format is similar to the percentage option, but you use a number from 0 to 255 to indicate each color: `rgb(255, 0, 33)`.
- **RGBA.** RGBA adds transparency to the mix. That is, you can make the color see-through so underlying background colors, images, or text show through. You add a value of 0 (completely invisible) to 1 (totally opaque) to the end of an RGB color. You can use either the percentage or decimal values for the colors, but only use decimal values for the transparency. For example, both of these creates a middle gray color that's 50 percent transparent:

```
rgba(50%,50%,50%,.5)
```

```
rgba(122,122,122,.5)
```


- **HSL stands for hue, saturation, and lightness (also sometimes labeled luminance).** It's yet another way to specify color. It's not supported by Internet Explorer 8 or earlier, but works in all other browsers. If you're used to RGB or Hex colors, you may find the HSL syntax is a bit unusual. Here's an example of a bright red color:

```
hsl(0, 100%, 50%);
```

The first number (*hue*) is a degree value from 0 to 360 representing the spectrum of colors in a color wheel, with 0 and 360 both representing red and 180 representing green. The second number is *saturation*, or how pure the color is, specified in a percentage from 0% (dull grey) to 100% (vibrant). The last value is *lightness* and it's also specified as a percentage from 0% (completely black) to 100% (completely white). As with RGB color, there is a version of HSL that supports transparency, called HSLA: `hsla(0, 100%, 50%, .5)`.

It doesn't matter which method you use—they all work. For consistency, you may want to pick one way of specifying RGB values and stick with it. However, using keywords like `white` and `black` can be quick and convenient. The Windows and Mac operating systems both have color pickers that let you find the perfect color from a palette of millions, and then show you the RGB value. Alternatively, you can use this free online color picker: www.ficml.org/jemimap/style/color/wheel.html. Or for more advanced color picking (including the ability to create and save a palette of colors), check out <http://kuler.adobe.com>.

Lengths and Sizes

CSS provides many different ways to measure the size of type, the width of a box, or the thickness of a borderline. To indicate type size, you can use inches, picas, points, centimeters, millimeters, em-heights, ex-heights, pixels, and percentages. However, even though there are a lot of options, most don't apply to the world of onscreen display, for reasons discussed on page 155. You really need to think about these three only—pixels, ems, and percentages.

■ PIXELS

A pixel is a single dot on a computer screen. Pixels give you a consistent method of identifying lengths and font sizes from computer to computer: 72 pixels on one monitor is 72 pixels on another monitor. That doesn't mean the actual, real-world length is the same for everyone, though. Since people set their monitors to different resolutions—800 x 600, 1024 x 768, 1600 x 1200, or whatever—72 pixels may take up 1 inch on one monitor, but only half an inch for someone else. Nevertheless, pixels give you the most consistent control over presentation.

NOTE There's just one drawback to using pixels: Folks using Internet Explorer 6 or earlier can't resize any type that's sized using pixels. If your text is too small for someone's eyes, the visitor won't be able to enlarge it to make it more readable. (See page 158 for more on pixel measurements.)

■ EMS

Originally from the typographic world, an *em* is a unit that represents the height of the capital letter M for a particular font. In web pages, 1em is the height of the web browser's base text size, which is usually 16 pixels. However, anyone can change that base size setting, so 1em may be 16 pixels for one person, but 24 pixels in someone else's browser. In other words, ems are a relative unit of measurement.

In addition to the browser's initial font-size setting, ems can inherit size information from containing tags. A type size of .9em would make text about 14 pixels tall on most browsers with a 16 pixel base size. But if you have a `<p>` tag with a font size of .9ems, and then a `` tag with a font size of .9ems inside that `<p>` tag, that `` tag's em size isn't 14 pixels—it's 12 pixels (16 x .9 x .9). So keep inheritance in mind when you use em values.

■ PERCENTAGES

CSS uses percentages for many different purposes, like sizing text, determining the width or height of an element, and specifying the placement of an image in the background of a style, to name a few. Now, what you're taking a percentage of varies from property to property. For font sizes, the percentage is calculated based on the text's inherited value. Say the general font size for a paragraph is 16 pixels tall. If you created a style for one special paragraph and set its font size to 200%, that text is displayed at 32 pixels tall. When applied to width, however, percentages are calculated based on the width of the page or on the width of the nearest parent element. You specify a percentage with a number followed by the percent sign: 100%.

Keywords

Instead of color or size, many properties have their own specific values that affect how the properties display and are represented by keywords. The `text-align` property, which aligns text on screen, can take one of four keywords: `right`, `left`, `center`, and `justify`. Since keywords vary from property to property, read the property descriptions that follow to learn the keyword appropriate to each property.

One keyword, however, is shared by all properties—`inherit`. This keyword lets you force a style to inherit a value from a parent element. You can use the `inherit` keyword on any property. This keyword gives you the power to make styles inherit properties that aren't normally inherited from parent tags. For instance, say you use the `border` property to add a border around a paragraph. Other tags, such as `` and ``, inside the `<p>` tag don't inherit this value, but you can force them to do so with the `inherit` keyword:

```
em, strong {
  border: inherit;
}
```

That way, the `` and `` tags display the same border value as their parent `<p>` tag. So the `` and `` elements of the paragraph each get their own borders, as does the entire paragraph, so you'd end up with boxes within boxes (a good reason why that property *isn't* inherited normally). If you change the `<p>` tag's

border value to a *different color or thickness*, the `` and `` tags inherit that value and display the same type of border, too.

NOTE The border property isn't a very useful example, mainly because `inherit` isn't a very useful value. But this wouldn't be a Missing Manual if it didn't give you all the facts.

URLs

URL values let you point to another file on the Web. For example, the `background-image` property accepts a URL—the path to the file on the Web—as its value, which lets you assign a graphic file as a background for a page element. This technique is handy for adding a tiling image in the background of a page or using your own graphic for bulleted lists (see page 176).

In CSS, you specify a URL like this: `url(images/tile.gif)`. A style that adds an image called *tile.gif* to the background of the page would look like this:

```
body { background-image: url(images/tile.gif); }
```

Unlike in HTML, in CSS, quotes around the URL are optional, so `url("images/tile.gif")`, `url('images/tile.gif')`, and `url(images/tile.gif)` are equivalent.

NOTE The URL itself is just like the HTML `href` attribute used for links, meaning you can use an absolute URL like <http://www.missingmanuals.com/images/tile.gif>, a root-relative path like </images/tile.gif>, or a document-relative URL like ../images/tile.gif. See page 244 for the full story on these kinds of paths.

Text Properties

The following properties affect how text is formatted on a web page. Since most of the properties in this category are inherited, you don't necessarily have to apply them to tags specifically intended for text (like the `<p>` tag). You can apply these properties to the `<body>` tag, so that other tags inherit and use the same settings. This technique is a quick way to define an overall font, color, and so on for a page or section.

color (inherited)

Sets the color of text. Since it's inherited, if you set the color of the `<body>` tag to red, for example, all text inside of the body—and all other tags inside the `<body>` tag—is red, too.

- **Values:** any valid color value
- **Example:** `color: #FFF333;`

NOTE The preset link colors for the `<a>` tag override color inheritance. In the above example, any links inside the `<body>` tag would still be standard hyperlink blue. See page 115 for ways to change preset link colors.

font (inherited)

This is a shortcut method for cramming the following text properties into a single style declaration: `font-style`, `font-variant`, `font-weight`, `font-size`, `line-height`, and `font-family`. (Read on for the individual descriptions.)

You must separate each value by a space and include at least `font-size` and `font-family`, and those two properties must be the last two items in the declaration. The others are optional. If you don't set a property, the browser uses its own preset value, potentially overriding inherited properties.

- **Values:** Any value that's valid for the specific font property. When including a line height, add a slash followed by the line height after the font size like this: `1.25em/150%`.
- **Example:** `font: italic small-caps bold 1.25em/150% Arial, Helvetica, sans-serif;`

font-family (inherited)

Specifies the font the browser should use to display text. Fonts are usually specified as a series of three to four options to accommodate the fact that a particular font may not be installed on a visitor's computer. See page 129.

- **Values:** A comma-separated list of font names. When a font has a space in its name, surround that font name with quotes. The last font listed is usually a generic font type instructing browsers to choose a suitable font if the other listed fonts aren't available: `serif`, `sans-serif`, `monospace`, `fantasy`, or `cursive`.
- **Example:** `font-family: "Lucida Grande", Arial, sans-serif;`

NOTE

All browsers let you specify additional fonts that you either keep on your web server or your visitors' browsers download from a web font service. See page 132 for a detailed description of using web fonts.

font-size (inherited)

Sets the size of text. This property is inherited, which can lead to some weird behaviors when using relative length measurements like percentages and ems.

- **Values:** Any valid CSS measurement unit (page 158), plus the following keywords: `xx-small`, `x-small`, `small`, `medium`, `large`, `x-large`, `xx-large`, `larger`, and `smaller`. Medium represents the web browser's normal, preset font size, and the other sizes are multiples of medium.

Each of the other options decreases or increases the size by a different factor. While each size change is supposed to be a consistent increase or decrease from the previous size, it isn't. Basically, `xx-small` is the equivalent of 9 pixels (assuming you haven't adjusted the base font size in your browser); `x-small` is 10 pixels; `small` is 13 pixels; `large` is 18 pixels; `x-large` is 24 pixels; and `xx-large` is 32 pixels. Due to the uncertainty of how each browser handles these keywords, many designers use pixels, ems, or percentages instead.

- **Example:** `font-size: 1.25em;`

font-style (inherited)

Makes text italic. Applied to italic text, it turns it back to plain text. The options `italic` and `oblique` are functionally the same.

- **Values:** `italic`, `oblique`, `normal`
- **Example:** `font-style: italic;`

font-variant (inherited)

Makes text appear in small caps, like this: `SPECIAL PRESENTATION`. The value `normal` removes small caps from text already formatted that way.

- **Values:** `small-caps`, `normal`
- **Example:** `font-variant: small-caps;`

font-weight (inherited)

Makes text bold or removes bolding from text already formatted that way.

- **Values:** CSS actually provides 14 different `font-weight` keywords, but only a couple actually work with today's browsers and computer systems—`bold` and `normal`.
- **Example:** `font-weight: bold;`

letter-spacing (inherited)

Adjusts the space between letters to spread out letters (adding spacing between each) or cram letters together (removing space).

- **Values:** Any valid CSS measurement unit, though `ems` and `pixels` are most common. For this property, percentages don't work in most browsers. Use a positive value to increase the space between letters and a negative value to remove space (scrunch letters together). The value `normal` resets letter-spacing to its regular browser value of 0.
- **Examples:** `letter-spacing: -1px;` `letter-spacing: 2em;`

line-height (inherited)

Adjusts space between lines of text in a paragraph (often called `line spacing` in word-processing programs). The normal line height is 120 percent of the size of the text (page 167).

- **Values:** Most valid CSS lengths (page 158), though `ems` and `pixels` and percentages are most common.
- **Example:** `line-height: 200%;`

text-align (inherited)

Positions a block of text to the left, right, or center of the page or container element.

- **Values:** left, center, right, justify (the justify option often makes text difficult to read on monitors).
- **Example:** `text-align: center;`

text-decoration (inherited)

Adds lines above, under, and/or through text. Underlining is common with links, so it's usually a good idea *not* to underline text that isn't a link. The color of the underline, overline, or strike-through line is the same as the font color of the tag being styled. The property also supports a `blink` value that makes text flash off and on obnoxiously (but most browsers ignore `blink` anyway).

- **Values:** underline, overline, line-through, blink, none. The *none* value turns off all decoration. Use this to hide the underline that normally appears under links. You can also add multiple decorations by listing the name of each type (except *none*) separated by a space.
- **Example:** `text-decoration: underline overline line-through;`

text-indent (inherited)

Sets the indent size of the first line of a block of text. The first line can be indented (as in many printed books) or outdented, so that the first line hangs off and over the left edge of the rest of the text.

- **Values:** Any valid CSS measurement unit. Ems and pixels are most common; percentages behave differently than with the `font-size` property. Here, percentages are based on the width of the box containing the text, which can be the width of the entire browser window. So 50% would indent the first line half of the way across the window. To outdent (hang the first line off the left edge), use a negative value. This technique works well in conjunction with a positive `margin-left` property, which indents the left side of the other lines of text a set amount.
- **Example:** `text-indent: 3em;`

text-shadow (inherited)

Lets you add a drop shadow to any text.

- **Values:** Two measurement values (ems or pixels) for horizontal and vertical offset, a value for the amount of blur applies to the text, and a color value. For the horizontal offset, a negative number places the shadow to the left of the text, a positive value to the right. For vertical offset, a negative number moves the shadow above the text, and positive value places it below. Each value is separated from the next by a space. You can also add multiple shadows by adding additional shadow values separated by a comma.

- **Examples:**

```
text-shadow: -4px 4px 3px #999999;  
text-shadow: -4px 4px 3px #999999  
2px 3px 10px #000;
```

text-transform (inherited)

Changes the capitalization of text, so text appears in all uppercase letters, all lowercase, or only the first letter of each word capitalized.

- **Values:** uppercase, lowercase, capitalize, none. The none option returns the text to whatever case is in the actual HTML code. If *aBCDefg* are the actual letters typed in HTML, then none removes any other inherited case set by an ancestor tag and displays *aBCDefg* onscreen.
- **Example:** text-transform: uppercase;

vertical-align

Sets the baseline of an inline element relative to the baseline of the surrounding contents. With it, you can make a character appear slightly above or below surrounding text. Use this to create superscript characters like ™, ®, or ©. When applied to a table cell, the values top, middle, bottom, and baseline control the vertical placement of content inside the cell.

- **Values:** baseline, sub, super, top, text-top, middle, bottom, text-bottom, a percentage value, or an absolute value (like pixels or ems). Percentages are calculated based on the element's line-height value.
- **Examples:**

```
vertical-align: top;  
vertical-align: -5px;  
vertical-align: 75%;
```

white-space

Controls how the browser displays space characters in the HTML code. Normally, if you include more than one space between words—"Hello Dave"—a web browser displays only one space—"Hello Dave." You can preserve any white space exactly as is in the HTML by using the pre value, which does the same as the HTML <pre> tag. In addition, web browsers will split a line of text at a space, if the line won't fit within the window's width. To prevent text from wrapping, use the nowrap value. But the nowrap value makes *all* the paragraph's text stay on one line, so don't use it with long paragraphs (unless you like the idea of making your visitors scroll endlessly to the right).

- **Values:** nowrap, pre, normal. Two other values—pre-line and pre-wrap—don't work in many browsers.
- **Example:** white-space: pre;

word-spacing (inherited)

Works like the letter-spacing property (page 569), but instead of letters, it adjusts space between words.

- **Values:** Any valid CSS measurement unit, though ems and pixels are most common; percentages don't work in most browsers. Use a positive value to increase the space between words and a negative value to remove space (scrunch words together). The value `normal` resets word spacing to its regular browser value of 0.
- **Examples:** `word-spacing: -1px;` `word-spacing: 2em;`

List Properties

The following properties affect the formatting of bulleted lists (``) and numbered lists (``). (See page 173 for more on using CSS with lists.)

list-style (inherited)

This property is a shorthand method of specifying the three properties listed next. You can include a value for one or more of those properties, separating each by a space. You can even use this property as a shortcut for writing a single property and save a couple of keystrokes: `list-style: outside`, instead of `list-style-position: outside`. If you specify both a type and an image, a web browser will display the bullet type (disc, square, and so on) *only* if it can't find the image. This way, if the path to your custom bullet image doesn't work, you don't end up with a bulletless bulleted list.

- **Values:** Any valid value for `list-style-type`, `list-style-image`, and/or `list-style-position`.
- **Example:** `list-style: disc url(images/bullet.gif) inside;`

list-style-image (inherited)

Specifies an image to use for a bullet in a bulleted list.

- **Values:** A URL value or `none`.
- **Example:** `list-style-image: url(images/bullet.gif);`

NOTE

The `background-image` property does the custom bullet job just as well and offers more control (see page 240).

list-style-position (inherited)

Positions the bullets or numbers in a list. These markers can appear outside of the text, hanging off to the left, or inside the text (exactly where the first letter of the first line normally begins). The outside position is how web browsers normally display bullets and numbers.

- **Values:** inside, outside
- **Example:** list-style: inside;

list-style-type (inherited)

Sets the type of bullet for a list—round, square, roman numeral, and so on. You can even turn an unordered (bulleted) list into an ordered (numbered) list by changing the list-style-type property. Use the none option to completely remove bullets or numbers from the list.

- **Values:** disc, circle, square, decimal, decimal-leading-zero, upper-alpha, lower-alpha, upper-roman, lower-roman, lower-greek, none
- **Example:** list-style-type: square;

■ Padding, Borders, and Margins

The following properties control the space around an element, and let you add border lines to a style.

box-shadow Adds a shadow around a box element.

- **Values:** An optional value—inset—adds a drop shadow inside an element, followed by four measurement values and a color. The first two measurement values (ems or pixels) are for horizontal and vertical offset; the third value specifies the amount of blur applied to the box; the fourth value, which is optional, adds a “spread” to the shadow, making the shadow wider. For the horizontal offset, a negative number places the shadow to the left of the box, a positive value to the right. For vertical offset, a negative number moves the shadow above the box, and positive value places it below. Each value is separated from the next by a space. You can also add multiple shadows by adding additional shadows values separated by a comma.
- **Example:**

```
box-shadow: -4px 4px 3px #999999;
box-shadow: inset 4px 4px 3px 5px #999999;
box-shadow: inset 4px 4px 3px 5px #999999
            2px 2px 5px black;
```

border

Draws a line around the four edges of an element.

- **Values:** The width (thickness) of the border line in any valid CSS measurement unit (except percentages).

You can also specify a style for the line: solid, dotted, dashed, double, groove, ridge, inset, outset, none, and hidden. (See Figure 7-7 on page 203 for an illustration of the different styles.) The none and hidden values do the same thing—remove any border.

Finally, you can specify a color by using any valid CSS color type (a keyword like green or a hex number like #33fc44).

- **Example:** `border: 2px solid #f33;`

border-radius

Rounds the corners of an element. Only has a visual effect if the element has a border, background color, or image.

- **Values:** One, two, three, or four values (px, em, or %) that indicate the size of a radius of a circle drawn at the corners of an element's box. If you supply only one value, it applies the same size rounded corner to all four corners; with two values, the first specifies the top-left and bottom-right corners, while the second indicates the top-right and bottom-left corner radii. If you use three values, the first specifies the top-left corner; the second, both the top-right and bottom-left; and the third, the bottom-right corner. With four values, each value applies in order to the top-left, top-right, bottom-right, and bottom-left corner. You can add a / followed by a second value to create an elliptical corner rather than a perfectly circular one.

- **Examples:**

```
border-radius: .5em;
border-radius: 15px 10px 25px 5px;
border-radius: 15px / 5px;
```

border-top, border-right, border-bottom, border-left

Adds a border to a single edge. For example, `border-top` adds a border to the top of the element.

- **Values:** same as for `border`.
- **Example:** `border-left: 1em dashed red;`

border-color

Defines the color used for all four borders.

- **Values:** Any valid CSS color type (a keyword like green or a hex number like #33fc44).
- **Example:** `border-color: rgb(255,34,100);`

This property also supports a shorthand method, which lets you assign different colors to each of the four borders.

- **Values:** Any valid CSS color type for each border: top, right, bottom, left. If you include just two colors then the first color applies to the top and bottom, and the second color to the left and right.
- **Example:** `border-color: #000 #F33 #030 #438F3C;`

border-top-color, border-right-color, border-bottom-color, border-left-color

Functions just like the `border-color` property but sets color for only one edge. Use these properties to override the color set by the `border` property. In this way, you can customize the color for an individual edge while using a more generic border style to define the basic size and style of all four edges.

- **Values:** See `border-color`.
- **Example:** `border-left-color: #333;`

border-style

Defines the style used for all four borders.

- **Values:** One of these keywords: `solid`, `dotted`, `dashed`, `double`, `groove`, `ridge`, `inset`, `outset`, `none`, and `hidden`. See Figure 7-7 on page 203 for an illustration of the different styles. The `none` and `hidden` values act identically—they remove any border.
- **Example:** `border-style: inset;`

This property also supports a shorthand method, which lets you assign different styles to each of the four borders.

- **Values:** One of the keywords (mentioned previously) for each border: `top`, `right`, `bottom`, `left`. If you include just two keywords, then the first style applies to the top and bottom and the second style to the left and right.
- **Example:** `border-style: solid dotted dashed double;`

border-top-style, border-right-style, border-bottom-style, border-left-style

Functions just like the `border-style` property, but applies only to one edge.

- **Values:** See `border-style`.
- **Example:** `border-top-style: none;`

border-width

Defines the width or thickness of the line used to draw all four borders.

- **Values:** Any valid CSS measurement unit except percentages. The most common are `ems` and `pixels`.
- **Example:** `border-width: 1px;`

This property also supports a shorthand method, which lets you assign different widths to each of the four borders.

- **Values:** Any valid CSS measurement unit (except percentages) for each border: top, right, bottom, left. If you include just two values, then the first value sets the width for the top and bottom border and the second value the width for the left and right borders.
- **Example:** `border-width: 3em 1em 2em 3.5em;`

border-top-width, border-right-width, border-bottom-width, border-left-width

Functions just like the `border-width` property but applies only to one edge.

- **Values:** See `border-width`.
- **Example:** `border-bottom-width: 3em;`

box-sizing

Dictates how a browser measures an element's height and width. Normally, browsers combine the `border`, `padding`, and `width` properties to determine the amount of screen space an element takes up. This system can be confusing, since you can specify an element's width to be 300 pixels, but if the element also has padding and borders, the browser displays that element wider than 300 pixels onscreen.

- **Values:** `content-box`, `padding-box`, or `border-box`. The `content-box` option is the normal way browsers do it. `padding-box` tells a browser to include the padding with the width and height values; `border-box` also includes the border width and height in its calculations. For example, if you have a `<div>` tag that you set to 300 pixels width, with 20 pixels of padding and a 2-pixel border, a browser will normally display that div in 344 pixels of screen space ($300 + 20 + 20 + 2 + 2$); however, if you set the `box-sizing` property to `padding-box`, the browser would display that div in 304 pixels of space ($300 + 2 + 2$) because the padding is considered part of that 300 pixels; the `border-box` setting would tell a browser to simply make the div 300 pixels wide. The `border-box` option is commonly used to make it easier to keep track of element widths. Unfortunately, Internet Explorer 7 and earlier don't understand it.
- **Example:** `box-sizing: border-box;`

outline

This property is a shorthand way to combine `outline-color`, `outline-style`, and `outline-width` (listed next). An outline works just like a border, except the outline takes up no space (that is, it doesn't add to the width or height of an element), and it applies to all four edges. It's intended more as a way of highlighting something on a page than as a design detail. Outline works in Firefox, Safari, Chrome, Opera, and only version 8 or later of Internet Explorer.

- **Values:** The same as for `border` with one exception—see `outline-color`.
- **Example:** `outline: 3px solid #F33;`

outline-color

Specifies the color for an outline (see `outline`).

- **Values:** Any valid CSS color, plus the value `invert`, which merely reverses the color the outline is sitting on. If the outline is drawn on a white background, the `invert` value makes the outline black. Works just like `border-color` (page 574).
- **Example:** `outline-color: invert;`

outline-style

Specifies the type of line for the outline—dotted, solid, dashed, and so on.

- **Values:** Same as `border-style` (page 575).
- **Example:** `outline-style: dashed;`

outline-width

Specifies the thickness of the outline. Works just like `border-width`.

- **Values:** Any valid CSS measurement unit except percentages. The most common are `ems` and `pixels`.
- **Example:** `outline-width: 3px;`

padding

Sets the amount of space between the content, border, and edge of the background. Use it to add empty space around text, images, or other content. (See Figure 7-1 on page 194 for an illustration.)

- **Values:** Any valid CSS measurement unit, like `pixels` or `ems`. Percentage values are based on the width of the containing element. A headline that's a child of the `<body>` tag uses the width of the browser window to calculate a percentage value, so a padding of 20 percent adds 20 percent of the window's width. If the visitor resizes his browser, the padding size changes proportionately. You can specify the padding for all four edges by using a single value or set individual padding sizes per edge using this order: `top`, `right`, `bottom`, `left`.
- **Examples:** `padding: 20px;` `padding: 2em 3em 2.5em 0;`

padding-top

Works just like the `padding` property, but sets padding for top edge only.

- **Example:** `padding-top: 20px;`

padding-right

Works just like the `padding` property, but sets padding for right edge only.

- **Example:** `padding-right: 20px;`

padding-bottom

Works just like the padding property, but sets padding for bottom edge only.

- **Example:** padding-bottom: 20px;

padding-left

Works just like the padding property, but sets padding for left edge only.

- **Example:** padding-left: 20px;

margin

Sets the amount of space between an element's border and the margin of other elements (see Figure 7-1 on page 194). It lets you add white space between two elements—between one picture and another picture, or between a sidebar and the main content area of a page.

NOTE

Vertical margins between elements can collapse. That is, browsers use only the top or bottom margin and ignore the other, creating a smaller gap than expected (see page 198).

- **Values:** Any valid CSS measurement unit like pixels or ems. Percentage values are based on the width of the containing element. A headline that's a child of the <body> tag uses the width of the browser window to calculate a percentage value, so a margin of 10% adds 10 percent of the window's width to the edges of the headline. If the visitor resizes his browser, the margin size changes. As with padding, you specify the margin for all four edges using a single value, or set individual margins in this order: top, right, bottom, left.
- **Examples:** margin: 20px; margin: 2em 3em 2.5em 0;

margin-top

Works just like the margin property, but sets margin for top edge only.

- **Example:** margin-top: 20px;

margin-right

Works just like the margin property, but sets margin for right edge only.

- **Example:** margin-right: 20px;

margin-bottom

Works just like the margin property, but sets margin for bottom edge only.

- **Example:** margin-bottom: 20px;

margin-left

Works just like the margin property, but sets margin for left edge only.

- **Example:** margin-left: 20px;

■ Backgrounds

CSS provides several properties for controlling the background of an element, including coloring the background, placing an image behind an element, and controlling how that background image is positioned.

background

Provides a shorthand method of specifying properties that appear in the background of an element, like a color, an image, and the placement of that image. It combines the five background properties (described next) into one compact line, so you can get the same effect with much less typing. However, if you don't set one of the properties, browsers use that property's normal value instead. For example, if you don't specify how a background image should repeat, browsers will tile that image from left to right and top to bottom.

- **Values:** The same values used for the background properties listed next. The order of the properties isn't important (except for positioning, as described below), but usually follow the order of `background-color`, `background-image`, `background-repeat`, `background-attachment`, `background-position`.
- **Example:** `background: #333 url(images/logo.gif) no-repeat fixed left top;`

background-attachment

Specifies how a background image reacts when your visitor scrolls the page. The image either scrolls along with the rest of the content or remains in place. You can add a logo to the upper-left corner of a very long web page, using the `background-attachment` property's `fixed` value, and make that image stay in the upper-left corner even when the page is scrolled. (In Internet Explorer 6 and earlier, this property works only for the `<body>` tag.)

- **Values:** `scroll` or `fixed`. `Scroll` is the normal behavior: An image will scroll off the screen along with text. `Fixed` locks the image in place.
- **Example:** `background-attachment: fixed;`

background-clip

This property limits the area in which a background image appears. Normally a background image fills the entire area of an element including its borders, padding, and content. However, you may want a background image to only appear behind the padding area and exclude the borders—useful when you have a dotted or dashed border, to keep the image from appearing in the gaps of the border. Likewise, you might want to exclude the padding area so a tiled background appears only in the content area, and a solid color in the padding area. This property is not supported by Internet Explorer 8 or earlier.

- **Values:** `border-box`, `padding-box`, or `content-box`. The `border-box` option is the normal method—placing an image behind the border, paddings, and content. `Padding-box` keeps a background image in the padding area only, so it won't appear behind the border. `Content-box` places a background image in the content area only, so it won't appear in the padding area or behind the border.

- **Examples:**

```
background-clip: content-box;  
background-clip: padding-box;
```

background-color

Adds a color to the background of a style. The background sits underneath the border and underneath a background image, a fact to keep in mind if you use one of the nonsolid border styles like `dashed` or `dotted`. In these cases, the background color shows through the gaps between the dashes or dots.

- **Values:** Any valid color value (page 155).
- **Example:** `background-color: #FFF;`

background-image

Places an image into the background of a style. Other page elements sit on top of the background image, so make sure that text is legible where it overlaps the image. You can always use padding to move content away from the image, too. The image tiles from left to right and top to bottom, unless you set the `background-repeat` property as well. CSS3 lets you apply multiple background images (page 257).

- **Values:** The URL of an image. Can also include a browser-generated `linear-gradient` or `radial-gradient` (see page 260).
- **Examples:**

```
background-image: url(images/photo.jpg);  
background-image: url(http://www.example.org/photo.jpg);
```

background-origin

Tells a browser where to place a background image in relationship to the border, padding, and content of an element. This is most useful for a nonrepeating image, since this property lets you better control the image's position. This property is not supported by Internet Explorer 8 or earlier.

- **Values:** `border-box`, `padding-box`, or `content-box`. The `border-box` option is the normal method—placing an image in the top-left corner of the border. `Padding-box` starts a background image in the padding area only, so it won't appear behind the border. `Content-box` places a background image in the content area only, so it won't appear in the padding area or behind the border. However, if the image is tiled, you'll still see the image behind the borders and padding regardless, since this property only controls where the image starts.

Use the `background-clip` property (page 252) to keep a tiled image from appearing behind borders or padding.

- **Example:** `background-origin: content-box;`

background-position

Controls the placement of an image in the background of a page element. Unless you specify otherwise, an image begins in the element's top-left corner. If the image tiles, `background-position` controls the image's start point (see `background-repeat`). If you position an image in the center of an element, the browser puts the image there and then tiles the image up and to the left *and* down and to the right. In many cases, the exact placement of an image doesn't cause a visible difference in the background tiling, but it lets you make subtle changes to the positioning of a pattern in the background.

- **Values:** Any valid CSS measurement unit, like pixels or ems, as well as keywords or percentages. The values come in pairs, with the first being the horizontal position, and the second being vertical. Keywords include `left`, `center`, and `right` for horizontal positioning and `top`, `center`, and `bottom` for vertical. Pixel and em values are calculated from the top-left corner of the element, so to place a graphic 5 pixels from the left edge and 10 pixels from the top, you'd use a value of `5px 10px`.

Percentage values map one point on the image to one point in the background of the element, calculated by the specified percentage from the left and top edges of the image and the specified percentage from the left and top edges of the element. `50% 50%` places the point that's 50 percent across and 50 percent down the image on top of the point that's 50 percent across and 50 percent down the element. In other words, it puts the image directly in the middle of the element. You can mix and match these values: If you want, use a pixel value for horizontal placement and a percentage value for vertical placement.

- **Examples:** `background-position: left top;` `background-position: 1em 3em;` `background-position: 10px 50%;`

background-repeat

Controls whether or how a background image repeats. Normally, background images tile from the top-left to the bottom-right, filling the element's entire background.

- **Values:** `repeat`, `no-repeat`, `repeat-x`, `repeat-y`. The `repeat` option is the normal method—tiling left to right, top to bottom. `no-repeat` places the image a single time in the background with no tiling. `repeat-y` tiles the image top to bottom only—perfect for adding a graphical sidebar. `repeat-x` tiles the image from left to right only, so you can add a graphical bar to an element's top, middle, or bottom.
- **Example:** `background-repeat: no-repeat;`

background-size

Lets you resize a background image scaling it up, down, or even distorting its proportions.

- **Values:** You can use specific values in pixels, ems, or percentages or one of two keywords: `contain` or `cover`. `Contain` forces the image to resize to completely fit the entire element while still maintaining its aspect ratio. `Cover` forces the width of the image to fit the width of the element and the height of the image to fit the height of the element, which usually distorts the image by stretching it or squishing it to fit within the element.

- **Example:**

```
background-size: 200px 400px;  
background-size: contain;
```

Page Layout Properties

The following properties control the placement and size of elements on a web page.

bottom

This property is used with `absolute`, `relative`, and `fixed` positioning (see page 488). When used with `absolute` or `fixed` positioning, `bottom` determines the position of the bottom edge of the style relative to the bottom edge of its closest positioned ancestor. If the styled element isn't inside of any positioned tags, then the placement is relative to the bottom edge of the browser window. You can use this property to place a footnote at the bottom of the browser window. When used with `relative` positioning, the placement is calculated from the element's bottom edge (prior to positioning).

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Percentages are calculated based on the width of the containing element.
- **Example:** `bottom: 5em;`

clear

Prevents an element from wrapping around a floated element. Instead, the cleared element drops below the bottom of the floated element.

- **Values:** `left`, `right`, `both`, `none`. The `left` option means the element can't wrap around left-floated elements. Similarly, `right` drops the element below any right-floated items. The `both` value prevents an element from wrapping around *either* left- or right-floated elements. `None` turns the property off, so you use it to override a previously set `clear` property. This trick comes in handy when a particular tag has a style that drops below a floated element but you want the tag to wrap in just one case. Create a more specific style to override the float for that one tag.

- **Example:** `clear: both;`

clip

Creates a rectangular window that reveals part of an element. If you had a picture of your high-school graduating class, and the class bully was standing on the far right edge of the photo, you could create a display area that crops out the image of your tormentor. The full image is still intact, but the clipping area only displays the bully free portion of it. The `clip` property is most effective when used with JavaScript programming to animate the clip. You can start with a small clipping area and expand it until the full photo is revealed.

- **Values:** Coordinates of a rectangular box. Enclose the coordinates in parentheses and precede them by the keyword `rect`, like so: `rect(5px,110px,40px,10px);`.

Here's how the order of these coordinates works: The first number indicates the top offset—the top edge of the clipping window. In this example, the offset is 5px, so everything in the first four rows of pixels is hidden. The last number is the left offset—the left edge of the clipping window. In this example, the offset is 10px, so everything to the left (the first 9 pixels of the element) is hidden. The second number is the width of the clipping window plus the last number; if the left edge of the clip is 10 pixels and you want the visible area to be 100 pixels, the second number would be 110px. The third number is the height of the clipping region plus the top offset (the first number). So, in this example, the clipping box is 35 pixels tall ($35\text{px} + 5\text{px} = 40\text{px}$).

- **Example:** `clip: rect(5px,110px,40px,10px);`

NOTE

Since the order of the coordinates is a little strange, most designers like to start with the first and last numbers, and then compute the two other numbers from them.

display

Determines the kind of box used to display a web page element—block-level or inline (page 44). Use it to override how a browser usually displays a particular element. You can make a paragraph (block-level element) display without line breaks above and below it—exactly like, say, a link (inline element).

- **Values:** `block`, `inline`, `none`. The `display` property accepts 17 values, most of which have no effect in the browsers available today. `Block`, `inline`, and `none`, however, work in almost all browsers. `Block` forces a line break above and below an element, just like other block-level elements (like paragraphs and headers). `Inline` causes an element to display on the same line as surrounding elements (just as text within a `` tag appears right on the same line as other text). `None` makes the element completely disappear from the page. Then you can make the element reappear with some JavaScript programming or the `:hover` pseudo-class (see page 294). Some of the other properties work in a handful of browsers (the most notable exceptions being Internet Explorer 7 and 6). You

can use the table display properties to create some interesting page layouts, as mentioned on page 387.

- **Example:** `display: block;`

float

Moves an element to the left or right edge of the browser window, or, if the floated element is inside another element, to the left or right edge of that containing element. Elements that appear after the floated element move up to fill the space to the right (for left floats) or left (for right floats) and then wrap around the floated element. Use floats for simple effects—like moving an image to one side of the page—or for very complex layouts—like those described in Chapter 12.

- **Values:** `left`, `right`, `none`. To turn off floating entirely, use `none`: This comes in handy when a particular tag has a style with a left or right float applied to it and you want to create a more specific style to override the float for that one tag.
- **Example:** `float: left;`

height

Sets the height of the content area—the area of an element’s box that contains content like text, images, or other tags. The element’s actual onscreen height is the total of height, top, and bottom margins, top and bottom padding, and top and bottom borders.

- **Values:** Any valid CSS measurement unit, such as pixels, ems, or percentages. Percentages are calculated based on the height of the containing element.
- **Example:** `height: 50%;`

NOTE

Sometimes, your content ends up taller than the set height—if you type a lot of text, for instance, or your visitor increases text size in her browser. Browsers handle this situation differently: IE 6 (and earlier) simply makes the box bigger, while other browsers make the content extend outside of the box.

left

When used with absolute or fixed positioning (page 410), this property determines the position of the left edge of the style relative to the left edge of its closest positioned ancestor. If the styled element isn’t inside of any positioned tags, then the placement is relative to the left edge of the browser window. You can use this property to place an image 20 pixels from the left edge of the browser window. When used with relative positioning, the placement is calculated from the element’s left edge (prior to positioning).

- **Values:** Any valid CSS measurement unit, such as pixels, ems, or percentages.
- **Example:** `left: 5em;`

max-height

Sets the *maximum* height for an element. That is, the element's box may be shorter than this setting, but it can't be any taller. If the element's contents are taller than the `max-height` setting, they overflow the box. You can control what happens to the excess by using the `overflow` property. Internet Explorer 6 (and earlier) doesn't understand the `max-height` property.

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Browsers calculate percentages based on the height of the containing element.
- **Example:** `max-height: 100px;`

max-width

Sets the *maximum* width for an element. The element's box can be narrower than this setting, but not wider. If the element's contents are wider than the `max-width` setting, they overflow the box, which you can control with the `overflow` property. You mostly use `max-width` in liquid layouts (page 406) to make sure a page design doesn't become unreadably wide on very large monitors. This property doesn't work in Internet Explorer 6 (or earlier).

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Percentages are calculated based on the width of the containing element.
- **Example:** `max-width: 950px;`

min-height

Sets the *minimum* height for an element. The element's box may be taller than this setting, but it can't be shorter. If the element's contents aren't as tall as the `min-height` setting, the box's height shrinks to meet the `min-height` value. Internet Explorer 6 (and earlier) doesn't recognize this property.

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Percentages are based on the containing element's height.
- **Example:** `min-height: 20em;`

min-width

Sets the *minimum* width for an element. The element's box may be wider than this setting, but it can't be narrower. If the element's contents aren't as wide as the `min-width` value, the box simply gets as thin as the `min-width` setting. You can also use `min-width` in liquid layouts, so that the design doesn't disintegrate at smaller window widths. When the browser window is thinner than `min-width`, it adds horizontal scroll bars. Internet Explorer 6 (and earlier) doesn't understand this property.

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Percentages are based on the containing element's width.
- **Example:** `min-width: 760px;`

NOTE

You usually use the `max-width` and `min-width` properties in conjunction when creating liquid layouts. See Chapter 12.

overflow

Dictates what should happen to text that overflows its content area, like a photo that's wider than the value set for the width property.

- **Values:** `visible`, `hidden`, `scroll`, `auto`. Visible makes the overflowing content extend outside the box—potentially overlapping borders and other web page elements on the page. IE 6 (and earlier) simply enlarges the box (borders and all) to accommodate the larger content. Hidden hides any content outside of the content area. Scroll adds scroll bars to the element so a visitor can scroll to read any content outside the content area—sort of like a mini-frame. Auto adds scrollbars *only* when they're necessary to reveal more content.
- **Example:** `overflow: hidden;`

position

Determines what type of positioning method a browser uses when placing an element on the page.

- **Values:** `static`, `relative`, `absolute`, `fixed`. Static is the normal browser mode—one block-level item stacked on top of the next with content flowing from the top to the bottom of the screen. Relative positions an element in relation to where the element currently appears on the page—in other words, it can offset the element from its current position. Absolute takes an element completely out of the page flow. Other items don't see the absolute element and may appear underneath it. It's used to position an element in an exact place on the page or to place an element in an exact position relative to a parent element that's positioned with `absolute`, `relative`, or `fixed` positioning. Fixed locks an element on the page, so that when the page is scrolled, the fixed element remains on the screen—much like HTML frames. Internet Explorer 6 (and earlier) ignores the `fixed` option.
- **Example:** `position: absolute;`

TIP

You usually use `relative`, `absolute`, and `fixed` in conjunction with `left`, `right`, `top`, and `bottom`. See Chapter 13 for the full details on positioning.

right

When used with `absolute` or `fixed` positioning, this property determines the position of the right edge of the style relative to the right edge of its closest positioned ancestor. If the styled element isn't inside of any positioned tags, then the placement is relative to the right edge of the browser window. You can use this property to place a sidebar a set amount from the right edge of the browser window. When

used with relative positioning, the placement is calculated from the element's right edge (prior to positioning).

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages.
- **Example:** `left: 5em;`

WARNING

Internet Explorer 6 (and earlier) can have problems when positioning an element, using the `right` property. See the box on page 440 for details.

top

Does the opposite of what the `bottom` property does (page 582). In other words, when used with absolute or fixed positioning, this property determines the position of the top edge of the style relative to the top edge of its closest positioned ancestor. If the styled element isn't inside of any positioned tags, then the placement is relative to the top edge of the browser window. You can use this property to place a logo a set amount from the top edge of the browser window. When used with relative positioning, the placement is calculated from the element's top edge (prior to positioning).

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages.
- **Example:** `top: 5em;`

visibility

Determines whether a web browser displays the element. Use this property to hide part of the content of the page, such as a paragraph, headline, or `<div>` tag. Unlike the `display` property's `none` value—which hides an element and removes it from the flow of the page—the `visibility` property's `hidden` option doesn't remove the element from the page flow. Instead, it just leaves an empty hole where the element would have been. For this reason, you most often use the `visibility` property with absolutely positioned elements, which have already been removed from the flow of the page.

Hiding an element doesn't do you much good unless you can show it again. JavaScript programming is the most common way to toggle the `visibility` property to show and hide items on a page. You can also use the `:hover` pseudo-class (page 294) to change an element's `visibility` property when a visitor hovers over some part of the page.

- **Values:** `visible`, `hidden`. You can use the `collapse` value to hide a row or column in a table as well.
- **Example:** `visibility: hidden;`

width

Sets the width of the content area (the area of an element's box that contains text, images, or other tags). The amount of onscreen space actually dedicated to the element may be much wider, since it includes the width of the left and right margin, left and right padding, and left and right borders. IE 6 (and earlier) handles overflow situations differently than other browsers.

- **Values:** Any valid CSS measurement unit, like pixels, ems, or percentages. Percentages are based on the containing element's width.
- **Example:** `width: 250px;`

z-index

Controls the layering of positioned elements. Only applies to elements with a position property set to absolute, relative, or fixed (page 488). It determines where on the z axis an element appears. If two absolutely positioned elements overlap, the one with the higher z-index appears to be on top.

- **Values:** An integer value, like 1, 2, or 10. You can also use negative values, but different browsers handle them differently. The larger the number, the more “on top” the element appears. An element with a z-index of 20 appears below an element with a z-index of 100 (if the two overlap). However, when the element is inside another positioned element, it's “positioning context” changes and it may not appear above another element—no matter what its z-index value. See Figure 13-6.
- **Example:** `z-index: 12;`

NOTE

The values don't need to be in exact integer order. If element A has a z-index of 1, you don't have to set element B's z-index to 2 to put it on top. You can use 5, 10, and so on to get the same effect, as long as it's a bigger number. So, to make sure an element always appears above other elements, simply give it a very large value, like 10000. However, Firefox can only handle a maximum value of 2147483647, so don't set your z-index above that number.

Animation, Transform, and Transition Properties

CSS3 added some spiffy properties to transform elements by scaling, rotating, skewing, and moving them, as well as the ability to animate changes from one CSS property to another.

@keyframes

The heart of CSS animations is the @keyframes rule. It lets you name an animation, which you can then apply to any element on a page, and create a set of keyframes. (Keyframes, as described on page 355, are places within the animation where CSS

properties change.) For example, to fade the background of an element from black to white, you'd need two keyframes: The first keyframe sets the CSS background-color property to `black`, and the second keyframe sets it to `white`. You can have any number of keyframes in a variety of CSS properties.

At the time of this writing, you need to use vendor prefixes for an `@keyframe` rule, and animations don't work at all in Internet Explorer 9 and earlier.

- **Values:** The `@keyframes` rule isn't like any other CSS property—in fact, it's not a property at all. It's called an *at rule*, and it's more complex than a regular property. You need to supply a name (which you'll use later when you apply the animation to an element on the page) and then a set of braces: { }. Inside the braces are the keyframes, which can be as simple as the two keywords `from` and `to` to mark the first and last keyframes. Each keyframe has its own set of braces, in which you put CSS properties that you'd like to animate: `background-color`, `font-size`, `position` on the page, and so on. For detailed information on how animations work, turn to page 354.

- **Example:**

```
@keyframes myAnimation {  
  from {  
    background-color: black;  
  }  
  
  to {  
    background-color: white;  
  }  
}
```

animation

This is the shorthand method of applying an animation to an element. It's a compact way to include the following properties into one: `animation-name`, `animation-duration`, `animation-timing-function`, `animation-iteration-count`, `animation-direction`, `animation-delay`, and `animation-fill-mode`, all of which are explained in the following pages. As this is a CSS3 property, it requires vendor prefixes for most browsers and doesn't work in IE 9 and earlier.

- **Values:** A space separated list of values that includes the animation properties listed in the previous paragraph. For the exact type of values you need to supply for each, read the following entries (`animation-name`, `animation-duration`) and so on. Only two values are required—`animation-name` and `animation-duration`. Animation requires vendor-prefixes (page 209). You can apply multiple named animations to the same element by providing a comma-separated list of animation values.

- **Examples:**

```
animation: myAnimation 2s;  
animation: myAnimation 2s ease-in 2 alternate 5s forwards;  
animation: fadeOut 2s ease-in-out 2 alternate 5s forwards,  
glow 5s;
```

animation-name

Use this property to assign an animation that you've created with the `@keyframes` rule. You add this property as part of a CSS selector that applies to one or more page elements. For example, adding this property to a `h1` tag style, will tell a browser to run the specified animation on all `<h1>` tags when the page loads. You also need to assign the `animation-duration` property for this to work. This property requires vendor prefixes and doesn't work in IE 9 or earlier (page 209).

- **Values:** A name from an `@keyframes` rule.
- **Example:** `animation-name: myAnimation;`

animation-duration

Specifies how long an animation specified by the `animation-name` property takes to complete.

- **Values:** A value in seconds—`1s`—or milliseconds—`1000ms`.
- **Example:** `animation-duration: 2s;`

animation-timing-function

Dictates the speed of an animation within the allotted animation duration. For example, while you may set the duration of an animation to 5 seconds, you can also control how the animation plays back within that 5 seconds, such as starting slowly and finishing quickly. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** One of five keywords `linear`, `ease`, `ease-in`, `ease-out`, and `ease-in-out`. Can also supply a cubic Bezier value for a custom timing function (page 349).
- **Examples:**

```
animation-timing-function: ease-out;  
animation-timing-function: cubic-bezier(.20, .96, .74, .07);
```

animation-delay

Specifies a time in seconds or milliseconds that an animation should wait before beginning to play. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** A value in seconds—`1s`—or milliseconds—`1000ms`.
- **Example:** `animation-delay: 1.5s;`

animation-iteration-count

Specifies how many times an animation runs. Normally, an animation runs once and then stops, but you can make an animation run 4, 5, 100, or an infinite number of times. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** A positive integer or the keyword `infinite`.
- **Examples:**

```
animation-iteration-count: 5;  
animation-iteration-count: infinite;
```

animation-direction

When an animation runs more than once, this property specifies the starting point for each subsequent animation. Normally, a browser simply replays an animation from its original starting point, over and over. However, you can also make the animation forwards then backwards then forwards again. For example, if you have an animation that makes an element's background color progress from white to black, you may want to give it a pulsing quality by having it run many times and animate from white to black, then black back to white, then white to black, then black to white, and so on. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** The keyword `normal` or `alternate`. Normal is the way a browser already plays back animations, so you only need to use this property if you want to use the `alternate` keyword.
- **Example:** `animation-direction: alternate;`

animation-fill-mode

Dictates how an animated element should be styled at the beginning and/or end of an animation. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** One of three keywords: `backwards`, `forwards`, or `both`. Forwards is the most common as it leaves the element styled in the same way as the end of the animation instead of reverting back to the styling before the animation began.
- **Example:** `animation-fill-mode: backwards;`

animation-play-state

Controls whether an animation is playing or not. You can use this property on a `:hover` pseudo-class to pause an animation when a visitor hovers over the element. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** One of two keywords: `pause` or `running`. Paused stops the animation, while `running` makes it go. The default value is `running`.
- **Example:** `animation-play-state: paused;`

transform

Changes an element in one or more ways including scaling, rotating, skewing, or moving the element. Requires vendor prefixes and doesn't work in IE 8 or earlier.

- **Values:** Keywords `rotate()`, `translate()`, `skew()`, or `scale()`. Each keyword takes its own kind of value. For example `rotate` requires a degree value—`180deg`; `translate` requires a measurement like percentage, ems, or pixels; `skew` takes two degree values; and `scale` takes a positive or negative number. You can apply more than one type of transformation to an element.

- **Examples:**

```
transform: rotate(45deg);  
transform: scale(1.5);  
transform: skew(45deg 0) rotate(200deg) translate(100px, 0)  
scale(.5);
```

transform-origin

Controls the point at which a transformation is applied. For example, normally when you rotate an element, you spin it around its center. However, you can also rotate it around one of its four corners. Requires vendor prefixes and doesn't work in IE 8 or earlier.

- **Values:** Two values, one for the horizontal origin, the other for the vertical origin. You use the same keywords and values as for the `background-position` property (page 581).

- **Examples:**

```
transform-origin: left top;  
transform-origin: 0% 100%;  
transform-origin: 10px -100px;
```

transition

A shorthand method to specify the `transition-property`, `transition-duration`, `transition-timing-function`, and `transition-delay` properties (discussed next). Transitions tell a browser to animate changes in CSS properties on an element. For example, you can animate the change of a navigation button's background color from red to green as a visitor mouses over that button. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** A space separated list of properties, which include the `transition-property` (optional, defaults to `all`), `transition-duration` (required), `transition-timing-function` (optional, defaults to `ease`), `transition-delay` (optional, defaults to `0`).
- **Example:** `transition: background-color 1.5s ease-in-out 500ms;`

transition-property

Specifies the specific CSS properties that should be animated when an element's CSS properties change. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** An animatable CSS property (see page 346), or the keyword `all`.
- **Example:** `transition-property: width, left, background-color; transition-property: all;`

transition-duration

Specifies how long a transition animation takes to complete.

- **Values:** A value in seconds—`1s`—or milliseconds—`1000ms`.
- **Example:** `animation-duration: 2s;`

transition-timing-function

Dictates the speed of a transition animation within the specified duration. For example, while you may set the duration of a transition to 5 seconds, you can also control how the transition plays back within that 5 seconds, such as starting slowly and finishing quickly. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** One of five keywords `linear`, `ease`, `ease-in`, `ease-out`, and `ease-in-out`. Can also supply a cubic Bezier value for a custom timing function (page 349).
- **Examples:**

```
transition-timing-function: ease-out;
transition-timing-function: cubic-bezier(.20, .96, .74, .07);
```

transition-delay

Specifies a time in seconds or milliseconds that the transition animation should wait before beginning to play. Requires vendor prefixes and doesn't work in IE 9 or earlier.

- **Values:** A value in seconds—`1s`—or milliseconds—`1000ms`.
- **Example:** `transition-delay: 1.5s;`

■ Table Properties

There are a handful of CSS properties that relate solely to HTML tables. Chapter 10 has complete instructions on using CSS with tables.

border-collapse

Determines whether the borders around the cells of a table are separated or collapsed. When they're separated, browsers put a space of a couple of pixels between each cell. Even if you eliminate this space by setting the `cellspacing` attribute for

the HTML `<table>` tag to 0, browsers still display double borders. That is, the bottom border of one cell will appear above the top border of the cell below, causing a doubling of border lines. Setting the `border-collapse` property to `collapse` eliminates both the space between cells and this doubling up of borderlines (page 381). This property works only when applied to a `<table>` tag.

- **Values:** `collapse`, `separate`
- **Example:** `border-collapse: collapse;`

border-spacing

Sets the amount of space between cells in a table. It replaces the `<table>` tag's `cellspacing` HTML attribute. However, Internet Explorer 7 and earlier doesn't understand the `border-spacing` property, so it's best to continue to use the `cellspacing` attribute in your `<table>` tags to guarantee space between cells in all browsers.

NOTE

If you want to eliminate the space browsers normally insert between cells, just set the `border-collapse` property to `collapse`.

- **Values:** Two CSS length values. The first sets the horizontal separation (the space on either side of each cell), and the second sets the vertical separation (the space separating the bottom of one cell from the top of the one below it).
- **Example:** `border-spacing: 0 10px;`

caption-side

When applied to a table caption, this property determines whether the caption appears at the top or bottom of the table. (Since, according to HTML rules, the `<caption>` tag must immediately follow the opening `<table>` tag, a caption would normally appear at the top of the table.)

- **Values:** `top`, `bottom`
- **Example:** `caption-side: bottom;`

NOTE

Unfortunately, this property has no effect in Internet Explorer 6 or 7 (it works in IE 8), so it's safest to stick with the HTML equivalent: `<caption align="bottom">` or `<caption align="top">`.

empty-cells

Determines how a browser should display a table cell that's completely empty, which in HTML would look like this: `<td></td>`. The `hide` value prevents any part of the cell from being displayed. Instead, only an empty placeholder appears, so borders, background colors, and background images don't show up in an emptied cell. Apply this property to a style formatting the `<table>` tag.

- **Values:** show, hide
- **Example:** empty-cells: show;

NOTE The empty-cells property has no effect in Internet Explorer 7 and earlier.

table-layout

Controls how a web browser draws a table and can slightly affect the speed at which the browser displays it. The `fixed` setting forces the browser to render all columns the same width as the columns in the first row, which (for complicated technical reasons) draws tables faster. The `auto` value is the normal “browser just do your thing” value, so if you’re happy with how quickly your tables appear on a page, don’t bother with this property. If you use it, apply `table-layout` to a style formatting the `<table>` tag.

- **Values:** auto, fixed
- **Example:** table-layout: fixed;

Miscellaneous Properties

CSS 2.1 offers a few additional—and sometimes interesting—properties. They let you enhance your web pages with special content and cursors, offer more control over how a page prints, and so on. (Unfortunately, browser understanding of these properties is spotty at best.)

content

Specifies text that appears either before or after an element. Use this property with the `:after` or `:before` pseudo-elements. You can add an opening quotation mark in front of quoted material and a closing quotation after the quote. Internet Explorer 6 and 7 don’t understand this property, so its use is limited.

- **Values:** Text inside of quotes “like this”, the keywords `normal`, `open-quote`, `close-quote`, `no-open-quote`, `no-close-quote`. You can also use the value of an HTML attribute.
- **Examples:**

```
p.advert:before { content: "And now a word from our sponsor..."; }
```

```
a:after { content: " (" attr(href) ") "; }
```

NOTE Adding text in this way (like the opening and closing quote example) is called generated content. Read a simple explanation of the generated content phenomenon at www.westciv.com/style_master/academy/css_tutorial/advanced/generated_content.html. For a deeper explanation, visit www.w3.org/TR/CSS21/generate.html.

cursor

Lets you change the look of the mouse pointer when it moves over a particular element. You can make a question mark appear next to the cursor when someone mouses over a link that provides more information on a subject (like a word definition).

- **Values:** auto, default, crosshair, pointer, move, e-resize, ne-resize, nw-resize, n-resize, se-resize, sw-resize, s-resize, w-resize, text, wait, help, progress. You can also use a URL value to use your own graphic as a cursor (see the Note below). The look of a cursor when mousing over a link is pointer, so if you want to make some element on the page display the “click me” icon, you can add the declaration `cursor: pointer` to the style.
- **Example:** `cursor: help; cursor: url(images/cursor.cur);`

NOTE

Not all browsers recognize URL cursor values. For more information, visit www.quirksmode.org/css/cursor.html.

opacity

Lets you control the transparency of any element and all of its descendents. In this way, you can have underlying colors, images, and content show through an element. Note that if you apply opacity to a div, all of the items inside that div—headlines, images, paragraphs, and other divs—will share the same opacity level. In other words, if you set a `<div>` tag to `.5 opacity` (50% transparent), an image inside that div will also be 50 percent transparent—even explicitly setting the opacity of that image to 1 won’t override the 50 percent transparency.

- **Values:** A decimal value from 0 to 1. 0 is invisible, 1 is completely opaque.
- **Example:** `opacity: .5;`

orphans

Specifies the minimum number of lines of text that can be left at the bottom of a printed page. Suppose you’re printing your web page on a laser printer, and a five-line paragraph is split between two pages with just one line at the bottom of page one, and the four remaining lines at the top of page two. Because a single line all by itself looks odd (sort of like a lost *orphan*—get it?), you can tell the browser to break a paragraph *only* if at least, say, three lines are left on the bottom of the page. (At this writing, only the Opera browser understands this property.)

- **Values:** A number like 1, 2, 3, or 5.
- **Example:** `orphans: 3;`

page-break-after

Determines whether a page break (in printing) occurs after a particular element. With it, you can make sure that a particular paragraph is always the last item to appear on a printed page.

- **Values:** auto, always, avoid, left, right. Auto represents the normal value and lets the browser determine when and how to break content across printed pages. Always forces the element that follows to appear at the top of a separate printed page, and it's the only value that works consistently across browsers. Avoid prevents a page break after an element; it's a great way to keep a headline *with* the paragraph that follows it, but unfortunately, most browsers don't understand it. Left and right determine whether the element following appears on a left- or right-handed page, which may force the browser to print an extra empty page. But since no browsers understand these values, don't worry about wasting paper. Browsers treat left and right the same as always.
- **Example:** `page-break-after: always;`

page-break-before

Works like `page-break-after`, except the page break appears before the styled element, placing it at the top of the next printed page. You can use this property to make sure headlines for different sections of a long web page each appear at the top of a page.

- **Values:** Same as `page-break-after`.
- **Example:** `page-break-before: always;`

page-break-inside

Prevents an element from being split across two printed pages. If you want to keep a photo and its caption together on a single page, wrap the photo and caption text in a `<div>` tag, and then apply a style with `page-break-inside` to that `<div>`. (At this writing, only Opera understands this property.)

- **Values:** avoid
- **Example:** `page-break-inside: avoid;`

widows

The opposite of `orphans`, it specifies the minimum number of lines that must appear at the top of a printed page. Say the printer can manage to fit four out of five lines of a paragraph at the bottom of a page and has to move the last line to the top of the next page. Since that line might look weird all by itself, use `widows` to make the browser move at least two or three (or whatever number of) lines together to the top of a printed page. (Only Opera understands this property, so it's of limited use.)

- **Values:** A number like 1, 2, 3 or 5.
- **Example:** `widows: 3;`

CSS Resources

No one book—not even this one—can answer all of your CSS questions. Luckily, CSS resources abound for both beginning and expert web designers. In this appendix, you'll find resources to help you with general CSS concepts as well as specific CSS tasks, like building a navigation bar or laying out a web page.

■ References

References that cover CSS properties range from the official to the obscure. There are websites and online tutorials, of course, but you don't have to be on the Web to learn about CSS. Some of these guides come on good old-fashioned paper.

World Wide Web Consortium (W3C)

- **CSS Current Work** (www.w3.org/Style/CSS/current-work). Here you'll find all of the CSS specifications, including the newest additions. The different specifications are organized by status, like Completed, Revising, or Abandoned. You can click any specification to dig into the nitty gritty details, but just because a specification is listed as “completed” doesn't necessarily mean it's been fully implemented in all web browsers. However, this site does provide the final (sometimes overly complex and hard-to-understand) word on CSS.

Books

- ***Cascading Style Sheets: The Definitive Guide*** by Eric Meyer (O'Reilly). For comprehensive technical (yet readable) coverage of CSS, check out this guide.

Other Online References

- **CSS Reference at the Mozilla Developer Network** (https://developer.mozilla.org/en-US/docs/CSS/CSS_Reference). The Mozilla Developer Network (MDN) provides one of the most comprehensive references to CSS (as well as HTML5, JavaScript, and other web technologies).
- The **Sitepoint CSS Reference** (<http://reference.sitepoint.com/css>) provides a clear, designer-oriented reference to CSS properties and concepts. It's a good place to turn if the W3C or MDN docs cause your eyes to glaze over.
- **Can I use...** (<http://caniuse.com>). This frequently updated site provides detailed information on CSS and browser compatibility. Here, you'll be able to determine whether a particular CSS property works in Internet Explorer 9, for example.
- **CSS3 Files** (<http://www.css3files.com/>) provides very good instruction and even better demonstrations of popular CSS3 properties like animation, shadows, gradients, and more.

■ CSS Help

Even with the best references (like this book), sometimes you need to ask an expert. You can join a discussion list, where CSS-heads answer questions by email, or peruse a wealth of information in an online forum.

Discussion Boards

- **CSSCreator Forum** (www.csscreator.com/css-forum). A very active online forum offering help and advice for everything from basic CSS to advanced layout.
- **SitePoint.com's CSS Forum** (<http://www.sitepoint.com/forums/forumdisplay.php?53-CSS-amp-Page-Layout>). Another helpful group of CSS addicts.
- **CSS-Tricks.com Forum** (<http://css-tricks.com/forums>). A relative newcomer, this small forum holds some good information. (If you like PHP and JavaScript, there's some good discussion on those topics here as well.)

■ CSS Tips, Tricks, and Advice

The Web makes it easy for anyone to become a publisher. That's the good news. The bad news is, when everyone's a publisher, it's harder to sort through all the chaff to find the golden wheat of clear, concise, and accurate information. There's plenty of good CSS information on the Web—and a lot that's not good. Here are a few of the best destinations for CSS information:

- **CSS-Tricks.com** (<http://css-tricks.com>). This one-man blog is full of great CSS tips. You'll find frequently updated tips and tricks as well as comprehensive video tutorials.

- **Sitepoint** (www.sitepoint.com/tags/css). Lots of articles and tutorials on CSS techniques. You'll often find the latest news and information about CSS here, too.
- **Smashing Magazine** (www.smashingmagazine.com/tag/css). Smashing Magazine gathers some of the best resources on the Web, and in the CSS category, you'll find a nearly endless number of links highlighting some of the most creative thinking on CSS and web design.
- **NetMagazine** (<http://www.netmagazine.com/tag/css?ct=tutorial>). NetMagazine often has interesting and useful CSS tutorials.

■ CSS Navigation

Chapter 9 shows you how to create navigation buttons for your website from scratch. But online tutorials are a great way to solidify your knowledge. Also, once you understand the process in detail, you don't have to do it yourself every single time. On the Web, you can find examples of navigation features for inspiration.

Tutorials

- **Listutorial** (<http://css.maxdesign.com.au/listutorial>). Step-by-step tutorials on building navigation systems from unordered lists.
- **40 Premium CSS Menu and Navigation Solutions** (www.tripwiremagazine.com/2012/06/css-menu-and-navigation.html). More tutorials than you can shake a stick at.
- **The Apple.com navigation menu created using only CSS3** (www.marcofolio.net/css/the_apple.com_navigation_menu_created_using_only_css3.html). If you like the simple, clean appearance of Apple.com, you might be interested in how to create their menu with CSS.

Online Examples

- **CSS Navigation Bar Code Generator** (<http://lab.mattvarone.com/navbar>). Feeling lazy? Let this online tool create all the code you need to use the CSS sprite method described on page 314.
- **CSS Menu Maker** (<http://cssmenumaker.com>). Choose from a selection of fancy CSS3-rich navigation bars. You can customize them to fit your site, and then download the code.
- **CSS Showcase** (www.alvit.de/css-showcase). A gallery of navigation menus, tabs, and CSS navigation techniques.
- **Listamatic** (<http://css.maxdesign.com.au/listamatic>). Showcase of CSS-based navigation systems. Also lots of links to related websites.
- **Listamatic2** (<http://css.maxdesign.com.au/listamatic2>). More CSS menus, including nested lists with submenus.

- **CSS Menu Builder** (www.cssmenubuilder.com/). Lots of cool menus, many useful techniques. A must see.
- **Responsive CSS Navigation Menu** (<http://pixelsdaily.com/resources/html-css/responsive-css-navigation-menu/>). A responsive menu that changes from a horizontal bar, to a two-row bar, to a two-column stack of buttons.

■ CSS Layout

CSS layout is so flexible, you could spend a lifetime exploring the possibilities. And some people seem to be doing just that. You can gain from their labors by reading articles, checking out online examples, and experimenting with tools that can do some of the CSS work for you.

Box Model Information

- **Interactive CSS Box Model** (www.redmelon.net/tstme/box_model/). Fun, interactive tool for visualizing the box model.
- **Paul Irish's * { box-sizing: border-box } FTW blog post** (<http://paulirish.com/2012/box-sizing-border-box-ftw/>). An influential blog post that champions abandoning the old CSS box model and using the box-sizing property as a more sane way to keep track of element heights and widths.

Layout Examples

- **PageBlox** (www.pageblox.com). Provides an online tool for generating a CSS-based responsive design. It takes care of browser bugs and generates the media queries for large and small screens.
- **CSS Layout Generator** (www.pagecolumn.com). Pick the number of columns, tweak a few knobs, and this website generates all the HTML and CSS required. With a site like this, who needs a book? (Just kidding!)
- **Even More Layout Generators** ([www.webdesignbooth.com/15-extremely-useful-css-grid-layout-generator-for-web-designers](http://www.webdesignbooth.com/15-extremely-useful-grid-layout-generator-for-web-designers)). If you can't get enough of websites that automatically create your CSS and HTML, you'll find a list of 15 different online tools.
- **960 Grid System** (<http://960.gs>). One of the better CSS frameworks that provides a set of basic styles and a technique for using divs and class names to create complex, multicolumn, fixed-width layouts. (You can find a detailed video introduction to this system at <http://nettuts.com/videos/screencasts/a-detailed-look-at-the-960-css-framework/>). There's even an online tool to help you generate your own grid based on the 960 grid system: <http://grids.heroku.com>.

- **YUI Grids CSS** (<http://yuilibrary.com/yui/docs/cssgrids/>). Yahoo's very own CSS-layout system. It's a bit techy, but like the 960 Grid System, provides a basic framework for building complicated multicolumn layouts.
- **Twitter Bootstrap** (<http://twitter.github.com/bootstrap/>). A complete website toolkit, this site includes HTML, CSS, and JavaScript components that make it easy to build a complete, responsive, grid-based page, with some fancy JavaScript thrown in.
- **Foundation** (<http://foundation.zurb.com>). Another take on the complete website toolkit. Very much like Twitter bootstrap, Foundation includes HTML, CSS, and JavaScript. It has excellent documentation and is relatively easy to learn.

Miscellaneous Layout Resources

- **Adaptive CSS Layouts** (www.smashingmagazine.com/2009/06/09/smart-fixes-for-fluid-layouts). Provides many resources for building flexible layouts that adapt to the full width of the browser window.
- **One clean HTML markup, many layouts** (http://tjkdesign.com/articles/one_html_markup_many_css_layouts.asp). Great blog post that takes a single HTML page and demonstrates eight different ways to lay it out with just CSS.
- **Variable fixed width layout** (www.clagnut.com/blog/1663). Short blog post about a technique for adjusting the number of columns on a page, based on the width of the browser window.
- **3-Column Layout Index** (<http://css-discuss.incutio.com/?page=ThreeColumnLayouts>). A nearly exhaustive (or at least exhausting) list of different three-column layouts.

Showcase Sites

Knowing the CSS standard inside out is no help when your imagination is running dry. A great source of inspiration is the creative work of others. There are more CSS showcase sites than you can shake a search engine at, so here's a handful of sites where you can appreciate and study beautiful CSS designs.

- **CSS ZenGarden** (www.csszengarden.com). The mother of all CSS showcase sites: many different designs for the exact same HTML.
- **CSS Beauty** (www.cssbeauty.com). A wonderful gallery of inspirational CSS designs.
- **CSS Elite** (www.csselite.com). "Showcasing the best in CSS web design"...of course they all say that.
- **CSS Mania** (<http://cssmania.com>). Yet another showcase site, whose ungrammatical claim to fame is "Since March 2004, the most updated CSS showcase all over the globe."

- **CSS Winner** (www.csswinner.com). Highlights a new “winner” everyday. It’s unclear if the judges are really just teenagers surfing the Web from their bedrooms, but the site does highlight some very nicely designed sites.

■ CSS Books

Hey, not even this book can tell you *everything* there is to know about CSS!

- **Handcrafted CSS: More Bulletproof Web Design** by Dan Cederholm (New Riders). A bit dated, but this book has some great design and very good thinking about how to craft HTML for formatting with CSS.
- **Bulletproof Web Design** by Dan Cederholm (New Riders). A classic, updated for HTML5 and CSS3, covers how best to create CSS styles that can withstand the pressure of visitors changing text sizes, resizing their browser windows, and the general instability of the browser environment. Great tips on building layouts, navigation bars, and more.
- **Head First HTML with CSS & XHTML** by Elisabeth Freeman and Eric Freeman (O’Reilly). A lively, highly illustrated introduction to websites integrating HTML and CSS.
- **Stunning CSS3: A Project-Based Guide to the Latest in CSS** by Zoe Mickley Gillenwater (New Riders). Provides many good tips and techniques for using CSS3 to create attractive and flexible web pages.

■ CSS Software

There are lots of different ways to create Cascading Style Sheets. Keeping it simple, you can stick with the free text editors that come with Windows and Mac OS, like Notepad or TextEdit. There are also CSS-only editors and full-fledged web page-development programs like Dreamweaver that include CSS creation tools.

Windows and Mac

- **Style Master** (www.westciv.com/style_master/product_info). This powerful CSS editor with a long history includes many tools, including simple wizards to get you started, sample templates, tutorials, and a complete CSS guide.
- **Dreamweaver** (www.adobe.com/dreamweaver). Definitely not just for CSS, this premium web-development tool includes everything you need to build complete websites. Visual editing tools make it easier to see the effect of CSS on your web pages as you work.
- **Sublime Text** (<http://www.sublimetext.com>). This powerful code editor is useful for creating a wide variety of text documents. While not specifically a CSS tool, it’s a popular tool among web developers.

Windows Only

- **Top Style** (www.topstyle4.com). The venerable CSS editor that also lets you edit your HTML documents—a one-stop shop for web page building. Includes many tools to increase your productivity. There's also a free “lite” version.
- **Microsoft Expression Web** (www.microsoft.com/expression/products/Web_Overview.aspx). A complete website-construction tool that works very well with CSS.

Mac Only

- **Espresso** (<http://www.macrabbit.com/espresso/>). This all-in-one web design tool includes a code editor, an FTP program, and CSSEdit 3, a powerful, yet simple CSS editor.
- **Coda** (<http://panic.com/coda/>). Another all-in-one web-building tool with built-in CSS-editing tools.

Index

Symbols

3D transforms, 345

40 Premium CSS Menu and Navigation Solutions, 601

960 Grid System, 602

2011 BeerCamp website, 345

=\$ (“ends in”) selector, 317

=\$ (“ends with”) selector, 74

/* and */, for comments, 539

> (angle bracket), for child relationship, 74

- (“begins with”) selector, 73, 316
and `:not()` selector, 81

{ } (braces), 37
for internal style, 46

***= (contains) attribute selector**, 81

<![endif]--> statement, 559

/ (forward slash), for closing tags, 4

(hash symbol), for hex numbers, 564

<!--[if IE]> statement, 559

!important, 535
to override onscreen styling, 524
to override specificity, 111
for print, 525

@import directive, 41, 42–43, 355
for multiple style sheets, 547
Internet Explorer and, 522
for media queries, 462
for targeting version of IE, 560

@keyframes statement, 355, 588–589
for fade-in animation, 359–360

vendor prefixes, 372

@media statement, 355, 463, 522
for smartphone, 483

. (period), for class selector, 57

+ (plus sign), for adjacent sibling selector, 79

(pound symbol), for ID selectors, 61, 90

‘ (quotes), for animation name, 360

; (semicolon)
for end of `src` property, 139
for property/value pair, 38

~ (tilde), for general sibling combinatory selector, 80

*** (universal selector)**, 535
for formatting every tag with black text, 525

@viewport rule, 457

A

a:active state, 69

<abbr> tag (HTML), 20

absolute path, 244
for background image, 243

absolute positioning, 410, 488, 489, 491, 496, 510
overlapping elements from, 509–510
relative to boundaries of ancestor, 493–495

accent characters, 151

:active pseudo-class, 294, 295
of link, 341
as transition trigger, 345

- active state of link**, 69
- adaptive images**, 473
- <address> tag**, 29
- adjacent sibling**, 79
- adjacent sibling selector**, 91
- Adobe**
 - Acrobat files, assigning icon to link, 323
 - BrowserLab tool, 34
 - Edge Inspect tool, 470
 - text layout ideas, 436
 - TypeKit, 153
- :after pseudo-class**, 259, 428
- :after pseudo-element**, 71, 528
 - content property and, 595
- a: hover state**, 68–69
- alignment**
 - of form elements, 395–396
 - of text, 169
- a: link state**, 68
- all keyword, for transition property**, 347
- all media type**, 520
- alphabet, finding font with alphabet by language**, 148
- alphabetic glossary, links to alphabet letters**, 62
- alpha channel**, 155
- alpha transparency, in PNG32 files**, 242
- alternate keyword**, 363
 - for animation-direction property, 364
- Amazon sprites**, 315
- ancestor styles, conflict resolution**, 105
- ancestor tag**, 65
- anchor tag**. *See* <a> tag (HTML); links
- Android browser**
 - box-sizing property in, 216
 - and element corners, 209
 - vendor prefix for box shadow, 212
 - WOFF fonts and, 133
- angle bracket (>), for child relationship**, 74
- animation**, 354–366. *See also* transitions
 - adding, 369–374
 - applying to element, 359–361
 - of CSS properties, 346
 - delaying beginning, 362
 - finishing, 363–364
 - keyframes in, 354
 - defining, 355–359
 - @keyframes rule for fade-in, 359–360
 - of opacity property, 499
 - pausing, 365–366
 - properties, 588–593
 - of rotating element, 337
 - speed of, 372
- animation-delay property**, 590
- animation-direction property**, 363, 591
 - alternate value for, 364
- animation-duration property**, 360, 361, 590
- animation-fill-mode property**, 591
 - forwards value, 364
- animation-iteration-count property**, 363, 591
- animation-name property**, 360, 590
- animation-play-state property**, 365, 591
- animation property**, 370, 589–590
 - shorthand, 364–365
- animation-timing-function property**, 361, 590
- anti-aliasing**, 130
- Apple**
 - Boot Camp software, 34
 - Horizontal 3D picture gallery, 345
 - Morphing Power Cubes, 345
- Arial Black font**, 131, 132
- Arial font**, 130
- Arial Narrow font**, 131
- arrow notations**, 11
- <article> tag (HTML5)**, 23, 24, 25, 30, 409, 443
- <aside> tag (HTML5)**, 23, 25, 441
- <a> tag (HTML)**, 5. *See also* links
 - browser predefined style for, 106
 - as inline tag, 200
 - width for, 306, 311
- at rule**, 355, 589. *See also* @...
- attaching**
 - multiple style sheets to web page, 42
 - style sheet to web page, 41

attributes, 5
 adding class to tag, 59
 for <body> tag. those to avoid, 26
 for <style> tag, 40
 vs. CSS, 27

attribute selectors, 72–74, 316
 for form styling, 387
 for submit buttons, 397

<audio> tag (HTML5), 24

auto keyword

for margin property, 227, 229, 449
 for overflow property, 217–218
 for width property, 466, 481

a:visited state, 68

B

background

floated elements and, 222
 properties for, 579–582

background-attachment property, 251, 579

background attribute of <body> tag, CSS alternatives, 240

background-clip property, 252, 579–580

background shorthand and, 256

background color

alternating for rows, 76
 background image combined with, 285
 for block level element, 230
 color gradients, 259–269
 with Colorzilla, 269–272
 linear gradients, 260–264
 radial, 266–269
 vendor prefixes and Internet Explorer, 264

for headlines, 230
 for hover state, 368
 for <nav> element, 450
 of padding, 195
 for page, 189, 226
 print style sheet to remove, 526
 RGBA for transparency, 206
 for sidebar, 234
 styling for print, 525–527
 tutorial, 225–229

background-color property, 87, 194, 206, 526, 580
 animating change, 369

for buttons, 301
 for tag, 274
 ::selection selector to change, 71

background-image property, 91, 178, 240–244, 415, 495

for <body> tag, 242–243
 for buttons, 301
 for <html> tag, 49
 for links, 302

for multiple background images, 257–259

for page, 283
 repetition, 244–245
 tutorial, 282–291

background images, 2

background color combined with, 285

for <body> tag, 119
 defining origin and clipping, 252–253
 faking multiple for Internet Explorer, 259

fixing in place, 250–251
 for links, 299, 321–322
 media queries and, 459
 multiple, 257–259

of padding, 195
 pixels or ems for positioning, 248–249

positioning, 245–254
 padding for, 321
 percentage values for, 249–250
 scaling, 253–254
 for sidebar, 288–291
 under sidebar, 431–436
 styling for print, 525–527
 for table, 393
 for tables, 382

background-origin property, 252, 580–581

background shorthand and, 256

background-position property, 246–247, 286, 303, 314, 581

for bulleted list, 287
 for element with gradient background, 262
 for graphic link, 303

background property, 579

for column in tables, 383
 for html property, 189
 for link as button, 300

- for navigation a style, 326
- shorthand, 255–256, 264, 327
- with multiple images, 289
- background-repeat property**, 244–245, 246, 257, 581
 - no-repeat option, 284, 302
- background-size property**, 253, 582
 - background shorthand and, 256
- backwards keyword, for animation-fill-mode property**, 591
- bandwidth, image file size and**, 472
- banners**
 - adjusting for print, 534
 - enhancing, 507–510
 - position property for, 506
 - set height for, 215
 - vertical or horizontal, 246
- base font of web page**, 181
- baseline keyword, for vertical-align property**, 379, 571
- base text size**, 158
 - percentage changes to, 159
- :before pseudo class**, 259
- :before pseudo-element**, 70, 290
 - content property and, 595
- “begins with” (-) selector**, 73, 316
 - and :not() selector, 81
- beveled design for button**, 300
- Bezier curve**, 349–350
- BgPatterns**, 256
- blinking text**, 163, 570
- block boxes**, 200
- block elements**, 60
 - converting link to, 303
 - display property for, 583
 - floating, 221
- block-level tag**, 200
- <blockquote> tag (HTML)**, 19, 29, 409
- block value, for display property**, 303
- blurriness of text shadow**, 166
- body style**, 226
- <body> tag (HTML)**, 5, 64
 - attributes to avoid, 26
 - background attribute, CSS
 - alternatives, 240
 - background image for, 248
 - background-image property, 242–243
 - class attribute, 329, 330
 - class for home page, 555
 - class style for, 99–100
 - style for, 49
- bold type**, 107, 319, 569
 - for Internet Explorer, 144–146
 - from web fonts, 140–146
 - tag (HTML) for, 5
 - for words and letters, 162–163
- border-bottom property**, 52, 204, 574
 - for links, 298
- border-bottom-style property**, 575
- border-bottom-width property**, 576
- border-box option, for box-sizing property**, 216
- border-box value**
 - for background-clip property, 252
 - for background-origin property, 252
 - for box-sizing property, 439
- border-collapse property**, 380, 381, 393, 593–594
 - for table, 392
- border-color property**, 205, 574
- border declaration property**
 - for link, 319–320
- border-left property**, 204, 574
- border-left-style property**, 575
- border-left-width property**, 576
- border property**, 285, 321, 573–574
 - for tag, 274
 - inheritance and, 95–96
 - for link as button, 300
 - shorthand, 203
 - for tables, 380–381
- border-radius property**, 207–209, 574
 - for buttons, 300, 301, 399
 - for table cells, 381
- border-right-color property**, 205
- border-right property**, 204, 574
- border-right-style property**, 205, 575
- border-right-width property**, 205, 576
- borders**, 193, 194, 202–205
 - advantages, 164
 - bottom for navigation bar, 327
 - and column layout, 438
 - and element size, 576
 - floatated elements and, 222
 - for button, removing, 398
 - formatting individual, 204–205
 - for images, 239
 - inheritance inaction, 101
 - in navigation bar, 307

lines for headlines, 85
of linked images, 551
properties for, 573–578
replacing with graphics, 285–286
for separating columns, 447
space between content and, 195
style for decorative, 183
for table cells, 391
 browser default for, 550
for `` tag, 332

border-spacing property, 380, 594
border-style property, 205, 575
border-top property, 204, 574
border-top-style property, 575
border-top-width property, 576
border-width property, 205, 575–576
both keyword, for clear property, 223
bottom keyword
 for background-position
 property, 246
 for transform-origin property, 344
 for vertical align property, 379

bottom property, 490, 582
Box Alignment module, 9
box model in CSS, 193–195
 box-sizing for redefining width, 215–217
 calculating actual width and
 height, 213–215
 and float drops, 437
 height and width properties, 212–219
 margins and padding, 195–202
 online information, 602
 resetting, 467–468
 tutorial, 225–238
 types of boxes, 200

box-shadow property, 210, 228, 573
 for button, 300, 301
 for photo gallery, 281
 RGBA and, 155
 for tables and cells, 381

box-sizing property, 447, 467, 576
 float drop prevention with, 439–440
 for redefining width, 215–217

braces ({ }), 37
 for internal style, 46

braille media type, 520
breakpoints for media queries, 459–465
browsers. *See* web browsers

Browsershots, 34
BrowserStack, 34
**
 tag (HTML)**, 4, 26, 427
**
 tag (XHTML)**, 4, 30, 427
** tag (HTML)**, 26, 146
bulleted lists, 173, 202
 customizing, 177
 graphics for, 286–288
 for links, 297
 margins for, 289
 `` tag for, 20
 padding property use by browsers to
 indent, 115

**Bulletproof Web Design
(Cederholm)**, 604

bullets
 custom for list, 248, 249
 finding free graphics for, 256
 graphic, 176–178
 positioning in lists, 174–176
 removing from navigation bar
 list, 305
 sites with free, 176
 types of, 173, 573

bullseye look, 269

buttons
 centering text, 311, 333
 on forms, 386
 : hover state for color change, 346
 link appearance as, 297
 for links, 299–302
 scaling on mouseover, 367–368
 width for navigation bar, 306

C

cache
 for external style sheet, 39
 for web browsers, 550

Can I use.. website, 600
capitalization of text, 163, 571
**capitalize keyword, for text-transform
property**, 163, 571

captions, 275
 `<div>` tag to group with photo, 60
 hiding, 513
 placing on photos, 510–516
 positioning, 499
 size of, and reflow, 279
 of table, 391
 width of, 276

- caption-side property**, 594
- <caption> tag (HTML)**, 377
- carriage return, as space**, 310
- cascade**, 97, 100, 103–124, 393
 - controlling, 111–117
 - properties applied with, 104–108
 - specificity in, 108–111
 - tutorial, 117–124
 - CSS reset, 117–119
 - hybrid style creation, 119–120
- Cascading Style Sheets (CSS)**. *See also* CSS layout
 - attributes vs., 27
 - benefits, 1, 2
 - comments, 442
 - different flavors, 9
 - formatting with, 21
 - help, 600
 - how it works, 1–13
 - HTML vs., 2
 - navigation, 601–602
 - Object Oriented, 558
 - references, 599–600
 - showcase sties, 603–604
 - software, 7–13, 604–606
 - specification modules, 563
 - tips, tricks, and advice, 600–601
 - validating code, 41
 - writing HTML for, 20–30
- case sensitivity of class names**, 58
- c-click (Mac)**, 10
- Ceasar tool**, 349–350
- Cederholm, Dan**, 431
 - Bulletproof Web Design, 604
 - Handcrafted CSS, 604
- cellspacing attribute, of <table> tag**, 594
- centering**
 - content, 91
 - horizontal navigation bar, 309
 - paragraph, 169
 - text in button, 311, 333
- center keyword**
 - for background-position property, 246
 - for text-align property, 169, 379
- center of radial gradient**, 267
- characters**. *See* letters (characters)
- character sets**, 151
- checkboxes**, 73, 386
 - :checked pseudo-class for, 389
- :checked pseudo-class**, 389
- child selectors**, 74–79
- child tag**, 65
- child type selectors**, 77–79
- Chrome browser**, 6, 34
 - Developer's Tools, 110
 - font types used by, 139
 - form field display, 385
 - gradients in, 264
 - HTML Tidy extension, 27
 - text-transform property and, 173
 - vendor prefix for transforms, 336–337
- circular corners**, 208
- circular gradients**, 266
- <cite> tag (HTML5)**, 26, 29
- class attribute**, 22, 554
 - adding to tag, 59
- classes**, 553–558
 - adding to navigation bar links, 329
 - attribute selectors for, 73
 - for <body> tag (HTML), 329
 - for differently sized images, 471
 - for <div> tags, 408
 - for fine-tuning formatting, 187–188
 - for external links, 295
 - for images, 478
 - increasing specificity, 111
 - using multiple, 479, 542–545
 - for navigation links list, 304
 - pseudo-classes, 68–72
 - for <p> tag, 188
- class selectors**, 53, 57–60, 330
 - replacing ID selectors with, 114–115
 - specificity, 108
 - tutorials, 85–88
- class styles**, 118
 - applying animation to, 359
 - vs. attribute selector, 74
 - background-color property in, 206
 - for <body> tag, 99–100
 - descendent selector for, 67
 - for first paragraph, 122
 - ID style and, 107
 - for tag, 274
 - vs. tag style, 100
- clearing float**, 425–440
- clear property**, 223–225, 427, 428, 481, 582–583

- for footer, 445
- Clear Type**, 130
- click**, 10
 - translate in response to, 341
- clicked link**, 293
- clipping, defining for background images**, 252–253
- clip property**, 583
- closest-corner keyword, for radial gradient**, 267–268
- closest-side keyword, for radial gradient**, 267–268
- closing tags**, 30, 45
 - `</style>`, 47
- Coda2 (Mac)**, 7
- Coda (editing software)**, 605
- code**
 - HTML-only vs. HTML with CSS, 18
 - JavaScript location in, 40
- `<code>` tag (HTML)**, 20, 21
- `<colgroup>` tag (HTML)**, 377, 383–384
- collapse keyword, for border-collapse property**, 381
- collapsing margins**, 198, 199
- collection of fonts**, 148, 150
- colliding margins**, 197–198
- color**
 - of background, 206
 - for `<body>` tag, 119
 - of border, 574
 - of borders, 202–203
 - of buttons, `:hover` state for changing, 346
 - formatting text with, 154–157
 - keywords in HTML, 155
 - of background, 87
 - of text, changing for unvisited link, 294
 - of outlines, 577
 - property values for, 563–565
 - resources on coordinating, 154
 - solid, from linear gradient, 434
 - of text shadow, 166
- color gradients**, 259–269
 - with Colorzilla, 269–272
 - radial, 266–269
 - repeating, 269
 - repeating, 265–266
 - vendor prefixes and Internet Explorer, 264
- color pickers in Windows and Mac**, 154
- color property**, 37, 154, 567
 - for button, 301
 - for text, 98
 - for `<h1>` tag, 182
 - inheritance, 119
 - `::selection` selector to change, 71
 - for tables, 378
- color stops in gradients**, 262–263, 434
 - in Colorzilla, 270
 - matching column widths, 435
- Colorzilla**, 269–272
- ColourLovers.com**, 256
- `<col>` tag (HTML)**, 377, 383–384, 390
 - width setting, 394
- column-count property**, 430
- column-gap property**, 430
- column-rule property**, 430
- columns in tables**
 - background property for, 383
 - formatting, 383–384
 - styles for, 381–384
- columns on web page**
 - adjusting for media queries, 457
 - color stops matching widths, 435
 - `<div>` tag for, 118
 - floating, 421–423
 - full-height, 430–436
 - linear gradients for
 - background, 433–436
 - multiple, 418
 - rule (line) between, 430
 - tutorial, 440–452
 - adding column, 443–445
 - HTML structure, 440–441
 - layout styles, 441–443
 - padding, 445
 - width, in responsive web design, 476
- column wrapper**
 - in mobile web design, 476, 481
 - for smartphone, 483
- comments (CSS)**, 442, 539–540
 - to separate style groups, 545–546
- comments (HTML)**, 441, 443–444
- Compass.app**, 543
- Compatibility View List (Microsoft)**, 33
- complex grid layout module**, 436
- compression of graphics files**, 242

- conditional comments, for Internet Explorer**, 559–560
- container element, width of**, 421
- containing element**
 - floated elements and, 221
 - floating, and containment of elements inside, 428
 - width of, 196
- containing float**, 425–440
- containing keyword, for background-size property**, 254
- contains (*=) attribute selector**, 81
- content**
 - controlling flow, 217–218
 - float property for wrapping, 220–225
 - height of area, 584
 - hiding on handheld devices, 458
 - as layout starting point, 412
 - left margin for, and sidebar width, 419
- content attribute, in <meta> tag**, 456
- content-box value**
 - for background-clip property, 252
 - for background-origin property, 252
 - for box-sizing property, 216, 439
- content management system**, 558
- content of box**, 194
- content property**, 528, 595
- contrast in graphic design**, 162
- converting font formats**, 135
- copyright notice**
 - fixed positioning for, 514
 - font size for, 536
 - preventing wrap, 223
 - in print, 533
- corners, rounded**, 207–209
 - for sidebar, 235
- counter-clockwise rotation, negative numbers for**, 337
- Courier font**, 132
- cover keyword, for background-size property**, 254
- Coyier, Chris**, 436, 473
 - CSS-Tricks.com blog post, 425
- Creative Commons licenses**, 256
- cropping picture, negative values for**, 248
- cross browser testing**, 34
- cross-browser display problems**
 - avoiding inconsistencies, 115
 - style eliminating, 225
- CrossBrowserTesting.com**, 34
- CSS**. *See also* Cascading Style Sheets (CSS)
- CSS3 Button generator**, 302
- CSS3 Files website**, 600
- CSS3 pattern gallery**, 265
- CSS Beauty**, 603
- CSS box model**. *See* box model in CSS
- CSSCreator Forum**, 600
- CSS Elite**, 603
- .css extension**, 41, 48
- CSS grid layout module**, 413
- CSS layout**, 405–416. *See also* <div> tag (HTML)
 - how it works, 408–411
 - layering elements, 415–416
 - multi-column layouts, 413
 - resources, 602
 - sketches, 413–414
 - identifying boxes, 414
 - strategies, 412–416
 - techniques for, 410–411
- CSS Layout Generator**, 602
- CSS Mania**, 603
- CSS Menu Builder**, 602
- CSS Menu Maker**, 601
- CSS Navigation Bar Code Generator**, 601
- CSS Positioning**, 487. *See also* positioning
- CSS reset**, 115–116, 195
 - tutorial, 117–119
- CSS Showcase**, 601
- CSS Sprites**, 314, 328, 329
- CSS-Tricks.com**, 425, 600
- CSS Winner**, 604
- CSS ZenGarden**, 241, 603
- Ctrl-click (Windows)**, 10
- cubic-Bezier curve**, 362
 - for animation-duration property, 361
 - for transition-timing-function property, 349–350
- cursor property**, 596
- curves for element corners**, 207–209

D

- dashed border**, 203, 575
 - background color and, 206
- <dd> tag (HTML)**, 29
- decimal values, for column width percentages**, 469
- declaration block**, 35, 37, 55
 - for class styles, 59
- decorative border**, 183
- default design, desktop vs. mobile**, 460
- default font of web browser**, 128
- default values, for background properties**, 255–256
- definition description, <dd> tag for**, 29
- definition list, <dl> tag for**, 29
- definition term, <dt> tag for**, 29
- degrees, for direction of linear gradient**, 261
- delay**
 - for animation, 362, 590
 - for transition start, 351–352
- descendent selectors**, 63–64, 107, 182, 321, 553–558
 - creating, 65–67, 120
 - <div> tag and, 554–555
 - for grouping links, 296–297
 - for tag inside <figure> tag, 276
 - for links, 322–323
 - for images, 240
 - for images inside figure, 278
 - for module of code, 67–68
 - for sidebar, 236
 - specificity, 109
 - for table cells, 380
 - to format navigation links, 325
 - tutorials, 88–89
 - universal selector as part, 63
- descendent tags**, 65, 93
- desktop computers**
 - media queries for, 460
 - web browsing on, 457
- device pixel, vs. CSS pixel**, 473
- disabled form elements**, 389
- display**
 - size variations, 405–407
 - style eliminating cross-browser problems, 225
- display area of browser window**, 490
- display: block property**, 311
 - for <a> tag, 326
- Display fonts**, 148
- display:inline-block property**, 201, 280, 307, 388
 - for navigation bars, 308–310
- display: inline property, for navigation bars**, 308–310
- display property**, 202, 303, 583–584
 - to hide or display elements for print, 528
 - for image in table cell, 379
 - for tag, 308
 - options, 202
 - for print style sheet, 531
 - vs. visibility property, 498
- <div> tag (HTML)**
 - float property, 417
- <div> tag (HTML)**, 22, 25, 30, 60, 182, 408–409, 411
 - absolute positioning relative to parent, 494
 - for announcement to fade into view, 359–360
 - as block-level tag, 200
 - code order, screen readers and, 422
 - for columns on page, 118
 - to control entire page width, 448
 - descendent selectors, 554–555
 - determining need for, 409
 - inheritance and, 95
 - for navigation links, 296
 - for page elements, 505
 - for page layout, 528
 - scaling, 338
 - for sidebar, 196, 234–236, 441
 - style for page content, 284
 - width property, 189
- <dl> tag (HTML)**, 29
- DOCTYPE declaration**, 3, 4
- document--relative links**, 80
- document-relative path**, 243, 244
 - for style sheet location, 50
- Document Type Definition (DTD)**, 30–32
- document types**, 3–13
- dotted border**, 203, 575
 - background color and, 206

- double borders**, 203, 575
 - eliminating from tables, 381
 - double-click**, 10
 - double-colon syntax**, 69
 - download**
 - @import directive and, 43
 - web fonts, 129
 - time required, 150–151
 - dragging**, 10
 - Dreamweaver**, 8, 604
 - doctype declaration added by, 31
 - drop cap**, 69
 - drop-down menus**
 - disappearing slowly, 352
 - on forms, 386
 - drop shadows**, 49, 51, 91, 210–212, 573
 - for glow, 399
 - for photo gallery, 281–282
 - for sidebar, 235
 - for text, 570
 - DTD (Document Type Definition)**, 30
 - <dt> tag (HTML)**, 29
-
- E**
- ease-in keyword**
 - for animation-duration property, 361
 - for transition-timing-function property, 348
 - ease-in-out keyword**
 - for animation-duration property, 361
 - for transition-timing-function property, 348
 - ease-in timing method**, 369
 - ease keyword**
 - for animation-duration property, 361
 - for transition-timing-function property, 348
 - ease-out keyword**
 - for animation-duration property, 361
 - for transition-timing-function property, 348
 - EditPlus (Windows)**, 7
 - elements**
 - breaking out of box, 503–504
 - overlapping, from absolute positioning, 509–510
 - stacking, 497–498
 - element selectors**, 56. *See also* tag selectors
 - elliptical corners**, 208
 - elliptical radial gradients**, 270
 - email links**, 317, 321
 - embossed media type**, 520
 - em measurement unit**, 37, 213, 566
 - converting fixed-sized type to, 469
 - for text-indent property, 169
 - for line spacing, 168
 - for margin or padding, 196
 - for text size, 160
 - empty-cells:hide property**, 384
 - empty-cells property**, 594
 - tag (HTML)**, 26, 140, 143, 162
 - enabled form elements**, 389
 - ending tag in HTML**, 4
 - “ends in” (\$=) selector**, 317
 - “ends with” (\$=) selector**, 74
 - EOT (Embedded Open Type) file format**, 133
 - erasing styles built-in to web browsers**, 115–117
 - Espresso**, 605
 - even child elements, selecting**, 76
 - Even More Layout Generators**, 602
 - Exljibris font foundry**, 134
 - experimental CSS property**, 209
 - Expression Web**, 8
 - doctype declaration added by, 31
 - Extensible Markup Language (XML)**, 6
 - external links**
 - class for, 295
 - style to highlight, 73
 - external style sheets**, 41–43, 274
 - conflict with internal style sheet, 110
 - internal vs., 178–179
 - <link> tag for, 42
 - link to Google fonts, 147
 - media type for, 522
 - for responsive web design, 460
 - specifying graphic in, 177
 - tutorial on creating, 48–54
 - using multiple, 113
 - vs. internal, 39
-
- F**
- fade-in animation, @keyframes rule for**, 359–360
 - fading element into view, animation for**, 355
 - farthest-corner keyword, for radial gradient**, 267–268

- farthest-side keyword, for radial gradient**, 267–268
- faux column technique**, 431–436
- <fieldset> tag (HTML)**, 386
- <figcaption> tag (HTML5)**, 23, 275, 499, 511
 - absolutely positioned, 512
- <figure> tag (HTML5)**, 23, 275, 410, 499, 511
 - descendent selector for tag inside, 276
 - for photo gallery, 278
- file formats, for graphics**, 242
- file size for images, bandwidth consumption and**, 472
- file types**
 - for fonts, 133–134
 - icons for different, 323
 - links to specific types, 317
- filtering fonts by category**, 148
- finding**
 - free images, 256
 - Google web fonts, 148–150
 - web fonts, 134–135
- Firefox**, 6, 34
 - box-sizing property in, 216, 468
 - form field display, 385
 - gradients in, 264
 - padding property for indenting
 - bulleted lists, 115
 - transitions and, 348
 - vendor prefix
 - for transforms, 336–337
 - vendor-prefix, 71
 - Web Developer extension for, 27
- Fireworks CS6**, 314
- :first-child pseudo-class**, 75–76
- first letter or first line of paragraph**
 - formatting, 171–173
- :first-letter pseudo-element**, 69, 171
- first line indents**, 169–171
- :first-line pseudo-element**, 69, 171, 184
- :first-of-type selector**, 77
- FitVids JavaScript program**, 473
- fixed design, mixing with liquid**, 450–452
- fixed elements**, 488
- fixed keyword**
 - for background-attachment property, 251
- fixed positioning**
 - for copyright notice, 514
 - frames from, 504–507
- fixed-width layouts**, 405
 - converting liquid layout to, 421, 448–450
 - converting to flexible grids, 468–470
 - vs. flexibility, 465
- Flash content, scaling to containers**, 473
- flexbox**, 436
- flexible box layout module**, 413
- flexible box model**, 431, 436
- flexible grids**
 - converting fixed-width layouts to, 468–470
- flexible grids for layout**, 465–470
- flexible media**, 455
- Flickr**, 256
- flipping element upside down and backwards**, 340
- float-based layout, problems printing**, 534
- floated element**
 - ignoring, 222–225
 - preventing drops, 437–439, 446–447, 467
 - width for, 419
- floating**
 - applying to layout, 421–425
 - of caption with image, 275
 - clearing and containing, 425–440
 - columns on web page, 421–423
 - horizontal navigation bars, 310–313
 - images, 240
 - list items, 313
 - troubleshooting problems, 425–440
 - within floats, 423–425
- float property**, 186, 220–225, 417, 584
 - and absolute or fixed positioning, 488
 - and HTML source order, 466
 - for tag, 274
 - for layout, 410
 - none keyword, 480
- flow of content, controlling**, 217–218
- fluid images**, 470–473
 - tutorial, 477–479
 - W3C community group to study, 473

:focus pseudo-class, 70, 294, 389, 401
for transition trigger, 345, 351

:focus selector, 70

folders for fonts, 142

font color, 37

Fontex.org, 135

@font-face directive, 129, 132, 137-140
for font variants, 141-143
for headlines, 143
for Internet Explorer, 144
for loading web fonts, 180-181
tutorial, 178

@font-face Generator, 135-137

@font-face Kits, 135

font family

declaration, 52
in font property, 170

font-family property, 127, 181, 568

in @font-face directive, 138
for <h1> tag, 182
inheritance, 119
limitations, 132

font property, 170, 183

for button, 301
shorthand, 568

fonts, 127-132

alternative options, 129
changes, 157-162
choosing common, 129-132
file types, 133-134
generating multiple formats, 135-137
Google web fonts, 146-153
inheritance for, 95
licenses for, 134
points for measuring, 524
quote marks for multi-word
names, 129
of table text, 391-392
web browser default, 128
web fonts, 132-146

font services, 153

font size, 37

browser default for, 549
changes for media queries, 458
in font property, 170
for print, 524, 535

font-size property, 37, 157, 181,

484-485, 568-569
for <h1> tag, 182
line-height property and, 168

Font Squirrel, 133, 135, 135-137

font-style property, 162, 569

in @font-face directive, 141
in font shorthand property, 170
font variants and, 146

** tag (HTML)**, 2, 19, 21

alternative to, 56

font-variant property, 163, 569

font-weight property, 107, 140, 143,

162, 319, 569
in @font-face directive, 141
font variants and, 146
for Google web fonts, 152

footer

float and, 426
position property for, 506
problems from, 444

<footer> tag (HTML5), 6, 23, 25, 30,
409, 415

forcing reload for web page, 39

formatting text

black color for printing, 525
classes for fine-tuning, 187-188
color, 154-157
CSS for, 21
drop shadows, 166-167
first letter or first line of
paragraph, 171-173
fonts, 127-132
choosing common, 129-132
file types, 133-134
generating multiple formats, 135-
137
web fonts, 132-146
font size changes, 157-162
for printing, 535-536
paragraphs, 167-173
aligning text, 169
first line indents and removing
margins, 169-171
space adjustment between text
lines, 167-168
properties for, 567-572
shorthand method for, 170
styling lists, 173-178
tutorial, 178-192
finishing touches, 188
headings and paragraphs, 182-185
lists, 185-187

words and letters, 162–166
 capitalizing, 163
 text-decoration property, 163–165
 zeroing out, 548–552

form elements (HTML), 386–387

alignment, 395–396
 style for, 399

form pseudo-classes, 389

forms, 384–389

attribute selector for, 73
 browser variations in display, 385
 layout with CSS, 387–389
 tutorial, 395–402

forwards keyword, for animation-fill-mode property, 591

forward slash (/), for closing tags, 4

forwards value

for animation-fill-mode
 property, 364

Foundation, 425, 603

frameset, 504

frames, from fixed positioning, 504–507

framing images, 273–277

free fonts, 134

Freeman, Elisabeth, Head First HTML with CSS & XHTML, 604

from keyword, for @keyframe, 356

fun fonts, 131

G

Gallagher, Nicolas, 428

general sibling combinatory selector, 80

generated content, 71, 177, 259, 595

Georgia font, 130

GIF (Graphics Interchange Format) files, 242

Gillenwater, Zo Mickley, Stunning CSS3, 604

glossary

creating, 29
 links to alphabet letters, 62

glow, 212, 228, 374

for button, 398
 drop shadow for, 399

Google

on search-friendly websites, 22
 showcase of best fonts from, 149
 web fonts, 50, 51

Google Analytics, 32

Google Chrome. See Chrome browser

Google fonts, 134, 135, 146–153

finding and selecting, 148–150
 numerical values for font
 weights, 162
 using, 150–153

gradient backgrounds, 259–269

linear, 260–264
 for column background, 433–436
 radial, 266–269
 repeating linear, 265–266
 repeating radial, 269

gradient image, linear gradient vs., 283

graphic bullets, 176–178

graphic design

contrast in, 162
 grid for layouts, 425

graphics. See also tag (HTML)

adding to links, 302–304
 file formats, 242
 for bulleted lists, 286–288
 for element background, 242
 in <header> tag, positioning, 508–509
 multiple in one file, 314–315
 positioning background image, 245–254
 replacing borders with, 285–286
 specifying in external style
 sheets, 177

graphics programs, for web-page mock-ups, 413

Gridinator, 422

grids for layout, 425

in responsive web design, 455

groove border, 203, 575

grouping links, descendent selectors for, 296–297

grouping, to organize styles, 545

group selectors, 62–63, 557–558

tutorial, 84

groups of tags, styles for, 62–63

gutter, 195, 425. See also space

H

<h.> tag (HTML), 28

<h1> tag (HTML), 18, 20, 182
inline style for, 44
internal style sheet for, 45
style, 230–232

<h2> tag (HTML), 18, 232
style
for graphic border, 285–286
style for, 120, 183

h3 style, 183–184

Handcrafted CSS (Cederholm), 604

handheld devices. *See* mobile devices

handheld media type, 520

Handwriting fonts, 148

hanging indent, 170

hash symbol (#), for ID style, 61

<header> tag (HTML5), 6, 23, 25, 409,
410, 415
positioning graphic in, 508–509

**Head First HTML with CSS & XHTML
(Freeman and Freeman)**, 604

headings, 28

formatting, 182–185

headlines

background color for, 230
as block-level tag, 200
border line for, 85
@font-face directive for, 143
style for, 190
in tables, cascading style for, 393
tightening space between, 199
type size, 157

<head> tag (HTML), 5, 27, 64

height

of elements, 576
max-height property for, 585
min-height property for, 585
minimum and maximum, 219
of table cells, 379

height property, 584

in box model, 212–219
for positioned elements, 492

Helvetica font, 130

hexadecimal number for color, 226,
564

for color value, 154

hidden border, 203, 575

**hidden value, for overflow
property**, 217–218, 236

**hide keyword, for empty-cells
property**, 384

hiding

captions, 513
content on handheld devices, 458
unwanted page areas for print, 527–
529
web page parts, 498–501

highlighting links, 322–324

**Horizontal 3D picture gallery
(Apple)**, 345

horizontal navigation bars, 307–313
centering on page, 309
change to vertical, 331–334
float for, 310–313
with display: inline and display:
inline-block, 308–310

horizontal offset

for box-shadow property, 211
for text-shadow property, 166

horizontal scaling, 339

:hover pseudo-class, 294, 295,
298–299, 303, 313
for making caption visible, 500
for transition trigger, 345
for transition trigger, 351
for visibility, 499

:hover pseudo-class selector, 294

:hover state, 68–69, 367

animating on, 366
background-position property
and, 314
button color change and, 346
for buttons, 301, 328
for caption display, 513
for resources links, 324
and scaling element, 338–339
translate in response to, 341

href attribute, for <link> tag, 42

HSLA format, 157, 565

**HSL (hue, saturation, lightness) color
notation**, 156–157, 565–566

HTML. *See also* tags

color keywords, 155
comments, 441, 443–444
family tree for tags, 64–65
online tutorials, 3
past and present, 17–19

- and search engines, 22
 - source order, 466–467
 - changing for RWD, 474–477
 - floated elements and, 418
 - screen readers and, 422
 - vs. CSS, 2
 - writing for CSS, 20–30
 - HTML 4.01 doctype**, 3
 - HTML 4.01 Transitional**
 - doctype declaration for, 31
 - <link> tag for, 42
 - HTML5**, 6–13
 - doctype declaration for, 31
 - element display as blocks, 549
 - <link> tag, 42
 - sectioning elements, 409–410
 - semantic tags in, 23
 - HTML5 Doctor**, 23, 24
 - HTML5 doctype**, 4
 - HTML Dog**, 3
 - HTML frames**, 504
 - <html> tag (HTML)**, 4, 27, 64, 181–182
 - background image for, 248
 - background property, 189
 - based text size, 161
 - HTML Tidy extension for Chrome**, 27
 - hue in color**, 565–566
 - hybrid style, creating**, 119–120
 - hyperlink**, 5. *See also* <a> tag (HTML); links
-
- I**
 - icons**
 - finding free graphics for, 176, 256
 - fonts containing, 140
 - multiple in one file, 328
 - varying by link type, 322
 - id attribute**, 22, 61
 - IDs**, 553–558
 - for <div> tags, 408
 - ID selectors**, 60–62
 - overriding, 114
 - replacing with classes, 114–115
 - specificity, 108
 - tutorials, 89–91
 - ID style, class style and**, 107
 - IE**. *See* Internet Explorer
 - <iframe> tag (HTML)**, 217, 470, 473
 - images**. *See also* background-image property
 - adding to web page, 189, 283–285
 - background property with
 - multiple, 289
 - for bullet, 572
 - descendent selector for those inside
 - figure, 278
 - finding free, 256
 - fluid, 470–473
 - :hover style to enlarge, 339
 - moving in from edge, 303
 - styles for, 2
 - tutorial on enhancing, 272–277
 - framing, 273–277
 - tag (HTML)**, 23, 239–240
 - alternately floating left and right, 78
 - border attribute, and IE border for
 - linked images, 297
 - as inline tag, 200
 - padding and margin changes, 201
 - removing width and height attribute,
 - for fluid images, 478
 - in table cell, display property, 379
 - tag (XHTML)**, 30
 - Impact font**, 131, 132
 - !important**, 535
 - to override specificity, 111
 - for print, 525
 - to override onscreen styling, 524
 - @import directive**, 41, 42–43, 355
 - for Google Web fonts, 151
 - Internet Explorer and, 522
 - for media queries, 462
 - for multiple style sheets, 547
 - for targeting version of IE, 560
 - indentation in styles**, 46, 84
 - indented text**
 - for first line of paragraph, 169, 570
 - margins to move text beyond
 - sidebar, 442
 - InDesign**, 410
 - infinite keyword, for animation-iteration-count property**, 363, 591
 - inheritance**, 63, 79
 - accumulated styles, 104–105
 - basics, 93–95
 - and cascade, 119
 - inaction, 101–102
 - limits, 95–97
 - line-height property, 168
 - properties specificity, 109

- streamlining style sheets with, 95
- for table font family, 391
- of text size, 160
 - in nested lists, 161
- tutorials, 97–102
- inherit keyword**, 566
- inline-block elements, figure tags as**, 511
- inline-block value, for display property**, 202, 303
- inline boxes**, 200
- inline elements**
 - display property for, 583
 - float property with, 221
 - line breaks and, 308
- inline styles**, 41
 - specificity, 108
 - tutorial on creating, 44–45
- inline tags**, 200
- inline text, tag for**, 22
- <input> tag (HTML)**, 73, 386
- inset border**, 203, 575
- inset value, for box-shadow property**, 211
- Inspect Element command, in web browsers**, 110
- integer values, for color**, 564
- intellectual property, fonts as**, 136
- Interactive CSS Box Model**, 602
- internal style sheets**, 40–41
 - benefits, 82
 - conflict with external style sheet, 110
 - external vs., 178–179
 - location in page code, 279
 - to override styles, 113
 - tutorial on creating, 45–48
- Internet Explorer**, 33
 - adjacent sibling selectors and, 92
 - animations and, 354
 - auto-update feature, 32–34
 - background images, 258
 - faking multiple, 259, 290
 - background-origin and background-clip properties and, 252
 - and background properties, 256
 - box shadow in, 212
 - box-shadow in, 210
 - box-sizing property and, 447, 468
 - browser bugs, 440
 - bug in @font-family directive, 139
 - color gradients and, 264
 - CSS for, 558–560
 - drop shadow and, 166–167
 - earlier versions, 32
 - and element corners, 209
 - filters for gradient, 271
 - font variants, 143–146
 - form checkboxes and radio buttons, 386
 - form field display, 385
 - gradients and, 436
 - HTML5 and, 4, 24, 511
 - border attribute, and border for linked images, 297
 - and inline-block, 309
 - keyframes and, 359
 - media queries and, 460
 - multiple background images and, 290
 - negative z-index values and, 498
 - and :not() selector, 316
 - nth-of-type selector and, 382
 - popularity of, 146
 - radial gradients and, 268
 - and rem measurement unit, 161
 - repeating linear gradients and, 265
 - RGBA color issues, 155
 - targeting different versions, 560
 - and transforms, 367
 - transitions and, 346, 348, 501
 - transparency settings and, 512
 - vendor prefix, for transforms, 336–337
 - web fonts support, 133
- “Internet Explorer conditional comment” (IECC)**, 24
- iPhones**
 - pixels on, 473
 - Retina Display, 158
 - SVG fonts for, 135
- Irish, Paul**, 602
- <i> tag (HTML)**, 26, 146, 162
- italics type**, 569
 - for Internet Explorer, 144–146
 - web fonts, 140–146
 - for words and letters, 162–163

J**JavaScript**

- to apply animation-play-state property, 366
- applying ID for, 62
- FitVids program, 473
- location in code, 40
- for mouseover, 501
- navigation menu change to HTML drop-down menu, 458
- for pop-up submenus, 311
- respond.js program, 462
- to trigger transitions, 351
- tutorial on, 351
- for TypeKit, 153
- visibility property and, 499
- for web fonts, 152

jEdit, 7**JPEG (Joint Photographic Experts Group) graphics**, 242**jQuery aTip2 plug-in**, 501**justifying text**, 169**justify keyword, for text-align property**, 169, 379**K****keyboard shortcuts**, 11**keyframes in animation**, 354, 371

- defining, 355–359
- percentage values for multiple, 356–358

@keyframes statement, 355, 588–589

- for fade-in animation, 359–360
- vendor prefixes, 372–373

keywords

- for background image position, 246
- for color, 564
- for text size changes, 159

L**labels, changing from inline elements to inline-block**, 396**<label> tag (HTML)**, 387, 388**large keyword for font size**, 159, 568**larger keyword for font size**, 568**:last-child selector**, 76**:last-of-type selector**, 77**Latin Extended character set**, 151**layering elements**, 415–416**LayoutGala site**, 422**layout generators**, 422

- layout of web page**, 24–25, 405. *See also* CSS layout; *See also* CSS layout
- adjusting for print, 533–535
- avoiding <table> tag for, 26
- float-based, 417, 421
- future methods, 436
- grid for, 425
- mixing liquid with fixed design, 450–452
- multi-column layouts
 - module, 430
 - tutorial, 440–452
- online designs, 422
- properties, 582–588
- three-column design, 421
- two-column design, 418–421
 - flexible grids and, 465–466

leading, 168**League Gothic font**, 134**League of Movable Type**, 134**left keyword**

- for background-position property, 246
- for clear property, 223
- for float property, 221, 417
- for text-align property, 169, 379
- for transform-origin property, 344

left property, 490, 584

- of images, 504

<legend> tag (HTML), 386**Lein, Mathew, Caesar tool**, 349–350**LESS preprocessor**, 543**letters (characters)**

- formatting, 162–166
 - capitalizing, 163
 - text-decoration property, 163–165
 - spacing, 165–166

letter-spacing property, 165–166, 569**licenses, for fonts**, 134**lightness value in HSL color notation**, 157, 565–566**linear-gradient property**

- for button, 300
- for Submit button, 398

linear gradients, 260–264

- for buttons, 301, 386
- with color stops matching column widths, 435
- for column background, 433–436

- gradient image vs., 283
 - in tables, 382
 - header background, 393
 - linear keyword**
 - for animation-duration property, 361
 - for transition-timing-function property, 348
 - line breaks**
 -
 or
tag for, 4, 26
 - for float problem, 427
 - inline elements and, 308
 - line height**
 - browser default, 550
 - in font property, 170
 - line-height property**, 91, 117, 121, 167-168, 184, 569
 - for navigation links, 307
 - line (rule) between columns**, 430
 - line-through option for text**, 164, 570
 - :link pseudo-class selector**, 294
 - links**. *See also* <a> tag (HTML)
 - adding background image to, 321-322
 - adding graphics, 302-304
 - adding tooltips, 72
 - blue, underline to indicate, 297-299
 - border-bottom property for, 298
 - bulleted lists for, 297
 - buttons for, 299-302
 - converting to block-level element, 303
 - descendent selectors for grouping, 296-297
 - email, 317
 - highlighting, 322-324
 - order for styles, 295
 - to other websites, 316
 - removing underline, 107
 - selecting for style, 293-297
 - to specific file types, 317
 - styles for, 68-69, 297-304
 - particular link types, 315-317
 - to highlight external, 73
 - tutorial, 318-324
 - targeting particular, 295-297
 - “you are here”, 328-331
 - link states**, 293-295
 - <link> tag (HTML)**
 - for external style sheet, and internal style placement, 278
 - for Google web fonts, 50, 151, 152
 - media attribute, 522
 - for style sheet, 41, 42, 50
 - updating for revised style sheet, 550
 - liquid designs**, 406, 407, 448
 - mixing with fixed, 450-452
 - Listamatic**, 601
 - A List Apart website**, 521
 - list items, floating**, 313
 - List-O-Matic wizard**, 313
 - lists**
 - as block-level tag, 200
 - bulleted
 - graphics for, 286-288
 - tag for, 20
 - child selectors for, 79
 - numbered, 29
 - ordered, tag for, 19
 - properties for, 572-573
 - removing indent from all, 175
 - space between items, 186
 - styling, 173-178
 - tutorial, 185-187
 - types of, 173-174
 - unordered
 - for navigation bar, 304-305
 - tag for, 29
 - list-style-image property**, 176, 572
 - list-style-position property**, 174-175, 572-573
 - list-style property**, 178, 572
 - list-style-type property**, 173, 573
 - Listutorial**, 601
 - tag (HTML)**, 174, 176
 - background image for, 248, 249
 - display property of, 308
 - in horizontal navigation bar, 331
 - left float for, 310
 - style for, 186
 - living examples**, 12
 - logo image, spinning and scaling**, 369
 - lowercase keyword, for text-transform property**, 163, 571
 - Lucida Console font**, 132
-
- M**
- Mac**
 - font display on, 130
 - monospaced fonts on, 132
 - mailto link, visual cue for**, 321

- Marcotte, Ethan**, 406, 454
 - Responsive Web Design, 455
- Marcott, Ethan**, 468
- margin-bottom property**, 196, 578
 - for list items, 176
 - for paragraphs, 171
- margin-left property**, 102, 196, 578
 - and list indent, 175
- margin property**, 184, 578
 - for <body> tag, 49
 - for <div> tag, 189
 - for <h2> tags, 232
 - for tag, 274
 - order of values, 186
 - shorthand, 232
- margin-right property**, 196, 578
 - negative value for, 190
- margins**, 121, 194, 195–202
 - browser default for, 548
 - collapsing, 198, 199
 - colliding, 197–198
 - for bulleted list, 289
 - for indenting main text beyond sidebar, 442
 - inheritance inaction, 101
 - inline boxes and, 201
 - negative, for removing space, 199–200
 - between paragraphs, 171
 - for positioning, 416
 - properties for, 573–578
 - recommendation on zeroing out, 171
 - removing, 169–171
 - from navigation bar, 305
 - from print style sheet, 533
 - shorthand property, 196–197
 - for space between tag, 186
- margin-top property**, 196, 227, 391, 578
 - for list items, 176
- matrix**, 343
- max-height property**, 219, 585
- max-width notation, for link media attribute**, 461
- max-width property**, 219, 449, 450, 465, 477, 585
 - for img style, 470
- measurement units**
 - for fonts, 157
 - for margin or padding, 196
- media queries**, 407, 455, 457–465, 480
 - for 480-pixel display, 485–486
 - basic stylesheet structure for, 463–465
 - breakpoints, 459–465
 - creating, 461–462
 - in stylesheet, 462–463
 - strategies for using, 457–459
- @media statement**, 355, 463, 522
- media style sheets**
 - !important to override onscreen styling, 524
 - for printed page, 519–521
- medium keyword for font size**, 159, 568
- menus**, 10
 - drop-down, slowly disappearing, 352
 - pop-up, 311
- <meta> tag (HTML)**, 456
 - for IE8 to ignore compatibility view, 33
- Meyer, Eric**, 116
- “Micro Clear Fix”**, 428
- Microsoft Compatibility View List**, 33
- Microsoft Expression Web**, 605
- middle keyword, for vertical align property**, 379
- min-height property**, 219, 585
- min-width notation, for link media attribute**, 461–462
- min-width property**, 219, 585
- mobile devices**
 - displays, 406
 - hiding content on, 458
 - page layout for, 412
 - troubleshooting display, 484
- mobile-first design, stylesheet for**, 464–465
- Mobile First movement**, 412
- mobile-only websites, screen variations**, 453
- modular CSS design**, 547
- module of code, descendent selectors for**, 67–68
- Monaco font**, 132
- monospaced fonts**, 131, 132
- Morgue File**, 256
- Morphing Power Cubes (Apple)**, 345
- mouseover, caption appearance with**, 500

mouse pointer, appearance of, 596
moving
background image, padding for, 321
images in from edge, 303

Mozilla Developer Network, CSS Reference, 600

-moz- vendor prefix, 209
for color gradients, 264

-ms- vendor prefix, 209

multi-column layout module, 430

multi-column layouts

three-column design, 421
troubleshooting, 444
tutorial, 440–452
adding column, 443–445
HTML structure, 440–441
layout styles, 441–443
padding, 445
two-column design, 418–421

N

names

for animations, 355
for classes, 58
for styles, 541–542
of fonts, quote marks for multi-word, 129

<nav> element (HTML5), 367, 485
background color for, 450

navigation

resources on, 601–602
selecting links for style, 293–297

navigation bars, 304–313

adding class to links, 329
borders, 307
bottom border for, 327
changing horizontal to vertical, 331–334
formatting button based on site section, 555–557
help for creating, 313
horizontal, 307–313
centering on page, 309
with display: inline and display: inline-block, 308–310
float for, 310–313
on smartphone, 485
pop-up menus, 311
removing from printed page, 531
rollover effect, 328

tutorials, 324–334
 tag for, 30
unordered lists for, 304–305
vertical, 305–307

navigation menus, for media queries, 458

<nav> tag (HTML5), 6, 23, 24, 30, 296, 510

negation pseudo-class, 80

negative margins, for removing space, 199–200

negative numbers

for cropping picture, 248
for rotating counter-clockwise, 337
for positioning, 490, 504
in translate function, 341
for z-index property, 498

negative percentage values, for background image positioning, 250

negative value

for margin-right property, 190

nested elements

descendent selectors for, 66
inheritance and, 93
relative positioning for, 494–495, 495–497

nested lists

child selectors for unordered, 79
inheritance of text size, 161

nesting tables, 19

NetMagazine, 601

NetMarketShare, 32, 135

NetRenderer, 34

New York Times site, on phones, 456

none keyword

for border, 205
for clear property, 223
for display property, 202
for float property, 417, 480
for border property, 321
for border-style property, 575
for float property, 221
for list-style property, 287
for list-style-type property, 174
for text-decoration property, 164, 297, 570
for text-transform property, 163, 571

non-numbered lists, tag for, 20

no-repeat value, for background-repeat property, 245, 284, 302, 581

normal

as font-style property value, 142, 162
as font-weight property value, 140, 142, 143

Normalize.css project, 552

Notepad (Windows), 7

Notepad++ (Windows), 7

:not() selector, 79, 80, 316

nowrap value, for white-space property, 571

:nth-child selector, 76

:nth-of-type selector, 78

for alternating rows in tables, 394

for table rows, 381

numbered lists, 29, 173

customizing numbers, 177

positioning numbers, 174–176

number measurement method

line spacing by, 168

O

Object Oriented CSS, 558

oblique, as font-style property value, 162

odd child elements, selecting, 76

** tag (HTML)**, 19, 29, 173

online resources, 12–13

online tutorials, on HTML, 3

OOCSS project, 558

opacity

of box shadow, 211

in HSL color, 157

opacity property, 501, 513, 596

0 value to hide element, 499

opaque color, 155

Open Font Library, 135

opening tag in HTML, 4

Open Photo, 256

Open Type fonts, 133

Opera browser, 34

form checkboxes and radio

buttons, 386

gradients in, 264

transitions and, 348

vendor prefix

for transforms, 336–337

ordered list, tag for, 19

order of stacked elements, 497

origin

for background image, 252–253, 580

for transform property, 343–345,

592

orphans property, 596

.otf file extension, 133

outline-color property, 577

outline property, 576

outline-style property, 577

outline-width property, 577

outset border, 203, 575

-o- vendor prefix, 209

for color gradients, 264

overflow:hidden property, 312, 333,

428

overflow property, 217–218, 236, 586

hidden float and, 222

overlapping elements

from absolute positioning, 509–510

from transformed element, 336

underline option for text, 164, 570

overriding styles, selectively, 113–114

P

padding, 193, 194, 195–202

borders and, 205

browser default for, 548

for columns on web page, 438, 445

and element size, 576

for form text boxes, 400

for space in list item, 287

for graphics for link, 303

for header, 509

inheritance inaction, 101

inline boxes and, 201

for positioning, 416

properties for, 573–578

removing from navigation bar, 305

shorthand property, 196–197

for sidebar, 289

for table cells, 380, 392

for <table> tag, 378

to move background image, 321

padding-bottom property, 196, 578

padding-box value

for background-clip property, 252

for background-origin property, 252

for box-sizing property, 216, 439

- padding-left property**, 175, 196, 578
 - and list indent, 175
- padding property**, 85, 102, 228, 577
 - for <body> tag, 49
 - for <div> tag, 189
 - for <h2> tags, 232
 - for images, 240, 274
 - for link as button, 300
 - shorthand, 231, 446
 - for space between link text and border, 299
- padding-right property**, 196, 577
- padding-top property**, 196, 577
 - for <html> tag, 49
- PageBlox**, 602
- page-break-after property**, 529–530, 597
- page-break-before property**, 529–530, 597
- page-break-inside property**, 597
- page breaks for printed page**, 529–530
- page elements**
 - guidelines for setting heights, 214–215
 - positioning, tutorials, 507–516
- page loads, animation start when**, 354
- paragraphs**
 - class styles for first, 122
 - formatting, 167–173, 182–185
 - aligning text, 169
 - first letter or first line, 171–173
 - first line indents and removing margins, 169–171
 - space adjustment between text lines, 167–168
 - HTML tag for, 5, 29
 - margins between, 171
 - style for, 47, 91, 121–122
- Parallels Desktop**, 34
- parent tag**, 65
 - inheriting value from, 566
- Pattern4u**, 256
- PatternCooler**, 256
- patterns, online creators**, 256
- pause keyword, for animation-play-state property**, 365, 591
- pausing animation**, 365–366
- PDF documents**
 - assigning icon to link, 323
 - style for link, 317
- percentage values**, 566
 - for color stop placement, 262
 - for column widths, 215, 468
 - for float width, 419
 - for height property, 213
 - for line spacing, 168
 - for liquid design widths, 406
 - for margins and padding, 196
 - for multiple keyframes, 356–358
 - for text-indent property, 170
 - for text size, 159
 - to position background image, 249–250
 - for transform-origin property, 344
 - for width property, 213
- period (.), for class selector**, 57
- photo gallery**, 272
 - for photos of differing widths, 279
 - tutorial, 278–282
 - drop shadows, 281–282
- photos**. *See* graphics; tag (HTML)
 - in div background, 415
 - <div> tag to group caption with, 60
 - finding free, 256
 - positioning captions on, 510–516
- physical style, for font search**, 148
- Picasa Web Albums**, 256
- pixels**, 213, 473, 565
 - for color stop placement, 262
 - for font size measurement, 158
 - for line spacing, 168
 - for margin or padding measurement, 196
 - for text-indent property, 169
 - for transform-origin property, 344
- plus sign (+), for adjacent sibling selector**, 79
- PNG (Portable Network Graphics) file format**, 242
- PNG8 file format**, 242
- PNG24 file format**, 242
- PNG32 file format**, 242
- points, for font measurement**, 524
- pop-up menus**, 311
- pop-up messages**, 72
- pop-up tooltips**, 501
- positioning**
 - animating, 370–371

- background image, 245–254, 581
 - bullets and numbers in lists, 174–176
 - captions, 499, 510–516
 - fixed distance from side of
 - browser, 491
 - frames from fixed, 504–507
 - negative values for, 504
 - page element, tutorial, 507–516
 - setting values, 490–493
 - strategies, 502–507
 - breaking element out of box, 503–504
 - within element, 502–503
 - table content in cell, 379–380
 - position property**, 488–501, 586
 - for layer elements, 416
 - pound symbol (#)**
 - for ID selectors, 90
 - for ID style, 61
 - preloading rollovers**, 313–315
 - preprocessors**, 543
 - <pre> tag (HTML)**, 571
 - printed page**, 519
 - adjusting banners for, 534
 - background images and color for, 525–527
 - backgrounds, 250
 - displaying URLs on, 528
 - formatting text for, 535–536
 - hiding unwanted areas, 527–529
 - issues with background, 415
 - media style sheets for, 519–521
 - page breaks for, 529–530
 - print media type**, 520
 - print style sheets**, 522
 - creating, 523–530
 - hiding unwanted elements, 528
 - for text, 524
 - tutorial, 530–538
 - privacy concerns**, 294
 - projection media type**, 520
 - properties**
 - animation, transform and transition, 588–593
 - of backgrounds, 579–582
 - in declarations, 37
 - of lists, 572
 - overcoming conflicts, 120–124
 - of padding, borders, and margins, 573–578
 - tables, 593–595
 - of text, 567–572
 - values, 563–567
 - color, 563–565
 - lengths and sizes, 565–566
 - web page layout, 582–588
 - pseudo-classes**, 68–72
 - applying animation to, 359
 - for links, 303
 - specificity value, 108
 - pseudo-class selectors**, 294
 - pseudo-elements**, 68–72
 - specificity value, 108
 - <p> tag (HTML)**, 5, 20, 29, 200
 - adding class, 188
 - font-family property for, 127–129
 - Pure CSS Menu generator**, 311
 - px**, 158. *See also* pixels
-
- ## Q
- <q> tag (HTML)**, 29
 - <q> tag (HTML)**, 551
 - Quark Xpress**, 410
 - query**, 461. *See also* media queries
 - quirks mode**, 30–31, 33
 - quotations, <blockquote> tag for**, 29
 - quote marks (‘)**
 - browser default for, 551
 - for animation name, 360
-
- ## R
- radial gradients**, 266–269
 - radio buttons on forms**, 386
 - :checked pseudo-class for, 389
 - radius, of box shadow**, 211
 - relative positioning**, 488, 489, 496
 - uses for, 495–497
 - rel attribute, for <link> tag**, 42, 50
 - rem measurement unit**, 161, 213
 - removing**
 - margins, 197
 - space between table cells, 392
 - space for a margin or padding, 196
 - repeating**
 - background-image property, 244–245
 - color gradients, 265–266
 - repeat value, for background-repeat property**, 245, 581

repeat-x value, for background-repeat property, 245, 581

repeat-y value, for background-repeat property, 245, 581

reset.css file, 117

reset styles, 225

resources, online, 12-13

Responsinator, 470

Responsive CSS Navigation Menu, 602

responsivepx site, 470

responsive web design (RWD), 406, 407

- basics, 454-455
- desktop first or mobile first, 460
- flexible grids, 465-470
- fluid images, 470-473
- media queries, 457-465
 - basic stylesheet structure for, 463-465
 - breakpoints, 459-465
 - creating, 461-462
 - stylesheets in, 462-463
- testing, 470
- tutorial, 474-486
- web page setup for, 455-457

Retina Display, 158

reversing animation direction, 364

RGBA (Red, Green, Blue, Alpha) colors, 51, 155, 183, 226, 564

- background shorthand property for, 264
- for background transparency, 206
- for box shadows, 211
- percentages for, 564

RGB colors, 154, 226

ridge border, 203, 575

right keyword

- for background-position property, 246
- for clear property, 223, 224
- for float property, 417
- for float property, 221
- for text-align property, 169, 379
- for transform-origin property, 344

right property, 490, 491, 586-587

rollovers

- for :hover, 320
- preloading, 313-315
- tutorial, 328-331

Root EM, 161

root-relative path, 80, 243, 244

- for style sheet location, 50

rotate function, of transform property, 337, 592

rotate property, 371

rounded corners, 207-209, 574

- for button, removing, 398
- for table cells, 381
- for sidebar, 235

rows in tables, styles for, 381-384

rule (line) between columns, 430

rules, 36. *See also* styles

running keyword, for animation-play-state property, 365, 591

Rupert, Dave, 473

RWD. *See* responsive web design (RWD)

S

Safari browser, 34

- box-sizing property in, 216
- and element corners, 209
- form field display, 385
- gradients in, 264
- Inspect Element command, 110
- padding property for indenting
 - bulleted lists, 115
- radial gradients and, 268
- repeating linear gradients and, 265
- text-transform property and, 173
- validate tool for, 27
- vendor prefix
 - for box shadow, 212
 - for transforms, 336-337

sans-serif fonts, 129, 130-131

SASS preprocessor, 543

saturation in color, 156, 565-566

Scalable and Modular Architecture for CSS (SMACSS), 558

scale function, of transform property, 338-340, 592

scaleX function, 339

scaleY function, 339

scaling

- background images, 253-254
- buttons on mouseover, 367-368
- logo image, 369

Scout, 543

screen media type, 520

screen readers, 422

- script fonts**, 148
- scrollable content area, fixed position elements and**, 507
- scroll bars, window width and**, 449
- scrolling**
 - and image position, 250
 - page elements in view, 505
- scroll value**
 - for background-attachment property, 251
 - for overflow property, 217–218
- search engines**
 - and content order, 422
 - HTML and, 22
- sectioning elements (HTML5)**, 409–410
- <section> tag (HTML5)**, 23, 25, 30, 415
- selecting**
 - Google web fonts, 148–150
 - links for style, 293–297
- ::selection selector**, 71–72
- Selectoracle**, 72
- selectors**, 35, 37, 55–92
 - attribute, 72–74
 - child, 74–79, 77–79
 - class, 57–60
 - descendent, 63–64
 - universal selector as part, 63
 - group, 62–63
 - ID, 60–62
 - :not(), 80
 - tag, 56–57
 - tutorial, 81–92
 - class selector, 85–88
 - descendent selector, 88–89
 - group selector, 84–85
 - ID selector, 89–91
 - type, 82
 - * (universal), 63, 535
 - for formatting every tag with black text, 525
- Selectors module**, 9
- <select> tag (HTML)**, 386
- self-closing tags**, 30
- semantic tags in HTML5**, 23
- semicolon (;)**
 - for end of src property, 139
 - for property/value pair, 38
- separate keyword, for border-collapse property**, 381
- serif fonts**, 130
- sibling tags**, 65, 79–80
- sidebar**, 23, 25
 - background image for, 288–291
 - background image under, 431–436
 - changing code order, 474
 - <div> tag for, 441
 - floating, 418
 - hidden for printed page, 533
 - position property for, 506
 - removing from printed page, 531
 - tutorial, 233–237
- simulated screens**, 470
- Sitepoint.com**, 600, 601
 - CSS Reference, 600
- site root folder**, 137
- size**
 - of background image, 582
 - of fonts, changes, 157–162
 - of image, scaling, 253
 - of radial gradient, 267–268
 - scale function to change, 338–340
- skEdit (Mac)**, 7
- skew function, of transform property**, 342–343, 592
- skewing**, 335
- skewX function**, 343
- skewY function**, 343
- Slant slider, for finding fonts**, 148
- small caps**, 163, 569
- smaller keyword for font size**, 568
- small keyword, for font size**, 159, 568
- smartphones**, 455
 - media queries for, 460
 - navigation bar on, 485
 - previewing page for, 470
 - styles for, 483–486
 - web browsing on, 457
- Smashing Magazine**, 601
- Snook, Jonathon**, 558
- Snow Stack**, 345
- software for CSS**, 7–13, 604–606
- software piracy**, 136
- solid border**, 203, 575
- Some Random Dude**, 256
- source order**, 466–467
 - changing for responsive web design, 474
 - and floated elements display, 221
 - screen readers and, 422

- space**, 193. *See also* margin property
 - adjusting around tags, 229–233
 - adjustment between text lines, 167–168, 569
 - avoiding rivers of, 169
 - between letters, 165, 569
 - between navigation bar tags, 309–310
 - between table cells, 382
 - removing, 380, 392, 593
 - carriage return as, 310
 - for columns on web page
 - padding to add, 445
 - around content, 195–202
 - in list item, padding for, 287
 - between list items, 186
 - negative margins for removing, 199–200
 - padding property for, 85, 577
 - removing for a margin or padding, 196
 - tightening for media queries, 458
 - troubleshooting in table cell with image, 379
 - between words, 165–166, 572
- tag (HTML)**, 22, 30, 57, 177, 388, 396, 502
 - class formatting for, 59
 - on form, 387
 - for inline elements, 60
- specificity**
 - changing, 111
 - for styles, 108–111
 - overruling, 111
 - tie in, 109–111
- specificity wars**, 112
 - avoiding, 114–115
- speech media type**, 520
- speed of animation**, 590
- spinning logo image**, 369
- spread for drop shadow**, 211, 212
- SpritePad**, 314
- Sprites (CSS)**, 314, 328, 329
- Squidfingers**, 256
- src property**
 - in @font-face directive, 138
 - for font formats, 139
- stacking elements**, 497–498
- StatCounter**, 32
- states of links**, 68
- static keyword, for position property**, 586
- static positioning**, 489, 490
- statistics, on web browser use**, 32
- Stock.xchng**, 256
- strict doctype style**, 3
- strike-through effect, for text**, 164
- Stripe Generator 2.0**, 256
- tag (HTML)**, 5, 26, 140, 143, 188, 190
- structure, HTML for**, 19, 20–21
- Stunning CSS3 (Gillenwater)**, 604
- Style Master**, 604
- styles**
 - accumulated by inheritance, 104–105
 - for all link states, 294
 - anatomy of, 35–38
 - applying animation to, 360
 - applying many to tag, 106–108
 - of border, 202–203
 - built-in to web browsers
 - erasing, 115–117
 - for class, 188
 - code indentation, 46, 84
 - conflicts, 97, 103, 104, 105
 - eliminating interference, 548–552
 - for figure, 276
 - for font variants in Internet Explorer, 145
 - for groups of tags, 62–63
 - for <h2> tag, 183
 - for headlines, 190
 - inline, 41
 - for links, 68–69, 297–304
 - tutorial, 318–324
 - for lists, 173–178
 - multiple, for transitions, 345
 - names for, 541–542
 - for navigation bar tags, 325
 - order of, 189
 - organizing, 541–548
 - by grouping, 545
 - removing all margins, padding and font size, 225
 - selectively overriding, 113–114
 - for smartphones, 483–486
 - specificity for, 108–111
 - for tablets, 480–482
 - tutorial on creating, 43–54
 - external style sheet, 48–54

inline style, 44–45
internal style sheet, 45–48
using web fonts, 140, 152

style sheets

attaching multiple to web page, 42
attaching to multiple web pages, 51–52
basic structure for media queries, 463
choosing external or internal, 39
code order in, 509
comments in, 539–540
conflict between internal and external, 110
external, 41–43
 <link> tag for, 42
 @font-face directive in, 137
inheritance for streamlining, 95
internal, 40–41
 benefits, 82
 internal or external, 38–39
 media queries in, 462–463
 media type specified within, 522–523
 multiple, 546–548
 multiple with same style name, 107
 organizing, 541–548
 for print, 523–530
 to reset browser styles, 551–552

<style> tag (HTML), 40, 82, 179

excluding from external style sheet, 49
@import directive in, 42

subdividing page, <div> tag for, 22**Sublime Text (Mac),** 7, 604**Submit button**

benefit of generic appearance, 384
properties for, 398

Subscribe button, aligning with other form elements, 397**subset of font,** 136**Sullivan, Nicole,** 558**superscript characters,** 571**SVG (scalable vector graphic)**

fonts, 133
for Chrome, 139
for iPhone fonts, 135

symbols, fonts with, 140, 176**T****table-layout property,** 595**tables**

as block-level tag, 200
border-collapse property, 392
border property for, 380–381
browser default for borders, 550
cell height, 379
color property for, 378
content position in cell, 379–380
equal-height columns in, 430
for form layout, 387–389
HTML tags for, 376–377
properties, 593–595
proper use, 375–378
rounded corners for cells, 381
styles for rows and columns, 381–384
tutorials, 390–394
vertical-align property for cells, 571

<table> tag (HTML), 19, 377, 408

avoiding for page layout, 26

tablets

media queries for, 460
previewing page for, 470
styles for, 480–482
web browsing on, 457

tabs in styles, readability and, 38**tags,** 3

adding class attribute to, 59
adjusting space around, 229–233
as boxes, 193
closing, 30
descendant, 93
how they work, 4–13
list of, 20
many styles applied, 106–108
those to forget, 26
within tags, styles for, 63–68

tag selectors, 56–57

specificity, 108

tags in HTML5

new, 6
semantic, 23

tag styles

class style vs., 100
for groups, 62–63
for specific, 2

:target pseudo-class, 345

<tbody> tag (HTML), 377

<td> tag (HTML), 377, 392
valign attribute of, 380

testing

cross browser, 34
responsive web design (RWD), 470

text. *See also* formatting text

centering in button, 311, 333
color, changing for unvisited
link, 294

color property, 98
importance, and heading level, 28–
29
preventing wrap, 571
properties, 567–572
styles for print, 524–525

text-align: center property, 311, 333

text-align property, 169, 230, 535,
566, 570
for button, 301
for table content, 379

<textarea> tag (HTML), 386

text box, 73

text-decoration property, 107,
163–165, 570
for button, 301
none value, 297, 318

TextEdit (Mac), 7

text fields in forms, 386, 399

text-indent property, 169, 570

text shadow, 183

text-shadow property, 166–167,
570–571
for button, 300, 301
RGBA and, 155

text-transform property, 163, 184, 237,
571

TextWrangler (Mac), 7

<thead> tag (HTML), 377

thickness slider, for font search, 148

3D transforms, 345

<th> tag (HTML), 377, 392

**tilde (-), for general sibling
combinatory selector**, 80

tiling image, 246

Times font, 130

Times New Roman font, 130

timing

for multiple animations, 361

title attribute, 72

<title> tag (HTML), 27

to keyword, for @keyframe, 356
tooltips, 72

top keyword

for background-position
property, 246
for transform-origin property, 344
for vertical align property, 379

top property, 490, 587
of images, 504

Top Style, 605

transform-origin property, 343–345,
592

transform property, 335–345, 592
with multiple functions, 343
online tool for visualizing effect, 343
rotate function, 337
scale function, 338–340
skew function, 342–343
translate function, 340–342

transitional doctype style, 3

transition-delay property, 351–352,
593

transition-duration property, 347, 593

transition property, 345, 514, 592–593
shorthand, 353–354

transition-property property, 347, 593

transitions, 345–354

adding, 346–348
animating drop-down menus, 311
delaying start, 351–352
properties, 588–593

**transition-timing-function
property**, 348–351, 593

**translate function, of transform
property**, 340–342, 592

translateX function, 341

translateY function, 341

transparency, 596

of background, RGBA color method
for, 206
of color, 155
of element, 596
HSLA format for, 565
RGBA color for, 564

trigger

to pause animation, 366
for transitions, 345
JavaScript for, 351

troubleshooting

- float problems, 425–440
- horizontal navigation bar, 332
- mobile device display, 484
- multi-column layout, 444
- space in table cell with image, 379

<tr> tag (HTML), 377**True Type fonts, 133****.ttf file extension, 133****tty media type, 520****tutorial files**

- webfonts-demo folder, 143

tutorials, 12

- background-image property, 282–291
- cascade, 117–124
 - CSS reset, 117–119
 - hybrid style creation, 119–120
- CSS box model, 225–238
- formatting text, 178
 - finishing touches, 188–192
 - headings and paragraphs, 182–185
 - lists, 185–187
- forms, 395–402
- on HTML, 3, 20
- image enhancement, 272–277
 - framing image, 273–277
- inheritance, 97–102
 - one level, 97–98
 - to restyle entire page, 98–101
- on JavaScript, 351
- multi-column layouts
 - adding column, 443–445
 - HTML structure, 440–441
 - layout styles, 441–443
 - padding, 445
- on navigation, online resources, 601
- on navigation bars, 313, 324–334
- photo gallery, 278–282
 - drop shadows, 281–282
- positioning page elements, 507–516
- print style sheet, 530–538
- responsive web design (RWD), 474–486
- selectors, 81–92
 - class selector, 85–88
 - descendent selector, 88–89
 - group selector, 84–85
- sidebar, 233–237
- style creation, 43–54

- external style sheet, 48–54
- inline style, 44–45
- internal style sheet, 45–48
- styles for links, 318–324
- tables, 390–394
- transforms, animation and transitions, 366–374

tv media type, 520**Twitter Bootstrap, 425, 603****two-column design, flexible grids and, 465–466****TypeKit, 134, 153****type selectors, 56, 82. *See also* tag selectors****type="text/css" attribute for <style> tag, 83****typography, 128****U****ul style, 185**** tag (HTML), 20, 29, 173, 304**

- border, 332
- child selector for, 79
- for navigation bar, 30, 324
- width of, 326

Ultimate CSS Gradient Generator, 269

- simulating gradient for IE, 271

underline, 163, 164, 570

- removing from links, 107, 297, 309, 318

Uniform Resource Locator

(URL). *See* URL (Uniform Resource Locator)

universal selector (*), 63, 535

- for formatting every tag with black text, 525

unordered lists, 29, 173–174

- for navigation bar, 304–305
- nested, child selectors for, 79
- style to remove padding, margins and bullets, 308

unvisited link, 293**updating website, style sheets and, 2****uppercase keyword, for text-transform property, 163, 571****url for list-style-image property, 176**

- URL (Uniform Resource Locator), 5**
 - absolute, for background image, 243
 - displaying on print page, 528, 536–538
 - as property value, 567

V

- validating**
 - CSS code, 41
 - web pages, 27, 28
- valign attribute of <td> tag, 380**
- value, in declaration, 37**
- Values and Units module, 9**
- variables, preprocessors to define, 543**
- vector graphics, 133**
- vendor prefixes, 209, 543**
 - for animation properties, 358, 360, 365, 589
 - for animation-delay property, 362
 - for animation-timing-function property, 362
 - for color gradients
 - linear, 435
 - for color gradients, 264
 - linear, 260
 - for @keyframes rule, 372–373
 - for linear gradient property, 394
 - for transitions, 368
 - for multi-column layout, 430
 - for transforms, 336–337
 - for transition-delay property, 351
 - for transition property, 348, 353
- vendor-prefixes**
 - for Firefox, 71
- Verdana font, 130**
- vertical-align: middle property, 201**
- vertical-align property, 571**
 - for forms, 388
 - for table cells, 379–380, 380
- vertical navigation bar, 305–307**
 - changing horizontal to, 331–334
- vertical offset**
 - for box-shadow property, 211
 - for text-shadow property, 166
- vertical scaling, 339**
- <video> tag (HTML5), 24**
 - scaling to container, 473
- viewport, 490**
 - in <meta> tag (HTML), 456

- @viewport rule, 457**
- virtual machines, for testing, 34**
- visibility property, 498, 587**
- visible option, for overflow property, 217–218**
- vision-impaired visitors, <div> tag impact for, 422**
- visited links, 293**
- :visited pseudo-class, 294, 303, 320**
- visited state for link, 68**
- visitor feedback, :focus selector for, 70**
- VMware Fusion, 34**

W

- W3C.** *See* World Wide Web Consortium (W3C)
- W3Schools, 3**
- web address.** *See* URL (Uniform Resource Locator)
- web browsers**
 - built-in styles, 96–97
 - erasing, 115–117
 - cache, 550
 - default font of, 128
 - display area of window, 490
 - eliminating style interference, 548–552
 - forcing background image to bottom of window, 248
 - Inspect Element, 110
 - predefined style for <a> tag, 106
 - Print Preview command, 524, 532
 - testing web pages in multiple, 34
 - zoom function, 159
- Webdings, 176**
- web fonts, 50, 51, 129, 132–146**
 - bold and italic variants, 140–146
 - finding, 134–135
 - Google, 146–153
 - finding and selecting, 148–150
 - legal issues, 134
 - styles using, 140
- Web forms.** *See* forms
- WebKit syntax, 370**
- webkit- vendor prefix, 209**
- web pages.** *See also* layout of web page; responsive web design (RWD)
 - adding image to background, 283–285

- attaching multiple style sheets, 42
 - attaching style sheet to, 41
 - attaching style sheet to second, 51–52
 - background color, 189, 226
 - background image for, 2
 - base font of, 181
 - graphics programs for mock-ups, 413
 - hiding parts, 498–501
 - inheritance to restyle, 98–101
 - setup
 - tutorial, 178–182
 - validating, 27, 41
 - website for book, tutorial files on, 44**
 - websites**
 - external style sheet for, 48
 - Google on search-friendly, 22
 - links to other, 316
 - web typography, 128**
 - weight of font, 151**
 - white space, 193. *See also* space**
 - white-space property, 571**
 - widows property, 597**
 - width**
 - of <a> tag (HTML), 311
 - of border, 202–203
 - box-sizing property for
 - redefining, 215–217
 - of caption, 276
 - of columns, 476
 - of container element, 421
 - of containing element, 196
 - of element display, 437
 - of elements, 468, 576
 - border and, 467
 - flexible, for media queries, 457
 - of floated element, 419
 - of form text boxes, 400
 - max-width property for, 585
 - minimum and maximum, 219
 - min-width property for, 585
 - of navigation bar buttons, 306, 309
 - of photos, photo gallery for
 - variation, 279
 - of outlines, 577
 - of page
 - <div> tag to control, 448
 - of table cells in columns, 390
 - of tag, 326
 - width property, 186, 588**
 - for <body> tag, 49, 226
 - in box model, 212–219
 - of columns, 466
 - for <div> tag, 189
 - for positioned elements, 492
 - removing from print style sheet, 533
 - for sidebar div, 442
 - when floating block-level
 - elements, 221
 - Width slider for finding fonts, 148**
 - Windows**
 - font display on, 130
 - monospaced fonts on, 132
 - Windows XP, and Internet Explorer 8, 32**
 - WOFF (Web Open Font Format) files, 133, 135**
 - for Chrome, 139
 - Word documents, assigning icon to link, 323**
 - words**
 - capitalizing, 163
 - formatting, 162–166
 - text-decoration property, 163–165
 - spacing, 165–166
 - word-spacing property, 165, 572**
 - World Wide Web Consortium (W3C), 6, 599**
 - CSS working group, 413
 - tool for validating CSS code, 41
 - website for validating pages, 27, 28
 - wrapper div element, 284**
 - wrapping content, float property for, 220–225**
 - Wroblewski, Luke, 413**
- ## X
-
- XHTML, 5–13**
 - <link> tag for, 42
 - XHTML 1.0 doctype, 3**
 - XHTML 1.0 Transitional, 31**
 - x-large keyword for font size property, 159, 568**
 - XML (Extensible Markup Language), 6**
 - x-small keyword for font size property, 159, 568**
 - xx-large keyword for font size property, 159, 568**

xx-small keyword for font size property, 159, 568

Y

Yahoo, Stencil Kit, 413

“you are here” links, 328–331

YouTube videos, 473

YUI Grids CSS, 603

Z

zeroing out formatting, 548–552

 margins and padding, 225

 recommendation on margins, 171

zeroing out tags, 116

z-index, 497, 509–510

z-index property, 498, 588

Zip archives, assigning icon to link, 323

zoom function in web browsers, 159

zoom property, 428, 429